

Join the discussion @ p2p.wrox.com



Covers Visual C++ 2012



Ivor Horton's
Beginning
Visual C++® 2012

Ivor Horton

www.it-ebooks.info

IVOR HORTON'S BEGINNING VISUAL C ++® 2012

INTRODUCTION.....	xxxv	
CHAPTER 1	Programming with Visual C++	1
CHAPTER 2	Data, Variables, and Calculations	25
CHAPTER 3	Decisions and Loops	97
CHAPTER 4	Arrays, Strings, and Pointers	135
CHAPTER 5	Introducing Structure into Your Programs.....	189
CHAPTER 6	More about Program Structure	231
CHAPTER 7	Defining Your Own Data Types	277
CHAPTER 8	More on Classes.....	333
CHAPTER 9	Class Inheritance and Virtual Functions	441
CHAPTER 10	The Standard Template Library.....	491
CHAPTER 11	Windows Programming Concepts	601
CHAPTER 12	Windows Programming with the Microsoft Foundation Classes (MFC)	635
CHAPTER 13	Working with Menus and Toolbars	659
CHAPTER 14	Drawing in a Window.....	685
CHAPTER 15	Improving the View	739
CHAPTER 16	Working with Dialogs and Controls	769
CHAPTER 17	Storing and Printing Documents	815
CHAPTER 18	Programming Windows 8 Apps.....	849
INDEX.....	905	

IVOR HORTON'S
BEGINNING

Visual C ++® 2012

IVOR HORTON'S
BEGINNING

Visual C++® 2012

Ivor Horton



John Wiley & Sons, Inc.

Ivor Horton's Beginning Visual C++® 2012

Published by
John Wiley & Sons, Inc.
10475 Crosspoint Boulevard
Indianapolis, IN 46256
www.wiley.com

Copyright © 2012 by Ivor Horton

Published by John Wiley & Sons, Inc., Indianapolis, Indiana

Published simultaneously in Canada

ISBN: 978-1-118-36808-4
ISBN: 978-1-118-43941-8 (ebk)
ISBN: 978-1-118-41703-4 (ebk)
ISBN: 978-1-118-43431-4 (ebk)

Manufactured in the United States of America

10 9 8 7 6 5 4 3 2 1

No part of this publication may be reproduced, stored in a retrieval system or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, scanning or otherwise, except as permitted under Sections 107 or 108 of the 1976 United States Copyright Act, without either the prior written permission of the Publisher, or authorization through payment of the appropriate per-copy fee to the Copyright Clearance Center, 222 Rosewood Drive, Danvers, MA 01923, (978) 750-8400, fax (978) 646-8600. Requests to the Publisher for permission should be addressed to the Permissions Department, John Wiley & Sons, Inc., 111 River Street, Hoboken, NJ 07030, (201) 748-6011, fax (201) 748-6008, or online at <http://www.wiley.com/go/permissions>.

Limit of Liability/Disclaimer of Warranty: The publisher and the author make no representations or warranties with respect to the accuracy or completeness of the contents of this work and specifically disclaim all warranties, including without limitation warranties of fitness for a particular purpose. No warranty may be created or extended by sales or promotional materials. The advice and strategies contained herein may not be suitable for every situation. This work is sold with the understanding that the publisher is not engaged in rendering legal, accounting, or other professional services. If professional assistance is required, the services of a competent professional person should be sought. Neither the publisher nor the author shall be liable for damages arising herefrom. The fact that an organization or Web site is referred to in this work as a citation and/or a potential source of further information does not mean that the author or the publisher endorses the information the organization or Web site may provide or recommendations it may make. Further, readers should be aware that Internet Web sites listed in this work may have changed or disappeared between when this work was written and when it is read.

For general information on our other products and services please contact our Customer Care Department within the United States at (877) 762-2974, outside the United States at (317) 572-3993 or fax (317) 572-4002.

Wiley publishes in a variety of print and electronic formats and by print-on-demand. Some material included with standard print versions of this book may not be included in e-books or in print-on-demand. If this book refers to media such as a CD or DVD that is not included in the version you purchased, you may download this material at <http://booksupport.wiley.com>. For more information about Wiley products, visit www.wiley.com.

Library of Congress Control Number: 2012946046

Trademarks: Wiley, the Wiley logo, Wrox, the Wrox logo, Wrox Programmer to Programmer, and related trade dress are trademarks or registered trademarks of John Wiley & Sons, Inc. and/or its affiliates, in the United States and other countries, and may not be used without written permission. Visual C++ is a registered trademark of Microsoft Corporation. All other trademarks are the property of their respective owners. John Wiley & Sons, Inc., is not associated with any product or vendor mentioned in this book.

This book is for my dear wife, Eve, who for so many years has given me unconditional support and love in whatever I choose to do. I could not have written this without her.

ABOUT THE AUTHOR



IVOR HORTON graduated as a mathematician and was lured into information technology by promises of great rewards for very little work. In spite of the reality usually being a great deal of work for relatively modest rewards, he has continued to work with computers to the present day. He has been engaged at various times in programming, systems design, consultancy, and the management and implementation of projects of considerable complexity.

Horton has many years of experience in the design and implementation of computer systems applied to engineering design and manufacturing operations in a variety of industries. He has considerable experience in developing occasionally useful applications in a wide variety of programming languages, and in teaching primarily scientists and engineers to do likewise. He has been writing books on programming for many years, and his currently published works include tutorials on C, C++, and Java. At the present time, when he is not writing programming books or providing advice to others, he spends his time fishing, traveling, and enjoying life in general.

ABOUT THE TECHNICAL EDITOR



MARC GREGOIRE is a software engineer from Belgium. He graduated from the Catholic University of Leuven, Belgium, with a degree in “Burgerlijk ingenieur in de computer wetenschappen” (equivalent to master of science in engineering in computer science). The year after, he received the cum laude degree of master in artificial intelligence at the same university. After his studies, Marc started working for a big software consultancy company called Ordina Belgium. As a consultant, he worked for Siemens and Nokia Siemens Networks on critical 2G and 3G software running on Solaris for big telecom operators. This required working in international teams stretching from South America and USA to EMEA and Asia. Now, Marc is working for Nikon Metrology on 3D scanning software.

His main expertise is C/C++, and specifically Microsoft VC++ and the MFC framework. Next to C/C++, Marc also likes C# and uses PHP for creating web pages. In addition to his main interest for Windows development, he also has experience in developing C++ programs running 24/7 on Linux platforms; for example, EIB home automation-controlling and monitoring software.

Since April 2007, he received the yearly Microsoft MVP (Most Valuable Professional) award for his Visual C++ expertise.

Marc is the founder of the Belgian C++ Users Group (www.becpp.org) and an active member on the CodeGuru forum (as Marc G). He also creates freeware and shareware programs that are distributed through his website at www.nuonsoft.com, and maintains a blog on www.nuonsoft.com/blog/.

CREDITS

Executive Editor

Robert Elliott

Project Editor

Ed Connor

Technical Editor

Marc Gregoire

Production Editor

Daniel Scribner

Copy Editor

Kim Cofer

Editorial Manager

Mary Beth Wakefield

Freelancer Editorial Manager

Rosemarie Graham

Associate Director of Marketing

David Mayhew

Marketing Manager

Ashley Zurcher

Business Manager

Amy Kries

Production Manager

Tim Tate

Vice President and Executive Group Publisher

Richard Swadley

Vice President and Executive Publisher

Neil Edde

Associate Publisher

Jim Minatel

Project Coordinator, Cover

Katie Crocker

Proofreaders

James Saturnio, Word One

Sarah Kaikini, Word One

Indexer

Ron Strauss

Cover Designer

Ryan Sneed

Cover Image

© Kyu Oh / iStockPhoto

ACKNOWLEDGMENTS

THE AUTHOR IS ONLY ONE MEMBER of the large team of people necessary to get a book into print. I'd like to thank the John Wiley & Sons and Wrox Press editorial and production teams for their help and support throughout.

I would particularly like to thank my technical editor, Marc Gregoire, for doing such a fantastic job of reviewing the text and checking out all the code fragments and examples. He has an uncanny knack for finding my errors, and his many constructive comments and suggestions have undoubtedly made the book a much better tutorial.

CONTENTS

<i>INTRODUCTION</i>	<i>xxxv</i>
<hr/>	
CHAPTER 1: PROGRAMMING WITH VISUAL C++	1
Learning with Visual C++	1
Writing C++ Applications	2
Learning Desktop Applications Programming	3
Learning C++	3
Console Applications	4
Windows Programming Concepts	4
What Is the Integrated Development Environment?	5
The Editor	6
The Compiler	6
The Linker	6
The Libraries	6
Using the IDE	7
Toolbar Options	8
Dockable Toolbars	9
Documentation	10
Projects and Solutions	10
Defining a Project	10
Debug and Release Versions of Your Program	15
Executing the Program	16
Dealing with Errors	18
Setting Options in Visual C++	19
Creating and Executing Windows Applications	20
Creating an MFC Application	20
Building and Executing the MFC Application	22
Summary	23
<hr/>	
CHAPTER 2: DATA, VARIABLES, AND CALCULATIONS	25
The Structure of a C++ Program	26
Program Comments	31
The #include Directive — Header Files	32
Namespaces and the Using Declaration	33
The main() Function	34
Program Statements	34

Whitespace	37
Statement Blocks	37
Automatically Generated Console Programs	37
Precompiled Header Files	38
Main Function Names	39
Defining Variables	39
Naming Variables	39
Keywords in C++	40
Declaring Variables	41
Initial Values for Variables	41
Fundamental Data Types	42
Integer Variables	42
Character Data Types	44
Integer Type Modifiers	45
The Boolean Type	46
Floating-Point Types	47
Fundamental Types in C++	47
Literals	48
Defining Synonyms for Data Types	49
Basic Input/Output Operations	50
Input from the Keyboard	50
Output to the Command Line	50
Formatting the Output	51
Escape Sequences	53
Calculating in C++	55
The Assignment Statement	55
Arithmetic Operations	55
The const Modifier	58
Constant Expressions	58
Program Input	59
Calculating the Result	59
Displaying the Result	60
Calculating a Remainder	61
Modifying a Variable	61
The Increment and Decrement Operators	62
The Sequence of Calculation	65
Operator Precedence	65
Type Conversion and Casting	66
Type Conversion in Assignments	67
Explicit Type Conversion	68
Old-Style Casts	69

The auto Keyword	69
Discovering Types	70
The Bitwise Operators	70
The Bitwise AND	71
The Bitwise OR	72
The Bitwise Exclusive OR	73
The Bitwise NOT	74
The Bitwise Shift Operators	74
Introducing Lvalues and Rvalues	76
Understanding Storage Duration and Scope	77
Automatic Variables	78
Positioning Variable Declarations	80
Global Variables	80
Static Variables	84
Variables with Specific Sets of Values	85
Old Enumerations	85
Type-Safe Enumerations	87
Namespaces	90
Declaring a Namespace	91
Multiple Namespaces	92
Summary	93
CHAPTER 3: DECISIONS AND LOOPS	97
Comparing Values	97
The if Statement	99
Nested if Statements	100
The Extended if Statement	102
Nested if-else Statements	104
Logical Operators and Expressions	106
Logical AND	107
Logical OR	107
Logical NOT	108
The Conditional Operator	109
The switch Statement	111
Unconditional Branching	115
Repeating a Block of Statements	115
What Is a Loop?	116
Variations on the for Loop	118
Using the continue Statement	122
Floating-Point Loop Counters	126

The while Loop	126
The do-while Loop	128
The Range-Based for Loop	129
Nested Loops	130
Summary	133
CHAPTER 4: ARRAYS, STRINGS, AND POINTERS	135
Handling Multiple Data Values of the Same Type	135
Arrays	136
Declaring Arrays	137
Initializing Arrays	140
Using the Range-Based for Loop	142
Character Arrays and String Handling	143
String Input	144
Using the Range-Based for Loop with Strings	146
Multidimensional Arrays	146
Initializing Multidimensional Arrays	147
Indirect Data Access	150
What Is a Pointer?	150
Declaring Pointers	150
The Address-Of Operator	151
Using Pointers	152
The Indirection Operator	152
Why Use Pointers?	152
Initializing Pointers	152
Pointers to char	155
The sizeof Operator	159
Constant Pointers and Pointers to Constants	161
Pointers and Arrays	163
Pointer Arithmetic	164
Using Pointers with Multidimensional Arrays	168
Pointer Notation with Multidimensional Arrays	169
Dynamic Memory Allocation	170
The Free Store, Alias the Heap	170
The new and delete Operators	171
Allocating Memory Dynamically for Arrays	172
Dynamic Allocation of Multidimensional Arrays	175
Using References	176
What Is a Reference?	176
Declaring and Initializing Lvalue References	176

Using References in a Range-Based for Loop	177
Rvalue References	178
Library Functions for Strings	178
Finding the Length of a Null-Terminated String	179
Joining Null-Terminated Strings	179
Copying Null-Terminated Strings	181
Comparing Null-Terminated Strings	182
Searching Null-Terminated Strings	183
Summary	185
CHAPTER 5: INTRODUCING STRUCTURE INTO YOUR PROGRAMS	189
Understanding Functions	189
Why Do You Need Functions?	191
Structure of a Function	191
The Function Header	191
The Function Body	193
The return Statement	193
Alternative Function Syntax	194
Using a Function	194
Function Prototypes	194
Passing Arguments to a Function	198
The Pass-by-Value Mechanism	199
Pointers as Arguments to a Function	200
Passing Arrays to a Function	202
Passing Multidimensional Arrays to a Function	204
References as Arguments to a Function	206
Use of the const Modifier	208
Rvalue Reference Parameters	210
Arguments to main()	212
Accepting a Variable Number of Function Arguments	214
Returning Values from a Function	216
Returning a Pointer	216
A Cast-Iron Rule for Returning Addresses	218
Returning a Reference	219
A Teflon-Coated Rule: Returning References	222
Static Variables in a Function	222
Recursive Function Calls	224
Using Recursion	227
Summary	227

CHAPTER 6: MORE ABOUT PROGRAM STRUCTURE	231
Pointers to Functions	231
Declaring Pointers to Functions	232
A Pointer to a Function as an Argument	235
Arrays of Pointers to Functions	237
Initializing Function Parameters	238
Exceptions	239
Throwing Exceptions	241
Catching Exceptions	242
Rethrowing Exceptions	244
Exception Handling in the MFC	244
Handling Memory Allocation Errors	245
Function Overloading	247
What Is Function Overloading?	247
Reference Types and Overload Selection	250
When to Overload Functions	251
Function Templates	251
Using a Function Template	251
Using the decltype Operator	254
An Example Using Functions	256
Implementing a Calculator	257
Analyzing the Problem	257
Eliminating Blanks from a String	260
How the Function Functions	260
Evaluating an Expression	260
How the Function Functions	262
Getting the Value of a Term	263
How the Function Functions	264
Analyzing a Number	264
How the Function Functions	266
Putting the Program Together	268
How the Function Functions	269
Extending the Program	269
How the Function Functions	271
Extracting a Substring	271
How the Function Functions	273
Running the Modified Program	273
Summary	274

CHAPTER 7: DEFINING YOUR OWN DATA TYPES	277
The struct in C++	277
What Is a struct?	278
Defining a struct	278
Initializing a struct	279
Accessing the Members of a struct	279
IntelliSense Assistance with Structures	283
The struct RECT	285
Using Pointers with a struct	285
Accessing Structure Members through a Pointer	286
The Indirect Member Selection Operator	287
Types, Objects, Classes, and Instances	287
First Class	289
Operations on Classes	289
Terminology	290
Understanding Classes	290
Defining a Class	291
Access Control in a Class	291
Declaring Objects of a Class	291
Accessing the Data Members of a Class	292
Member Functions of a Class	294
Positioning a Member Function Definition	296
Inline Functions	297
Class Constructors	298
What Is a Constructor?	298
The Default Constructor	300
Default Parameter Values	303
Using an Initialization List in a Constructor	305
Making a Constructor Explicit	306
Private Members of a Class	307
Accessing private Class Members	310
The friend Functions of a Class	310
Placing friend Function Definitions Inside the Class	312
The Default Copy Constructor	313
The Pointer this	314
const Objects	317
const Member Functions of a Class	318
Member Function Definitions Outside the Class	319
Arrays of Objects	320

Static Members of a Class	322
Static Data Members	322
Static Function Members of a Class	325
Pointers and References to Objects	325
Pointers to Objects	326
References to Class Objects	328
Implementing a Copy Constructor	329
Summary	330
CHAPTER 8: MORE ON CLASSES	333
Class Destructors	334
What Is a Destructor?	334
The Default Destructor	334
Destructors and Dynamic Memory Allocation	337
Implementing a Copy Constructor	340
Sharing Memory Between Variables	342
Defining Unions	343
Anonymous Unions	344
Unions in Classes and Structures	345
Operator Overloading	345
Implementing an Overloaded Operator	346
Implementing Full Support for Comparison Operators	350
Overloading the Assignment Operator	354
Fixing the Problem	355
Overloading the Addition Operator	359
Overloading the Increment and Decrement Operators	364
Overloading the Function Call Operator	365
The Object Copying Problem	366
Avoiding Unnecessary Copy Operations	367
Applying Rvalue Reference Parameters	370
Named Objects are Lvalues	372
Default Class Members	377
Class Templates	378
Defining a Class Template	379
Template Member Functions	381
Creating Objects from a Class Template	382
Class Templates with Multiple Parameters	386
Templates for Function Objects	388
Perfect Forwarding	388
Using Classes	392
The Idea of a Class Interface	392
Defining the Problem	393

Implementing the CBox Class	393
Comparing CBox Objects	395
Combining CBox Objects	396
Analyzing CBox Objects	398
Organizing Your Program Code	412
Naming Program Files	413
Library Classes for Strings	414
Creating String Objects	414
Concatenating Strings	416
Accessing and Modifying Strings	420
Comparing Strings	424
Searching Strings	428
Summary	437
CHAPTER 9: CLASS INHERITANCE AND VIRTUAL FUNCTIONS	441
Object-Oriented Programming Basics	441
Inheritance in Classes	443
What Is a Base Class?	443
Deriving Classes from a Base Class	444
Access Control Under Inheritance	447
Constructor Operation in a Derived Class	450
Declaring Protected Class Members	454
The Access Level of Inherited Class Members	457
The Copy Constructor in a Derived Class	458
Preventing Class Derivation	461
Class Members as Friends	462
Friend Classes	464
Limitations on Class Friendship	464
Virtual Functions	464
What Is a Virtual Function?	467
Ensuring Correct Virtual Function Operation	469
Preventing Function Overriding	469
Using Pointers to Class Objects	470
Using References with Virtual Functions	472
Incomplete Class Declaration	473
Pure Virtual Functions	473
Abstract Classes	474
Indirect Base Classes	477
Virtual Destructors	479
Casting Between Class Types	483
Nested Classes	483
Summary	487

CHAPTER 10: THE STANDARD TEMPLATE LIBRARY	491
What Is the Standard Template Library?	491
Containers	492
Allocators	494
Comparators	494
Container Adapters	495
Iterators	495
Iterator Categories	495
SCARY Iterators	497
std::begin() and std::end() Functions	497
Smart Pointers	497
Using unique_ptr Objects	498
Using shared_ptr Objects	499
Accessing the Raw Pointer in a Smart Pointer	500
Casting SmartPointers	500
Algorithms	500
Function Objects in the STL	501
Function Adapters	502
The Range of STL Containers	502
Sequence Containers	502
Creating Vector Containers	504
The Capacity and Size of a Vector Container	507
Accessing the Elements in a Vector	512
Inserting and Deleting Elements in a Vector	513
Insert Operations	513
Emplace Operations	514
Erase Operations	515
Swap and Assign Operations	515
Storing Class Objects in a Vector	516
Sorting Vector Elements	522
Storing Pointers in a Vector	523
Array Containers	526
Double-Ended Queue Containers	529
Using List Containers	533
Adding Elements to a List	533
Accessing Elements in a List	535
Sorting List Elements	535
Other Operations on Lists	538
Using forward_list Containers	544
Using Other Sequence Containers	546

Queue Containers	546
Priority Queue Containers	549
Stack Containers	555
The tuple Class Template	557
Associative Containers	561
Using Map Containers	561
Storing Objects	562
Accessing Objects	564
Other Map Operations	565
Using a Multimap Container	574
More on Iterators	575
Using Input Stream Iterators	575
Using Inserter Iterators	578
Using Output Stream Iterators	580
More on Function Objects	582
More on Algorithms	584
Type Traits and Static Assertions	587
Lambda Expressions	588
The Capture Clause	589
Capturing Specific Variables	590
Templates and Lambda Expressions	591
Naming a Lambda Expression	595
Summary	598
CHAPTER 11: WINDOWS PROGRAMMING CONCEPTS	601
Windows Programming Basics	602
Elements of a Window	602
Windows Programs and the Operating System	604
Event-Driven Programs	605
Windows Messages	605
The Windows API	605
Windows Data Types	606
Notation in Windows Programs	607
The Structure of a Windows Program	608
The WinMain() Function	609
Specifying a Program Window	611
Creating a Program Window	613
Initializing the Program Window	615
Dealing with Windows Messages	616
A Complete WinMain() Function	620
How It Works	621

Processing Windows Messages	621
The WindowProc() Function	622
Decoding a Windows Message	622
Ending the Program	625
A Complete WindowProc() Function	625
How It Works	626
The Microsoft Foundation Classes	627
MFC Notation	627
How an MFC Program Is Structured	628
Summary	632
CHAPTER 12: WINDOWS PROGRAMMING WITH THE MICROSOFT FOUNDATION CLASSES (MFC)	635
The MFC Document/View Concept	636
What Is a Document?	636
Document Interfaces	636
What Is a View?	636
Linking a Document and Its Views	637
Document Templates	638
Document Template Classes	638
Your Application and MFC	639
Creating MFC Applications	640
Creating an SDI Application	641
MFC Application Wizard Output	645
Viewing Project Files	647
Viewing Classes	647
The Class Definitions	648
Creating an Executable Module	653
Running the Program	653
How the Program Works	654
Creating an MDI Application	655
Running the Program	656
Summary	657
CHAPTER 13: WORKING WITH MENUS AND TOOLBARS	659
Communicating with Windows	659
Understanding Message Maps	660
Message Handler Definitions	661
Message Categories	662
Handling Messages in Your Program	663
How Command Messages Are Processed	664

Extending the Sketcher Program	664
Elements of a Menu	665
Creating and Editing Menu Resources	665
Adding a Menu Item to the Menu Bar	666
Adding Items to the Element Menu	667
Modifying Existing Menu Items	667
Completing the Menu	668
Adding Menu Message Handlers	668
Choosing a Class to Handle Menu Messages	670
Creating Menu Message Handlers	670
Implementing Menu Message Handlers	672
Adding Members to Store Color and Element Mode	672
Defining Element and Color Types	674
Initializing the Color and Element Type Members	675
Implementing Menu Command Message Handlers	675
Running the Extended Example	676
Adding Menu Update Message Handlers	676
Coding a Command Update Handler	677
Exercising the Update Handlers	678
Adding Toolbar Buttons	678
Editing Toolbar Button Properties	680
Exercising the Toolbar Buttons	681
Adding Tooltips	682
Summary	682
CHAPTER 14: DRAWING IN A WINDOW	685
Basics of Drawing in a Window	685
The Window Client Area	686
The Windows Graphical Device Interface	686
Working with a Device Context	687
Mapping Modes	687
The MFC Drawing Mechanism	689
The View Class in Your Application	689
The OnDraw() Member Function	690
The CDC Class	691
Displaying Graphics	691
Drawing in Color	695
Drawing Graphics in Practice	700
Programming for the Mouse	702
Messages from the Mouse	703
WM_LBUTTONDOWN	704

WM_MOUSEMOVE	704
WM_LBUTTONDOWN	704
Mouse Message Handlers	704
Drawing Using the Mouse	706
Getting the Client Area Redrawn	708
Defining Element Classes	709
The CElement Class	713
The CLine Class	714
The CRectangle Class	717
The CCircle Class	719
The CCurve Class	722
Completing the Mouse Message Handlers	724
Drawing a Sketch	731
Running the Example	732
Capturing Mouse Messages	733
Summary	734
CHAPTER 15: IMPROVING THE VIEW	739
Sketcher Limitations	739
Improving the View	740
Updating Multiple Views	740
Scrolling Views	742
Logical Coordinates and Client Coordinates	744
Dealing with Client Coordinates	745
Using MM_ENGLISH Mapping Mode	747
Deleting and Moving Elements	748
Implementing a Context Menu	748
Associating a Menu with a Class	750
Checking Context Menu Items	751
Identifying an Element under the Cursor	752
Exercising the Context Menus	754
Highlighting Elements	754
Drawing Highlighted Elements	757
Exercising the Highlights	757
Implementing Move and Delete	758
Deleting an Element	758
Moving an Element	758
Updating Other Views	761
Getting the Elements to Move Themselves	762
Dropping the Element	764
Exercising the Application	765

Dealing with Masked Elements	765
Summary	767
CHAPTER 16: WORKING WITH DIALOGS AND CONTROLS	769
Understanding Dialogs	770
Understanding Controls	770
Creating a Dialog Resource	771
Adding Controls to a Dialog	771
Testing the Dialog	773
Programming for a Dialog	773
Adding a Dialog Class	773
Modal and Modeless Dialogs	774
Displaying a Dialog	775
Displaying the Dialog	776
Code to Close the Dialog	776
Supporting the Dialog Controls	777
Initializing Dialog Controls	778
Handling Radio Button Messages	779
Completing Dialog Operations	780
Adding Pen Widths to the Document	780
Adding Pen Widths to the Elements	781
Creating Elements in the View	783
Exercising the Dialog	784
Using a Spin Button Control	785
Adding a Scale Menu Item and Toolbar Button	785
Creating the Spin Button	786
The Controls' Tab Sequence	786
Generating the Scale Dialog Class	787
Dialog Data Exchange and Validation	788
Initializing the Dialog	789
Displaying the Spin Button	790
Using the Scale Factor	791
Scalable Mapping Modes	791
Setting the Document Size	793
Setting the Mapping Mode	793
Implementing Scrolling with Scaling	795
Setting Up the Scrollbars	796
Working with Status Bars	797
Adding a Status Bar to a Frame	797
Creating Status Bar Panes	798
Updating the Status Bar	800

The CString Class	801
Using an Edit Box Control	802
Creating an Edit Box Resource	803
Creating the Dialog Class	804
Adding the Text Menu Item	805
Defining a Text Element	806
Implementing the CText Class	807
The CText Constructor	807
Creating a Text Element	807
Drawing a CText Object	809
Moving a CText Object	810
Summary	812
CHAPTER 17: STORING AND PRINTING DOCUMENTS	815
Understanding Serialization	815
Serializing a Document	816
Serialization in the Document Class Definition	816
Serialization in the Document Class Implementation	817
The Serialize() Function	818
The CArchive Class	818
Functionality of CObject-Based Classes	820
The Macros that Add Serialization to a Class	821
How Serialization Works	821
How to Implement Serialization for a Class	823
Applying Serialization	823
Recording Document Changes	823
Serializing the Document	825
Serializing the Element Classes	827
The Serialize() Functions for the Element Classes	829
Exercising Serialization	831
Printing a Document	833
The Printing Process	833
The CPrintInfo Class	835
Implementing Multipage Printing	837
Getting the Overall Document Size	838
Storing Print Data	838
Preparing to Print	839
Cleaning Up after Printing	841
Preparing the Device Context	841
Printing the Document	842
Getting a Printout of the Document	846
Summary	847

CHAPTER 18: PROGRAMMING WINDOWS 8 APPS	849
Understanding Windows 8 Apps	850
Developing Windows 8 Apps	851
Windows Runtime Concepts	852
WinRT Namespaces	852
WinRT Objects	852
C++ Component Extensions (C++/CX)	853
C++/CX Namespaces	853
Defining WinRT Class Types	854
Variables of Ref Class Types	857
Accessing Members of a Ref Class Object	857
Event Handler Functions	858
Casting Ref Class References	858
The eXtensible Application Markup Language (XAML)	859
XAML Elements	859
UI Elements in XAML	861
Attached Properties	864
Parents and Children	865
Control Elements	865
Layout Elements	865
Handling Events for UI Elements	866
Creating a Windows 8 App	867
Application Files	867
Defining the User Interface	868
Creating the Title	870
Adding Game Controls	872
Creating a Grid to Contain the Cards	874
Defining a Card	875
Creating a Card	875
Adding Event Handling	877
Creating All the Cards	878
Implementing Game Operations	879
Defining the Card Class	880
Adding Data Members to the MainPage Class	881
Adding Function Members	882
Initialize the MainPage Object	883
Initializing the Card Pack	884
Setting Up the Child Elements of cardGrid	884
Initializing the Game	886
Shuffling the Cards	889

Highlighting the UI Cards	889
Handling Card Back Events	890
Handling Shape Events	892
Recognizing a Win	894
Handling Game Control Button Events	895
Scaling UI Elements	897
Transitions	899
Application Startup Transitions	899
Storyboard Animations	900
Summary	902
<i>INDEX</i>	905

INTRODUCTION

WELCOME TO *Ivor Horton's Beginning Visual C++ 2012*. With this book, you can become an effective C++ programmer using Microsoft's latest application-development system, Visual Studio 2012. I aim to teach you the C++ programming language, and then how to apply C++ in the development of your own Windows applications. Along the way, you will also learn about many of the exciting new capabilities introduced by this latest version of Visual C++.

Visual C++ 2012 comes as part of any of the editions of the Microsoft development environment Visual Studio 2012. When I refer to Visual C++ in the rest of the book, I mean the Visual C++ 2012 capability that comes as part of Visual Studio 2012.

WHO THIS BOOK IS FOR

This book is for anyone who wants to learn how to write C++ applications for the Microsoft Windows operating system using Visual C++. I make no assumptions about prior knowledge of any particular programming language, so there are no prerequisites other than some aptitude for programming and sufficient enthusiasm and commitment for learning to program in C++ to make it through this book. This tutorial is for you if:

- You are a newcomer to programming and sufficiently keen to jump into the deep end with C++. To be successful, you need to have at least a rough idea of how your computer works, and it will be helpful if you understand the way in which the memory is organized and how data and instructions are stored.
- You have a little experience of programming in some other language, such as BASIC, and you are keen to learn C++ and develop practical Microsoft Windows programming skills.
- You have some experience in C or C++, but not in a Microsoft Windows context and want to extend your skills to program for the Windows environment using the latest tools and technologies.

WHAT THIS BOOK COVERS

The first part of the book teaches you the essentials of C++ programming using the C++ language supported by Visual Studio 2012 through a detailed, step-by-step tutorial. You'll learn the syntax and use of the ISO/IEC C++ language and gain experience and confidence in applying it in a practical context through an extensive range of working examples. There are also exercises that you can use to test your knowledge, with solutions available for download if you get stuck.

Of course, the language tutorial also introduces and demonstrates the use of the C++ standard library facilities you are most likely to need. You'll add to your knowledge of the standard libraries incrementally as you progress through the C++ language. Additionally, you will learn about the powerful tools provided by the Standard Template Library (STL).

Once you are confident in applying C++, you move on to Windows programming. You will learn how to develop Windows applications using the Microsoft Foundation Classes (MFC) by creating a substantial working application of more than 2000 lines of code. You develop the application over several chapters, utilizing a broad range of user interface capabilities provided by the MFC. You also learn the essentials of programming applications using the Windows 8 UI and develop a working example.

HOW THIS BOOK IS STRUCTURED

The book is structured as follows:

- Chapter 1 introduces you to the basic concepts you need to understand for programming in C++ together with the main ideas embodied in the Visual C++ development environment. It describes how you use the capabilities of Visual C++ for creating the various kinds of C++ applications you'll learn about in the rest of the book.
- Chapters 2 through 9 teach you the C++ language. You start with simple procedural program examples and progress to learning about classes and object-oriented programming.
- Chapter 10 teaches you how you use the Standard Template Library (STL). The STL is a powerful and extensive set of tools for organizing and manipulating data in your C++ programs. The STL is application-neutral, so you will be able to apply it in a wide range of contexts.
- Chapter 11 discusses how Microsoft Windows desktop applications are structured and describes and demonstrates the essential elements that are present in every desktop application written for the Windows operating system. The chapter explains elementary examples of how Windows applications work, with programs that use C++ with the Windows API and with the MFC.
- Chapters 12 through 17 teach you Windows desktop application programming. You learn to write C++ Windows applications using the MFC for building a GUI. You learn how you create and use common controls to build the graphical user interface for your application, and how you handle the events that result from user interaction with your program. In addition to the techniques you learn for building a GUI, the application that you develop also shows you how you handle printing and how you can save your application data on disk.
- Chapter 18 introduces the fundamental ideas involved in writing applications for Windows 8.

All chapters in the book include working examples that demonstrate the programming techniques discussed. Every chapter concludes with a summary of the key points that were covered, and most chapters include a set of exercises at the end that you can attempt, to apply what you have learned.

Solutions to the exercises, together with all the code from the book, are available for download from the publisher's website.

WHAT YOU NEED TO USE THIS BOOK

There are several versions of Visual Studio 2012 and they each have a different range of capabilities. You can only develop applications using the Windows 8 UI if you have Visual Studio 2012 installed with Windows 8. Here's what you can use to work with various parts of the book:

- If you have a free version of Visual Studio 11 installed with Windows 8, you can work with all the examples and exercises in the book. The lowest-cost fee version of Visual Studio 2012 is the Professional Edition. This edition or better installed with Windows 8 is fine for the whole book.
- If you have Visual Studio 2012 Professional Edition or better installed with Windows 7, you can work with all the examples and exercises in Chapters 1 to 17, but not Chapter 18. Chapter 18 is about applications that make use of the Windows 8 UI and this requires Visual Studio 2012 to be installed with Windows 8.

There is a free Visual Studio 2012 Express Edition for Windows 8, which is not sufficient to run many of the examples in the book. None of the examples in Chapters 12 to 17 can be compiled with the Visual Studio 2012 Express Edition.

CONVENTIONS

To help you get the most from the text and keep track of what's happening, we've used a number of conventions throughout the book.

TRY IT OUT

The *Try It Out* is an exercise you should work through, following the text in the book.

1. They usually consist of a set of steps.
2. Each step has a number.
3. Follow the steps through with your copy of the program.

How It Works

After each *Try It Out*, the code you've typed will be explained in detail.

WARNING Boxes like this one hold important, not-to-be forgotten information that is directly relevant to the surrounding text.

NOTE Notes, tips, hints, tricks, and asides to the current discussion are offset and placed in italics like this.

As for styles in the text:

- We *highlight* new terms and important words when we introduce them.
- We show keyboard strokes like this: Ctrl+A.
- We show filenames, URLs, and code within the text like so: `persistence.properties`.
- We present code in two different ways:

We use a monofont type with no highlighting for most code examples.

We use bold highlighting to emphasize code that is of particular importance in the present context.

SOURCE CODE

As you work through the examples in this book, you may choose either to type in all the code manually, or to use the source code files that accompany the book. The code downloads for the complete examples in the book are located at www.wrox.com/remtitle.cgi?isbn=9781118368084 on the Download Code tab.

NOTE Because many books have similar titles, you may find it easiest to search by ISBN; this book's ISBN is 978-0-470-36808-4.

Once you download the code, just decompress it with your favorite compression tool. Alternately, you can go to the main Wrox code download page at www.wrox.com/dynamic/books/download.aspx to see the code available for this book and all other Wrox books.

EXERCISES

Many of the chapters have a set of exercises for you to test your knowledge. I encourage you to try all of these. If you get stuck you can download solutions to all of these exercises from www.wrox.com/remtitle.cgi?isbn=9781118368084.

ERRATA

We make every effort to ensure that there are no errors in the text or in the code. However, no one is perfect, and mistakes do occur. If you find an error in one of our books, like a spelling mistake or faulty piece of code, we would be very grateful for your feedback. By sending in errata, you may save another reader hours of frustration, and at the same time, you will be helping us provide even higher quality information.

To find the errata page for this book, go to <http://www.wrox.com> and locate the title using the Search box or one of the title lists. Then, on the book's detail page, click the Book Errata link. On this page, you can view all errata that has been submitted for this book and posted by Wrox editors. A complete book list, including links to each book's errata, is also available at www.wrox.com/mis.../booklist.shtml.

If you don't spot "your" error on the Book Errata page, go to www.wrox.com/contact/techsupport.shtml and complete the form there to send us the error you have found. We'll check the information and, if appropriate, post a message to the book's errata page and fix the problem in subsequent editions of the book.

P2P.WROX.COM

For author and peer discussion, join the P2P forums at p2p.wrox.com. The forums are a web-based system for you to post messages relating to Wrox books and related technologies and interact with other readers and technology users. The forums offer a subscription feature to e-mail you topics of interest of your choosing when new posts are made to the forums. Wrox authors, editors, other industry experts, and your fellow readers are present on these forums.

At <http://p2p.wrox.com>, you will find a number of different forums that will help you, not only as you read this book, but also as you develop your own applications. To join the forums, just follow these steps:

- 1.** Go to p2p.wrox.com and click the Register link.
- 2.** Read the terms of use and click Agree.
- 3.** Complete the required information to join, as well as any optional information you wish to provide, and click Submit.
- 4.** You will receive an e-mail with information describing how to verify your account and complete the joining process.

NOTE You can read messages in the forums without joining P2P, but in order to post your own messages, you must join.

Once you join, you can post new messages and respond to messages other users post. You can read messages at any time on the web. If you would like to have new messages from a particular forum e-mailed to you, click the Subscribe to this Forum icon by the forum name in the forum listing.

For more information about how to use the Wrox P2P, be sure to read the P2P FAQs for answers to questions about how the forum software works, as well as many common questions specific to P2P and Wrox books. To read the FAQs, click the FAQ link on any P2P page.

1

Programming with Visual C++

WHAT YOU WILL LEARN IN THIS CHAPTER:

- What the principal components of Visual C++ are
- What solutions and projects are and how you create them
- About console programs
- How to create and edit a program
- How to compile, link, and execute C++ console programs
- How to create and execute basic Windows programs

WROX.COM CODE DOWNLOADS FOR THIS CHAPTER

You can find the wrox.com code downloads for this chapter on the Download Code tab at www.wrox.com/remtitle.cgi?isbn=9781118368084. The code is in the Chapter 1 download and individually named according to the names throughout the chapter.

LEARNING WITH VISUAL C++

Windows programming isn't difficult. Microsoft Visual C++ makes it remarkably easy, as you'll see throughout the course of this book. There's just one obstacle in your path: Before you get to the specifics of Windows programming, you have to be thoroughly familiar with the capabilities of the C++ programming language, particularly the object-oriented capabilities. Object-oriented techniques are central to the effectiveness of all the tools provided by Visual C++ for Windows programming, so it's essential that you gain a good understanding of them. That's exactly what this book provides.

This chapter gives you an overview of the essential concepts involved in programming applications in C++. You'll take a rapid tour of the integrated development environment (IDE) that comes with Visual C++. The IDE is straightforward and generally intuitive in its operation, so you'll be able to pick up most of it as you go along. The best way to get familiar with it is to work through the process of creating, compiling, and executing a simple program. So power up your PC, start Windows, load the mighty Visual C++, and begin your journey.

WRITING C++ APPLICATIONS

You have tremendous flexibility in the types of applications and program components that you can develop with Visual C++. Applications that you can develop fall into two broad categories: *desktop applications* and *Windows 8 apps*. Desktop applications are the applications that you know and love; they have an application window that typically has a menu bar and a toolbar and frequently a status bar at the bottom of the application window. This book focuses primarily on desktop applications.

Windows 8 apps are different from desktop applications. They have a user interface that is completely different from desktop applications. The focus is on the content where the user interacts directly with the data, rather than interacting with controls such as menu items and toolbar buttons.

Once you have learned C++, this book concentrates on using the Microsoft Foundation Classes (MFC) with C++ for building desktop applications. The application programming interface (API) for Windows desktop applications is referred to as *Win32*. Win32 has a long history and was developed long before the object-oriented programming paradigm emerged, so it has none of the object-oriented characteristics that would be expected if it were written today. The MFC consists of a set of C++ classes that encapsulate the Win32 API for user interface creation and control and greatly eases the process of program development. You are not obliged to use the MFC, though. If you want the ultimate in performance you can write your C++ code to access the Windows API directly, but it certainly won't be as easy.

Figure 1-1 shows the basic options you have for developing C++ applications.

Figure 1-1 is a simplified representation of what is involved. Desktop applications can target Windows 7, Windows 8, or Windows Vista. Windows 8 apps execute only with Windows 8 and you must have Visual Studio 2012 installed under Windows 8 to develop them. Windows 8 apps communicate with the operating system through the Windows Runtime, WinRT. I'll introduce you to programming Windows 8 applications in Chapter 18.




FIGURE 1-1

LEARNING DESKTOP APPLICATIONS PROGRAMMING

There are always two basic aspects to interactive desktop applications executing under Windows: You need code to create the *graphical user interface* (GUI) with which the user interacts, and you need code to process these interactions to provide the functionality of the application. Visual C++ provides you with a great deal of assistance in both aspects. As you'll see later in this chapter, you can create a working Windows program with a GUI without writing any code at all. All the basic code to create the GUI can be generated automatically by Visual C++. Of course, it's essential to understand how this automatically generated code works because you need to extend and modify it to make the application do what you want. To do that you need a comprehensive understanding of C++.

For this reason you'll first learn C++ without getting involved in Windows programming considerations. After you're comfortable with C++ you'll learn how to develop fully fledged Windows applications. This means that while you are learning C++, you'll be working with programs that involve only command line input and output. By sticking to this rather limited input and output capability, you'll be able to concentrate on the specifics of how the C++ language works and avoid the inevitable complications involved in GUI building and control. Once you are comfortable with C++ you'll find that it's an easy and natural progression to applying C++ to the development of Windows application programs.

NOTE As I'll explain in Chapter 18, Windows 8 apps are different. You specify the GUI in XAML, and the XAML is used to generate the C++ program code for GUI elements.

Learning C++

Visual C++ supports the C++ language defined by the most recent ISO/IEC C++ standard that was published in 2011. The standard is defined in the document ISO/IEC 14882:2011 and commonly referred to as C++ 11. The Visual C++ compiler does not support all the new language features introduced by this latest standard, just some of the most commonly used features, but it will surely be extended over time. Programs that you write in standard C++ can be ported from one system environment to another reasonably easily, although the library functions that a program uses — particularly those related to building a graphical user interface — are a major determinant of how easy or difficult it will be. ISO/IEC standard C++ is the first choice of a great many professional program developers because it is so widely supported, and because it is one of the most powerful programming languages available today.

Chapters 2 through 9 of this book teach you the C++ language and introduce some of the most commonly used C++ standard library facilities along the way. Chapter 10 explains how you can use the Standard Template Library (STL) for C++ for managing collections of data.

Console Applications

Visual C++ *console applications* enable you to write, compile, and test C++ programs that have none of the baggage required for Windows programs. These programs are called console applications because you communicate with them through the keyboard and the screen in character mode, so they are essentially character-based, command-line programs.

When you write console applications, it might seem as if you are being sidetracked from the main objective of programming applications for Windows, but when it comes to learning C++ it's by far the best way to proceed in my view. There's a lot of code in even a simple Windows program, and it's very important not to be distracted by the complexities of Windows when learning the ins and outs of the C++ language. In the early chapters of the book that are concerned with how C++ works, you'll spend time walking with a few lightweight console applications before you get to run with the heavyweight sacks of code in the world of Windows.

Windows Programming Concepts

The project creation facilities provided with Visual C++ can generate skeleton code for a wide variety of C++ application programs automatically. A Windows program has a different structure from that of the typical console program that you execute from the command line and it's more complicated. In a console program you can get user input from the keyboard and write output back to the command line directly, and that is essentially it. A Windows application can access the input and output facilities of the computer only by way of functions supplied by the host environment; no direct access to the hardware resources is permitted. Several programs can be active at one time under Windows, so the operating system has to determine which application a given raw input such as a mouse click or the pressing of a key on the keyboard is destined for, and signal the program concerned accordingly. Thus, the Windows operating system always has primary control of all communications with the user.

The nature of the interface between a user and a Windows desktop application is such that a wide range of different inputs is usually possible at any given time. A user may select any of a number of menu options, click on one of several toolbar buttons, or click the mouse somewhere in the application window. A well-designed Windows application has to be prepared to deal with any of the possible types of input at any time because there is no way of knowing in advance which type of input is going to occur. These user actions are received by the operating system in the first instance, and are all regarded by Windows as *events*. An event that originates with the user interface for your application will typically result in a particular piece of your program code being executed. How program execution proceeds is therefore determined by the sequence of user actions. Programs that operate in this way are referred to as *event-driven programs*, and are different from traditional procedural programs that have a single order of execution. Input to a procedural program is controlled by the program code and can occur only when the program permits it; therefore, a Windows program consists primarily of pieces of code that respond to events caused by the action of the user, or by Windows itself. This sort of program structure is illustrated in Figure 1-2.




FIGURE 1-2

Each block within the Desktop Application block in Figure 1-2 represents a piece of code written specifically to deal with a particular event. The program may appear to be somewhat fragmented because of the disjointed blocks of code, but the primary factor welding the program into a whole is the Windows operating system itself. You can think of your program as customizing Windows to provide a particular set of capabilities.

Of course, the modules servicing external events such as the selection of a menu or a mouse click, all typically have access to a common set of application-specific data in a particular program. This data contains information that relates to what the program is about — for example, blocks of text recording scoring records for a player in a program aimed at tracking how your baseball team is doing — as well as information about some of the events that have occurred during execution of the program. This shared collection of data allows various parts of the program that look independent to communicate and operate in a coordinated and integrated fashion. I will go into this in much more detail later in the book.

Even an elementary Windows program involves several lines of code, and with Windows programs generated by the application wizards that come with Visual C++, “several” turns out to be “very many.” To simplify the process of understanding how C++ works, you need a context that is as uncomplicated as possible and at the same time has the tools to make it easy to navigate around sacks of code. Fortunately, Visual C++ comes with an environment that is designed specifically for the purpose.

WHAT IS THE INTEGRATED DEVELOPMENT ENVIRONMENT?

The integrated development environment (IDE) that comes with Visual C++ is a completely self-contained environment for creating, compiling, linking, and testing your C++ programs. It also happens to be a great environment in which to learn C++ (particularly when combined with a great book).

Visual C++ incorporates a range of fully integrated tools designed to make the whole process of writing C++ programs easy. You will see something of these in this chapter, but rather than grind through a boring litany of features and options in the abstract, you can first take a look at the basics to get a view of how the IDE works and then pick up the rest in context as you go along.

The fundamental parts of Visual C++, provided as part of the IDE, are the editor, the compiler, the linker, and the libraries. These are the basic tools that are essential to writing and executing a C++ program.

The Editor

The editor provides an interactive environment in which to create and edit C++ source code. As well as the usual facilities, such as cut and paste, which you are certainly already familiar with, the editor also provides color cues to differentiate between various language elements. The editor automatically recognizes fundamental words in the C++ language and assigns a color to them according to what they are. This not only helps to make your code more readable, but also provides a clear indicator of when you make errors in keying such words. Another very helpful feature is *IntelliSense*. IntelliSense analyzes the code as you enter it, and underlines anything that is incorrect with a red squiggle. It can also provide prompts where the options for what you need to enter next in the code can be determined.

NOTE *IntelliSense doesn't just work with C++. It works with XAML too.*

The Compiler

You execute the compiler when you have entered the C++ code for your program. The compiler converts your source code into *object code*, and detects and reports errors in the compilation process. The compiler can detect a wide range of errors caused by invalid or unrecognized program code, as well as structural errors, such as parts of a program that can never be executed. The object code output from the compiler is stored in files called *object files* that have names with the extension .obj.

The Linker

The linker combines the various modules generated by the compiler from source code files, adds required code modules from program libraries that are supplied as part of C++, and welds everything into an executable whole, usually in the form of an .exe file. The linker can also detect and report errors — for example, if part of your program is missing, or a nonexistent library component is referenced.

The Libraries

A *library* is simply a collection of prewritten routines that supports and extends the C++ language by providing standard professionally produced code units that you can incorporate into your programs to carry out common operations. The operations implemented by the various libraries

provided by Visual C++ greatly enhance productivity by saving you the effort of writing and testing the code for such operations yourself.

The *Standard C++ Library* defines a basic set of facilities that are common to all ISO/IEC standard-conforming C++ compilers. It contains a wide range of commonly used routines, including numerical functions, such as the calculation of square roots and the evaluation of trigonometrical functions; character- and string-processing functions, such as the classification of characters and the comparison of character strings; and many others. It also defines data types and standard templates for generating customized data types and functions. You'll get to know quite a number of these as you develop your knowledge of C++.

Window-based desktop applications are supported by a library called the *Microsoft Foundation Classes* (MFC). The MFC greatly reduces the effort needed to build the GUI for an application. (You'll see a lot more of the MFC when you finish exploring the nuances of the C++ language.)

USING THE IDE

All program development and execution in this book is performed from within the IDE. When you start Visual C++ you'll see an application window similar to that shown in Figure 1-3.




FIGURE 1-3

The pane to the left in Figure 1-3 is the *Solution Explorer window*, the top right pane presently showing the Start page is the *Editor window*, and the tab visible in the pane at the bottom is the *Output window*. The Solution Explorer window enables you to navigate through your program files and display their contents in the Editor window, and to add new files to your program. The Solution Explorer window can display other tabs (only three are shown in Figure 1-3), and you can select which tabs are to be displayed from the View menu. The Editor window is where you enter and modify source code and other components of your application. The Output window displays the output from build operations in which a project is compiled and linked. You can choose to display other windows by selecting from the View menu.

Note that a window can generally be undocked from its position in the Visual C++ application window. Just right-click the title bar of the window you want to undock and select Float from the pop-up menu. In general, I will show windows in their undocked state in the book. You can restore a window to its docked state by right-clicking its title bar and selecting Dock from the pop-up or by dragging it with the left mouse button down to the position that you want in the application window.

Toolbar Options

You can choose which toolbars are displayed in your Visual C++ window by right-clicking in the toolbar area. The range of toolbars in the list depends on which edition of Visual Studio 2012 you have installed. A pop-up menu with a list of toolbars (Figure 1-4) appears, and the toolbars currently displayed have checkmarks alongside them.

This is where you decide which toolbars are visible at any one time. You can make your set of toolbars the same as those shown in Figure 1-3 by making sure the Build, Debug, Formatting, Layout, Standard, and Text Editor menu items are selected. Clicking a toolbar in the list checks it if it is deselected, and results in its being displayed; clicking a toolbar that is selected/deselects it and hides the toolbar.




FIGURE 1-4

NOTE A toolbar won't necessarily display all the buttons that are available for it. You can add or remove buttons for a toolbar by clicking the down arrow that appears at the right of the button set. The buttons in the TextEditor toolbar that indent and unindent a set of highlighted statements are particularly useful, as are the buttons that comment out or uncomment a highlighted set of statements.

You don't need to clutter up the application window with all the toolbars you think you might need at some time. Some toolbars appear automatically when required, so you'll probably find that the default toolbar selections are perfectly adequate most of the time. As you develop your applications, from time to time you might think it would be more convenient to have access to toolbars that aren't displayed. You can change the set of visible toolbars whenever it suits you by right-clicking in the toolbar area and choosing from the context menu.

NOTE As in many other Windows applications, the toolbars that make up Visual C++ come complete with tooltips. Just let the mouse pointer linger over a toolbar button for a second or two, and a white label will display the function of that button.

Dockable Toolbars

A *dockable toolbar* is one that you can move around to position it at a convenient place in the window. You can arrange for any of the toolbars to be docked at any of the four sides of the application window. If you right-click in the toolbar area and select Customize from the pop-up, the Customize dialog will be displayed. You can choose where a particular toolbar is docked by selecting it and clicking the Modify Selection button. You can then choose from the drop-down list to dock the toolbar where you want. Figure 1-5 shows how the dialog looks after the user selects the Build toolbar on the left and clicks the Modify Selection drop-down list.




FIGURE 1-5

You'll recognize many of the toolbar icons that Visual C++ uses from other Windows applications, but you may not appreciate exactly what these icons do in the context of Visual C++, so I'll describe them as we use them.

Because you'll use a new project for every program you develop, looking at what exactly a project is and understanding how the mechanism for defining a project works is a good place to start finding out about Visual C++.

Documentation

There will be plenty of occasions when you'll want to find out more information about Visual C++ and its features and options. Press Ctrl+F1 to access the product documentation. With the cursor on elements in your code that are part of the C++ language or a standard library item, pressing F1 will usually open browser window showing documentation for the element. The Help menu also provides various routes into the documentation, as well as access to program samples and technical support.

Projects and Solutions

A *project* is a container for all the things that make up a program of some kind — it might be a console program, a window-based program, or some other kind of program — and it usually consists of one or more source files containing your code, plus possibly other files containing auxiliary data. All the files for a project are stored in the *project folder*; detailed information about the project is stored in an XML file with the extension .vcxproj, also in the project folder. The project folder also contains other folders that are used to store the output from compiling and linking your project.

The idea of a *solution* is expressed by its name, in that it is a mechanism for bringing together one or more programs and other resources that represent a solution to a particular data-processing problem. For example, a distributed order-entry system for a business operation might be composed of several different programs that could each be developed as a project within a single solution; therefore, a solution is a folder in which all the information relating to one or more projects is stored, and one or more project folders are subfolders of the solution folder. Information about the projects in a solution is stored in two files with the extensions .sln and .suo, respectively. When you create a project a new solution is created automatically unless you elect to add the project to an existing solution.

When you create a project along with a solution, you can add further projects to the same solution. You can add any kind of project to an existing solution, but you will usually add only a project related in some way to the existing project, or projects, in the solution. Generally, unless you have a good reason to do otherwise, each of your projects should have its own solution. Each example you create with this book will be a single project within its own solution.

Defining a Project

The first step in writing a Visual C++ program is to create a project for it using the File \Rightarrow New \Rightarrow Project menu option from the main menu or by pressing Ctrl+Shift+N; you can also simply click New Project... on the Start page. As well as containing files that define all the code and any other data that makes up your program, the project XML file in the project folder also records the Visual C++ options you're using. That's enough introductory stuff for the moment. It's time to get your hands dirty.

TRY IT OUT**Creating a Project for a Win32 Console Application**

You'll now take a look at creating a project for a console application. First, select File \Rightarrow New \Rightarrow Project or use one of the other possibilities mentioned earlier to bring up the New Project dialog box.

The left pane in the New Project dialog box displays the types of projects you can create; in this case, click Win32. This also identifies an application wizard that creates the initial contents for the project. The right pane displays a list of templates available for the project type you have selected in the left pane. The template you select is used by the application wizard in creating the files that make up the project. In the next dialog box you have an opportunity to customize the files that are created when you click the OK button in this dialog box. For most of the type/template options, a basic set of program source modules is created automatically. You can choose Win32 Console Application in this instance.

You can now enter a suitable name for your project by typing into the Name: text box — for example, you could call this one Ex1_01, or you can choose your own project name. Visual C++ supports long filenames, so you have a lot of flexibility. The name of the solution folder appears in the bottom text box and, by default, the solution folder has the same name as the project. You can change this if you want. The dialog box also enables you to modify the location for the solution that contains your project — this appears in the Location: text box. If you simply enter a name for your project, the solution folder is automatically set to a folder with that name, with the path shown in the Location: text box. By default the solution folder is created for you, if it doesn't already exist. If you want to specify a different path for the solution folder, just enter it in the Location: text box. Alternatively, you can use the Browse button to select another path for your solution. Clicking OK displays the Win32 Application Wizard dialog box.

This dialog box explains the settings currently in effect. In this case, you can click Application Settings on the left to display the Application Settings page of the wizard, shown in Figure 1-6.




FIGURE 1-6

The Application Settings page enables you to choose options that you want to apply to the project. You can see that you are creating a console application and not a Windows application. The Precompiled header option is a facility for compiling source files such as those from the standard library that do not change just once. When you recompile your program after making changes or additions to your code, the precompiled code will be reused as is. You can see on the right of the dialog options for using MFC, which I have mentioned, and ATL — the Application Template Library — which is outside the scope of this book. Here, you can leave things as they are and click Finish. The application wizard then creates the project with all the default files.

The project folder will have the name that you supplied as the project name and will hold all the files making up the project definition. If you didn't change it, the solution folder has the same name as the project folder and contains the project folder plus the files defining the contents of the solution. If you use Windows Explorer to inspect the contents of the solution folder, you'll see that it contains four files:

- A file with the extension .sln that records information about the projects in the solution.
- A file with the extension .suo in which user options that apply to the solution will be recorded.
- A file with the extension .sdf that records data about IntelliSense for the solution. IntelliSense is the facility that I mentioned earlier that provides auto-completion and prompts you for code in the Editor window as you enter it.
- A file with the extension .opensdf that records information about the state of the project. This file exists only while the project is open.

If you use Windows Explorer to look in the Ex1_01 project folder, you will see that there are seven files initially, including a file with the name ReadMe.txt that contains a summary of the contents of the files that have been created for the project. The project you have created will automatically open in Visual C++ with the Solution Explorer pane, as in Figure 1-7.

The Solution Explorer tab presents a view of all the projects in the current solution and the files they contain — here, of course, there is just one project. You can display the contents of any file as an additional tab in the Editor pane just by double-clicking the name in the Solution Explorer tab. In the Editor pane, you can switch instantly to any of the files that have been displayed just by clicking on the appropriate tab.

The Class View tab displays the classes defined in your project and also shows the contents of each class. You don't have any classes in this application, so the view is empty. When I discuss classes you will see that you can use the Class View tab to move around the code relating to the definition and implementation of all your application classes quickly and easily.

You can also display the Property Manager tab by selecting it from the View menu. It shows the properties that have been set for the Debug and Release versions of your project. I'll explain these a little later in this chapter. You can change any of the properties for a version by right-clicking a version and selecting Properties from




FIGURE 1-7


the context menu; this displays a dialog where you can set the project properties. You can also press Alt+F7 to display the Property Pages dialog at any time. I'll discuss this in more detail when we go into the Debug and Release versions of a program.

If it is not already visible, you can display the Resource View tab by selecting from the View menu or by pressing Ctrl+Shift+E. The Resource View shows the dialog boxes, icons, menus, toolbars, and other resources used by the program. Because this is a console program, no resources are used; however, when you start writing Windows applications, you'll see a lot of things here. Through this tab you can edit or add to the resources available to the project.

As with most elements of the Visual C++ IDE, the Solution Explorer and other tabs provide context-sensitive pop-up menus when you right-click items displayed in the tab, and in some cases when you right-click in the empty space in the tab, too. If you find that the Solution Explorer pane gets in your way when you're writing code, you can hide it by clicking the Auto Hide icon. To redisplay it, click the Name tab on the left of the IDE window.

Modifying the Source Code

The application wizard generates a complete Win32 console program that you can compile and execute. Unfortunately, the program doesn't do anything as it stands, so to make it a little more interesting you need to change it. If it is not already visible in the Editor pane, double-click `Ex1_01.cpp` in the Solution Explorer pane. This is the main source file for the program that the application wizard generated, and is shown in Figure 1-8.



```

Ex1_01 - Ex1_01.cpp

Ex1_01.cpp  ✎ X
(Global Scope)
1 // Ex1_01.cpp : Defines the entry point for the console application.
2 //
3
4 #include "stdafx.h"
5
6
7 int _tmain(int argc, _TCHAR* argv[])
8 {
9     return 0;
10 }
11

```

FIGURE 1-8

If the line numbers are not displayed on your system, select Tools \Rightarrow Options from the main menu to display the Options dialog. If you extend the C/C++ option in the Text Editor subtree in the left pane and select General from the extended tree, you can check the Line numbers option in the right pane of the dialog. I'll give you a rough guide to what this code in Figure 1-8 does, and you'll see more on all of this later.

The first two lines are just comments. Anything following // in a line is ignored by the compiler. When you want to add descriptive comments in a line, precede your text with //.

Line 4 is an #include directive that adds the contents of the file stdafx.h to this file in place of this #include directive. This is the standard way to add the contents of .h source files to a .cpp source file in a C++ program.

Line 7 is the first line of the executable code in this file and the beginning of the function called _tmain(). A function is simply a named unit of executable code in a C++ program; every C++ program consists of at least one — and usually many more — functions.

Lines 8 and 10 contain left and right braces, respectively, that enclose all the executable code in the function _tmain(). The executable code is just the single line 9, and all this does is end the program.

Now you can add the following two lines of code in the Editor window:

```
// Ex1_01.cpp : Defines the entry point for the console application.  
//  
#include "stdafx.h"  
#include <iostream>  
  
int _tmain(int argc, _TCHAR* argv[]){  
    std::cout << "Hello world!\n";  
    return 0;  
}
```

The new lines you should add are shown in bold; the others are generated for you. To introduce each new line, place the cursor at the end of the text on the preceding line and press Enter to create an empty line in which you can type the new code. Make sure it is exactly as shown in the preceding example; otherwise the program may not compile.

The first new line is an #include directive that adds the contents of one of the C++ standard library files to the Ex1_01.cpp source file. The iostream library defines facilities for basic I/O operations, and the one you are using in the second line that you added writes output to the command line.

std::cout is the name of the standard output stream, and you write the string "Hello world!\n" to std::cout in the second addition statement. Whatever appears between the pair of double-quote characters is written to the command line.

Building the Solution

To build the solution, press F7 or select the Build ⇔ Build Solution menu item. Alternatively, you can click the toolbar button corresponding to this menu item. The toolbar buttons for the Build menu may not be displayed, but you can easily fix this by right-clicking in the toolbar area and selecting the Build toolbar from those in the list. The program should compile successfully. If there are errors, it may be that you created them while entering the new code, so check the two new lines very carefully.

Files Created by Building a Console Application

After the example has been built without error, take a look in the project folder by using Windows Explorer to see a new subfolder to the solution folder `Ex1_01` called `Debug`. This is the folder `Ex1_01\Debug`, not the folder `Ex1_01\Ex1_01\Debug`. This folder contains the output of the build you just performed on the project. Notice that this folder contains three files.

Other than the `.exe` file, which is your program in executable form, you don't need to know much about what's in these files. In case you're curious, however, the `.ilk` file is used by the linker when you rebuild your project. It enables the linker to incrementally link the object files produced from the modified source code into the existing `.exe` file. This avoids the need to relink everything each time you change your program. The `.pdb` file contains debugging information that is used when you execute the program in debug mode. In this mode, you can dynamically inspect information generated during program execution.

There's a `Debug` subdirectory in the `Ex1_01` project folder too. This contains a large number of files that were created during the build process, and you can see what kind of information they contain from the Type description in Windows Explorer.

Debug and Release Versions of Your Program

You can set a range of options for a project through the Project \Rightarrow `Ex1_01` Properties menu item. These options determine how your source code is processed during the compile and link stages. The set of options that produces a particular executable version of your program is called a *configuration*. When you create a new project workspace, Visual C++ automatically creates configurations for producing two versions of your application. The Debug version includes additional information that helps you debug the program. With the Debug version of your program, you can step through the code when things go wrong, checking on the data values in the program as you go. The Release version has no debug information included and has the code-optimization options for the compiler turned on to provide you with the most efficient executable module. These two configurations are sufficient for your needs throughout this book, but when you need to add other configurations for an application you can do so through the Build \Rightarrow Configuration Manager menu. (Note that this menu item won't appear if you haven't got a project loaded. This is obviously not a problem, but might be confusing if you're just browsing through the menus to see what's there.)

You can choose which configuration of your program to work with by selecting from the drop-down list in the toolbar. If you select Configuration Manager... from the drop-down list, the Configuration Manager dialog will be displayed. You use this dialog when your solution contains multiple projects. Here you can choose configurations for each of the projects and choose which ones you want to build.

After your application has been tested using the debug configuration and appears to be working correctly, you typically rebuild the program as a release version; this produces optimized code without the debug and trace capability, so the program runs faster and occupies less memory.

Executing the Program

After you have successfully compiled the solution, you can execute your program by pressing Ctrl+F5. You should see the window shown in Figure 1-9.

As you can see, you get the text between the double quotes written to the command line. The "\n" that appeared at the end of the text string is a special sequence called an *escape sequence* that denotes a newline character. Escape sequences are used to represent characters in a text string that you cannot enter directly from the keyboard.




FIGURE 1-9

TRY IT OUT Creating an Empty Console Project

The previous project contained a certain amount of excess baggage that you don't need when working with simple C++ language examples. The precompiled headers option chosen by default resulted in the `stdafx.h` file being created in the project. This is a mechanism for making the compilation process more efficient when there are a lot of files in a program, but it won't be necessary for most of our examples. In these instances, you start with an empty project to which you can add your own source files. You can see how this works by creating a new project in a new solution for a Win32 console program with the name `Ex1_02`. After you have entered the project name and clicked OK, click Application Settings on the left side of the dialog box that follows. You can then select Empty project from the additional options.

When you click Finish, the project is created as before, but this time without any source files.

By default, the project options will be set to use Unicode libraries. This makes use of a non-standard name for the main function in the program. In order to use standard native C++ in your console programs, you need to switch off the use of Unicode libraries. To do this, select the Project \Rightarrow Properties menu item, or press Alt+F7, to display the Property Pages dialog for the project. Select the All Configurations option from the Configuration: drop-down list at the top. Select the General option under Configuration Properties in the left pane and select the Character Set property in the right pane. You will then be able to set the value of this property to Not Set from the drop-down list to the right of the property name, as shown in Figure 1-10. Click OK to close the dialog. You should do this for all the C++ console program examples in the book. If you forget to do so, they won't build. You will be using Unicode libraries in the Windows examples, though.

Next, you can add a new source file to the project. Right-click the Solution Explorer pane and then select Add \Rightarrow New Item... from the context menu. A dialog displays: click Code in the left pane and C++ File(.cpp) in the right pane. Enter the filename as `Ex1_02`.

When you click Add in the dialog, the new file is added to the project and is displayed in the Editor window. The file is empty, of course, so nothing will be displayed. Enter the following code in the Editor window:




FIGURE 1-10

```
// Ex1_02.cpp A simple console program
#include <iostream> // Basic input and output library
int main()
{
    std::cout << "This is a simple program that outputs some text." << std::endl;
    std::cout << "You can output more lines of text" << std::endl;
    std::cout << "just by repeating the output statement like this." << std::endl;
    return 0; // Return to the operating system
}
```

Note the automatic indenting that occurs as you type the code. C++ uses indenting to make programs more readable, and the editor automatically indents each line of code that you enter based on what was in the previous line. You can change the indenting by selecting the Tools \Rightarrow Options... menu item to display the Options dialog. Selecting Text Editor \Rightarrow C/C++ \Rightarrow Tabs in the left pane of the dialog displays the indenting options in the right pane. The editor inserts tabs by default, but you can change it to insert spaces if you want.

You can also see the syntax color highlighting in action as you type. Some elements of the program are shown in different colors, as the editor automatically assigns colors to language elements depending on what they are.

The preceding code is the complete program. You probably noticed a couple of differences compared to the code generated by the application wizard in the previous example. There's no `#include` directive for the `stdafx.h` file. You don't have this file as part of the project here because you are not using the precompiled headers facility. The name of the function here is `main`; before it was `_tmain`. In fact all ISO/IEC standard C++ programs start execution in a function called `main()`. Microsoft also provides for this function to be called `wmain` when Unicode characters are used, and the name `_tmain` is defined to be either `main` or `wmain` (in the `tchar.h` header file), depending on whether or not the program is going to use Unicode characters. In the previous example the name `_tmain` is defined behind the scenes to be `main`. I'll use the standard name `main` in all the C++ examples, which is why you need to change the `Character Set` property value for these projects to `Not Set`.

The output statements are a little different. The first statement in `main()` is the following:

```
std::cout << "This is a simple program that outputs some text." << std::endl;
```

You have two occurrences of the `<<` operator, and each one sends whatever follows to `std::cout`, the standard output stream. First, the string between double quotes is sent to the stream, and then `std::endl`, where `std::endl` is defined in the standard library as a newline character. Earlier, you used the escape sequence `\n` for a newline character within a string between double quotes. You could have written the preceding statement as follows:

```
std::cout << "This is a simple program that outputs some text.\n";
```

You can now build this project in the same way as the previous example. Note that any open source files in the Editor pane are saved automatically if you have not already saved them. When you have compiled the program successfully, press `Ctrl+F5` to execute it. If everything works as it should, the output will be as follows:

```
This is a simple program that outputs some text.  
You can output more lines of text  
just by repeating the output statement like this.
```

Dealing with Errors

Of course, if you didn't type the program correctly, you get errors reported. To see how this works you could deliberately introduce an error into the program. If you already have errors of your own, you can use those to perform this exercise. Go back to the Editor pane and delete the semicolon at the end of the second-to-last line between the braces (line 8); then rebuild the source file. The Output pane at the bottom of the application window will include the following error message:

```
C2143: syntax error : missing ';' before 'return'
```

Every error message during compilation has an error number that you can look up in the documentation. Here the problem is obvious, but in more obscure cases the documentation may help

you figure out what is causing the error. To get the documentation on an error, click the line in the Output pane that contains the error number and then press F1. A new window displays containing further information about the error. You can try it with this simple error, if you like.

When you have corrected the error, you can then rebuild the project. The build operation works efficiently because the project definition keeps track of the status of the files making up the project. During a normal build, Visual C++ recompiles only the files that have changed since the program was last compiled or built. This means that if your project has several source files, and you've edited only one of the files since the project was last built, only that file is recompiled before linking to create a new .exe file. If you modify a header file, all files that include that header will be recompiled, along with the header file itself of course.

Setting Options in Visual C++

Two sets of options are available. You can set options that apply to the tools provided by Visual C++, which apply in every project context. You also can set options that are specific to a project, and that determine how the project code is to be processed when it is compiled and linked. Options that apply to every project are set through the Options dialog that's displayed when you select Tools ➔ Options from the main menu. You used this dialog earlier to change the code indenting used by the editor. The Options dialog box is shown in Figure 1-11.




FIGURE 1-11

Clicking the symbol to the left of any of the items in the left pane displays a list of subtopics. Figure 1-11 shows the options for the General subtopic under Projects and Solutions. The right pane displays the options you can set for the topic you have selected in the left pane. You should concern yourself with only a few of these at this time, but you'll find it useful to spend a little time browsing the range of options available to you. Clicking the Help button (the one with the question mark) at the top right of the dialog box displays an explanation of the current options.

One option you should set right now relates to how IntelliSense works. Expand Text Editor \Rightarrow C/C++ \Rightarrow Advanced in the Options dialog and select the last property in the IntelliSense group, Member List Commit Characters. Delete the characters that appear as the property value in the right column. This will prevent IntelliSense from selecting wholly inappropriate choices from the list of possibilities by default. Just to make sure, I'll remind you about this again later in the book.

You probably want to choose a path to use as a default when you create a new project, and you can do this through the first option shown in Figure 1-11. Just set the path to the location where you want your projects and solutions stored.

You can set options that apply to every C++ project in the Options dialog that is displayed by selecting the Projects and Solutions \Rightarrow VC++ Project Settings topic in the left pane. You can set options specific to the current project through the dialog that displays when you select the Project \Rightarrow Ex1_02 Properties menu item in the main menu, or by pressing Alt+F7. This menu item label is tailored to reflect the name of the current project. You used this to change the value of the Character Set property for the Ex1_02 console program.

Creating and Executing Windows Applications

Just to show how easy it's going to be, you can now create a working Windows application. I'll defer discussion of the program that you'll generate until I've covered the necessary ground for you to understand it in detail. You will see, though, that the processes are straightforward.

Creating an MFC Application

To start with, if an existing project is active — as indicated by the project name appearing in the title bar of the Visual C++ main window — you can select Close Solution from the File menu. Alternatively, you can create a new project and have the current solution closed automatically. Create directory for solution is selected by default in the New Project dialog.

To create the Windows program, select New \Rightarrow Project from the File menu or press Ctrl+Shift+N; then set the project type as MFC, and select MFC Application as the project template. You can then enter the project name as **Ex1_03**. When you click OK the MFC Application Wizard dialog is displayed. The dialog has a range of options that let you choose the features you'd like to have included in your application. These are identified by the items in the list on the left of the dialog.

Click Application Type to display these options. Click the Tabbed documents option to deselect it and select Windows Native/Default from the drop-down list to the right. The dialog should then look as shown in Figure 1-12.




FIGURE 1-12

Click Advanced Features next, and deselect Explorer docking pane, Output docking pane, Properties docking pane, ActiveX controls, Common Control Manifest, and Support Restart Manager so that the dialog looks as shown in Figure 1-13.




FIGURE 1-13

Finally, click Finish to create the project. The undocked Solution Explorer pane in the IDE window will look as shown in Figure 1-14.

The list shows the large number of source files that have been created, and several resource files. You need plenty of space on your hard drive when writing Windows programs! The files with the extension .cpp contain executable C++ source code, and the .h files contain C++ code consisting of definitions that are used by the executable code. The .ico files contain icons. The files are grouped into subfolders you can see for ease of access. These aren't real folders, though, and they won't appear in the project folder on your disk.

If you now take a look at the Ex1_03 solution folder and subfolders using Windows Explorer or whatever else you may have handy for looking at the files on your hard disk, you'll notice that you have generated a total of 28 files. Four of these are in the solution folder that includes the transient .opensdf file, a further 19 are in the project folder, and the rest are in a subfolder, res, of the project folder. The files in the res subfolder contain the resources used by the program, such as the menus and icons. You get all this as a result of just entering the name you want to assign to the project. You can see why, with so many files and filenames being created automatically, a separate directory for each project becomes more than just a good idea.

One of the files in the Ex1_03 project directory is ReadMe.txt, and it provides an explanation of the purpose of each of the files that the MFC Application Wizard has generated. You can take a look at using Notepad, WordPad, or even the Visual C++ editor. To view it in the Editor window, double-click it in the Solution Explorer pane.




FIGURE 1-14

Building and Executing the MFC Application

Before you can execute the program, you have to build the project — that is, compile the source code and link the program modules. You do this in exactly the same way as with the console application example. To save time, press Ctrl+F5 to get the project built and then executed in a single operation.

After the project has been built, the Output window indicates that there are no errors, and the executable starts running. The window for the program you've generated is shown in Figure 1-15.




FIGURE 1-15

As you see, the window is complete with menus and a toolbar. Although there is no specific functionality in the program — that's what you need to add to make it *your* program — all the menus work. You can try them out. You can even create further windows by selecting New from the File menu.

I think you'll agree that creating a Windows program with the MFC Application Wizard hasn't stressed too many brain cells. You'll need to get a few more ticking away when it comes to developing the basic program you have here into a program that does something more interesting, but it won't be that hard. Certainly, for many people, writing a serious Windows program the old-fashioned way, without the aid of Visual C++, required at least a couple of months on a brain-enhancing fish diet before making the attempt. That's why so many programmers used to eat sushi. That's all gone now with Visual C++. You never know, however, what's around the corner in programming technology. If you like sushi, it's best to continue eating it to be on the safe side.

SUMMARY

In this chapter you have run through the basic mechanics of using Visual C++ to create applications. You created and executed console programs, and with the help of the application wizard you created an MFC-based Windows program.

Starting with the next chapter, all the examples illustrating how C++ language elements are used are executed using Win32 console applications. You will return to the application wizard for MFC-based programs as soon as you have finished delving into the secrets of C++.

► WHAT YOU LEARNED IN THIS CHAPTER

TOPIC	CONCEPT
C++	Visual C++ supports C++ language statements that conform to the C++ 11 language standard that is defined in the document ISO/IEC 14882:2011. Visual C++ does not yet implement all language features defined by this standard.
Solutions	A solution is a container for one or more projects that form a solution to an information-processing problem of some kind.
Projects	A project is a container for the code and resource elements that make up a functional unit in a program.
The Solution Explorer Pane	The Solution Explorer pane displays one or more tabs showing different aspects of a project. The Solution Explorer tab shows the project files. The Class View tab shows classes in the project. The Resource View tab shows project resources.
Project Options	You can display and modify the options that apply to all C++ projects through the dialog that is displayed when you select Options from the Tools menu.
Project Properties	You can set values for properties for the current project through the dialog that is displayed when you select Properties from the Project menu.
Console Applications	A console application is a basic C++ application with no GUI. Typically, input is from the keyboard and output is to the command line.
The <code>main()</code> function	The starting point for a standard C++ program is the <code>main()</code> function. The New Project dialog generates a console application that starts with the <code>_tmain()</code> function.
Unicode	The default console program uses Unicode characters by default. If you want to use the standard <code>main()</code> function in a console program, you can generate an empty Win32 project and add the source file for <code>main()</code> after disabling the Character Set project property value that selects the Unicode character set.
Windows 8 Apps	Windows 8 Apps target tablet computers and desktop PCs running the Windows 8 operating system.
Windows Runtime	The Windows Runtime, WinRT, provides the interface to the operating system for Windows 8 Apps.
Windows Desktop Applications	Windows desktop applications have an application window and a GUI incorporating controls such as menus, toolbars, and dialogs. Desktop applications interface to the operating system through the Win32 set of functions. Desktop applications execute under Windows Vista, Windows 7 and Windows 8.
The Microsoft Foundation Classes.	The MFC is a set of C++ classes that encapsulate the functions provided by Win32. MFC makes it easier to develop Windows desktop applications.
MFC Projects	You create an MFC project by selecting MFC then MFC Application in the New Project dialog.



Data, Variables, and Calculations

WHAT YOU WILL LEARN IN THIS CHAPTER:

- C++ program structure
- Namespaces
- Variables in C++
- Defining variables and constants
- Basic input from the keyboard and output to the screen
- Performing arithmetic calculations
- Casting operands
- Variable scope
- What the auto keyword does
- How to discover the type of an expression

WROX.COM CODE DOWNLOADS FOR THIS CHAPTER

You can find the wrox.com code downloads for this chapter on the Download Code tab at www.wrox.com/remtitle.cgi?isbn=9781118368084. The code is in the Chapter 2 download and individually named according to the names throughout the chapter.


THE STRUCTURE OF A C++ PROGRAM

Programs that will run as console applications under Visual C++ are programs that read data from the command line and output the results to the command line. To avoid having to dig into the complexities of creating and managing application windows before you have enough knowledge to understand how they work, all the examples that you'll write to understand how the C++ language works will be console programs. This will enable you to focus entirely on C++ in the first instance; once you have mastered that, you'll be ready to deal with creating and managing application windows. I'll start by explaining how console programs are structured.

A program in C++ consists of one or more functions. In Chapter 1, you saw an example that was a Win32 console program consisting simply of the function `main()`, where `main` is the name of the function. Every C++ program contains the function `main()`, and all C++ programs of any size consist of several functions — the `main()` function where execution of the program starts, plus a number of other functions. A function is simply a self-contained block of code with a name that you invoke for execution by using the name of the function. As you saw in Chapter 1, a console program that is generated by the Application Wizard has a main function with the name `_tmain`. This is a programming construct to allow the name to be `main` or `wmain`, depending on whether or not the program is using Unicode characters. The names `wmain` and `_tmain` are Microsoft-specific. The name for the main function conforming to the standard for C++ is `main`. I'll use the name `main` for all our C++ examples because this is the most portable option. If you intend to compile your code only with Microsoft Visual C++, then it is advantageous to use the Microsoft-specific names for `main`, in which case you can use the Application Wizard to generate your console applications. To use the Application Wizard with the console program examples in this book, just copy the code that is shown in the body of the `main` function to `_tmain`.

Figure 2-1 shows how a typical console program might be structured. The execution of the program shown starts at the beginning of the function `main()`. From `main()`, execution transfers to a function `input_names()`, which returns execution to the position immediately following the point where it was called in `main()`. The `sort_names()` function is then called from `main()`, and, once control returns to `main()`, the final function `output_names()` is called. Eventually, once output has been completed, execution returns once again to `main()` and the program ends.

Of course, different programs may have radically different functional structures, but they all start execution at the beginning of `main()`. If you define your programs as a number of functions, you can write and test each function separately. Segmenting your programs in this way gives you a further advantage because functions you write to perform a particular task can be reused in other programs. The libraries that come with C++ provide a lot of standard functions that you can use and save yourself a great deal of work.

**FIGURE 2-1**

NOTE You'll see more about creating and using functions in Chapter 5.

TRY IT OUT A Simple Program

A simple example can help you to understand the elements of a program a little better. Start by creating a new project — you can use the Ctrl+Shift+N key combination as a shortcut for this. When the dialog appears, select Win32 as the project type and Win32 Console Application as the template. You can name the project **Ex2_01**.

If you click the OK button, you'll see a new dialog in the form shown in Figure 2-2 that shows an overview of what the Application Wizard will generate.




FIGURE 2-2

If you now click Application Settings on the left of this dialog, you'll see further options for a Win32 application displayed, as shown in Figure 2-3.




FIGURE 2-3

The default setting is a Console application that includes a file containing a default version of `main()`, but you'll start from the most basic project structure, so choose Empty project from the set of additional options and click the Finish button. Now you have a project, but it contains no files at all. You can see what the project contains from the Solution Explorer pane on the left of the Visual C++ main window, as shown in Figure 2-4. Because you are starting with an empty project, you need to check that the project properties are set appropriately. You can display the project properties dialog by selecting Properties from the Project menu or just pressing Alt+F7. Select Configuration Properties in the left pane, and then General in the left pane if it is not already highlighted. You want the changes to apply to all versions of your project so click on the drop-down list labeled Configuration and select All Configurations from the list. In the right pane, you'll see a list of properties, so select Character Set in the Project Defaults set. To the right of the property name, you'll see a drop-down list, from which you should select Not Set. The default value for this property for a Win32 console implies you are going to use the Unicode character set in the application. This will cause the compiler to look for `_wmain`, which won't be present. If you fail to reset this project property, then you will get an error message during the build operation because `_wmain` cannot be found. Having set the Character Set property, you are ready to create the program code.

You'll start by adding a new source file to the project, so right-click Source Files in the Solution Explorer pane and select the Add \Rightarrow New Item... menu option. The Add New Item dialog displays, showing the options for what is to be added.

Select code in the left pane, select the C++ File(.cpp) template in the middle pane, and enter the filename `Ex2_01`. The file will automatically be given the extension `.cpp`, so you don't have to enter this. There is no problem having the name of the file the same as the name of the project. The project file will have the extension `.vcxproj`, so that will differentiate it from the source file.

Click the Add button to create the file. You can then type the following code in the Editor pane of the IDE window:

```
// Ex2_01.cpp
// A Simple Example of a Program
#include <iostream>

using std::cout;
using std::endl;

int main()
{
```




FIGURE 2-4

```

int apples, oranges;           // Declare two integer variables
int fruit;                   // ...then another one

apples = 5; oranges = 6;       // Set initial values
fruit = apples + oranges;     // Get the total fruit

cout << endl;                // Start output on a new line
cout << "Oranges are not the only fruit..." << endl
    << "- and we have " << fruit << " fruits in all.";
cout << endl;                // Output a new line character

return 0;                     // Exit the program
}

```

The preceding example is intended to illustrate some of the ways in which you can write C++ statements and is not a model of good programming style.

The editor will check the code as you type. Anything it thinks is not correct will be underlined with a red squiggle, so look out for these. If you see one, it usually means that you have mistyped something.

Since the file is identified by its extension as a file containing C++ code, the C++ keywords in the code that the editor recognizes will be colored to identify them. You will be able to see if you have entered `Int` where you should have entered `int`, because `Int` will not have the color used to highlight keywords.

If you look at the Solution Explorer pane (press `Ctrl+Alt+L` to display it) for your new project, you'll see the newly created source file. Solution Explorer will always show all the files in a project. You can display the Class View pane by selecting from the View menu or by pressing `Ctrl+Shift+C`. This consists of two panes, the upper pane showing global functions and macros within the project (and classes when you get to create a project involving classes), and the lower pane presently empty. The `main()` function will appear in the lower pane if you select Global Functions and Variables in the upper Class View pane; this is shown in Figure 2-5. I'll consider what this means in more detail later, but essentially, *globals* are functions and/or variables that are accessible from anywhere in the program.

You can display the Property Manager pane by selecting from the View menu. If you extend the items in the tree that is displayed by clicking the unfilled arrow symbols, it will look like Figure 2-6.




FIGURE 2-5




FIGURE 2-6

This shows the two possible versions you can build, the Debug version for testing and the Release version when your program has been tested. The properties for each version of the project are shown, and double-clicking on any of them will display a dialog showing the Property Pages, where you can change properties, if necessary.

You have three ways to compile and link the program; you can select the Build Ex2_01 menu item from the Build menu, you can press the F7 function key, or you can select the appropriate toolbar button — you can identify what a toolbar button does by hovering the mouse cursor over it. If there is no toolbar button that shows the tooltip Build Ex2_01 when the cursor is over it, then the Build toolbar is not currently displayed. You can remedy this by right-clicking on an empty part of the toolbar area and selecting Build from the list of toolbars that is displayed. It's a very long list and you will probably want to choose different sets of toolbars to be displayed, depending on what you are doing.

Assuming the build operation was successful, you can execute the program by pressing the Ctrl+F5 keys or by selecting Start Without Debugging from the Debug menu. You should get the following output in a command-line window:

```
Oranges are not the only fruit...
- and we have 11 fruits in all.
Press any key to continue ...
```

The first two lines were produced by the program, and the last line indicates how you can end the execution and close the command-line window. I won't show this last line of output from other console examples, but it's always there.

Program Comments

The first two lines in the program are *comments*. Comments are an important part of any program, but they're not executable code — they are there simply to help the human reader. All comments are ignored by the compiler. On any line of code, two successive slashes (//) that are not contained within a text string (you'll see what text strings are later) indicate that the rest of the line is a comment. You can see that several lines of the program contain comments as well as program statements.

You can also use an alternative form of comment bounded by /* and */. For example, the first line of the program could have been written:

```
/* Ex2_01.cpp */
```

The comment using // covers only the portion of the line following the two successive slashes, whereas the /*...*/ form defines whatever is enclosed between the /* and the */ as a comment, and this can span several lines. For example, you could write:

```
/*
Ex2_01.cpp
A Simple Program Example
*/
```

All four lines are comments and are ignored by the compiler. If you want to highlight some particular comment lines, you can always embellish them with a frame of some description:

```
*****  
* Ex2-01.cpp *  
* A Simple Program Example *  
*****
```

As a rule, you should always comment your programs comprehensively. The comments should be sufficient for another programmer or you, at a later date, to understand the purpose of any particular piece of code and how it works. I will often use comments in examples to explain in more detail than you would in a production program.

The #include Directive — Header Files

Following the comments, you have an `#include` directive:

```
#include <iostream>
```

This is called a *directive* because it directs the compiler to do something — in this case, to insert the contents of the file, `iostream`, that is identified between the angled brackets, `<>`, into the program source file before compilation. The `iostream` file is called a *header file* because it's invariably inserted in another source file. The `iostream` header file is part of the standard C++ library, and it contains definitions that are necessary for you to be able to use C++ input and output statements. If you didn't include the contents of `iostream` into the program, it wouldn't compile, because you use output statements in the program that depend on some of the definitions in this file. There are many different header files provided by Visual C++ that cover a wide range of capabilities. You'll be seeing more of them as you progress through the language facilities.

The name of the file to be inserted by an `#include` directive does not have to be written between angled brackets. The name of the header file can also be written between double quotes, thus:

```
#include "iostream"
```

The only difference between this and the preceding version between angled brackets is the places where the compiler is going to look for the file.

If you write the header file name between double quotes, the compiler searches for the header file first in the directory that contains the source file in which the directive appears. If the header file is not there, the compiler then searches the directories where the standard header files are stored.

If the filename is enclosed between angled brackets, the compiler only searches the directories in which it expects to find the standard header files. Thus, when you want to include a standard header in a source, place the name between angled brackets because it will be found more quickly. When you are including other header files, typically ones that you create yourself, place the name between double quotes; otherwise, they will not be found at all.

NOTE When you specify the file to be included between angled brackets, you are indicating to the compiler that it should search for the file along the path specified by the `/I` compiler option, and failing that along the path specified by the `INCLUDE` environment variable. These paths locate the C++ library files, which is why this form is reserved for library headers. The `INCLUDE` environment variable points to the folder holding the library header and the `/I` option allows an additional directory containing library headers to be specified. When the file name is between double quotes, the compiler will search the folder that contains the file in which the `#include` directive appears. If the file is not found it will search in any directories that `#include` the current file. If that fails to find the file it will search the library directories.

An `#include` directive is one of several available *preprocessor directives*, and I'll be introducing more of these as you need them throughout the book. The Visual C++ editor recognizes preprocessor directives and highlights them in blue in your edit window. Preprocessor directives are commands executed by the preprocessor phase of the compiler that executes before your code is compiled into object code, and preprocessor directives generally act on your source code in some way before it is compiled. They all start with the `#` character.

Namespaces and the Using Declaration

As you saw in Chapter 1, the *standard library* is an extensive set of routines that have been written to carry many common tasks: for example, dealing with input and output, and performing basic mathematical calculations. Since there are a very large number of these routines, as well as other kinds of things that have names, it is quite possible that you might accidentally use the same name as one of the names defined in the standard library for your own purposes. A *namespace* is a mechanism in C++ for avoiding problems that can arise when duplicate names are used in a program for different things, and it does this by associating a given set of names, such as those from the standard library, with a sort of family name, which is the namespace name.

Every name that is defined in code that appears within a namespace also has the namespace name associated with it. All the standard library facilities are defined within a namespace with the name `std`, so every item from this standard library that you can access in your program has its own name, plus the namespace name, `std`, as a qualifier. The names `cout` and `endl` are defined within the standard library so their full names are `std::cout` and `std::endl`, and you saw these in action in Chapter 1. The two colons that separate the namespace name from the name of an entity form an operator called the *scope resolution operator*, and I'll discuss other uses for this operator later on in the book. Using the full names in the program tends to make the code look a bit cluttered, so it would be nice to be able to use their simple names, unqualified by the namespace name, `std`. The two lines in our program that follow the `#include` directive for `iostream` make this possible:

```
using std::cout;
using std::endl;
```

These are *using declarations*. They tell the compiler that you intend to use the names `cout` and `endl` from the namespace `std` without specifying the namespace name. The compiler will now assume that wherever you use the name `cout` in the source file subsequent to the first `using declaration`,

you mean `std::cout`. The name `cout` represents the standard output stream that, by default, corresponds to the command line, and the name `endl` represents the newline character.

WARNING *You need to be careful with using declarations in header files, especially when they will be included into several other source files. In header files you should avoid placing using declarations at global scope because they will apply within any source file that includes the header file.*

You'll learn more about namespaces a little later in this chapter, including how you define your own namespaces.

The `main()` Function

The `main()` function in the example consists of the function header defining it as `main()` plus everything from the first opening curly brace (`{`) to the corresponding closing curly brace (`}`). The braces enclose the executable statements in the function, which are referred to collectively as the *body* of the function.

As you'll see, all functions consist of a header that defines (among other things) the function name, followed by the function body that consists of a number of program statements enclosed between a pair of braces. The body of a function may contain no statements at all, in which case, it doesn't do anything.

A function that doesn't do anything may seem somewhat superfluous, but when you're writing a large program, you may map out the complete program structure in functions initially, but omit the code for many of the functions, leaving them with empty or minimal bodies. Doing this means that you can compile and execute the whole program with all its functions at any time and add detailed coding for the functions incrementally.

Program Statements

The program statements making up the function body of `main()` are each terminated with a semicolon. It's the semicolon that marks the end of a statement, not the end of a line. Consequently, you can spread a statement over several lines when this makes the code easier to follow, and several statements can appear in a single line. The program statement is the basic unit in defining what a program does. This is a bit like a sentence in a paragraph of text, where each sentence stands by itself in expressing an action or an idea, but relates to and combines with the other sentences in the paragraph in expressing a more general concept. A statement is a self-contained definition of an action that the computer is to carry out, but that can be combined with other statements to define a more complex action or calculation.

The action of a function is always expressed by a number of statements, each ending with a semicolon. Take a quick look at each of the statements in the example just written, just to get a general feel for how it works. I will discuss each type of statement more fully later in this chapter.

The first statement in the body of the `main()` function is:

```
int apples, oranges; // Declare two integer variables
```

This statement declares two variables, `apples` and `oranges`. A *variable* is just a named bit of computer memory that you can use to store data, and a statement that introduces the names of one or more variables is called a *variable declaration*. The keyword `int` in the statement indicates that the variables with the names `apples` and `oranges` are to store values that are whole numbers, or integers. Whenever you introduce the name of a variable into a program, you always specify what kind of data it will store, and this is called the *type* of the variable.

The next statement declares another integer variable, `fruit`:

```
int fruit;                                // ...then another one
```

While you can declare several variables in the same statement, as you did in the preceding statement for `apples` and `oranges`, it is generally a good idea to declare each variable in a separate statement on its own line. This enables you to comment them individually to explain how you intend to use them.

The next line in the example is:

```
apples = 5; oranges = 6;           // Set initial values
```

This line contains two statements, each terminated by a semicolon. I put this here just to demonstrate that you can put more than one statement in a line. While it isn't obligatory, it's generally good programming practice to write only one statement on a line, as it makes the code easier to understand. Good programming practice is about adopting approaches to coding that make your code easy to follow, and minimize the likelihood of errors.

The two statements store the values 5 and 6 in the variables `apples` and `oranges`, respectively. These statements are called *assignment statements*, because they assign new values to variables, and the `=` is the assignment operator.

The next statement is:

```
fruit = apples + oranges;      // Get the total fruit
```

This is also an assignment statement, but is a little different because you have an *arithmetic expression* to the right of the assignment operator. This statement adds together the values stored in the variables `apples` and `oranges` and stores the result in the variable `fruit`.

The next three statements are:

```
cout << endl;                  // Start output on a new line
cout << "Oranges are not the only fruit..." << endl
    << "- and we have " << fruit << " fruits in all.";
cout << endl;                  // Start output on a new line
```

These are all *output statements*. The first statement sends a newline character, denoted by the word `endl`, to the command line on the screen. In C++, a source of input or a destination for output is referred to as a *stream*. The name `cout` specifies the “standard” output stream, and the operator `<<` indicates that what appears to the right of the operator is to be sent to the output stream, `cout`. The `<<` operator “points” in the direction that the data flows — from the variable, string, or expression that appears on the right of the operator to the output destination that is on the left.

Thus, in the first statement, the value represented by the name `endl` — which is a newline character — is sent to the stream identified by the name `cout` — and data transferred to `cout` is written to the command line.

The meaning of the name `cout` and the operator `<<` are defined in the standard library header file `iostream`, which you added to the program code by means of the `#include` directive at the beginning of the program. `cout` is a name in the standard library and, therefore, is within the namespace `std`. Without the `using` directive, it would not be recognized unless you used its fully qualified name, `std::cout`, as I mentioned earlier. Because `cout` has been defined to represent the standard output stream, you shouldn't use the name `cout` for other purposes, so you can't use it as the name of a variable in your program, for example. Obviously, using the same name for different things is likely to cause confusion.

The second output statement of the three is spread over two lines:

```
cout << "Oranges are not the only fruit..." << endl  
     << "- and we have " << fruit << " fruits in all.";
```

As I said earlier, you can spread each statement in a program over as many lines as you wish if it helps to make the code clearer. The end of a statement is always signaled by a semicolon, not the end of a line. Successive lines are read and combined into a single statement by the compiler until it finds the semicolon that defines the end of the statement. Of course, this means that if you forget to put a semicolon at the end of a statement, the compiler will assume the next line is part of the same statement and join them together. This usually results in something the compiler cannot understand, so you'll get an error message.

The statement sends the text string "Oranges are not the only fruit..." to the command line, followed by another newline character (`endl`), then another text string, "- and we have ", followed by the value stored in the variable `fruit`, then, finally, another text string, " fruits in all.". There is no problem stringing together a sequence of things that you want to output in this way. The statement executes from left to right, with each item being sent to `cout` in turn. Note that each item to be sent to `cout` is preceded by its own `<<` operator.

The third and last output statement just sends another newline character to the screen, and the three statements produce the output from the program that you see.

The last statement in the program is:

```
return 0; // Exit the program
```

This terminates execution of the `main()` function, which stops execution of the program. Control returns to the operating system, and the `0` is a return code that tells the operating system that the application terminated successfully after completing its task. I'll discuss all these statements in more detail later.

The statements in a program are executed in the sequence in which they are written, unless a statement specifically causes the natural sequence to be altered. In Chapter 3, you'll look at statements that alter the sequence of execution.

Whitespace

Whitespace is the term used in C++ to describe blanks, tabs, newline characters, form feed characters, and comments. Whitespace serves to separate one part of a statement from another and enables the compiler to identify where one element in a statement, such as `int`, ends and the next element begins. Otherwise, whitespace is ignored and has no effect.

For example, consider the following statement:

```
int fruit; // ...then another one
```

There must be at least one whitespace character (usually a space) between `int` and `fruit` for the compiler to be able to distinguish them, but if you add more whitespace characters, they will be ignored. The content of the line following the semicolon is all whitespace and is therefore ignored.

On the other hand, look at this statement:

```
fruit = apples + oranges; // Get the total fruit
```

No whitespace characters are necessary between `fruit` and `=`, or between `=` and `apples`, although you are free to include some if you wish. This is because the `=` is not alphabetic or numeric, so the compiler can separate it from its surroundings. Similarly, no whitespace characters are necessary on either side of the `+` sign, but you can include some if you want to aid the readability of your code.

Apart from its use as a separator between elements in a statement that might otherwise be confused, whitespace is ignored by the compiler (except, of course, in a string of characters between quotes). You can include as much whitespace as you like to make your program more readable, as you did when you spread an output statement in the last example, over several lines. Remember that in C++, the end of a statement is wherever the semicolon occurs.

Statement Blocks

You can enclose several statements between a pair of braces, in which case, they become a *block*, or a *compound statement*. The body of a function is an example of a block. Such a compound statement can be thought of as a single statement (as you'll see when you look at the decision-making possibilities in C++ in Chapter 3). In fact, wherever you can put a single statement in C++, you could equally well put a block of statements between braces. As a consequence, blocks can be placed inside other blocks. In fact, blocks can be nested, one within another, to any depth.

NOTE A statement block also has important effects on variables, but I will defer discussion of this until later in this chapter when I discuss something called variable scope.

Automatically Generated Console Programs

In the last example, you opted to produce the project as an empty project with no source files, and then you added the source file subsequently. If you just allow the Application Wizard to generate the

project, as you did in Chapter 1, the project will contain several files, and you should explore their contents in a little more depth. Create a new Win32 console project with the name **Ex2_01A**, and this time, just allow the Application Wizard to finish without choosing to set any of the options in the Application Settings dialog. The project will have four files containing code: the `Ex2_01A.cpp` and `stdafx.cpp` source files, the `stdafx.h` header file, and the `targetver.h` file that specifies the earliest version of Windows that is capable of running your application. This is to provide for basic capability that you might need in a console program, and represents a working program as it stands, which does nothing. If you have a project open, you can close it by selecting the File \Rightarrow Close Solution item on the main menu. You can create a new project with an existing project open, in which case, the old project will be closed automatically unless you elect to add it to the same solution.

First of all, the contents of `Ex2_01A.cpp` will be:

```
// Ex2_01A.cpp : Defines the entry point for the console application.  
  
//  
  
#include "stdafx.h"  
  
int _tmain(int argc, _TCHAR* argv[])  
{  
    return 0;  
}
```

This is decidedly different from the previous example. There is an `#include` directive for the `stdafx.h` header file that was not in the previous version, and the function where execution starts is called `_tmain()`, not `main()`.

Precompiled Header Files

The Application Wizard has generated the `stdafx.h` header file as part of the project, and if you take a look at the code in there, you'll see there are three further `#include` directives for the `targetver.h` header that I mentioned earlier, plus the standard library header files `stdio.h` and `tchar.h`. The old-style header `stdio.h` is for standard I/O and was used before the current standard for C++; this covers similar ground to the `iostream` header but does not define the same symbols. Our console examples will use `iostream` symbols so you will need to include that. `tchar.h` is a Microsoft-specific header file defining text functions.

The idea is that `stdafx.h` will be compiled once and not recompiled every time you change your code. If the Precompiled Header project option is switched on, which is the default for the standard console program, the compiler will only recompile `stdafx.h` when it has been changed. Compiling `stdafx.h` results in a `.pch` file (precompiled header file). The compiler will only recompile `stdafx.h` if there is no corresponding `.pch` file, or if the timestamp for the `.pch` file is earlier than the timestamp for the `stdafx.h` file. Some standard library header files are very large, so this feature can significantly reduce the time it takes to compile a project.

Thus `stdafx.h` should contain `#include` directives for all header files that are not going to be changed very often, if at all. These will be standard system include files for your project plus any of your own project header files that are rarely changed. While you are learning C++, you won't be using either of the headers that appear in `stdafx.h`, which is one reason for not using the default file-generation capability provided by the Application Wizard.

Main Function Names

As I already explained, Visual C++ supports `wmain()` as an alternative to `main()` when you are writing a program that's using Unicode characters — `wmain()` being a Microsoft-specific definition for `main()` that is not part of standard C++. In support of that, the `tchar.h` header defines the name `_tmain` such that it will normally be replaced by `main`, but will be replaced by `wmain` if the symbol `_UNICODE` is defined. Thus, to identify a program as using Unicode, you would add the following statement to the beginning of the `stdafx.h` header file:

```
#define _UNICODE
```

Actually, you don't need to do this with the `Ex2_01A` project because the `Character Set` project property will have been set to use the Unicode character set by default.

Now that I've explained all that, I'll stick to plain old `main()` for our C++ examples that are console applications, because this option is standard C++ and, therefore, the most portable coding approach.

NOTE You can use the default console project for the console examples in the book if you wish. In this case just put the code from the body of `main()` in each example as the body of `_tmain()`. You should also put any `#include` directives for standard library headers in `stdafx.h`.

DEFINING VARIABLES

A fundamental objective in all computer programs is to manipulate some data and get some answers. An essential element in this process is having a piece of memory that you can call your own, that you can refer to using a meaningful name, and where you can store an item of data. Each individual piece of memory so specified is called a *variable*.

As you already know, each variable will store a particular kind of data, and the type of data that can be stored is fixed when you define the variable in your program. One variable might store whole numbers (that is, integers), in which case, you couldn't use it to store numbers with fractional values. The value that each variable contains at any point is determined by the statements in your program, and, of course, its value will usually change many times as the program calculation progresses.

The next section looks first at the rules for naming a variable when you introduce it into a program.

Naming Variables

The name you give to a variable is called an *identifier* or, more conveniently, a *variable name*. Variable names can include the letters A-z (upper- or lowercase), the digits 0-9, and the underscore character. No other characters are allowed, and if you happen to use some other character, you will typically get an error message when you try to compile the program. Variable names must also begin with either a letter or an underscore. Names are usually chosen to indicate the kind of information to be stored.

Because variable names in Visual C++ can be up to 2048 characters long, you have a reasonable amount of flexibility in what you call your variables. In fact, as well as variables, there are quite a few other things that have names in C++, and they, too, can have names of up to 2048 characters, with the same definition rules as a variable name. Using names of the maximum length allowed can make your programs a little difficult to read, and unless you have amazing keyboard skills, they are the very devil to type in. A more serious consideration is that not all compilers support such long names. If you anticipate compiling your code in other environments, it's a good idea to limit names to a maximum of 31 characters; this will usually be more than adequate for devising meaningful names and will avoid problems of compiler name length constraints in most instances.

Although you can use variable names that begin with an underscore (for example, `_this` and `_that`), this is best avoided because of potential clashes with standard system variables that have the same form. You should also avoid using names starting with a double underscore for the same reason.

Examples of good variable names include the following:

- `price`
- `discount`
- `pShape`
- `value_`
- `COUNT`

`8_Ball`, `7Up`, and `6_pack` are not legal. Neither is `Hash!` nor `Mary-Ann`. This last example is a common mistake, although `Mary_Ann` with an underscore in place of the hyphen would be quite acceptable. Of course, `Mary Ann` would not be, because blanks are not allowed in variable names. Note that the variable names `republican` and `Republican` are quite different, as names are case-sensitive, so upper- and lowercase letters are differentiated. Of course, whitespace characters in general cannot appear within a name, and if you inadvertently include whitespace characters, you will have two or more names instead of one, which will usually cause the compiler to complain.

A convention that is often adopted in C++ is to reserve names beginning with a capital letter for naming classes and use names beginning with a lowercase letter for variables. I'll discuss classes in Chapter 8.

Keywords in C++

There are reserved words in C++ called *keywords* that have special significance within the language. They will be highlighted with a particular color by the Visual C++ editor as you enter your program — in my system, the default color is blue. If a keyword you type does not appear highlighted, then you have entered the keyword incorrectly. Incidentally, if you don't like the default colors used by the text editor, you can change them by selecting Options from the Tools menu and making changes when you select Environment/Fonts and Colors in the dialog.

Remember that keywords, like the rest of the C++ language, are case-sensitive. For example, the program that you entered earlier in the chapter contained the keywords `int` and `return`; if you write `Int` or `Return`, these are not keywords and, therefore, will not be recognized as such. You will see

many more as you progress through the book. You must ensure that the names you choose for entities in your program, such as variables, are not the same as any of the keywords in C++.

Declaring Variables

As you know, a variable *declaration* is a program statement that specifies the name of a variable of a given type. For example:

```
int value;
```

This declares a variable with the name `value` that can store integers. The type of data that can be stored in the variable `value` is specified by the keyword `int`, so you can only use `value` to store data of type `int`. Because `int` is a keyword, you can't use `int` as a name for one of your variables.

NOTE A variable declaration always ends with a semicolon.

A single declaration can specify the names of several variables, but it is generally better to declare variables in individual statements, one per line. I'll deviate from this from time to time in this book, but only in the interests of not spreading code over too many pages.

In order to store data (for example, an integer value), you not only need to have defined the name of the variable, you also need to have associated a piece of the computer's memory with the variable name. This process is called variable *definition*. In C++, a variable declaration is also a definition (except in a few special cases, which you will meet in the book). In the course of a single statement, you introduce the variable name, and also tie it to an appropriately sized piece of memory.

So, the statement

```
int value;
```

is both a declaration and a definition. You use the variable *name* `value` that you have declared to access the piece of the computer's *memory* that you have defined, and that can store a single value of type `int`.

NOTE The reason for this apparently pedantic differentiation between a declaration and a definition is that you will meet statements that are declarations but not definitions.

You must declare a variable at some point between the beginning of your program and when the variable is used for the first time. In C++, it is good practice to declare variables close to their first point of use.

Initial Values for Variables

When you declare a variable, you can also assign an initial value to it. A variable declaration that assigns an initial value to a variable is called an *initialization*. To initialize a variable when you

declare it, you just need to write an equals sign followed by the initializing value after the variable name. You can write the following statements to give each of the variables an initial value:

```
int value = 0;  
int count = 10;  
int number = 5;
```

In this case, `value` will have the value 0, `count` will have the value 10, and `number` will have the value 5.

There is another way of writing the initial value for a variable in C++ called *functional notation*. Instead of an equals sign and the value, you can simply write the value in parentheses following the variable name. So, you could rewrite the previous statements as:

```
int value(0);  
int count(10);  
int number(5);
```

Generally, it's a good idea to use either one notation or the other consistently. However, I'll use one notation in some examples and the other notation in others, so you get used to seeing both of them in working code.

If you don't supply an initial value for a variable, then it will usually contain whatever garbage was left in the memory location it occupies by the previous program you ran (there is an exception to this that you will meet later in this chapter). Wherever possible, you should initialize your variables when you declare them. If your variables start out with known values, it makes it easier to work out what is happening when things go wrong. And one thing you can be sure of — things *will* go wrong.

FUNDAMENTAL DATA TYPES

The sort of information that a variable can hold is determined by its *data type*. All data and variables in your program must be of some defined type. C++ provides you with a range of *fundamental data types*, specified by particular keywords. Fundamental data types are so called because they store values of types that represent fundamental data in your computer, essentially numerical values, which also includes characters because every character is represented by a unique numerical character code. You have already seen the keyword `int` for defining integer variables.

The fundamental types fall into three categories:

- Types that store integers
- Types that store non-integral values, called floating-point types
- The `void` type that specifies an empty set of values or no type

Integer Variables

Integer variables are variables that can have only values that are whole numbers. The number of players in a football team is an integer, at least at the beginning of the game. You already know that you can

declare integer variables using the keyword `int`. Variables of type `int` occupy 4 bytes in memory and can store both positive and negative integer values. The upper and lower limits for the values of a variable of type `int` correspond to the maximum and minimum signed binary numbers, which can be represented by 32 bits. The upper limit for a variable of type `int` is $2^{31}-1$, which is 2,147,483,647, and the lower limit is $-(2^{31})$, which is -2,147,483,648. Here's an example of defining a variable of type `int`:

```
int toeCount = 10;
```

The keyword `short` also defines an integer variable, this time occupying 2 bytes. The keyword `short` is equivalent to `short int`, and you could define two variables of type `short` with the following statements:

```
short feetPerPerson = 2;
short int feetPerYard = 3;
```

Both variables are of the same type here because `short` means exactly the same as `short int`. I used both forms of the type name to show them in use, but it would be best to stick to one representation of the type in your programs, and of the two, `short` is used most often.

C++ also provides the integer type, `long`, which can also be written as `long int`. Here's how you declare variables of type `long`:

```
long bigNumber = 1000000L;
long largeValue = 0L;
```

Of course, you could also use functional notation when specifying the initial values:

```
long bigNumber(1000000L);
long largeValue(0L);
```

These statements declare the variables `bigNumber` and `largeValue` with initial values 1000000 and 0, respectively. The letter `L` appended to the end of the literals specifies that they are integers of type `long`. You can also use the small letter `l` for the same purpose, but it has the disadvantage that it is easily confused with the digit 1. Integer literals without an `L` appended are of type `int`.

NOTE You must not include commas when writing large numeric values in a program. In text you might write the number 12,345, but in your program code you must write this as 12345.

Integer variables declared as `long` in Visual C++ occupy 4 bytes and can have values from -2,147,483,648 to 2,147,483,647. This is the same range as for variables declared as type `int`.

NOTE With other C++ compilers, variables of type `long` (which is the same as type `long int`) may not be the same as type `int`, so if you expect your programs to be compiled in other environments, don't assume that `long` and `int` are equivalent. For truly portable code, you should not even assume that an `int` is 4 bytes.

If you need to store integers of an even greater magnitude, you can use variables of type `long long`:

```
long long huge = 100000000LL;
```

Variables of type `long long` occupy 8 bytes and can store values from -9,223,372,036,854,775,808 to 9,223,372,036,854,775,807. The suffix to identify an integer constant as type `long long` is `LL` or `ll`, but the latter is best avoided because it looks like eleven.

Character Data Types

The `char` data type serves a dual purpose. It specifies a one-byte variable that you can use either to store integers within a given range, or to store the code for a single *ASCII* character, which is the *American Standard Code for Information Interchange*. You can declare a `char` variable with this statement:

```
char letter = 'A';
```

Or you could write this as:

```
char letter('A');
```

This declares the variable with the name `letter` and initializes it with the constant '`A`'. Note that you specify a value that is a single character between single quotes, rather than the double quotes used previously for defining a string of characters to be displayed. A string of characters is a series of values of type `char` that are grouped together into a single entity called an *array*. I'll discuss arrays and how strings are handled in C++ in Chapter 4.

Because the character '`A`' is represented in ASCII by the decimal value 65, you could have written the statement as:

```
char letter = 65; // Equivalent to A
```

This produces the same result as the previous statement. The range of integers that can be stored in a variable of type `char` with Visual C++ is from -128 to 127.

NOTE *The C++ standard does not require that type `char` should represent signed 1-byte integers. It is the compiler implementer's choice as to whether type `char` represents signed integers in the range -128 to +127 or unsigned integers in the range 0 to 255. You need to keep this in mind if you are porting your C++ code to a different environment.*

The type `wchar_t` is so called because it is a *wide character type*, and variables of this type store 2-byte character codes with values in the range from 0 to 65,535. Here's an example of defining a variable of type `wchar_t`:

```
wchar_t letter = L'Z'; // A variable storing a 16-bit character code
```

This defines a variable, `letter`, that is initialized with the 16-bit code for the letter Z. The `L` preceding the character constant, '`Z`', tells the compiler that this is a 16-bit character code value. A `wchar_t` variable stores Unicode code values.

You could have used functional notation here, too:

```
wchar_t letter(L'Z');           // A variable storing a 16-bit character code
```

You can also use hexadecimal constants to initialize integer variables, including those of type `char`, and it is obviously going to be easier to use this notation when character codes are available as hexadecimal values. A hexadecimal number is written using the standard representation for hexadecimal digits: 0 to 9, and A to F (or a to f) for digits with values from 10 to 15. It's also prefixed by `0x` (or `0X`) to distinguish it from a decimal value. Thus, to get exactly the same result again, you could rewrite the last statement as follows:

```
wchar_t letter(0x5A);           // A variable storing a 16-bit character code
```

NOTE *Don't write decimal integer values with a leading zero. The compiler will interpret such values as octal (base 8), so a value written as 065 will be equivalent to 53 in normal decimal notation.*

Notice that Microsoft Windows provides a Character Map utility that enables you to locate characters from any of the fonts available to Windows. It will show the character code in hexadecimal and tell you the keystroke to use for entering the character. You'll find the Character Map utility in Windows 7 if you click on the Start button and look in the System Tools folder that is within the Accessories folder.

Integer Type Modifiers

Variables of the types `char`, `int`, `short`, `long`, or `long long` store signed integer values by default, so you can use these types to store either positive or negative values. This is because these types are assumed to have the default *type modifier* `signed`. So, wherever you wrote `int` or `long`, you could have written `signed int` or `signed long`, respectively.

You can also use the `signed` keyword by itself to specify the type of a variable, in which case, it means `signed int`. For example:

```
signed value = -5;           // Equivalent to signed int
```

This usage is not particularly common, and I prefer to use `int`, which makes it more obvious what is meant.

The range of values that can be stored in a variable of type `char` is from -128 to 127, which is the same as the range of values you can store in a variable of type `signed char`. In spite of this, type `char` and type `signed char` are different types, so you should not make the mistake of assuming they are the same. Whether type `char` is `signed` or `unsigned` is implementation defined in general. Visual C++ happens to define it as `signed char` but it may be different with other compilers.

If you are sure that you don't need to store negative values in a variable (for example, if you were recording the number of miles you drive in a week), then you can specify a variable as `unsigned`:

```
unsigned long mileage = 0UL;
```

Here, the minimum value that can be stored in the variable `mileage` is zero, and the maximum value is 4,294,967,295 (that's $2^{32}-1$). Compare this to the range of -2,147,483,648 to 2,147,483,647 for a signed `long`. The bit that is used in a signed variable to determine the sign of the value is used in an unsigned variable as part of the numeric value instead. Consequently, an unsigned variable has a larger range of positive values, but it can't represent a negative value. Note how a `U` (or `u`) is appended to unsigned constants. In the preceding example, I also have `L` appended to indicate that the constant is `long`. You can use either upper- or lowercase for `U` and `L`, and the sequence is unimportant. However, it's a good idea to adopt a consistent way of specifying such values.

You can also use `unsigned` by itself as the type specification for a variable, in which case, you are specifying the variable to be of type `unsigned int`.

NOTE Remember, both `signed` and `unsigned` are keywords, so you can't use them as variable names.

The Boolean Type

Boolean variables are variables that can have only two values: a value called `true` and a value called `false`. The type for a logical variable is `bool`, named after George Boole, who developed Boolean algebra, and type `bool` is regarded as an integer type. Boolean variables are also referred to as *logical variables*. Variables of type `bool` are used to store the results of tests that can be either `true` or `false`, such as whether one value is equal to another.

You could declare the name of a variable of type `bool` with the statement:

```
bool testResult;
```

Of course, you can also initialize variables of type `bool` when you declare them:

```
bool colorIsRed = true;
```

Or like this:

```
bool colorIsRed(true);
```

NOTE You will find that the values `TRUE` and `FALSE` are used quite extensively with variables of numeric type, and particularly of type `int`. This is a hangover from the time before variables of type `bool` were implemented in C++ when variables of type `int` were typically used to represent logical values. In this case a zero value is treated as `false` and a non-zero value as `true`. The symbols `TRUE` and `FALSE` are still used within the MFC where they represent a non-zero integer value and 0, respectively. Note that `TRUE` and `FALSE` — written with capital letters — are not keywords in C++; they are just symbols defined within the MFC. Note also that `TRUE` and `FALSE` are not legal `bool` values, so don't confuse `true` with `TRUE`.

Floating-Point Types

Values that aren't integral are stored as *floating-point* numbers. A floating-point number can be expressed as a decimal value such as 112.5, or with an exponent such as 1.125E2 where the decimal part is multiplied by the power of 10 specified after the E (for Exponent). Our example is, therefore, 1.125×10^2 , which is 112.5.

NOTE A floating-point constant must contain a decimal point, or an exponent, or both. If you write a numerical value with neither, you have an integer.

You can specify a floating-point variable using the keyword `double`, as in this statement:

```
double in_to_mm = 25.4;
```

A variable of type `double` occupies 8 bytes of memory and stores values accurate to approximately 15 decimal digits. The range of values stored is much wider than that indicated by the 15 digits accuracy, being from 1.7×10^{-308} to 1.7×10^{308} , positive and negative.

If you don't need 15 digits' precision, and you don't need the massive range of values provided by `double` variables, you can opt to use the keyword `float` to declare floating-point variables occupying 4 bytes. For example:

```
float pi = 3.14159f;
```

This statement defines a variable `pi` with the initial value 3.14159. The `f` at the end of the constant specifies that it is of type `float`. Without the `f`, the constant would have been of type `double`. Variables that you declare as `float` have approximately 7 decimal digits of precision and can have values from 3.4×10^{-38} to 3.4×10^{38} , positive and negative.

The C++ standard also defines the `long double` floating-point type, which is implemented with the same range and precision as type `double` in Visual C++. With some compilers, `long double` corresponds to a 16-byte floating-point value with a much greater range and precision than type `double`.

Fundamental Types in C++

The following table contains a summary of all the fundamental types in C++ and the range of values that are supported for these in Visual C++:

TYPE	SIZE IN BYTES	RANGE OF VALUES
<code>bool</code>	1	<code>true</code> or <code>false</code>
<code>char</code>	1	By default, the same as type <code>signed char</code> : -128 to 127. Optionally, you can make <code>char</code> the same range as type <code>unsigned char</code> .
<code>signed char</code>	1	-128 to 127

continues

(continued)

TYPE	SIZE IN BYTES	RANGE OF VALUES
unsigned char	1	0 to 255
wchar_t	2	0 to 65,535
short	2	-32,768 to 32,767
unsigned short	2	0 to 65,535
int	4	-2,147,483,648 to 2,147,483,647
unsigned int	4	0 to 4,294,967,295
long	4	-2,147,483,648 to 2,147,483,647
unsigned long	4	0 to 4,294,967,295
long long	8	-9,223,372,036,854,775,808 to 9,223,372,036,854,775,807
unsigned long long	8	0 to 18,446,744,073,709,551,615
float	4	$\pm 3.4 \times 10^{\pm 38}$ with approximately 7-digits accuracy
double	8	$\pm 1.7 \times 10^{\pm 308}$ with approximately 15-digits accuracy
long double	8	$\pm 1.7 \times 10^{\pm 308}$ with approximately 15-digits accuracy

Literals

I have already used a lot of explicit constants to initialize variables. In C++, constant values of any kind are referred to as *literals*. A literal is a value of a specific type, so values such as 23, 3.14159, 9.5f, and true are examples of literals of type int, type double, type float, and type bool, respectively. The literal "Samuel Beckett" is an example of a literal that is a string, but I'll defer discussion of exactly what type this is until Chapter 4. Here's a summary of how you write literals of various types:

TYPE	EXAMPLES OF LITERALS
char, signed char, or unsigned char	'A', 'Z', '8', '*'
wchar_t	L'A', L'Z', L'8', L'*'
int	-77, 65, 12345, 0x9FE
unsigned int	10U, 64000u
long	-77L, 65L, 12345L

TYPE	EXAMPLES OF LITERALS
unsigned long	5UL, 999999UL, 25ul, 35U1
long long	-777LL, 66LL, 123456711
unsigned long long	55ULL, 999999999ULL, 885ull, 445U11
float	3.14f, 34.506F
double	1.414, 2.71828
long double	1.414L, 2.718281
bool	true, false

You can't specify a literal to be of type `short` or `unsigned short`, but the compiler will accept initial values that are literals of type `int` for variables of these types, provided the value of the literal is within the range of the variable type.

You will often need to use literals in calculations within a program, for example, conversion values such as 12 for feet to inches or 25.4 for inches to millimeters, or a string to specify an error message. However, you should avoid using numeric literals explicitly where their significance is not obvious. It is not necessarily apparent to everyone that 2.54 is the number of centimeters in an inch. It is better to declare a variable with a fixed value corresponding to your literal — you might name the variable `inchesToCentimeters`, for example. Then, wherever you use `inchesToCentimeters` in your code, it will be quite obvious what it is. You will see how to fix the value of a variable a little later on in this chapter.

Defining Synonyms for Data Types

The `typedef` keyword enables you to define your own type name for an existing type. Using `typedef`, you could define the type name `BigOnes` as equivalent to the standard `long int` type with the declaration:

```
typedef long int BigOnes;           // Defining BigOnes as a type name
```

This defines `BigOnes` as an alternative type specifier for `long int`, so you could declare a variable `mynum` as `long int` with the declaration:

```
BigOnes mynum = 0L;                // Define a long int variable
```

There's no difference between this declaration and the one using the built-in type name. You could equally well use

```
long int mynum = 0L;                // Define a long int variable
```

for exactly the same result. In fact, if you define your own type name such as `BigOnes`, you can use both type specifiers within the same program for declaring different variables that will end up as having the same type.

Because `typedef` only defines a synonym for an existing type, it may appear to be a bit superficial, but it is not at all. You'll see later that it fulfills a very useful role in enabling you to simplify more complex declarations by defining a single name that represents a somewhat convoluted type specification. This can make your code much more readable.

BASIC INPUT/OUTPUT OPERATIONS

Here, you will only look at enough of C++ input and output to get you through learning about C++. It's not that it's difficult — quite the opposite, in fact — but for Windows programming, you won't need it at all. C++ input/output incorporates the notion of a data stream. You can insert data into an output stream or extract data from an input stream. You have already seen that the standard output stream to the command line on the screen is referred to as `cout`. The complementary input stream from the keyboard is referred to as `cin`. Of course, both stream names are defined within the `std` namespace.

Input from the Keyboard

You obtain input from the keyboard through the standard input stream, `cin`, using the extraction operator for a stream, `>>`. To read two integer values from the keyboard into integer variables `num1` and `num2`, you can write this statement:

```
std::cin >> num1 >> num2;
```

The *extraction operator*, `>>`, “points” in the direction that data flows — in this case, from `cin` to each of the two variables in turn. Any leading whitespace is skipped, and the first integer value you key in is read into `num1`. This is because the input statement executes from left to right. Any whitespace following `num1` is ignored, and the second integer value that you enter is read into `num2`. There has to be some whitespace between successive values, though, so that they can be differentiated. The stream input operation ends when you press the Enter key, and execution then continues with the next statement. Of course, errors can arise if you key in the wrong data, but I will assume that you always get it right!

Floating-point values are read from the keyboard in exactly the same way as integers, and of course, you can mix the two. The stream input operations automatically deal with variables and data of any of the fundamental types. For example, in the statements,

```
int num1 = 0, num2 = 0;
double factor = 0.0;
std::cin >> num1 >> factor >> num2;
```

the last line will read an integer into `num1`, then a floating-point value into `factor`, and finally, an integer into `num2`.

Output to the Command Line

You have already seen output to the command line, but I'll revisit it anyway. Writing information to the display operates in a complementary fashion to input. As you have seen, the standard output stream is called `cout`, and you use the insertion operator, `<<`, to transfer data to the output stream. This operator

also “points” in the direction of data movement. You have already used this operator to output a text string. I can demonstrate the process of outputting the value of a variable with a simple program.

TRY IT OUT Output to the Command Line

I'll assume that you've got the hang of creating a new empty project by adding a new source file to the project and building it into an executable. Here's the code that you need to put in the source file once you have created the `Ex2_02` project:

```
// Ex2_02.cpp
// Exercising output
#include <iostream>

using std::cout;
using std::endl;

int main()
{
    int num1 = 1234, num2 = 5678;
    cout << endl;                                // Start on a new line
    cout << num1 << num2;                        // Output two values
    cout << endl;                                // End on a new line
    return 0;                                     // Exit program
}
```

How It Works

Because you have `using` declarations for `std::cout` and `std::endl`, you can use the unqualified stream names in the code. The first statement in the body of `main()` declares and initializes two integer variables, `num1` and `num2`. This is followed by three output statements, the first of which moves the screen cursor position to a new line. Because output statements execute from left to right, the second output statement displays the value of `num1` followed by the value of `num2`.

When you compile and execute this, you will get the output:

```
12345678
```

The output is correct, but it's not exactly helpful. You really need the two output values to be separated by at least one space. The default for stream output is to just output the digits in the output value, which doesn't provide for spacing successive output values out nicely so they can be differentiated. As it is, you have no way to tell where the first number ends and the second number begins.

Formatting the Output

You can fix the problem of there being no spaces between items of data quite easily, though, just by outputting a space between the two values. You can do this by replacing the following line in your original program:

```
cout << num1 << num2;                      // Output two values
```

Just substitute the statement:

```
cout << num1 << ' ' << num2; // Output two values
```

Of course, if you had several rows of output that you wanted to align in columns, you would need some extra capability because you do not know how many digits there will be in each value. You can take care of this situation by using what is called a *manipulator*. A manipulator modifies the way in which data output to (or input from) a stream is handled.

Manipulators are defined in the standard library header file `iomanip`, so you need an `#include` directive for it. The manipulator that you'll use is `setw(n)`. This causes the output value that follows to be right-justified in a field that is `n` spaces wide, so `setw(6)` causes the next output value to be presented in a field with a width of six spaces. Let's see it working.

TRY IT OUT Using Manipulators

To get something more like the output you want, you can change the program to the following:

```
// Ex2_03.cpp
// Exercising output
#include <iostream>
#include <iomanip>

using std::cout;
using std::endl;
using std::setw;

int main()
{
    int num1 = 1234, num2 = 5678;
    cout << endl; // Start on a new line
    cout << setw(6) << num1 << setw(6) << num2; // Output two values
    cout << endl; // Start on a new line
    return 0; // Exit program
}
```

How It Works

The changes from the last example are the addition of the `#include` directive for the `iomanip` header file, the addition of a `using` declaration for the `setw` name in the `std` namespace, and the insertion of the `setw()` manipulator in the output stream preceding each value so that the output values are presented in a field six characters wide. Now you get nice, neat output where you can actually separate the two values:

```
1234 5678
```

Note that the `setw()` manipulator works only for the single output value immediately following its insertion into the stream. You have to insert the manipulator into the stream immediately preceding each value that you want to output within a given field width. If you put only one `setw()`, it would apply to the first value to be output after it was inserted. Following values would be output in the default manner. You could try this out by deleting the second `setw(6)` and its insertion operator in the example.

Another useful manipulator that is defined in the `iomanip` header is `std::setiosflags`. This enables you to have the output left-aligned in a given field width instead of right-aligned by default. Here's how you can do that:

```
cout << std::setiosflags(std::ios::left);
```

You can also use the `std::setiosflags` manipulator to control the appearance of numerical output, so it is worth exploring.

Escape Sequences

When you write a character string between double quotes, you can include special character sequences called *escape sequences* in it. They are called escape sequences because they allow characters to be included in a string that otherwise could not be represented, and they do this by escaping from the default interpretation of the characters. An escape sequence starts with a backslash character, `\`, and the backslash character cues the compiler to interpret the character that follows in a special way. For example, a tab character is written as `\t`, so the `t` is understood by the compiler to represent a tab in the string, and not the letter `t`. Look at these two output statements:

```
cout << endl << "This is output.";
cout << endl << "\tThis is output after a tab.";
```

They will produce these lines:

```
This is output.
This is output after a tab.
```

The `\t` in the second output statement causes the output text to be indented to the first tab position.

In fact, instead of using `endl`, you could use the escape sequence for the newline character, `\n`, in each string, so you could rewrite the preceding statements as follows:

```
cout << "\nThis is output.";
cout << "\n\tThis is output after a tab.";
```

Note that `\n` is not quite the same as `endl`. `endl` will output a newline and flush the stream, while `\n` will output the newline without flushing the stream.

Here are some escape sequences that may be particularly useful:

ESCAPE SEQUENCE	WHAT IT DOES	ESCAPE SEQUENCE	WHAT IT DOES
<code>\a</code>	Sounds a beep	<code>\b</code>	Backspace
<code>\n</code>	Newline	<code>\t</code>	Tab
<code>\'</code>	Single quote	<code>\"</code>	Double quote
<code>\\"</code>	Backslash	<code>\?</code>	Question mark

Obviously, if you want to be able to include a backslash or a double quote as a character to appear in a string, you must use the appropriate escape sequences to represent them. Otherwise, the backslash would be interpreted as the start of another escape sequence, and the double quote would indicate the end of the character string.

NOTE You can put a question mark is a string. The \? escape sequence is there to avoid conflicts with trigraphs, which are a C language construct consisting of three characters that begin with ?? for defining characters that otherwise could not be specified.

You can also use characters specified by escape sequences in the initialization of variables of type `char`. For example:

```
char Tab = '\t'; // Initialize with tab character
```

Because a character literal is delimited by single quote characters, you must use '\'' to specify a character literal that is a single quote.

TRY IT OUT Using Escape Sequences

Here's a program that uses some of the escape sequences from the table in the previous section:

```
// Ex2_04.cpp
// Using escape sequences
#include <iostream>

using std::cout;

int main()
{
    char newline = '\n'; // Newline escape sequence
    cout << newline; // Start on a new line
    cout << "\"We'll make our escapes in sequence\", he said.";
    cout << "\n\tThe program's over, it's time to make a beep beep.\a\a";
    cout << newline; // Start on a new line
    return 0; // Exit program
}
```

If you compile and execute this example, it will produce the following output:

```
"We'll make our escapes in sequence", he said.
The program's over, it's time to make a beep beep.
```

How It Works

The first line in `main()` defines the variable `newline` and initializes it with a character defined by the escape sequence for a new line. You can then use `newline` instead of `endl` from the standard library.

After writing newline to cout, you output a string that uses the escape sequences for a double quote (\") and a single quote ('\'). You don't have to use the escape sequence for a single quote here because the string is delimited by double quotes, and the compiler will recognize a single quote character as just that, and not a delimiter. You must use the escape sequence for the double quote in a string, though. The second string starts with a newline followed by a tab, so the output line is indented by the tab distance. The string also ends with two instances of the escape sequence for a beep, so you should hear a double beep from your PC.

CALCULATING IN C++

This is where you actually start doing something with the data that you enter. You know how to carry out simple input and output; now, you are beginning the bit in the middle, the “processing” part of a C++ program. Almost all of the computational aspects of C++ are fairly intuitive, so you should slice through this like a hot knife through butter.

The Assignment Statement

You have already seen examples of the assignment statement. A typical assignment statement looks like this:

```
whole = part1 + part2 + part3;
```

The assignment statement enables you to calculate the value of an expression that appears on the right-hand side of the equals sign, in this case, the sum of part1, part2, and part3, and store the result in the variable specified on the left-hand side, in this case, the variable with the name whole. In this statement, the whole is exactly the sum of its parts, and no more.

NOTE Note how the statement, as always, ends with a semicolon.

You can also write repeated assignments, such as:

```
a = b = 2;
```

This is equivalent to assigning the value 2 to b and then assigning the value of b to a, so both variables will end up storing the value 2.

Arithmetic Operations

The basic arithmetic operators are addition, subtraction, multiplication, and division, represented by the symbols +, -, *, and /, respectively. Generally, these operate as you would expect, with the exception of division, which has a slight aberration when working with integer variables or constants, as you'll see. You can write statements such as the following:

```
netPay = hours * rate - deductions;
```

Here, the product of hours and rate will be calculated and then deductions subtracted from the value produced. The multiply and divide operators are executed before addition and subtraction, as you would expect. I will discuss the order of execution of the various operators in expressions more fully later in this chapter. The overall result of evaluating the expression hours * rate - deductions will be stored in the variable netPay.

The minus sign used in the last statement has two operands — it subtracts the value of its right operand from the value of its left operand. This is called a *binary operation* because two values are involved. The minus sign can also be used with one operand to change the sign of the value to which it is applied, in which case it is called a *unary minus*. You could write this:

```
int a = 0;
int b = -5;
a = -b;                                // Changes the sign of the operand
```

Here, a will be assigned the value +5 because the unary minus changes the sign of the value of the operand b.

Note that an assignment is not the equivalent of the equations you saw in high-school algebra. It specifies an action to be carried out rather than a statement of fact. The expression to the right of the assignment operator is evaluated and the result is stored in the location specified on the left.

NOTE Typically, the expression on the left of an assignment is a single variable name but it doesn't have to be. It can be an expression of some kind but if it is an expression then the result of evaluating it must be an lvalue. An lvalue, as you will see later, is a persistent location in memory where the result of the expression to the right of the assignment operator can be stored.

Look at this statement:

```
number = number + 1;
```

This means “add 1 to the current value stored in number and then store the result back in number.” As a normal algebraic statement, it wouldn't make sense, but as a programming action, it obviously does.

TRY IT OUT Exercising Basic Arithmetic

You can exercise basic arithmetic by calculating how many standard rolls of wallpaper are needed to paper a room. The following example does this:

```
// Ex2_05.cpp
// Calculating how many rolls of wallpaper are required for a room
#include <iostream>

using std::cout;
using std::cin;
using std::endl;

int main()
```

```

{
    double height = 0.0, width = 0.0, length = 0.0; // Room dimensions
    double perimeter = 0.0;                         // Room perimeter

    const double rollWidth = 21.0;                   // Standard roll width
    const double rollLength = 12.0*33.0;             // Standard roll length(33ft.)

    int strips_per_roll = 0;                         // Number of strips in a roll
    int strips_reqd = 0;                            // Number of strips needed
    int nrolls = 0;                                // Total number of rolls

    cout << endl                                     // Start a new line
        << "Enter the height of the room in inches: ";
    cin >> height;

    cout << endl                                     // Start a new line
        << "Now enter the length and width in inches: ";
    cin >> length >> width;

    strips_per_roll = rollLength / height;           // Get number of strips per roll
    perimeter = 2.0*(length + width);                // Calculate room perimeter
    strips_reqd = perimeter / rollWidth;              // Get total strips required
    nrolls = strips_reqd / strips_per_roll;            // Calculate number of rolls

    cout << endl
        << "For your room you need " << nrolls << " rolls of wallpaper."
        << endl;

    return 0;
}

```

Unless you are more adept than I am at typing, chances are, there will be a few errors when you compile this for the first time. Once you have fixed the typos, it will compile and run just fine. You'll get a couple of warning messages from the compiler. Don't worry about them — the compiler is just making sure you understand what's going on. I'll explain the reason for the warning messages in a moment.

How It Works

One thing needs to be clear at the outset — I assume no responsibility for you running out of wallpaper as a result of using this program! As you'll see, all errors in the estimate of the number of rolls required are due to the way C++ works and to the wastage that inevitably occurs when you hang your own wallpaper — usually 50 percent plus!

I'll work through the statements in this example in sequence, picking out the interesting, novel, or even exciting features. The statements down to the start of the body of `main()` are familiar territory by now, so I will take those for granted.

A couple of general points about the layout of the program are worth noting. First, the statements in the body of `main()` are indented to make the extent of the body easier to see, and second, various groups of statements are separated by a blank line to indicate that they are functional groups. Indenting statements is a fundamental technique in laying out program code in C++. You will see that this is applied universally to provide visual cues to help you identify the various logical blocks in a program.

The `const` Modifier

You have a block of declarations for the variables used in the program right at the beginning of the body of `main()`. These statements are also fairly familiar, but there are two that contain some new features:

```
const double rollWidth = 21.0;           // Standard roll width
const double rollLength = 12.0*33.0;      // Standard roll length(33ft.)
```

They both start out with a new keyword: `const`. This is a *type modifier* that indicates that the variables are not just of type `double`, but are also constants. Because you effectively tell the compiler that these are constants, the compiler will check for any statements that attempt to change the values of these variables, and if it finds any, it will generate an error message. You could check this out by adding, anywhere after the declaration of `rollWidth`, a statement such as:

```
rollWidth = 0;
```

You will find the program no longer compiles, returning 'error C3892: 'rollWidth' : you cannot assign to a variable that is `const`'.

It can be very useful to define constants that you use in a program by means of `const` variable types, particularly when you use the same constant several times in a program. For one thing, it is much better than sprinkling literals throughout your program that may not have blindingly obvious meanings; with the value 42 in a program, you could be referring to the meaning of life, the universe, and everything, but if you use a `const` variable with the name `myAge` that has a value of 42, it becomes obvious that you are not. For another thing, if you change the value of a `const` variable that you are using, the change will take effect everywhere you use it in a source file. If you use explicit literals, you have to change all occurrences individually.

Constant Expressions

The `const` variable `rollLength` is initialized with an arithmetic expression (`12.0*33.0`). Being able to use constant expressions to initialize variables saves having to work out the value yourself. It can also be more meaningful, as it is in this case, because 33 feet times 12 inches is a much clearer expression of what the value represents than simply writing 396. The compiler will generally evaluate constant expressions accurately, whereas if you do it yourself, depending on the complexity of the expression and your ability to number-crunch, there is a finite probability that it may be wrong.

You can use any expression that can be calculated as a constant at compile time, including `const` variables that you have already defined. So, for instance, if it were useful in the program to do so, you could declare the area of a standard roll of wallpaper as:

```
const double rollArea = rollWidth*rollLength;
```

This statement would need to be placed after the declarations for the two `const` variables used in the initialization of `rollArea`, because all the variables that appear in a constant expression must be known to the compiler at the point in the source file where the constant expression appears.

Program Input

After declaring some integer variables, the next four statements in the program handle input from the keyboard:

```
cout << endl // Start a new line
    << "Enter the height of the room in inches: ";
cin >> height;

cout << endl // Start a new line
    << "Now enter the length and width in inches: ";
cin >> length >> width;
```

Here, you write text to cout to prompt for the input required, and then read the input from the keyboard using cin, the standard input stream. You first obtain the value for the room height and then read the length and width, successively. In a practical program, you would need to check for errors and possibly make sure that the values that are read are sensible, but you don't have enough knowledge to do that yet!

Calculating the Result

You have four statements involved in calculating the number of standard rolls of wallpaper required for the size of the room:

```
strips_per_roll = rollLength / height; // Get number of strips in a roll
perimeter = 2.0*(length + width); // Calculate room perimeter
strips_reqd = perimeter / rollWidth; // Get total strips required
nrolls = strips_reqd / strips_per_roll; // Calculate number of rolls
```

The first statement calculates the number of strips of paper with a length corresponding to the height of the room that you can get from a standard roll, by dividing one into the other. So, if the room is 8 feet high, you divide 96 into 396, which would produce the floating-point result 4.125. There is a subtlety here, however. The variable where you store the result, strips_per_roll, was declared as int, so it can store only integer values. Consequently, any floating-point value to be stored as an integer is rounded down to the nearest integer, 4 in this case, and this value is stored. This is actually the result that you want here because, although they may fit under a window or over a door, fractions of a strip are best ignored when estimating.

The conversion of a value from one type to another is called *type conversion*. This particular example is called an *implicit type conversion*, because the code doesn't explicitly state that a conversion is needed, and the compiler has to work it out for itself. The two warnings you got during compilation were issued because information could be lost as a result of the implicit conversion that were inserted due to the process of changing a value from one type to another.

You should beware when your code necessitates implicit conversions. Compilers do not always supply a warning that an implicit conversion is being made, and if you are assigning a value of one type to a variable of a type with a lesser range of values, there is always a danger that you will lose information. If there are implicit conversions in your program that you have included accidentally, they may represent bugs that may be difficult to locate.

Where a conversion that may result in the loss of information is unavoidable, you can specify the conversion explicitly to demonstrate that it is no accident and that you really meant to do it. You do this by making an *explicit type conversion* or *cast* of the value on the right of the assignment to `int`, so the statement would become:

```
strips_per_roll = static_cast<int>(rollLength / height); // Get number  
// of strips in  
// a roll
```

The addition of `static_cast<int>` with the parentheses around the expression on the right tells the compiler explicitly that you want to convert the value of the expression between the parentheses to type `int`. Although this means that you still lose the fractional part of the value, the compiler assumes that you know what you are doing and will not issue a warning. You'll see more about `static_cast<>()` and other types of explicit type conversion later in this chapter.

Note how you calculate the perimeter of the room in the next statement. To multiply the sum of the `length` and the `width` by 2.0, you enclose the expression summing the two variables between parentheses. The parentheses ensure that the addition is performed first and the result is multiplied by 2.0 to produce the correct value for the perimeter. You can use parentheses to make sure that a calculation is carried out in the order you require because expressions in parentheses are always evaluated first. Where there are nested parentheses, the expressions within the parentheses are evaluated in sequence, from the innermost to the outermost.

The third statement that calculates how many strips of paper are required to cover the room uses the same effect that you observed in the first statement: the result is rounded down to the nearest integer because it is to be stored in the integer variable, `strips_reqd`. This is not what you need in practice. It would be best to round up for estimating, but you don't have enough knowledge of C++ to do this yet. Once you have read the next chapter, you can come back and fix it!

The last arithmetic statement calculates the number of rolls required by dividing the number of strips required (an integer) by the number of strips in a roll (also an integer). Because you are dividing one integer by another, the result has to be an integer, and any remainder is ignored. This would still be the case if the variable `nrolls` were floating-point. The integer value resulting from the expression would be converted to floating-point form before it was stored in `nrolls`. The result that you obtain is essentially the same as if you had produced a floating-point result and rounded down to the nearest integer. Again, this is not what you want, so if you want to use this, you will need to fix it.

Displaying the Result

The following statement displays the result of the calculation:

```
cout << endl  
<< "For your room you need " << nrolls << " rolls of wallpaper."  
<< endl;
```

This is a single output statement spread over three lines. It first outputs a newline character and then the text string "For your room you need". This is followed by the value of the variable `nrolls`

and, finally, the text string " rolls of wallpaper.". As you can see, output statements are very easy in C++. You could have written the statement using escape characters for the newlines:

```
cout << "\nFor your room you need " << nrolls << " rolls of wallpaper.\n";
```

Finally, the program ends when this statement is executed:

```
return 0;
```

The value zero here is a return value that, in this case, will be returned to the operating system. You will see more about return values in Chapter 5.

Calculating a Remainder

You saw that dividing one integer value by another produces an integer result that ignores any remainder, so 11 divided by 4 gives the result 2. Because the remainder after division can be of great interest, particularly when you are dividing cookies amongst children, for example: C++ provides a special operator, %, for this. You can write the following statements to handle the cookie-sharing problem:

```
int residue = 0, cookies = 19, children = 5;
residue = cookies % children;
```

The variable `residue` will end up with the value 4, which is the number left after dividing 19 by 5. To calculate how many cookies each child receives, you just need to use division, as in the statement:

```
each = cookies / children;
```

Modifying a Variable

It's often necessary to modify the existing value of a variable, such as by incrementing it or doubling it. You could increment a variable called `count` using the statement:

```
count = count + 5;
```

This simply adds 5 to the current value stored in `count` and stores the result back in `count`, so if `count` started out as 10, it would end up as 15.

You also have an alternative, shorthand way of writing the same thing:

```
count += 5;
```

This says, "Take the value in `count`, add 5 to it, and store the result back in `count`." You can also use other operators with this notation:

```
count *= 5;
```

This multiplies the current value of `count` by 5 and stores the result back in `count`. In general, you can write statements of the form

```
lhs op= rhs;
```

lhs stands for any legal expression for the left-hand side of the statement and is usually (but not necessarily) a variable name.

rhs stands for any legal expression on the right-hand side of the statement.

op is any of the following operators:

+	-	
*	/	%
<<	>>	
&	^	

You have already met the first five of these operators, and you'll see the others, which are the shift and logical operators, later in this chapter.

The general form of the statement is equivalent to this:

```
lhs = lhs op (rhs);
```

The parentheses around *rhs* imply that this expression is evaluated first, and the result becomes the right operand for *op*.

This means that you can write statements such as:

```
a /= b + c;
```

This will be identical in effect to this statement:

```
a = a / (b + c);
```

The value of *a* is divided by the sum of *b* and *c*, and the result is stored back in *a*, overwriting the original value.

The Increment and Decrement Operators

I'll now introduce some unusual arithmetic operators called the *increment* and *decrement operators*. You will find them to be quite an asset once you get further into applying C++ in earnest. These are unary operators that you use to increment or decrement the value stored in a variable that holds an integral value. For example, assuming the variable *count* is of type *int*, the following three statements all have exactly the same effect:

```
count = count + 1;      count += 1;      ++count;
```

They each increment the variable *count* by 1. The last form, using the increment operator, is clearly the most concise.

The increment operator not only changes the value of the variable to which you apply it, but also results in a value. Thus, using the increment operator to increase the value of a variable by

1 can also appear as part of a more complex expression. If incrementing a variable using the `++` operator, as in `++count`, is contained within another expression, then the action of the operator is to *first* increment the value of the variable and *then* use the incremented value in the expression. For example, suppose `count` has the value 5, and you have defined a variable `total` of type `int`. Suppose you write the following statement:

```
total = ++count + 6;
```

This results in `count` being incremented to 6, and this result is added to 6, so `total` is assigned the value 12.

So far, you have written the increment operator, `++`, in front of the variable to which it applies. This is called the *prefix* form of the increment operator. The increment operator also has a *postfix* form, where you write the operator *after* the variable to which it applies; the effect of this is slightly different. The variable is incremented only *after* its value has been used in context. For example:

```
total = count++ + 6;
```

If `count` has the value 5, `total` is assigned the value 11, because the initial value of `count` is used to evaluate the expression before the increment is applied. The preceding statement is equivalent to the two statements:

```
total = count + 6;
++count;
```

The clustering of `+` signs in the preceding example of the postfix form is likely to lead to confusion. Generally, it isn't a good idea to write the increment operator in the way that I have written it here. It would be clearer to write:

```
total = 6 + count++;
```

Alternatively you could put parentheses around `count++`. Where you have an expression such as `a++ + b`, or even `a+++b`, it becomes less obvious what is meant or what the compiler will do. They are actually the same, but in the second case, you might really have meant `a + ++b`, which is different. It evaluates to one more than the other two expressions.

The rules that I have discussed in relation to the increment operator also apply to the decrement operator, `--`. For example, if `count` has the initial value 5, then the statement

```
total = --count + 6;
```

results in `total` having the value 10 assigned, whereas

```
total = 6 + count--;
```

sets the value of `total` to 11. Both operators are usually applied to integers, particularly in the context of loops, as you will see in Chapter 3. You will see in later chapters that they can also be applied to other data types in C++, notably variables that store addresses.

TRY IT OUT **The Comma Operator**

The comma operator allows you to specify several expressions where normally only one might occur. This is best understood by looking at an example that demonstrates how it works:

```
// Ex2_06.cpp
// Exercising the comma operator
#include <iostream>

using std::cout;
using std::endl;

int main()
{
    long num1(0L), num2(0L), num3(0L), num4(0L);

    num4 = (num1 = 10L, num2 = 20L, num3 = 30L);
    cout << endl
        << "The value of a series of expressions "
        << "is the value of the rightmost: "
        << num4;
    cout << endl;

    return 0;
}
```

How It Works

If you compile and run this program you will get this output:

```
The value of a series of expressions is the value of the rightmost: 30
```

This is fairly self-explanatory. The first statement in `main()` creates four variables, `num1` through `num4`, and initializes them to zero using functional notation. The variable `num4` receives the value of the last of the series of three assignments, the value of an assignment being the value assigned to the left-hand side. The parentheses in the assignment for `num4` are essential. You could try executing this without them to see the effect. Without the parentheses, the first expression separated by commas in the series will become:

```
num4 = num1 = 10L
```

So, `num4` will have the value `10L`.

Of course, the expressions separated by the comma operator don't have to be assignments. You could equally well write the following statements:

```
long num1(1L), num2(10L), num3(100L), num4(0L);
num4 = (++num1, ++num2, ++num3);
```

The effect of the assignment statement will be to increment the variables `num1`, `num2`, and `num3` by 1, and to set `num4` to the value of the last expression, which will be `101L`. This example is aimed at illustrating the effect of the comma operator and is not an example of how to write good code.

The Sequence of Calculation

So far, I haven't talked about how you arrive at the sequence of calculations involved in evaluating an expression. It generally corresponds to what you have learned at school when dealing with basic arithmetic operators, but there are many other operators in C++. To understand what happens with these, you need to look at the mechanism used in C++ to determine this sequence. It's referred to as *operator precedence*.

Operator Precedence

Operator precedence orders the operators in a priority sequence. In any expression, operators with the highest precedence are always executed first, followed by operators with the next highest precedence, and so on, down to those with the lowest precedence of all. The precedence of the operators in C++ is shown in the following table:

PRECEDENCE	OPERATORS	ASSOCIATIVITY
1	::	None
2	() [] -> . postfix ++ postfix -- typeid const_cast dynamic_cast static_cast reinterpret_cast	Left
3	logical not ! one's complement ~ unary + unary - prefix ++ prefix -- address-of & indirection * type cast (type) sizeof decltype new delete	Right
4	. * -> *	Left
5	* / %	Left
6	+ -	Left
7	<< >>	Left
8	== !=	Left
9	&	Left

continues

(continued)

PRECEDENCE	OPERATORS	ASSOCIATIVITY
10	<code>^</code>	Left
11	<code> </code>	Left
12	<code>&&</code>	Left
13	<code> </code>	Left
14	<code>? :</code> (conditional operator)	Right
15	<code>= *=/ %=/ += -= &=/ ^= = <<=/ >>=</code>	Right
16	<code>Throw</code>	Right
17	<code>,</code>	Left

There are a lot of operators here that you haven't seen yet, but you will know them all by the end of the book. Rather than spreading them around, I have put all the C++ operators in the precedence table so that you can always refer back to it if you are uncertain about the precedence of one operator relative to another.

Operators with the highest precedence appear at the top of the table. All the operators that appear in the same row in the table have equal precedence. If there are no parentheses in an expression, operators with equal precedence are executed in a sequence determined by their *associativity*. Thus, if the associativity is "left," the left-most operator in an expression is executed first, progressing through the expression to the right-most. This means that an expression such as `a + b + c + d` is executed as though it was written `((a + b) + c) + d` because binary `+` is left-associative.

Note that where an operator has a unary (working with one operand) and a binary (working with two operands) form, the unary form is always of a higher precedence and is, therefore, executed first.

NOTE You can always override the precedence of operators by using parentheses. Because there are so many operators in C++, it's sometimes hard to be sure what takes precedence over what. It is a good idea to insert parentheses to make sure. A further plus is that parentheses often make the code much easier to read.

TYPE CONVERSION AND CASTING

Calculations in C++ can be carried out only between values of the same type. When you write an expression involving variables or constants of different types, for each operation to be performed, the compiler has to arrange to convert the type of one of the operands to match that of the other. This process is called *implicit type conversion*. For example, if you want to add a `double` value to

a value of an integer type, the integer value is first converted to `double`, after which the addition is carried out. Of course, the variable that contains the value to be converted is, itself, not changed. The compiler will store the converted value in a temporary memory location, which will be discarded when the calculation is finished.

There are rules that govern the selection of the operand to be converted in any operation. Any expression to be calculated breaks down into a series of operations between two operands. For example, the expression `2*3-4+5` amounts to the series `2*3` resulting in 6, `6-4` resulting in 2, and finally `2+5` resulting in 7. Thus, the rules for converting the type of operands where necessary need to be defined only in terms of decisions about pairs of operands. So, for any pair of operands of different types, the compiler decides which operand to convert to the other considering types to be in the following rank from high to low:

1. <code>long double</code>	2. <code>double</code>	3. <code>float</code>
4. <code>unsigned long long</code>	5. <code>long long</code>	
6. <code>unsigned long</code>	7. <code>long</code>	
8. <code>unsigned int</code>	9. <code>int</code>	

Thus, if you have an operation where the operands are of type `long long` and type `unsigned int`, the latter will be converted to type `long long`. Any operand of type `char`, `signed char`, `unsigned char`, `short`, or `unsigned short` is at least converted to type `int` before an operation.

Implicit type conversions can produce some unexpected results. For example, consider the following statements:

```
unsigned int a(10u);
signed int b(20);
std::cout << a - b << std::endl;
```

You might expect this code fragment to output the value `-10`, but it doesn't. It outputs the value `4294967286`. This is because the value of `b` is converted to `unsigned int` to match the type of `a`, and the subtraction operation results in an unsigned integer value. This implies that if you have to write integer operations that apply to operands of different types, you should not rely on implicit type conversion to produce the result you want, unless you are quite certain it will do so.

Type Conversion in Assignments

As you saw in example `Ex2_05.cpp` earlier in this chapter, you can cause an implicit type conversion by writing an expression on the right-hand side of an assignment that is of a different type from the variable on the left-hand side. This can cause values to be changed and information to be lost. For instance, if you assign an expression that results in a `float` or `double` value to a variable of type `int` or a `long`, the fractional part of the `float` or `double` result will be lost, and just the integer part will be stored. (You may lose even more information if the value of your floating-point result exceeds the range of values available for the integer type concerned.)

For example, after executing the following code fragment,

```
int number = 0;
float decimal = 2.5f;
number = decimal;
```

the value of `number` will be 2. Note the `f` at the end of the constant `2.5f`. This indicates to the compiler that this constant is single-precision floating-point. Without the `f`, the default would have been type `double`. Any constant containing a decimal point is floating-point. If you don't want it to be double-precision, you need to append the `f`. A capital letter `F` would do the job just as well.

Explicit Type Conversion

With mixed expressions involving the basic types, your compiler automatically arranges casting where necessary, but you can also force a conversion from one type to another by using an explicit type conversion, which is also referred to as a *cast*. To cast the value of an expression to a given type, you write the cast in the form:

```
static_cast<the_type_to_convert_to>(expression)
```

The keyword `static_cast` reflects the fact that the cast is checked statically — that is, when your program is compiled. No further checks are made when you execute the program to see if this cast is safe to apply. Later, when you get to deal with classes, you will meet `dynamic_cast`, where the conversion is checked dynamically — that is, when the program is executing. There are also two other kinds of cast — `const_cast` for removing the `const`-ness of an expression, and `reinterpret_cast`, which is an unconditional cast — but I'll say no more about these here.

The effect of the `static_cast` operation is to convert the value that results from evaluating `expression` to the type that you specify between the angled brackets. The `expression` can be anything from a single variable to a complex expression involving lots of nested parentheses.

Here's a specific example of the use of `static_cast<>()`:

```
double value1 = 10.5;
double value2 = 15.5;
int whole_number = static_cast<int>(value1) + static_cast<int>(value2);
```

The initializing value for the variable `whole_number` is the sum of the integral parts of `value1` and `value2`, so they are each explicitly cast to type `int`. The variable `whole_number` will therefore have the initial value 25. The casts do *not* affect the values stored in `value1` and `value2`, which will remain as 10.5 and 15.5, respectively. The values 10 and 15 produced by the casts are just stored temporarily for use in the calculation and then discarded. Although both casts cause a loss of information in the calculation, the compiler will always assume that you know what you are doing when you specify a cast explicitly.

Also, as I described in `Ex2_05.cpp` relating to assignments involving different types, you can always make it clear that you know the cast is necessary by making it explicit:

```
strips_per_roll = static_cast<int>(rollLength / height); //Get number of strips
// in a roll
```

You can write an explicit cast for a numerical value to any numeric type, but you should be conscious of the possibility of losing information. If you cast a value of type `float` or `double` to an integer type, you will lose the fractional part of the value, so if the value started out as less than 1.0, the result will be 0. If you cast a value of type `double` to type `float`, you will lose accuracy because a `float` variable has only 7 digits precision, whereas `double` variables maintain 15. Even casting between integer types provides the potential for losing data, depending on the values involved. For example, the value of an integer of type `long long` can exceed the maximum that you can store in a variable of type `int`, so casting from a `long long` value to an `int` may lose information.

In general, you should avoid casting as far as possible. If you find that you need a lot of casts in your program, the overall design of your program may well be at fault. You need to look at the structure of the program and the ways in which you have chosen data types to see whether you can eliminate, or at least reduce, the number of casts in your program.

Old-Style Casts

Prior to the introduction of `static_cast<>()` (and the other casts: `const_cast<>()`, `dynamic_cast<>()`, and `reinterpret_cast<>()`, which I'll discuss later in the book) into C++, an explicit cast of the result of an expression to another type was written as:

```
(the_type_to_convert_to)expression
```

The result of `expression` is cast to the type between the parentheses. For example, the statement to calculate `strips_per_roll` in the previous example could be written:

```
strips_per_roll = (int)(rollLength / height); //Get number of strips in a roll
```

Essentially, there are four different kinds of casts, and the old-style casting syntax covers them all. Because of this, code using the old-style casts is more error-prone — it is not always clear what you intended, and you may not get the result you expected. Although you will still see the old style of casting used extensively (it's still part of the language and you will see it in MFC code for historical reasons), I strongly recommend that you stick to using only the new casts in your code.

THE AUTO KEYWORD

You can use the `auto` keyword as the type of a variable in a definition statement and have its type deduced from the initial value you supply. Here are some examples:

```
auto n = 16; // Type is int
auto pi = 3.14159; // Type is double
auto x = 3.5f; // Type is float
auto found = false; // Type is bool
```

In each of these cases, the type assigned to the variable you are defining is the same as that of the literal used as the initializer. Of course, when you use the `auto` keyword in this way, you must supply an initial value for the variable.

Variables defined using the `auto` keyword can also be specified as constants:

```
const auto e = 2.71828L;           // Type is const long double
```

Of course, you can also use functional notation:

```
const auto dozen(12);            // Type is const int
```

The initial value for a variable you define using the `auto` keyword can also be an expression:

```
auto factor(n*pi*pi);          // Type is double
```

In this case, the definitions for the variables `n` and `pi` that are used in the initializing expression must precede this statement.

When you use `auto`, you are telling the compiler to figure out the type of the variable. The `auto` keyword may seem at this point to be a somewhat trivial feature of C++, but you'll see later in the book, especially in Chapter 10, that it can save a lot of effort in determining complicated variable types and make your code more elegant.

DISCOVERING TYPES

The `typeid` operator enables you to discover the type of an expression. To obtain the type of an expression, you simply write `typeid(expression)`, and this results in an object of type `type_info` that encapsulates the type of the expression. Suppose that you have defined variables `x` and `y` that are of type `int` and type `double`, respectively. The expression `typeid(x*y)` results in a `type_info` object representing the type of `x*y`, which by now you know to be `double`. Because the result of the `typeid` operator is an object, you can't write it to the standard output stream just as it is. However, you can output the type of the expression `x*y` like this:

```
cout << "The type of x*y is " << typeid(x*y).name() << endl;
```

This will result in the output:

```
The type of x*y is double
```

You will understand better how this works when you have learned more about classes and functions in Chapter 7. You won't need to use the `typeid` operator very often, but when you do need it, it is invaluable.

THE BITWISE OPERATORS

The bitwise operators treat their operands as a series of individual bits rather than a numerical value. They work only with integer variables or integer constants as operands, so only data types `short`, `int`, `long`, `long long`, `signed char`, and `char`, as well as the `unsigned` variants of these, can be used. The bitwise operators are useful in programming hardware devices, where the status of

a device is often represented as a series of individual flags (that is, each bit of a byte may signify the status of a different aspect of the device), or for any situation where you might want to pack a set of on-off flags into a single variable. You will see them in action when you look at input/output in detail, where single bits are used to control various options in the way data is handled.

There are six bitwise operators:

& bitwise AND	bitwise OR	\wedge bitwise exclusive OR
\sim bitwise NOT	$>>$ shift right	$<<$ shift left

The following sections explain how each of them works.

The Bitwise AND

The bitwise AND, $\&$, is a binary operator that combines corresponding bits in its operands in a particular way. If both corresponding bits are 1, the result is a 1 bit, and if either or both bits are 0, the result is a 0 bit.

The effect of a particular binary operator is often shown using what is called a *truth table*. This shows, for various possible combinations of operands, what the result is. The truth table for $\&$ is as follows:

Bitwise AND	0	1
0	0	0
1	0	1

For each row and column combination, the result of $\&$ combining the two is the entry at the intersection of the row and column. You can see how this works in an example:

```
char letter1 = 'A', letter2 = 'Z', result = 0;
result = letter1 & letter2;
```

You need to look at the bit patterns to see what happens. The letters 'A' and 'Z' correspond to hexadecimal values 0x41 and 0x5A, respectively. The way in which the bitwise AND operates on these two values is shown in Figure 2-7.

You can confirm this by looking at how corresponding bits combine with $\&$ in the truth table. After the assignment, `result` will have the value 0x40, which corresponds to the character '@'.

letter1: 'A' 0x41	0 1 0 0	0 0 0 1
	↑ ↑ ↑ ↑	↑ ↑ ↑ ↑
	& & & &	& & & &
	↓ ↓ ↓ ↓	↓ ↓ ↓ ↓
letter2: 'Z' 0x5A	0 1 0 1	1 0 1 0
	↑ ↑ ↑ ↑	↑ ↑ ↑ ↑
	= = = =	= = = =
	↓ ↓ ↓ ↓	↓ ↓ ↓ ↓
result: 0x40	0 1 0 0	0 0 0 0

FIGURE 2-7

Because the `&` produces zero if *either* bit is zero, you can use this operator to make sure that unwanted bits are set to 0 in a variable. You achieve this by creating what is called a “mask” and combining it with the original variable using `&`. You create the mask by specifying a value that has 1 where you want to keep a bit, and 0 where you want to set a bit to zero. The result of AND-ing the mask with another integer will be 0 bits where the mask bit is 0, and the same value as the original bit in the variable where the mask bit is 1. Suppose you have a variable `letter` of type `char` where, for the purposes of illustration, you want to eliminate the high-order 4 bits, but keep the low-order 4 bits. This is easily done by setting up a mask as `0x0F` and combining it with the value of `letter` using `&` like this:

```
letter = letter & 0x0F;
```

or, more concisely:

```
letter &= 0x0F;
```

If `letter` started out as `0x41`, it would end up as `0x01` as a result of either of these statements. This operation is shown in Figure 2-8.

The 0 bits in the mask cause corresponding bits in `letter` to be set to 0, and the 1 bits in the mask cause corresponding bits in `letter` to be kept as they are.

Similarly, you can use a mask of `0xF0` to keep the 4 high-order bits, and zero the 4 low-order bits. Therefore, this statement,

```
letter &= 0xF0;
```

will result in the value of `letter` being changed from `0x41` to `0x40`.

The Bitwise OR

The bitwise OR, `|`, sometimes called the *inclusive OR*, combines corresponding bits such that the result is a 1 if either operand bit is a 1, and 0 if both operand bits are 0. The truth table for the bitwise OR is:

BITWISE OR	0	1
0	0	1
1	1	1

You can exercise this with an example of how you could set individual flags packed into a variable of type `int`. Suppose that you have a variable called `style` of type `short` that contains 16 individual 1-bit flags. Suppose further that you are interested in setting individual flags in the variable `style`.

letter1: 'A' 0x41	0 1 0 0	0 0 0 1
	↑ ↑ ↑ ↑	↑ ↑ ↑ ↑
	& & & &	& & & &
	↓ ↓ ↓ ↓	↓ ↓ ↓ ↓
mask: 0x0F	0 0 0 0	1 1 1 1
	↑ ↑ ↑ ↑	↑ ↑ ↑ ↑
	= = = =	= = = =
	↓ ↓ ↓ ↓	↓ ↓ ↓ ↓
result: 0x01	0 0 0 0	0 0 0 0

FIGURE 2-8

One way of doing this is by defining values that you can combine with the OR operator to set particular bits on. To use in setting the rightmost bit, you can define:

```
short vredraw = 0x01;
```

For use in setting the second-to-rightmost bit, you could define the variable `hredraw` as:

```
short hredraw = 0x02;
```

So, you could set the rightmost two bits in the variable `style` to 1 with the statement:

```
style = hredraw | vredraw;
```

The effect of this statement is illustrated in Figure 2-9. Of course, to set the third bit of `style` to 1, you would use the constant `0x04`.

Because the OR operation results in 1 if either of two bits is a 1, OR-ing the two variables together produces a result with both bits set on.




FIGURE 2-9

A common requirement is to be able to set flags in a variable without altering any of the others that may have been set elsewhere. You can do this quite easily with a statement such as:

```
style |= hredraw | vredraw;
```

This statement will set the two rightmost bits of `style` to 1, leaving the other bits at whatever they were before the execution of this statement.

The Bitwise Exclusive OR

The *exclusive OR*, `^`, is so called because it operates similarly to the inclusive OR but produces 0 when both operand bits are 1. Therefore, its truth table is as follows:

BITWISE XOR	0	1
0	0	1
1	1	0

Using the same variable values that I used with the AND, you can look at the result of the following statement:

```
result = letter1 ^ letter2;
```

This operation can be represented as:

```
letter1 0100 0001  
letter2 0101 1010
```

XOR-ed together produce:

```
result 0001 1011
```

The variable `result` is set to `0x1B`, or 27 in decimal notation.

The `^` operator has a rather surprising property. Suppose that you have two `char` variables, `first` with the value '`A`', and `last` with the value '`z`', corresponding to binary values `0100 0001` and `0101 1010`. If you write the statements

```
first ^= last;           // Result first is 0001 1011  
last ^= first;          // Result last is 0100 0001  
first ^= last;          // Result first is 0101 1010
```

the result of these is that `first` and `last` have exchanged values without using any intermediate memory location. This works with any integer values.

The Bitwise NOT


The bitwise NOT, `~`, takes a single operand, for which it inverts the bits: 1 becomes 0, and 0 becomes 1. Thus, if you execute the statement,

```
result = ~letter1;
```

if `letter1` is `0100 0001`, `result` will have the value `1011 1110`, which is `0xBE`, or 190 as a decimal value.

The Bitwise Shift Operators

These operators shift the value of an integer variable a specified number of bits to the left or right. The operator `>>` is for shifts to the right, while `<<` is the operator for shifts to the left. Bits that “fall off” either end of the variable are lost. Figure 2-10 shows the effect of shifting the 2-byte variable left and right, with the initial value shown.

**FIGURE 2-10**

You declare and initialize a variable called `number` with the statement:

```
unsigned short number = 16387U;
```

As you saw earlier in this chapter, you write unsigned integer literals with a letter U or u appended to the number. You can shift the contents of this variable to the left with the statement:

```
number <<= 2; // Shift left two bit positions
```

The left operand of the shift operator is the value to be shifted, and the number of bit positions that the value is to be shifted is specified by the right operand. The illustration shows the effect of the operation. As you can see, shifting the value 16,387 two positions to the left produces the value 12. The rather drastic change in the value is the result of losing the high-order bit when it is shifted out.

You can also shift the value to the right. Let's reset the value of `number` to its initial value of 16,387. Then you can write:

```
number >>= 2; // Shift right two bit positions
```

This shifts the value 16,387 two positions to the right, storing the value 4,096. Shifting right 2 bits is effectively dividing the value by 4 (discarding the remainder). This is also shown in the illustration.

As long as bits are not lost, shifting n bits to the left is equivalent to multiplying the value by 2^n times. In other words, it is equivalent to multiplying by 2^n . Similarly, shifting right n bits is equivalent to dividing by 2^n . But beware: as you saw with the left shift of the variable `number`, if significant bits are lost, the result is nothing like what you would expect. However, this is no different from the multiply operation. If you multiplied the 2-byte number by 4, you would get the same result, so shifting left and multiply are still equivalent. The problem of accuracy arises because the value of the result of the multiplication is outside the range of a 2-byte integer.

You might imagine that confusion could arise between the operators that you have been using for input and output and the shift operators. As far as the compiler is concerned, the meaning will always be clear from the context. If it isn't, the compiler will generate a message, but you need to be careful. For example, if you want to output the result of shifting a variable `number` left by 2 bits, you could write the following statement:

```
cout << (number << 2);
```

Here, the parentheses are essential. Without them, the shift operator will be interpreted by the compiler as a stream operator, so you won't get the result that you intended; the output would be the value of `number` followed by the value 2.

The right-shift operation is similar to the left-shift. For example, suppose `number` has the value 24, and you execute the following statement:

```
number >>= 2;
```

This will result in `number` having the value 6, effectively dividing the original value by 4. However, the right shift operates in a special way with `signed` integer types that are negative, where the sign bit, which is the leftmost bit, is 1. In this case, the sign bit is propagated to the right. For example, declare and initialize a variable `number` of type `char` with the value -104 in decimal:

```
char number = -104;           // Binary representation is 1001 1000
```

Now you can shift it right 2 bits with the operation:

```
number >>= 2;                // Result 1110 0110
```

The decimal value of the result is -26, as the sign bit is repeated. With operations on `unsigned` integer types, of course, the sign bit is not repeated and zeros appear.

NOTE You may be wondering how the shift operators, `<<` and `>>`, can be the same as the operators used with the standard streams for input and output. These operators can have different meanings in the two contexts because `cin` and `cout` are stream objects, and because they are objects it is possible to redefine the meaning of operators in context by a process called operator overloading. Thus the `>>` operator has been redefined for input stream objects such as `cin` so you can use it in the way you have seen. The `<<` operator has also been redefined for use with output stream objects such as `cout`. You will learn about operator overloading in Chapter 8.

INTRODUCING LVALUES AND RVALUES

Every expression in C++ results in either an *lvalue* or an *rvalue* (sometimes written *l-value* and *r-value* and pronounced like that). An lvalue refers to an address in memory in which something is stored on an ongoing basis. An rvalue, on the other hand, is the result of an expression that is stored

transiently. An lvalue is so called because any expression that results in an lvalue can appear on the left of the equals sign in an assignment statement. If the result of an expression is not an lvalue, it is an rvalue.

Consider the following statements:

```
int a(0), b(1), c(2);
a = b + c;
b = ++a;
c = a++;
```

The first statement declares the variables `a`, `b`, and `c` to be of type `int` and initializes them to 0, 1, and 2, respectively. In the second statement, the expression `b + c` is evaluated and the result is stored in the variable `a`. The result of evaluating the expression `b + c` is stored temporarily in a memory location and the value is copied from this location to `a`. Once execution of the statement is complete, the memory location holding the result of evaluating `b + c` is discarded. Thus, the result of evaluating the expression `b + c` is an rvalue.

In the third statement, the expression `++a` is an lvalue because its result is `a` after its value is incremented. The expression `a++` in the third statement is an rvalue because it stores the value of `a` temporarily as the result of the expression and then increments `a`.

An expression that consists of a single named variable is always an lvalue.

NOTE *This is by no means all there is to know about lvalues and rvalues. Most of the time, you don't need to worry very much about whether an expression is an lvalue or an rvalue but sometimes you do. Lvalues and rvalues will pop up at various times throughout the book so keep the idea in mind.*

UNDERSTANDING STORAGE DURATION AND SCOPE

All variables have a finite lifetime when your program executes. They come into existence at the point at which you declare them and then, at some point, they disappear — at the latest, when your program terminates. How long a particular variable lasts is determined by a property called its *storage duration*. There are three different kinds of storage duration that a variable can have:

- Automatic storage duration
- Static storage duration
- Dynamic storage duration

Which of these a variable will have depends on how you create it. I will defer discussion of variables with dynamic storage duration until Chapter 4, but you will be exploring the characteristics of the other two in this chapter.

Another property that variables have is *scope*. The scope of a variable is simply that part of your program over which the variable name is valid. Within a variable's scope, you can legally refer to

it, either to set its value or to use it in an expression. Outside of the scope of a variable, you cannot refer to its name — any attempt to do so will cause a compiler error. Note that a variable may still *exist* outside of its scope, even though you cannot refer to it by name. You will see examples of this situation a little later in this discussion.

All the variables that you have declared up to now have had *automatic storage duration*, and are therefore called *automatic variables*. Let's take a closer look at these first.

Automatic Variables

The variables that you have declared so far have been declared within a block — that is, within the extent of a pair of braces. These are called *automatic* variables and are said to have *local scope* or *block scope*. An automatic variable is “in scope” from the point at which it is declared until the end of the block containing its declaration. The space that an automatic variable occupies is allocated automatically in a memory area called the *stack* that is set aside specifically for this purpose. The default size for the stack is 1 MB, which is adequate for most purposes, but if it should turn out to be insufficient, you can increase the size of the stack by setting the /STACK option for the project to a value of your choosing.

An automatic variable is “born” when it is defined and space for it is allocated on the stack, and it automatically ceases to exist at the end of the block containing the definition of the variable. This will be at the closing brace matching the first opening brace that precedes the declaration of the variable. Every time the block of statements containing a declaration for an automatic variable is executed, the variable is created anew, and if you specified an initial value for the automatic variable, it will be reinitialized each time it is created. When an automatic variable dies, its memory on the stack will be freed for use by other automatic variables. Let's look at an example demonstrating some of what I've discussed so far about scope.

TRY IT OUT Automatic Variables

The following example shows the effect of scope on automatic variables:

```
// Ex2_07.cpp
// Demonstrating variable scope
#include <iostream>

using std::cout;
using std::endl;

int main()
{                               // Function scope starts here
    int count1 = 10;
    int count3 = 50;
    cout << endl
        << "Value of outer count1 = " << count1
        << endl;

    {                           // New scope starts here...
        int count1 = 20;          // This hides the outer count1
    }
}
```

```

int count2 = 30;
cout << "Value of inner count1 = " << count1
    << endl;
count1 += 3;                                // This affects the inner count1
count3 += count2;
}                                              // ...and ends here

cout << "Value of outer count1 = " << count1
    << endl
    << "Value of outer count3 = " << count3
    << endl;

// cout << count2 << endl;           // uncomment to get an error

return 0;
}                                              // Function scope ends here

```

The output from this example will be:

```

Value of outer count1 = 10
Value of inner count1 = 20
Value of outer count1 = 10
Value of outer count3 = 80

```

How It Works

The first two statements declare and define two integer variables, `count1` and `count3`, with initial values of 10 and 50, respectively. Both these variables exist from this point to the closing brace at the end of the program. The scope of these variables also extends to the closing brace at the end of `main()`.

Remember that the lifetime and scope of a variable are two different things. It's important not to get these two ideas confused. The lifetime is the period during execution from when the variable is first created to when it is destroyed and the memory it occupies is freed for other uses. The scope of a variable is the region of program code over which the variable may be accessed.

Following the variable definitions, the value of `count1` is written to `cout` to produce the first of the lines shown in the output. There is then a second brace, which starts a new block. Two variables, `count1` and `count2`, are defined within this block, with values 20 and 30, respectively. The `count1` declared here is *different* from the first `count1`. The first `count1` still exists, but its name is masked by the second `count1`. Any use of the name `count1` following the declaration within the inner block refers to the `count1` declared within that block.

I used a duplicate of the variable name `count1` here only to illustrate what happens. Although this code is legal, it isn't a good approach to programming in general. In a real-world programming environment, it would be confusing, and if you use duplicate names, it makes it very easy to hide variables defined in an outer scope accidentally.

The value shown in the second output line shows that within the inner block, you are using the `count1` in the inner scope — that is, inside the innermost braces:

```

cout << "Value of inner count1 = " << count1
    << endl;

```

Had you still been using the outer `count1`, then this would display the value 10. The variable `count1` is then incremented by the statement:

```
count1 += 3;           // This affects the inner count1
```

The increment applies to the variable in the inner scope, since the outer one is still hidden. However, `count3`, which was defined in the outer scope, is incremented in the next statement without any problem:

```
count3 += count2;
```

This shows that the variables that were declared at the beginning of the outer scope are accessible from within the inner scope. (Note that if `count3` had been declared *after* the second of the inner pair of braces, then it would still be within the outer scope, but in that case, `count3` would not exist when the preceding statement was executed.)

After the brace ending the inner scope, `count2` and the inner `count1` cease to exist. The variables `count1` and `count3` are still there in the outer scope, and the values displayed show that `count3` was indeed incremented in the inner scope.

If you uncomment the line,

```
// cout << count2 << endl;           // uncomment to get an error
```

the program will no longer compile correctly because it attempts to output a nonexistent variable. You will get an error message something like,

```
c:\microsoft visual studio\myprojects\Ex2_07\Ex2_07.cpp(29) : error  
C2065: 'count2' : undeclared identifier
```

This is because `count2` is out of scope at this point.

Positioning Variable Declarations

You have great flexibility as to where you can place the declarations for your variables. The most important aspect to consider is what scope the variables need to have. Beyond that, you should generally place a declaration close to where the variable is to be first used in a program. You should write your programs with the intention of making them as easy as possible for another programmer to understand, and declaring a variable at its first point of use can be helpful in achieving that.

It is possible to place declarations for variables outside of all of the functions that make up a program. The next section looks what effect that has on the variables concerned.

Global Variables

Variables that are declared outside of all blocks and classes (I will discuss classes later in the book) are called *globals* and have *global scope* (which is also called *global namespace scope* or *file scope*). This means that they are accessible throughout all the functions in the file, following the point at

which they are declared. If you declare them at the very beginning of your program, they will be accessible from anywhere in the file.

Globals have *static storage duration* by default. Global variables with static storage duration will exist from the start of execution of the program until execution of the program ends. If you do not specify an initial value for a global variable, it will be initialized with 0 by default. Initialization of global variables takes place before the execution of `main()` begins, so they are always ready to be used within any code that is within the variable's scope.

Figure 2-11 shows the contents of a source file, `Example.cpp`, and the arrows indicate the scope of each of the variables.




FIGURE 2-11

The variable `value1`, which appears at the beginning of the file, is declared at global scope, as is `value4`, which appears after the function `main()`. The scope of each global variable extends from the point at which it is defined to the end of the file. Even though `value4` exists when execution starts, it cannot be referred to in `main()` because `main()` is not within the variable's scope. For `main()` to use `value4`, you would need to move its declaration to the beginning of the file. Both

value1 and value4 will be initialized with 0 by default, which is not the case for the automatic variables. Note that the local variable called value1 in function() hides the global variable of the same name.

Since global variables continue to exist for as long as the program is running, this might raise the question in your mind, “Why not make all variables global and avoid this messing about with local variables that disappear?” This sounds very attractive at first, but as with the Sirens of mythology, there are serious side effects that completely outweigh any advantages you may gain.

Real programs are generally composed of a large number of statements, a significant number of functions, and a great many variables. Declaring all variables at the global scope greatly magnifies the possibility of accidental erroneous modification of a variable, as well as making the job of naming them sensibly quite intractable. They will also occupy memory for the duration of program execution. By keeping variables local to a function or a block, you can be sure they have almost complete protection from external effects, they will only exist and occupy memory from the point at which they are defined to the end of the enclosing block, and the whole development process becomes much easier to manage. That’s not to say you should never define variables at global scope. Sometimes, it can be very convenient to define constants that are used throughout the program code at global scope.

If you take a look at the Class View pane for any of the examples that you have created so far and extend the class tree for the project by clicking on the [unfilled] symbol, you will see an entry called Global Functions and Variables. If you click on this, you will see a list of everything in your program that has global scope. This will include all the global functions, as well as any global variables that you have declared.

TRY IT OUT The Scope Resolution Operator

As you have seen, a global variable can be hidden by a local variable with the same name. However, it’s still possible to get at the global variable by using the *scope resolution operator* (::), which you saw in Chapter 1 when I was discussing namespaces. I can demonstrate how this works with a revised version of the last example:

```
// Ex2_08.cpp
// Demonstrating variable scope
#include <iostream>

using std::cout;
using std::endl;

int count1 = 100;                                // Global version of count1

int main()
{
    int count1 = 10;
    int count3 = 50;
    cout << endl
        << "Value of outer count1 = " << count1
        << endl;
```

```

cout << "Value of global count1 = " << ::count1           // From outer block
<< endl;

{
    int count1 = 20;                      // New scope starts here...
    int count2 = 30;                      // This hides the outer count1
    cout << "Value of inner count1 = " << count1
    << endl;
    cout << "Value of global count1 = " << ::count1           // From inner block
    << endl;

    count1 += 3;                         // This affects the inner count1
    count3 += count2;
}

cout << "Value of outer count1 = " << count1
<< endl
<< "Value of outer count3 = " << count3
<< endl;

//cout << count2 << endl;           // uncomment to get an error
return 0;
}                                     // Function scope ends here
}

```

If you compile and run this example, you'll get the following output:

```

Value of outer count1 = 10
Value of global count1 = 100
Value of inner count1 = 20
Value of global count1 = 100
Value of outer count1 = 10
Value of outer count3 = 80

```

How It Works

The shaded lines of code indicate the changes I have made to the previous example; I'll just discuss the effects of those. The declaration of `count1` prior to the definition of the function `main()` is global, so in principle, it is available anywhere through the function `main()`. This global variable is initialized with the value of 100:

```
int count1 = 100;                      // Global version of count1
```

However, you have two other variables called `count1`, which are defined within `main()`, so, throughout the program, the global `count1` is hidden by the local `count1` variables. The first new output statement is:

```
cout << "Value of global count1 = " << ::count1           // From outer block
<< endl;
```

This uses the scope resolution operator (`::`) to make it clear to the compiler that you want to reference the global variable `count1`, *not* the local one. You can see that this works from the value displayed in the output.

In the inner block, the global `count1` is hidden behind *two* variables called `count1`: the inner `count1` and the outer `count1`. We can see the global scope resolution operator doing its stuff within the inner block, as you can see from the output generated by the statement we have added there:

```
cout << "Value of global count1 = " << ::count1           // From inner block
<< endl;
```

This outputs the value 100, as before — the long arm of the scope resolution operator used in this fashion always reaches a global variable.

You have seen earlier that you can refer to a name in the `std` namespace by qualifying the name with the namespace name, such as with `std::cout` or `std::endl`. The compiler searches the namespace that has the name specified by the left operand of the scope resolution operator for the name that you specify as the right operand. In the preceding example, you are using the scope resolution operator to search the global namespace for the variable `count1`. By not specifying a namespace name in front of the operator, you are telling the compiler to search the global namespace for the name that follows it.

You'll see a lot more of this operator when you get to explore object-oriented programming in Chapter 9, where it is used extensively.

Static Variables

It's conceivable that you might want to have a variable that's defined and accessible locally, but which also continues to exist after exiting the block in which it is declared. In other words, you need to declare a variable within a block scope, but to give it *static storage duration*. The `static` specifier provides you with the means of doing this, and the need for this will become more apparent when we come to deal with functions in Chapter 5.

In fact, a static variable will continue to exist for the life of a program even though it is declared within a block and available only from within that block (or its sub-blocks). It still has block scope, but it has static storage duration. To declare a static integer variable called `count`, you would write:

```
static int count;
```

If you don't provide an initial value for a static variable when you declare it, then it will be initialized for you. The variable `count` declared here will be initialized with 0. The default initial value for a static variable is always 0, converted to the type applicable to the variable. Remember that this is *not* the case with automatic variables.

NOTE If you don't initialize your automatic variables, they will contain junk values left over from the program that last used the memory they occupy.

VARIABLES WITH SPECIFIC SETS OF VALUES

You will sometimes be faced with the need for variables that have a limited set of possible values that can be usefully referred to by labels — the days of the week, for example, or months of the year, or the suits in a card deck. There is a specific facility in C++ to handle this situation, called an *enumeration*. There are two kinds of enumerations, those defined using the syntax used prior to the C++ 11 standard, and those defined using the syntax introduced by C++ 11. I'll describe both because the old syntax is used widely, but the new syntax has several real advantages so you should only use that.

Old Enumerations

Take one of the examples I have just mentioned — a variable that can assume values corresponding to days of the week. You can define this as follows:

```
enum Weekdays{Mon, Tues, Wed, Thurs, Fri, Sat, Sun} today;
```

This declares an enumeration type with the name `Weekdays` and the variable `today`, which is an instance of the enumeration type `Weekdays` that can assume only the constant values specified between the braces. If you try to assign to `today` anything other than one of the set of values specified, it will cause an error. The symbolic names listed between the braces are known as *enumerators*. Each of the names of the days will be automatically defined as representing a fixed integer value that will be type `int` by default. The first name in the list, `Mon`, will have the value 0, `Tues` will be 1, and so on.

You could assign one of the enumeration constants as the value of the variable `today` like this:

```
today = Thurs;
```

The value of `today` will be 3 because the symbolic constants that an enumeration defines are assigned values in sequence, starting with 0 by default. Each successive enumerator is one larger than the value of the previous one, but if you would prefer the implicit numbering to start at a different value, you can just write:

```
enum Weekdays {Mon = 1, Tues, Wed, Thurs, Fri, Sat, Sun} today;
```

Now, the enumeration constants will be equivalent to 1 through 7. The enumerators don't even need to have unique values. You could define `Mon` and `Tues` as both having the value 1, for example, with the statement:

```
enum Weekdays {Mon = 1, Tues = 1, Wed, Thurs, Fri, Sat, Sun} thisWeek;
```

Because the enumerators for `Weekdays` are of type `int`, the variable `today` stores a value of type `int` and it will occupy 4 bytes, as will all variables that are of this enumeration type. Enumerators and variables of an enumeration type will be implicitly converted to type `int` when required. For example, you can assign an enumerator as a value for an integer variable:

```
int value = Wed;
```

You can also write enumerator values to the standard output stream:

```
cout << today << endl;
```

The compiler will insert a conversion to type `int` for the value of `today` to allow this to work. In general, if you use an enumerator or a variable of an enumeration type, the compiler will insert a conversion of the value to the required numeric type for the expression. This is an undesirable feature because it allows the accidental use of a variable of an enumeration type as though it was a numeric type.

Having defined the form of an enumeration, you can define another variable as follows:

```
enum Weekdays tomorrow;
```

This defines a variable `tomorrow` that can assume the values previously specified. You can also omit the `enum` keyword in declaring a variable, so, instead of the previous statement, you could write:

```
Weekdays tomorrow;
```

If you wish, you can assign specific values to all the enumerators. For example, you could define this enumeration:

```
enum Punctuation {Comma = ',', Exclamation = '!', Question = '?'} things;
```

Here, you have defined the possible values for the variable `things` as the numerical equivalents of the appropriate symbols. The symbols are 44, 33, and 63, respectively, in decimal. As you can see, the values assigned don't have to be in ascending order. If you don't specify all the values explicitly, each enumerator will be assigned a value incrementing by 1 from the last specified value, as in our second `Weekdays` example.

You can declare and initialize a variable of an enumeration type like any other variable. For example:

```
Weekdays myBirthday = Tues;  
Weekdays yourBirthday(Thurs);
```

You can use either notation for specifying the initial value.

Note that you do not need to qualify an enumeration constant with the name of the enumeration, although you can if you wish:

```
Weekdays myBirthday = Weekdays::Tues;
```

The `enum` type name is separated from the enumerator name by the scope resolution operator.

You can omit the enumeration type if you don't need to define other variables of this type later. For example:

```
enum {Mon, Tues, Wed, Thurs, Fri, Sat, Sun} today, tomorrow, yesterday;
```

Here, you have three variables declared that can assume any of the values from Mon to Sun. Because the enumeration type is not specified, you cannot refer to it. This implies that you cannot define other variables for this enumeration *at all*, because you would not be permitted to repeat the definition. Doing so would imply that you were redefining values for Mon to Sun, and this isn't allowed.

You don't have to accept the default type for the enumerators in an `enum` type. You can explicitly specify the enumerator type as any integer type except `wchar_t`. Here's an example that shows how you do that:

```
enum Weekdays : unsigned long {Mon, Tues, Wed, Thurs, Fri, Sat, Sun} today;
```

Now the enumerators for `Weekdays` will be of type `unsigned long`.

The enumerator names are exported into the enclosing scope by default. This is why there is no need to qualify the names when you reference them. This can create a problem. Look at these two enumerations:

```
enum Suit {Clubs, Diamonds, Hearts, Spades};
enum Jewels {Diamonds, Emeralds, Opals, Rubies, Sapphires};
```

If you put these definitions in `main()` they won't compile. Both sets of enumerator names are available in the enclosing scope, that is, throughout the body of `main()`. The `Jewels` enumeration is seen to redefine `Diamonds`, which is not allowed.

Type-Safe Enumerations

Visual C++ implements a new form of enumeration that is introduced by the latest C++ language standard, C++ 11. These enumerations are said to be *type-safe* because you cannot get automatic conversion of enumerator values to another type. You use the `class` keyword following `enum` to specify the new enumeration. Here's an example:

```
enum class Suit {Clubs, Diamonds, Hearts, Spades};
```

With this form of enumeration, the enumerator names are not exported into the enclosing scope. You must qualify them using the name of the enumeration, like this:

```
Suit suit = Suit::Diamonds;
```

You can rewrite the two enumerations from the previous section that did not compile as type-safe enumerations:

```
enum class Suit {Clubs, Diamonds, Hearts, Spades};
enum class Jewels {Diamonds, Emeralds, Opals, Rubies, Sapphires};
```

These statements will compile. There are no name conflicts because the enumerator names are not exported into the enclosing scope. You must always qualify the enumerator names with the enumeration type name so `Suit::Diamonds` is always distinct from `Jewels::Diamonds`.

If you want to convert an enumeration value to another type, you must use an explicit cast. For example:

```
Suit suit(Suit::Diamonds);           // Create and initialize suit
int suitValue = static_cast<int>(suit); // Convert suit to int
```

This will not compile without the explicit conversion of `suit` to type `int`.

The enumerator values will be stored as type `int` by default, but you can change this by specifying the type for the enumerator values:

```
enum class Jewels : char {Diamonds, Emeralds, Opals, Rubies, Sapphires};
```

Here, enumerator values will be stored as type `char`.

The following example demonstrates aspects of both kinds of enumerations.

TRY IT OUT Using Enumerations

This example demonstrates both types of enumerations:

```
// Ex2_09.cpp
// Demonstrating type-safe and non-type-safe enumerations
#include <iostream>

using std::cout;
using std::endl;

// You can define enumerations at global scope
//enum Jewels {Diamonds, Emeralds, Rubies}; // Uncomment this for an error
enum Suit : long {Clubs, Diamonds, Hearts, Spades};

int main()
{
    // Using the old enumeration type...
    Suit suit = Clubs;                      // You can use enumerator names directly
    Suit another = Suit::Diamonds;            // or you can qualify them

    // Automatic conversion from enumeration type to integer
    cout << "suit value: " << suit << endl;
    cout << "Add 10 to another: " << another + 10 << endl;

    // Using type-safe enumerations...
    enum class Color : char {Red, Orange, Yellow, Green, Blue, Indigo, Violet};
    Color skyColor(Color::Blue);                // You must qualify enumerator names
    // Color grassColor(Green);                 // Uncomment for an error

    // No auto conversion to numeric type
    cout << endl
        << "Sky color value: "
```

```

        << static_cast<long>(skyColor) << endl;

//cout << skyColor + 10L << endl;           // Uncomment for an error
cout << "Incremented sky color: "
    << static_cast<long>(skyColor) + 10L // OK with explicit cast
    << endl;

    return 0;
}

```

If you compile and run this example, you'll get the following output:

```

suit value: 0
Add 10 to another: 11

Sky color value: 4
Incremented sky color: 14

```

How It Works

You can see from the example that you can define enumerations at global scope, in which case they are accessible throughout the source file. Enumerations defined locally within a block are available from the point at which they are defined to the end of the block.

Uncommenting the definition for the `Jewels` enumeration will result in a compiler error because of the duplication of `Diamonds`. If the `Suit` and `Jewels` types were defined as type-safe enums, no name collision would occur.

The `main()` function exercises the old-style enumerations first by showing that the type qualification for enumerator names is optional. These statements show automatic conversions in operation:

```

cout << "suit value: " << suit << endl;
cout << "Add 10 to another: " << another + 10 << endl;

```

The compiler will happily allow you to output `suit` as though it is an integer, even though it is of type `Suit`. You are also able to use it in an arithmetic expression.

The `Color` enumeration is type-safe:

```
enum class Color : char {Red, Orange, Yellow, Green, Blue, Indigo, Violet};
```

If you attempt to use the enumerator names without qualification, you will get an error message from the compiler. The compiler will insist that if you want to convert a `Color` value to another type, you must insert an explicit cast.

NOTE Always use type-safe enumerations in your programs. This will make your code less error-prone.

NAMESPACES

I have mentioned namespaces several times, so it's time you got a better idea of what they are about. They are not used in the libraries supporting MFC, but the C++ standard library uses namespaces extensively.

You know already that all the names used in the standard library are defined in a namespace with the name `std`. This means that all the names used in the standard library have an additional qualifying name, `std`; for example, `cout` is really `std::cout`. You have already seen how you can add a `using` declaration to import a name from the `std` namespace into your source file. For example:

```
using std::cout;
```

This allows you to use the name `cout` in your source file and have it interpreted as `std::cout`.

Namespaces provide a way to separate the names used in one part of a program from those used in another. This is invaluable with large projects involving several teams of programmers working on different parts of the program. Each team can have its own namespace name, and worries about two teams accidentally using the same name for different functions disappear.

Look at this line of code:

```
using namespace std;
```

This statement is a *using directive* and is different from a `using` declaration. The effect of this is to import *all* the names from the `std` namespace into the source file so you can refer to anything that is defined in this namespace without qualifying the name in your program. Thus, you can write the name `cout` instead of `std::cout` and `endl` instead of `std::endl`. This sounds like a big advantage, but the downside of this blanket `using` directive is that it effectively negates the primary reason for using a namespace — that is, preventing accidental name clashes. There are two ways to access names from a namespace without negating its intended effect. One way is to qualify each name explicitly with the namespace name; unfortunately, this tends to make the code very verbose and reduce its readability. The other possibility that I mentioned early on in this chapter is to introduce just the names that you use in your code with `using` declarations as you have seen in earlier examples, like this, for example:

```
using std::cout;           // Allows cout usage without qualification
using std::endl;           // Allows endl usage without qualification
```

Each `using` declaration introduces a single name from the specified namespace and allows it to be used unqualified within the program code that follows. This provides a much better way of importing names from a namespace, as you only import the names that you actually use in your program. In general, I recommend that you use `using` declarations in your own code rather than `using` directives when you are writing programs of any significant size.

Of course, you can define your own namespace that has a name that you choose. The following section shows how that's done.

WARNING You should not use using directives in a headers file because they will apply in all source files that include the header file. You should avoid using declarations at global scope in a header file.

Declaring a Namespace

You use the keyword `namespace` to declare a namespace — like this:

```
namespace myStuff
{
    // Code that I want to have in the namespace myStuff...
}
```

This defines a namespace with the name `myStuff`. All name declarations in the code between the braces will be defined within the `myStuff` namespace, so to access any such name from a point outside this namespace, the name must be qualified by the namespace name, `myStuff`, or have a `using` declaration that identifies that the name is from the `myStuff` namespace.

You can't declare a namespace inside a function. It's intended to be used the other way around; you use a namespace to contain functions, global variables, and other named entities such as classes in your program. You must not put the definition of `main()` in a namespace, though. The function `main()` is where execution starts, and it must always be at global namespace scope; otherwise, the compiler won't recognize it.

You could define the variable `value` in a namespace and use it in an example:

```
// Ex2_10.cpp
// Declaring a namespace
#include <iostream>

namespace myStuff
{
    int value = 0;
}

int main()
{
    std::cout << "enter an integer: ";
    std::cin  >> myStuff::value;
    std::cout << "\nYou entered " << myStuff::value
              << std::endl;
    return 0;
}
```

The `myStuff` namespace defines a scope, and everything within the namespace scope is qualified with the namespace name. To refer to a name declared within a namespace from outside, you must qualify it with the namespace name. Inside the namespace scope, any of the names declared within it can be referred to without qualification — they are all part of the same family. Now, you must

qualify the name `value` with `myStuff`, the name of our namespace. If not, the program will not compile. The function `main()` now refers to names in two different namespaces, and in general, you can have as many namespaces in your program as you need. You could remove the need to qualify `value` by adding a `using` directive:

```
// Ex2_11.cpp
// Using a using directive
#include <iostream>

namespace myStuff
{
    int value = 0;
}

using namespace myStuff;           // Make all the names in myStuff available

int main()
{
    std::cout << "enter an integer: ";
    std::cin  >> value;
    std::cout << "\nYou entered " << value
              << std::endl;
    return 0;
}
```

You could also have a `using` directive for `std` as well, so you wouldn't need to qualify standard library names either, but as I said, this defeats the whole purpose of namespaces. Generally, if you use namespaces in your program, you should not add `using` directives all over your program; otherwise, you might as well not bother with namespaces in the first place. Having said that, I will add a `using` directive for `std` in some of our examples to keep the code less cluttered and easier for you to read. When you are starting out with a new programming language, you can do without clutter, no matter how useful it is in practice.

Multiple Namespaces

A real-world program is likely to involve multiple namespaces. You can have multiple declarations of a namespace with a given name, and the contents of all namespace blocks with a given name are within the same namespace. For example, you might have a program file with two namespaces:

```
namespace sortStuff
{
    // Everything in here is within sortStuff namespace
}

namespace calculateStuff
{
    // Everything in here is within calculateStuff namespace
    // To refer to names from sortStuff they must be qualified
}

namespace sortStuff
```

```
{
    // This is a continuation of the namespace sortStuff
    // so from here you can refer to names in the first sortStuff namespace
    // without qualifying the names
}
```

A second declaration of a namespace with a given name is just a continuation of the first, so you can reference names in the first namespace block from the second without having to qualify them. They are all in the same namespace. Of course, you would not usually organize a source file in this way deliberately, but it can arise quite naturally with header files that you include into a program. For example, you might have something like this:

```
#include <iostream>           // Contents are in namespace std
#include "myheader.h"         // Contents are in namespace myStuff
#include <string>             // Contents are in namespace std

// and so on...
```

Here, `iostream` and `string` are C++ standard library headers, and `myheader.h` represents a header file that contains our program code. You have a situation with the namespaces that is an exact parallel of the previous illustration.

This has given you a basic idea of how namespaces work. There is a lot more to namespaces than I have discussed here, but if you grasp this bit, you should be able to find out more about it without difficulty, if the need arises.

SUMMARY

This chapter covered the basics of computation in C++. You have learned about all the elementary types of data provided for in the language, and all the operators that manipulate these types directly.

Although I have discussed all the fundamental types, don't be misled into thinking that's all there is. There are more complex types based on the basic set, as you'll see, and eventually, you will be creating original types of your own.

EXERCISES

1. Write a program that asks the user to enter a number and then prints it out, using an integer as a local variable.
2. Write a program that reads an integer value from the keyboard into a variable of type `int`, and uses one of the bitwise operators (i.e. not the `%` operator!) to determine the positive remainder when divided by 8. For example, $29 = (3 \times 8) + 5$ and $-14 = (-2 \times 8) + 2$ have positive remainder 5 and 2, respectively, when divided by 8.

3. Fully parenthesize the following expressions, in order to show the precedence and associativity:

1 + 2 + 3 + 4

16 * 4 / 2 * 3

a > b? a: c > d? e: f

a & b && c & d

4. Create a program that will calculate the aspect ratio of your computer screen, given the width and height in pixels, using the following statements:

```
int width = 1280;  
int height = 1024;  
  
double aspect = width / height;
```

When you output the result, what answer will you get? Is it satisfactory — and if not, how could you modify the code, without adding any more variables?

5. (Advanced) Without running it, can you work out what value the following code is going to output, and why?

```
unsigned s = 555;  
  
int i = (s >> 4) & ~(~0 << 3);  
cout << i;
```

► WHAT YOU LEARNED IN THIS CHAPTER

TOPIC	CONCEPT
The main() function	A program in C++ consists of one or more functions and must include a function called <code>main()</code> , which is where execution starts.
The function body	The executable part of a function is made up of statements contained between braces.
Statements	A C++ statement is terminated by a semicolon.
Names	Named objects in C++, such as variables or functions, can have names that consist of a sequence of letters and digits, the first of which is a letter, and where an underscore is considered to be a letter. Uppercase and lowercase letters are distinguished.
Reserved words	You must not use any of the C++ reserved words as names for things in your program code.
Fundamental types	All constants and variables in C++ are of a given type. The fundamental types are <code>char</code> , <code>signed char</code> , <code>unsigned char</code> , <code>wchar_t</code> , <code>short</code> , <code>unsigned short</code> , <code>int</code> , <code>unsigned int</code> , <code>long</code> , <code>unsigned long</code> , <code>long long</code> , <code>unsigned long long</code> , <code>bool</code> , <code>float</code> , <code>double</code> , and <code>long double</code> .
Declarations	You define the name and type of a variable in a declaration statement that ends with a semicolon. You can also specify initial values for variables in a declaration.
The const modifier	You can protect the value of a variable by using the modifier <code>const</code> . This will prevent direct modification of the variable within the program. Any attempt to modify the value of a <code>const</code> variable will result in a compiler error message.
Automatic variables	By default, a variable is automatic, which means that it exists only from the point at which it is declared to the end of the scope in which it is defined, indicated by the first closing brace after its declaration.
static variables	A variable may be declared as <code>static</code> , in which case, it continues to exist for the life of the program. It can be accessed only within the scope in which it was defined.
Global variables	Variables can be declared outside of all blocks within a program, in which case, they have global namespace scope. Variables with global namespace scope are accessible throughout a program, except where a local variable exists with the same name as the global variable. Even then, they can still be reached by using the scope resolution operator.

TOPIC	CONCEPT
Enumerations	An enumeration is a type that you define with a fixed set of values. You should use type-safe enumerations that you define using the keywords <code>enum class</code> .
Namespaces	A namespace defines a scope where each of the names declared within it is qualified by the namespace name. Referring to names from outside a namespace requires the names to be qualified. You can access individual objects in a namespace from outside the namespace by using the namespace name to qualify the object name. Alternatively, you can supply a <code>using</code> declaration for each name from the namespace that you want to reference.
The Standard library	The C++ Standard library defines a vast range of functions, operators, and constants that you can use in your programs. Everything in the standard library is defined in the <code>std</code> namespace.
Lvalues and rvalues	Every expression in C++ results in either an lvalue or an rvalue. An lvalue is a persistent address and can appear on the left side of an assignment. Non-const variables are examples of lvalues. Any result that is not an lvalue is an rvalue. This implies that an rvalue cannot be used on the left side of an assignment operation.

3

Decisions and Loops

WHAT YOU WILL LEARN IN THIS CHAPTER:

- How to compare data values
- How to alter the sequence of program execution based on the result
- How to apply logical operators and expressions
- How to deal with multiple choice situations
- How to write and use loops in your programs

WROX.COM CODE DOWNLOADS FOR THIS CHAPTER

You can find the wrox.com code downloads for this chapter on the Download Code tab at www.wrox.com/remtitle.cgi?isbn=9781118368084. The code is in the Chapter 3 download and individually named according to the names throughout the chapter.

COMPARING VALUES

Unless you want to make decisions on a whim, you need a mechanism for comparing things. This involves some new operators called relational operators. Because all information in your computer is ultimately represented by numerical values (in the last chapter you saw how character information is represented by numeric codes), comparing numerical values is the essence of all decision making. You have six operators for comparing two values:

<	less than	<=	less than or equal to
>	greater than	>=	greater than or equal to
==	equal to	!=	not equal to

NOTE The “equal to” comparison operator has two successive = signs. This is not the same as the assignment operator, which consists only of a single = sign. It’s a common mistake to inadvertently use the assignment operator instead of the comparison operator, so watch out for this.

Each operator compares the values of two operands and returns one of the two possible values of type `bool`: `true` if the comparison is true, or `false` if it is not. You can see how this works by having a look at a few simple examples. The operands can be variables, literals, or expressions. Suppose you have created integer variables `i` and `j` with the values 10 and -5, respectively. The expressions,

`i > j` `i != j` `j > -8` `i <= j + 15`

all return the value `true`.

Assume that you have defined the following variables:

```
char first = 'A', last = 'Z';
```

Here are some examples of comparisons using these:

`first == 65` `first < last` `'E' <= first` `first != last`

All four expressions compare ASCII code values. The first expression returns `true` because `first` was initialized with '`A`', which is the equivalent of decimal 65. The second expression checks whether the value of `first`, which is '`A`', is less than the value of `last`, which is '`Z`'. If you check the ASCII codes for these characters in Appendix B, notice that the capital letters are represented by an ascending sequence of numerical values from 65 to 90, 65 representing '`A`' and 90 representing '`Z`', so this comparison also returns the value `true`. The third expression returns the value `false` because '`E`' is greater than the value of `first`. The last expression returns `true` because '`A`' is definitely not equal to '`Z`'.

Let’s consider some slightly more complicated comparisons with variables defined by the statements:

```
int i = -10, j = 20;
double x = 1.5, y = -0.25E-10;
```

Take a look at the following expressions:

`-1 < y` `j < (10 - i)` `2.0*x >= (3 + y)`

Here you use expressions that result in numerical values as operands. The precedence table for operators that you saw in Chapter 2 shows that none of the parentheses are strictly necessary, but they do help to make the expressions clearer. The first comparison is `true`, and so returns the `bool` value `true`. The variable `y` has a very small negative value, -0.00000000025, and so is greater than -1. The second comparison returns the value `false`. The expression `10 - i` has the value 20, which is the same as `j`. The third expression returns `true` because the expression `3 + y` is slightly less than 3.

You can use relational operators to compare values of any of the fundamental types or of the enumeration types, so all you need now is a way of using the results of a comparison to modify the behavior of a program.

The if Statement

The basic `if` statement allows your program to execute a single statement — or a block of statements enclosed within braces — if a given condition expression evaluates to `true`, or to skip the statement or block of statements if the condition evaluates to `false`. This is illustrated in Figure 3-1.




FIGURE 3-1

A simple example of an `if` statement is:

```
if('A' == letter)
    cout << "The first capital, alphabetically speaking.";
```

The condition to be tested appears in parentheses immediately following the keyword, `if`, and this is followed by the statement to be executed when the condition is `true`. Note the position of the semicolon. It goes after the statement *following* the `if` and the condition between parentheses; there shouldn't be a semicolon after the condition in parentheses because the two lines essentially make up a single statement. You also can see how the line following the `if` is indented to indicate that it is only executed when the `if` condition returns the value `true`. The indentation is not essential, but it helps you to recognize the relationship between the `if` condition and the statement that depends on it. The output statement in the code fragment is executed only if the variable `letter` has the value '`A`'.

NOTE When you are comparing a variable to a constant of some kind using the == operator, it is a good idea to write the constant on the left of the == operator, as in 'A' == letter. That way, if you accidentally write 'A' = letter, you will get an error message from the compiler. If you write letter = 'A', this is perfectly legal, though not what you intended, and no error message will be produced.

You could extend this example to change the value of letter if it contains the value 'A':

```
if('A' == letter)
{
    cout << "The first capital, alphabetically speaking.";
    letter = 'a';
}
```

The block of statements that is controlled by the if statement is delimited by the curly braces. You execute the statements in the block only if the condition ('A' == letter) evaluates to true. Without the braces, only the first statement would be the subject of the if, and the statement assigning the value 'a' to letter would always be executed. Note that there is a semicolon after each of the statements in the block, but not after the closing brace at the end of the block. There can be as many statements as you like within a block. Now, as a result of letter having the value 'A', you change its value to 'a' after outputting the same message as before. If the condition returns false, neither of these statements is executed.

Nested if Statements

The statement to be executed when the condition in an if statement is true can also be an if. This arrangement is called a *nested if*. The condition for the inner if is only tested if the condition for the outer if is true. An if that is nested inside another can also contain a nested if. You can generally continue nesting ifs one inside the other like this for as long as you still know what you are doing.

TRY IT OUT Using Nested ifs

The following is a working example of the nested if:

```
// Ex3_01.cpp
// A nested if demonstration
#include <iostream>

using std::cin;
using std::cout;
using std::endl;

int main()
{
    char letter(0); // Store input in here
```

```

cout << endl
    << "Enter a letter: ";
cin >> letter;                                // Prompt for the input
                                                // then read a character

if(letter >= 'A')                               // Test for 'A' or larger
{
    if(letter <= 'Z')                           // Test for 'Z' or smaller
    {
        cout << endl
            << "You entered a capital letter."
            << endl;
        return 0;
    }
}

if(letter >= 'a')                               // Test for 'a' or larger
{
    if(letter <= 'z')                           // Test for 'z' or smaller
    {
        cout << endl
            << "You entered a lowercase letter."
            << endl;
        return 0;
    }
}

cout << endl << "You did not enter a letter." << endl;
return 0;
}

```

How It Works

This program starts with the usual comment lines, then the `#include` statement for the header file supporting input/output, followed by the `using` declarations for `cin`, `cout`, and `endl` that are in the `std` namespace. The first action in the body of `main()` is to prompt for a letter to be entered. This is stored in the `char` variable with the name `letter`.

The `if` statement that follows the input checks whether the character entered is '`A`' or larger. The ASCII codes for lowercase letters (97 to 122) are greater than those for uppercase letters (65 to 90). Entering a lowercase letter causes the program to execute the first `if` block, because `(letter >= 'A')` returns `true` for all lowercase letters. In this case, the nested `if`, which checks for an input of '`z`' or less, is executed. If `letter` is '`z`' or less, you know that you have a capital letter, so the appropriate message is displayed, and because there is nothing more to do, you execute a `return` statement to end the program. Both statements are between braces, so they are both executed when the nested `if` condition returns `true`.

The next `if` checks whether the character entered is lowercase using essentially the same mechanism as the first `if`, then displays a message and returns.

If the character entered is not a letter, the output statement following the last `if` block is executed. This displays a message to the effect that the character entered was not a letter. The `return` is then executed.

You can see that the relationship between the nested `ifs` and the output statement is much easier to follow because of the indentation applied to each.

A typical output from this example is:

```
Enter a letter: T
You entered a capital letter.
```

You could easily arrange to change uppercase to lowercase by adding just one extra statement to the `if`, checking for uppercase:

```
if(letter >= 'A')                                // Test for 'A' or larger
    if(letter <= 'Z')                                // Test for 'Z' or smaller
    {
        cout << endl
        << "You entered a capital letter."
        << endl;
        letter += 'a' - 'A';                         // Convert to lowercase
        return 0;
    }
```

The statement for converting from uppercase to lowercase increments the `letter` variable by the value '`a`' - '`A`'. It works because the ASCII codes for '`A`' to '`Z`' and '`a`' to '`z`' are two groups of consecutive numerical codes, decimal 65 to 90 and 97 to 122, respectively, so the expression '`a`' - '`A`' represents the value to be added to an uppercase letter to get the equivalent lowercase letter and corresponds to 97–65, which is 32. Thus, if you add 32 to the code value for '`k`', which is 75, you get 107, which is the code value for '`k`'.

You could equally use the equivalent ASCII values for the letters here, but by using the letters you've ensured that this code would work on computers where the characters were not ASCII, as long as both the upper- and lowercase sets are represented by a contiguous sequence of numeric values.

There is a standard library function to convert letters to uppercase, so you don't normally need to program this yourself. It has the name `toupper()` and appears in the `ctype` standard header file. You will see more about standard library facilities when you get to look at how functions are written.

The Extended `if` Statement

The `if` statement that you have been using so far executes a statement if the condition specified returns `true`. Program execution then continues with the next statement in sequence. You also have a version of the `if` that allows one statement to be executed if the condition returns `true`, and a different statement to be executed if the condition returns `false`. Execution then continues with the next statement in sequence. As you saw in Chapter 2, a block of statements can always replace a single statement, so this also applies to these `ifs`.

TRY IT OUT Extending the if

Here's an extended if example:

```
// Ex3_02.cpp
// Using the extended if
#include <iostream>

using std::cin;
using std::cout;
using std::endl;

int main()
{
    long number(0L);           // Store input here
    cout << endl
        << "Enter an integer number less than 2 billion: ";
    cin >> number;

    if(number % 2L)            // Test remainder after division by 2
        cout << endl           // Here if remainder 1
        << "Your number is odd." << endl;
    else
        cout << endl           // Here if remainder 0
        << "Your number is even." << endl;

    return 0;
}
```

Typical output from this program is:

```
Enter an integer less than 2 billion: 123456
Your number is even.
```

How It Works

After reading the input value into `number`, the value is tested by taking the remainder after division by two (using the remainder operator `%` that you saw in the previous chapter) and using that as the condition for the `if`. In this case, the condition of the `if` statement returns an integer, not a boolean. The `if` statement interprets a non-zero value returned by the condition as `true`, and interprets zero as `false`. In other words, the condition expression for the `if` statement

`(number % 2L)`

is equivalent to

`(number % 2L != 0)`

If the remainder is 1, the condition is `true`, and the statement immediately following the `if` is executed. If the remainder is 0, the condition is `false`, and the statement following the `else` keyword is executed. It's obvious here what the `if` expression is doing, but with more complicated expressions it's better to add the extra few characters needed for the comparison with zero to ensure that the code is easily understood.

NOTE The condition in an if statement can be an expression that results in a value of any of the fundamental data types that you saw in Chapter 2. When the condition expression evaluates to a numerical value, the compiler inserts an automatic conversion of the value to type bool. Casting a non-zero value to type bool results in true, and casting a zero value results in false.

The remainder from the division of an integer by two can only be one or zero. After either outcome, the return statement is executed to end the program.

NOTE The else keyword is written without a semicolon, similar to the if part of the statement. Again, indentation is used as a visible indicator of the relationship between various statements. You can clearly see which statement is executed for a true or non-zero result, and which for a false or zero result. You should always indent the statements in your programs to show their logical structure.

The if-else combination provides a choice between two options. The general logic of the if-else is shown in Figure 3-2.

The arrows in the diagram indicate the sequence in which statements are executed, depending on whether the if condition returns true or false.

Nested if-else Statements

As you have seen, you can nest if statements within if statements. You can also nest if-else statements within ifs, ifs within if-else statements, and if-else statements within if-else statements. This provides considerable room for confusion, so let's take a look at a few examples. The following is an example of an if-else nested within an if:

```
if('y' == coffee)
    if('y' == donuts)
        cout << "We have coffee and donuts.";
    else
        cout << "We have coffee, but not donuts";
```




FIGURE 3-2

The test for donuts is executed only if the result of the test for coffee returns true, so the messages reflect the correct situation in each case; however, it is easy to get this confused. If you write much the same thing with incorrect indentation, you can be trapped into the wrong conclusion:

```

if('y' == coffee)
    if('y' == donuts)
        cout << "We have coffee and donuts.";
else                                // This else is indented incorrectly
    cout << "We have no coffee...";    // Wrong!

```

The mistake is easy to see here, but with more complicated `if` structures you need to keep in mind the rule about which `if` owns which `else`.

NOTE An `else` always belongs to the nearest preceding `if` that is not already spoken for by another `else`.

Whenever things look a bit complicated, you can apply this rule to sort things out. When you are writing your own programs you can always use braces to make the situation clearer. It isn't really necessary in such a simple case, but you could write the last example as follows:

```

if('y' == coffee)
{
    if('y' == donuts)
        cout << "We have coffee and donuts.";
    else
        cout << "We have coffee, but not donuts";
}

```

and it should be absolutely clear. Now that you know the rules, understanding the case of an `if` nested within an `if-else` becomes easy:

```

if('y' == coffee)
{
    if('y' == donuts)
        cout << "We have coffee and donuts.";
}
else
    if('y' == tea)
        cout << "We have tea, but not coffee";

```

Here, the braces are essential. If you leave them out, the `else` would belong to the second `if`, which is looking out for `donuts`. In this kind of situation, it is easy to forget to include the braces and create an error that may be hard to find. A program with this kind of error compiles fine and even produces the right results some of the time.

If you removed the braces in this example, you get the correct results only as long as `coffee` and `donuts` are both equal to `'y'` so that the `if('y' == tea)` check wouldn't be executed.

`if-else` statements nested in `if-else` statements can get very messy, even with just one level of nesting:

```

if('y' == coffee)
    if('y' == donuts)
        cout << "We have coffee and donuts.";

```

```
    else
        cout << "We have coffee, but not donuts";
    else
        if('y' == tea)
            cout << "We have no coffee, but we have tea, and maybe donuts...";
        else
            cout << "No tea or coffee, but maybe donuts...";
```

The logic here doesn't look quite so obvious, even with the correct indentation. No braces are necessary. The rule you saw earlier verifies that each `else` belongs to the correct `if`, but it would be a lot clearer if you included them:

```
if('y' == coffee)
{
    if('y' == donuts)
        cout << "We have coffee and donuts.";
    else
        cout << "We have coffee, but not donuts";
}
else
{
    if('y' == tea)
        cout << "We have no coffee, but we have tea, and maybe donuts...";
    else
        cout << "No tea or coffee, but maybe donuts...";
}
```

There are much better ways of dealing with this kind of logic in a program. If you put enough nested `ifs` together, you can almost guarantee a mistake somewhere. The next section will help to simplify things.

Logical Operators and Expressions

As you have just seen, using `ifs` where you have two or more related conditions can be a bit cumbersome. We have tried our iffy talents on looking for coffee and donuts, but in practice you may want to test much more complex conditions.

Logical operators provide a neat and simple solution. Using logical operators, you can combine a series of comparisons into a single logical expression, so you end up needing just one `if`, virtually regardless of the complexity of the set of conditions, as long as the decision ultimately boils down to a choice between two possibilities — true or false.

You have just three logical operators:

&&	Logical AND
	Logical OR
!	Logical negation (NOT)

Logical AND

You would use the AND operator, `&&`, where you have two conditions that must both be `true` for a `true` result. You want to be rich and healthy. Thus the `&&` operator produces the result `true` when both operands have the value `true`, and `false` otherwise.

You could use the `&&` operator when you are testing a character to determine whether it's an uppercase letter; the value being tested must be both greater than or equal to '`A`' and less than or equal to '`Z`'. Both conditions must return `true` for the value to be a capital letter.

NOTE As before, the conditions you combine using logical operators may return numerical values. Remember that in this case a non-zero value converts to the value `true`; zero converts to `false`.

Taking the example of a value stored in a `char` variable `letter`, you could replace the test that uses two `ifs` with one that uses only a single `if` and the `&&` operator:

```
if((letter >= 'A') && (letter <= 'Z'))
    cout << "This is a capital letter.";
```

The parentheses inside the expression that is the `if` condition ensure that there is no doubt that the comparison operations are executed first, which makes the statement clearer. Here, the output statement is executed only if *both* of the conditions that are combined by the `&&` operator are `true`.

NOTE If the left operand for the `&&` operator is `false`, the right operand will not be evaluated. This becomes significant if the right operand is an expression that can change something, such as an expression involving the `++` or `--` operator. For example, in the expression `x>=5 && ++n<10`, `n` will not be incremented if `x` is less than 5.

Logical OR

The OR operator, `||`, applies when you have two conditions where you want a `true` result if either or both of them are `true`. For example, you might be considered credit worthy for a loan from the bank if your income was at least \$100,000 a year, or if you had \$1,000,000 in cash. This could be tested using the following `if`:

```
if((income >= 100000.00) || (capital >= 1000000.00))
    cout << "How much would you like to borrow, Sir (grovel, grovel)?";
```

The ingratiating response emerges when either or both of the conditions are `true`. (A better response might be, “Why do you want to borrow?” It’s strange how banks lend you money only if you don’t need it.)

You only get a `false` result with the `||` operator when both operands are `false`.

NOTE If the left operand for the `||` operator is true, the right operand will not be evaluated. For example, in the expression `x>=5 || ++n<10`, the variable `n` will not be incremented if `x` is greater than or equal to 5.

Logical NOT

The third logical operator, `!`, takes one operand of type `bool` and inverts its value. So, if the value of a variable `test` is true, `!test` is false; and if `test` is false, `!test` is true. To take the example of a simple expression, if `x` has the value 10, the expression `!(x > 5)` evaluates to false, because `x > 5` is true.

You could also apply the `!` operator in an expression that was a favorite of Charles Dickens:

```
!(income > expenditure)
```

If this expression is true, the result is misery, at least as soon as the bank starts bouncing your checks.

Finally, you can apply the `!` operator to other basic data types. Suppose you have a variable, `rate`, that is of type `float` and has the value 3.2. For some reason, you might want to verify that the value of `rate` is non-zero, in which case you could use the expression:

```
!(rate)
```

The value 3.2 is non-zero and thus converts to the `bool` value true, so the result of this expression is false.

TRY IT OUT Combining Logical Operators

You can combine conditional expressions and logical operators to any degree that you feel comfortable with. For example, using just a single `if`, you could construct a test for whether a variable contained a letter. Let's write it as a working example:

```
// Ex3_03.cpp
// Testing for a letter using logical operators
#include <iostream>

using std::cin;
using std::cout;
using std::endl;

int main()
{
    char letter();                                // Store input in here

    cout << endl
        << "Enter a character: ";
    cin >> letter;

    if(((letter >= 'A') && (letter <= 'Z')) ||
       ((letter >= 'a') && (letter <= 'z')))      // Test for alphabetic
        cout << endl
            << "You entered a letter." << endl;
    else

```

```

        cout << endl
        << "You didn't enter a letter." << endl;

    return 0;
}

```

How It Works

This starts out in the same way as `Ex3_01.cpp`, by reading a character after a prompt for input. The interesting part of the program is in the `if` statement condition. This consists of two logical expressions combined with the `||` (OR) operator, so that if either is `true`, the condition returns `true` and the following message is displayed:

You entered a letter.

If both logical expressions are `false`, the `else` statement is executed, which displays this message:

You didn't enter a letter.

Each logical expression combines a pair of comparisons with the operator `&&` (AND), so both comparisons must return `true` if the expression is to be `true`. The first logical expression returns `true` if the input is an uppercase letter, and the second returns `true` if the input is a lowercase letter.

The Conditional Operator

The conditional operator is sometimes called the ternary operator because it involves three operands. It is best understood by looking at an example. Suppose you have two variables, `a` and `b`, and you want to assign the maximum of `a` and `b` to a third variable, `c`. You can do this with the following statement:

```
c = a > b ? a : b;           // Set c to the maximum of a or b
```

The first operand for the conditional operator must be an expression that results in a `bool` value, `true` or `false`, and in this case it is `a > b`. If this expression returns `true`, the second operand — in this case `a` — is selected as the value resulting from the operation. If the first argument returns `false`, the third operand — in this case `b` — is selected as the value that results from the operation. Thus, the result of `a > b ? a : b` is `a`, if `a` is greater than `b`, and `b` otherwise. This value is stored in `c` by the assignment operation. The use of the conditional operator in this assignment statement is equivalent to the `if` statement:

```
if(a > b)
    c = a;
else
    c = b;
```

The conditional operator can be written generally as:

```
condition ? expression1 : expression2
```

If *condition* evaluates to `true`, the result is the value of *expression1*, and if it evaluates to `false`, the result is the value of *expression2*.

TRY IT OUT Using the Conditional Operator with Output

A common use of the conditional operator is to control output based on the result of an expression or the value of a variable. You can vary a message by selecting one text string or another, depending on the condition specified:

```
// Ex3_04.cpp
// The conditional operator selecting output
#include <iostream>

using std::cout;
using std::endl;

int main()
{
    int nCakes(1);           // Count of number of cakes

    cout << endl
        << "We have " << nCakes << " cake" << ((nCakes > 1) ? "s." : ".")
        << endl;

    ++nCakes;

    cout << endl
        << "We have " << nCakes << " cake" << ((nCakes > 1) ? "s." : ".")
        << endl;
    return 0;
}
```

The output from this program is:

```
We have 1 cake.
We have 2 cakes.
```

How It Works

You first create the `nCakes` variable with the initial value 1; then you have an output statement that shows the number of cakes. The part that uses the conditional operator simply tests the variable to determine whether you have a singular cake or several cakes:

```
((nCakes > 1) ? "s." : ".")
```

This expression evaluates to "s." if `nCakes` is greater than 1, or "." otherwise. This enables you to use the same output statement for any number of cakes and get grammatically correct output. You make use of this in the example by incrementing the `nCakes` variable and repeating the output statement.

There are many other situations where you can apply this sort of mechanism; selecting between "is" and "are", for example.

The switch Statement

The `switch` statement enables you to select from multiple choices based on a set of fixed values for a given expression. It operates like a physical rotary switch in that you can select one of a number of choices. Some washing machines provide a means of choosing an operation for processing your laundry in this way. There are a number of possible positions for the switch, such as cotton, wool, synthetic fiber, and so on, and you can select one of them by turning the knob to point to the option you want.

In the `switch` statement, the selection is determined by the value of an expression that you specify. You define the possible `switch` positions by one or more *case values*, a particular one being selected if the value of the `switch` expression is the same as the particular case value. There is one case value for each possible choice in the `switch`, and all the case values must be distinct.

The general form of the `switch` statement is:

```
switch(expression)
{
    case c1:
        // One or more statements for c1...
        break;
    case c2:
        // One or more statements for c2...
        break;
    // More case statements...
    default:
        // Statements for default case...
        break;
}
```

Both `switch` and `case` are keywords. `c1`, `c2`, and so on are integer constants, or expressions that the compiler can evaluate to produce an integer constant; that is, not an expression that has to be executed at run time. The cases can be in any sequence and each case value must be unique to allow the compiler to differentiate between them. When `expression` evaluates to one of the case values, the statements following that `case` statement are executed.

If the value of the `switch` expression does not match any of the case values, the `switch` automatically selects the `default` case. You can omit the `default` case, in which case the default is to do nothing.

The `break` statement at the end of each `case` statement causes execution to transfer to the statement following the `switch` block after a `case` statement executes. If you leave it out, statements for the next case will execute. The `break` at the end of the `default` case is not necessary, but including it is a good idea to provide for the possibility that you add a `case` statement after the `default` case later. Let's see it working.

TRY IT OUT The switch Statement

You can examine how the `switch` statement works with the following example:

```
// Ex3_05.cpp
// Using the switch statement
#include <iostream>

using std::cin;
```

```
using std::cout;
using std::endl;

int main()
{
    int choice(0);                                // Store selection value here

    cout << endl
        << "Your electronic recipe book is at your service." << endl
        << "You can choose from the following delicious dishes: "
        << endl
        << endl << "1 Boiled eggs"
        << endl << "2 Fried eggs"
        << endl << "3 Scrambled eggs"
        << endl << "4 Coddled eggs"
        << endl << endl << "Enter your selection number: ";
    cin >> choice;

    switch(choice)
    {
        case 1: cout << endl << "Boil some eggs." << endl;
                  break;
        case 2: cout << endl << "Fry some eggs." << endl;
                  break;
        case 3: cout << endl << "Scramble some eggs." << endl;
                  break;
        case 4: cout << endl << "Coddle some eggs." << endl;
                  break;
        default: cout << endl << "You entered a wrong number, try raw eggs."
                  << endl;
                  break;
    }

    return 0;
}
```

How It Works

The stream output statement displays the input options, and then a selection number is read into the variable `choice`. The `switch` statement has the condition specified as simply `choice`, in parentheses, immediately following the keyword `switch`. The possible options in the `switch` are enclosed between braces and are each identified by a *case label*. A case label is the keyword `case`, followed by the value of `choice` that corresponds to this option, and terminated by a colon.

As you can see, the statements to be executed for a particular `case` follow the colon at the end of the `case` label, and are terminated by a `break` statement. The `break` transfers execution to the statement after the `switch`. The `break` isn't mandatory, but if you don't include it, execution continues with the statements for the case that follows, which isn't usually what you want. You can demonstrate this by removing the `break` statements from this example and seeing what happens.

You can put the statements to be executed for a particular `case` between braces and sometimes this is necessary. For example, if you create a variable within a `case` statement, you must include braces. The following statement will result in an error message:

```

switch(choice)
{
case 1:
    int count = 2;
    cout << "Boil " << count
        << " eggs." << endl;
    // Code to do something with count...
    break;

default:
    cout << endl << "You entered a wrong number, try raw eggs." << endl;
    break;
}

```

Because it is possible that the `count` variable may not get initialized within the block for the `switch`, you get the following error message:

```
error C2360: initialization of 'count' is skipped by 'default' label
```

You can fix this by writing it as:

```

switch(choice)
{
case 1:
{
    int count = 2;
    cout << "Boil " << count
        << " eggs." << endl;
    // Code to do something with count...
    break;
}

default:
    cout << endl << "You entered a wrong number, try raw eggs." << endl;
    break;
}

```

If the value of `choice` doesn't correspond with any of the case values, the statements following the `default` label are executed. A `default` case isn't essential. In its absence, if the value of the test expression doesn't correspond to any of the cases, the `switch` is exited, and the program continues with the next statement after the `switch`.

TRY IT OUT Sharing a Case

Each of the case expressions in a `switch` statement must be constant expressions that can be evaluated at compile time and must evaluate to a unique integer value. The reason that no two case values can be the same is that the compiler would have no way of knowing which case statement should be executed for that particular value; however, different cases don't need to have a unique action. Several cases can share the same action, as shown here:

```

// Ex3_06.cpp
// Multiple case actions

```

```
#include <iostream>

using std::cin;
using std::cout;
using std::endl;

int main()
{
    char letter(0);
    cout << endl
        << "Enter a small letter: ";
    cin >> letter;

    switch(letter*(letter >= 'a' && letter <= 'z'))
    {
        case 'a': case 'e': case 'i': case 'o': case 'u':
            cout << endl << "You entered a vowel.";
            break;

        case 0:
            cout << endl << "That is not a small letter.";
            break;

        default: cout << endl << "You entered a consonant.";
    }

    cout << endl;
    return 0;
}
```

How It Works

In this example, you have a more complex expression in the `switch`. If the character entered isn't a lowercase letter, the expression

```
(letter >= 'a' && letter <= 'z')
```

results in the value `false`; otherwise it evaluates to `true`. Because `letter` is multiplied by this expression, the value of the logical expression is converted to an integer — 0 if the logical expression is `false` and 1 if it is `true`. Thus, the `switch` expression evaluates to 0 if a lowercase letter was not entered, and to the value of `letter` if it was. The statements following the `case 0` are executed whenever the character code stored in `letter` does not represent a lowercase letter.

If a lowercase letter was entered, the `switch` expression evaluates to the same value as `letter`; so, for all values corresponding to vowels, the output statement following the sequence of case labels that have vowels as values is executed. The same statement executes for any vowel because when any of these case labels is chosen, the following statements are executed until the `break` statement is reached. You can see that a single action can be taken for a number of different cases by writing the case labels, one after the other, before the statements to be executed. If a lowercase letter that is a consonant is entered, the `default` case is executed.

Unconditional Branching

The `if` statement provides you with the flexibility to choose to execute one set of statements or another, depending on a specified condition, so the statement execution sequence is varied, depending on the values of the data in the program. The `goto` statement, in contrast, is a blunt instrument. It enables you to branch to a specified program statement unconditionally. The statement to be branched to must be identified by a statement label, which is an identifier defined according to the same rules as a variable name. This is followed by a colon and placed before the statement requiring labeling. Here is an example of a labeled statement:

```
myLabel: cout << "myLabel branch has been activated" << endl;
```

This statement has the label `myLabel`, and an unconditional branch to this statement would be written as follows:

```
goto myLabel;
```

Whenever possible, you should avoid using `gotos` in your program. They tend to encourage convoluted code that can be extremely difficult to follow.

NOTE Because the `goto` is theoretically unnecessary in a program — there's always an alternative approach to using `goto` — a significant cadre of programmers say you should never use it. I don't subscribe to such an extreme view. It is a legal statement, after all, and there are occasions when it can be convenient, such as when you must exit from a deeply nested set of loops (you learn about loops in the next section). I do, however, recommend that you only use it where you can see an obvious advantage over other options that are available; otherwise, you may end up with convoluted, error-prone code that is hard to understand and even harder to maintain.

REPEATING A BLOCK OF STATEMENTS

The capability to repeat a group of statements is fundamental to most applications. Without this, an organization would need to modify the payroll program every time an extra employee was hired, and you would need to reload your favorite game every time you wanted to play. So, let's first understand how a loop works.

What Is a Loop?

A loop executes a sequence of statements subject to a given condition. You can write a loop with the statements that you have met so far. You just need an `if` and the dreaded `goto`. Look at the following example:

```
// Ex3_07.cpp
// Creating a loop with an if and a goto
#include <iostream>

using std::cout;
using std::endl;

int main()
{
    int i(1), sum(0);
    const int max(10);

loop:
    sum += i;           // Add current value of i to sum
    if(++i <= max)
        goto loop;     // Go back to loop until i = 11

    cout << endl
        << "sum = " << sum << endl
        << "i = "    << i    << endl;
    return 0;
}
```

This example accumulates the sum of integers from 1 to 10. The first time through the sequence of statements, `i` has the initial value 1 and is added to `sum`, which starts out as zero. In the `if`, `i` is incremented to 2 and, as long as it is less than or equal to `max`, the unconditional branch to `loop` occurs, and the value of `i`, now 2, is added to `sum`. This continues with `i` being incremented and added to `sum` each time, until finally, when `i` is incremented to 11 in the `if`, the branch back is not executed. If you run this example, you get the following output:

```
sum = 55
i = 11
```

This shows quite clearly how the loop works; however, it uses a `goto` and introduces a label into the program, both of which you should avoid, if possible. You can achieve the same thing, and more, with the `for` statement, which is specifically for writing a loop.

TRY IT OUT Using the for Loop

You can rewrite the last example using what is known as a `for` loop:

```
// Ex3_08.cpp
// Summing integers with a for loop
#include <iostream>

using std::cout;
```

```

using std::endl;

int main()
{
    int i(1), sum(0);
    const int max(10);

    for(i = 1; i <= max; i++)          // Loop specification
        sum += i;                  // Loop statement

    cout << endl
        << "sum = " << sum << endl
        << "i = "   << i   << endl;
    return 0;
}

```

How It Works

If you compile and run this, you get exactly the same output as the previous example, but the code is much simpler here. The conditions determining the operation of the loop appear in parentheses after the keyword `for`. There are three expressions that appear within the parentheses, separated by semicolons:

- The first expression executes once at the outset and sets the initial conditions for the loop. In this case, it sets `i` to 1.
- The second expression is a logical expression that determines whether the loop statement (or block of statements) should continue to be executed. If the second expression is `true`, the loop continues to execute; when it is `false`, the loop ends, and execution continues with the statement that follows the loop. In this case, the loop statement on the following line is executed as long as `i` is less than or equal to `max`.
- The third expression is evaluated after the loop statement (or block of statements) executes, and in this case increments `i` at each iteration. After this expression has been evaluated, the second expression is evaluated once more to see whether the loop should continue.

Actually, this loop is not exactly the same as the version in `Ex3_07.cpp`. You can demonstrate this if you set the value of `max` to 0 in both programs and run them again; then, you will find that the value of `sum` is 1 in `Ex3_07.cpp` and 0 in `Ex3_08.cpp`, and the value of `i` differs too. The reason for this is that the `if` version of the program always executes the loop at least once, because you don't check the condition until the end. The `for` loop doesn't do this, because the condition is actually checked at the beginning.


The general form of the `for` loop is:

```

for (initializing_expression ; test_expression ; increment_expression)
    loop_statement;

```

Of course, `loop_statement` can be a single statement, or a block of statements between braces. The sequence of events in executing the `for` loop is shown in Figure 3-3.

for loop logic**FIGURE 3-3**

The expressions controlling the `for` loop are very flexible. You can even write two or more expressions, separated by the comma operator, for each control expression. This gives you a lot of scope in what you can do with a `for` loop.

NOTE *The more mathematically minded will know that you can sum the first n integers without using a loop. The sum of the integers from 1 to n is given by the expression $\frac{1}{2}n(n+1)$. Using this wouldn't teach you much about loops though.*

Variations on the for Loop

Most of the time, the expressions in a `for` loop are used in a fairly standard way: the first to initialize one or more loop counters, the second to test if the loop should continue, and the third to increment or decrement one or more loop counters. You are not obliged to use these expressions in this way, however, and quite a few variations are possible.

The initialization expression can also include a declaration for a loop variable. In the previous example, you could have written the loop to include the declaration for the loop counter *i* in the first control expression.

```
for(int i = 1; i <= max; i++)           // Loop specification
    sum += i;                           // Loop statement
```

Naturally, the original declaration for *i* would need to be omitted in the program. If you make this change to the last example, you will find that it does not compile because the loop variable, *i*, ceases to exist after the loop, so you cannot refer to it in the output statement. A loop has a scope which extends from the `for` expression to the end of the body of the loop, which of course can be a block of code between braces, as well as just a single statement. The counter *i* is now declared within the loop scope, so you cannot refer to it in the output statement, which is outside the scope of the loop. If you need to use the value in the counter after the loop has executed, you must declare the counter variable *outside the scope of the loop*.

You can omit the initialization expression altogether from the loop. Because *i* has the initial value 1, you can write the loop as:

```
for(; i <= max; i++)           // Loop specification
    sum += i;                   // Loop statement
```

You still need the semicolon that separates the initialization expression from the test condition. In fact, both semicolons must always be present, regardless of whether any or all of the control expressions are omitted. If you omit the first semicolon, the compiler is unable to decide which expression has been omitted, or even which semicolon is missing.

The loop statement can be empty. For example, you could place the loop statement in the `for` loop from the previous example inside the increment expression; in this case the loop becomes:

```
for(; i <= max; sum += i++);      // The whole loop
```

You still need the semicolon after the closing parentheses, to indicate that the loop statement is now empty. If you omit this, the statement immediately following this line is interpreted as the loop statement. Sometimes you'll see the empty loop statement written on a separate line, like the following:

```
for(; i <= max; sum += i++)      // The whole loop
;
```

TRY IT OUT Using Multiple Counters

You can use the comma operator to include multiple counters in a `for` loop. You can see this in operation in the following program:

```
// Ex3_09.cpp
// Using multiple counters to show powers of 2
#include <iostream>
#include <iomanip>

using std::cout;
```

```
using std::endl;
using std::setw;

int main()
{
    const int max(10);

    for(long i = 0L, power = 1L; i <= max; i++, power += power)
        cout << endl
            << setw(10) << i << setw(10) << power;      // Loop statement

    cout << endl;
    return 0;
}
```

How It Works

You create and initialize two variables in the initialization section of the `for` loop and increment each of them in the increment section. You can create as many variables as you want here, as long as they are of the same type.

You can also specify multiple conditions, separated by commas, in the second expression that represents the test part of the `for` loop that determines whether it should continue, but this is not generally useful because only the right-most condition affects when the loop ends.

For each increment of `i`, the value of the variable `power` is doubled by adding it to itself. This produces the powers of two that we are looking for, and so the program produces the following output:

0	1
1	2
2	4
3	8
4	16
5	32
6	64
7	128
8	256
9	512
10	1024

You use the `setw()` manipulator that you saw in the previous chapter to align the output nicely. You have included the `iomanip` header file and added a `using` declaration for the name in the `std` namespace, so you can use `setw()` without qualifying the name.

TRY IT OUT The Indefinite for Loop

If you omit the second control expression that specifies the test condition for a `for` loop, the value is assumed to be `true`, so the loop continues indefinitely unless you provide some other means of exiting from it. In fact, you can omit all the expressions in the parentheses after `for`. This may not seem to be useful, but the reverse is true. You will often come across situations where you want to execute a loop a number of times, but you do not know in advance how many iterations you will need. Have a look at the following:

```

// Ex3_10.cpp
// Using an indefinite for loop to compute an average
#include <iostream>

using std::cin;
using std::cout;
using std::endl;

int main()
{
    double value(0.0);                                // Value entered stored here
    double sum(0.0);                                 // Total of values accumulated here
    int i(0);                                         // Count of number of values
    char indicator('n');                            // Continue or not?

    for(;;)                                         // Indefinite loop
    {
        cout << endl
            << "Enter a value: ";
        cin >> value;                               // Read a value
        ++i;                                         // Increment count
        sum += value;                             // Add current input to total

        cout << endl
            << "Do you want to enter another value (enter y or n)? ";
        cin >> indicator;                         // Read indicator
        if (('n' == indicator) || ('N' == indicator))
            break;                                // Exit from loop
    }

    cout << endl
        << "The average of the " << i
        << " values you entered is " << sum/i << ".";
    << endl;
    return 0;
}

```

How It Works

This program computes the average of an arbitrary number of values. After each value is entered, you must indicate whether you want to enter another value, by entering a single character, y or n. Typical output from executing this example is:

```

Enter a value: 10

Do you want to enter another value (enter y or n)? y

Enter a value: 20

Do you want to enter another value (enter y or n)? y

Enter a value: 30

Do you want to enter another value (enter y or n)? n

```

The average of the 3 values you entered is 20.

After declaring and initializing the variables that you're going to use, you start a `for` loop with no expressions specified, so there is no provision for ending it here. The block immediately following is the subject of the loop that is to be repeated.

The loop block performs three basic actions:

- It reads a value.
- It adds the value read from `cin` to `sum`.
- It checks whether you want to continue to enter values.

The first action within the block is to prompt you for input and then read a value into the variable `value`. The value that you enter is added to `sum`, and the count of the number of values, `i`, is incremented. After accumulating the value in `sum`, you are asked if you want to enter another value, and prompted to enter '`y`' or '`n`' if you have finished. The character that you enter is stored in `indicator`, for testing against '`n`' or '`N`' in the `if` statement. If neither is found, the loop continues; otherwise, a `break` is executed. The effect of `break` in a loop is similar to its effect in the context of the `switch` statement. It exits the loop immediately by transferring control to the statement following the closing brace of the loop block.

Finally, you output the count of the number of values entered and their average, which is calculated by dividing `sum` by `i`. Of course, `i` is promoted to type `double` before the calculation, as you remember from the casting discussion in Chapter 2.

Using the `continue` Statement

You write the `continue` statement simply as:

```
continue;
```

Executing `continue` within a loop starts the next loop iteration immediately, skipping over any statements remaining in the body of the loop. I can show how this works with the following code:

```
#include <iostream>

using std::cin;
using std::cout;
using std::endl;

int main()
{
    int value(0), product(1);

    for(int i = 1; i <= 10; i++)
    {
        cout << "Enter an integer: ";
        cin >> value;
        product *= value;
    }
    cout << "The product is " << product << endl;
}
```

```

    cin >> value;

    if(0 == value)           // If value is zero
        continue;            // skip to next iteration

    product *= value;
}

cout << "Product (ignoring zeros): " << product
     << endl;

return 0;                  // Exit from loop
}

```

This loop reads 10 values with the intention of producing the product of the values entered. The `if` checks each value, and if it is zero, the `continue` statement skips to the next iteration. This is so that you don't end up with a zero product if one of the values is zero. Obviously, if a zero value occurred on the last iteration, the loop would end. There are other ways of achieving the same result, but `continue` provides a very useful capability, particularly with complex loops where you may need to skip to the end of the current iteration from various points in the loop.

The effect of the `break` and `continue` statements on the logic of a `for` loop is illustrated in Figure 3-4.




FIGURE 3-4

Obviously, in a real situation, you would use the `break` and `continue` statements with some condition-testing logic to determine when the loop should be exited, or when an iteration of the loop should be skipped. You can also use the `break` and `continue` statements with the other kinds of loop, which I'll discuss later on in this chapter, where they work in exactly the same way.

TRY IT OUT Using Other Types in Loops

So far, you have only used integers to count loop iterations. You are in no way restricted as to what type of variable you use to count iterations. Look at the following example:

```
// Ex3_11.cpp
// Display ASCII codes for alphabetic characters
#include <iostream>
#include <iomanip>

using std::cout;
using std::endl;
using std::hex;
using std::dec;
using std::setw;

int main()
{
    for(char capital = 'A', small = 'a'; capital <= 'Z'; capital++, small++)
    {
        cout << endl
            << "\t" << capital           // Output capital as a character
            << hex << setw(10) << static_cast<int>(capital)   // and as hexadecimal
            << dec << setw(10) << static_cast<int>(capital)   // and as decimal
            << " " << small           // Output small as a character
            << hex << setw(10) << static_cast<int>(small)     // and as hexadecimal
            << dec << setw(10) << static_cast<int>(small);    // and as decimal
    }

    cout << endl;
    return 0;
}
```

How It Works

Here we have `using` declarations for the names of some new manipulators that are used in the program to affect how the output is presented.

The loop in this example is controlled by the `char` variable `capital`, which you declare along with the variable `small` in the initializing expression. You also increment both variables in the third control expression for the loop, so that the value of `capital` varies from '`A`' to '`Z`', and the value of `small` correspondingly varies from '`a`' to '`z`'.

The loop contains just one output statement spread over seven lines. The first line is:

```
cout << endl
```

This starts a new line on the screen.

The next three lines are:

```
<< "\t" << capital           // Output capital as a character
<< hex << setw(10) << static_cast<int>(capital) // and as hexadecimal
<< dec << setw(10) << static_cast<int>(capital) // and as decimal
```

After outputting a tab character on each iteration, the value of `capital` is displayed three times: as a character, as a hexadecimal value, and as a decimal value.

Inserting the `hex` manipulator into the `cout` stream causes subsequent integer data values to be displayed as hexadecimal values, rather than the default decimal representation, so the second output of `capital` is as a hexadecimal representation of the character code.

You then insert the `dec` manipulator into the stream to cause succeeding values to be output as decimals once more. By default, a variable of type `char` is interpreted by the stream as a character, not a numerical value. You get the `char` variable `capital` to output as a numerical value by casting its value to type `int`, using the `static_cast<>()` operator that you saw in the previous chapter.

The value of `small` is output in a similar way by the next three lines of the output statement:

```
<< " " << small           // Output small as a character
<< hex << setw(10) << static_cast<int>(small) // and as hexadecimal
<< dec << setw(10) << static_cast<int>(small); // and as decimal
```

As a result, the program generates the following output:

A	41	65	a	61	97
B	42	66	b	62	98
C	43	67	c	63	99
D	44	68	d	64	100
E	45	69	e	65	101
F	46	70	f	66	102
G	47	71	g	67	103
H	48	72	h	68	104
I	49	73	i	69	105
J	4a	74	j	6a	106
K	4b	75	k	6b	107
L	4c	76	l	6c	108
M	4d	77	m	6d	109
N	4e	78	n	6e	110
O	4f	79	o	6f	111
P	50	80	p	70	112
Q	51	81	q	71	113
R	52	82	r	72	114
S	53	83	s	73	115
T	54	84	t	74	116
U	55	85	u	75	117
V	56	86	v	76	118
W	57	87	w	77	119
X	58	88	x	78	120
Y	59	89	y	79	121
Z	5a	90	z	7a	122

Floating-Point Loop Counters

You can use a floating-point value as a loop counter. Here's an example of a `for` loop with this kind of counter:

```
double a(0.3), b(2.5);
for(double x = 0.0; x <= 2.0; x += 0.25)
    cout << "\n\tx = " << x
        << "\ta*x + b = " << a*x + b;
```

This code fragment calculates the value of `a*x + b` for values of `x` from 0.0 to 2.0, in steps of 0.25; however, you need to take care when using a floating-point counter in a loop. Many decimal values cannot be represented exactly in binary floating-point form, so discrepancies can build up with cumulative values. This means that you should not code a `for` loop such that ending the loop depends on a floating-point loop counter reaching a precise value. For example, the following poorly-designed loop never ends:

```
for(double x = 0.0; x != 1.0; x += 0.1)
    cout << x << endl;
```

The intention with this loop is to output the value of `x` as it varies from 0.0 to 1.0; however, 0.1 has no exact representation as a binary floating-point value, so the value of `x` is never exactly 1. Thus, the second loop control expression is always `false`, and the loop continues indefinitely.

NOTE It's easy to see why some decimal fractional values cannot be represented exactly as binary values. In a binary fraction, the digits to the right of the binary point are equivalent to the decimal fractions $1/2$, $1/4$, $1/8$, $1/16$, and so on. Thus any binary fraction as a decimal value is the sum of one or more of these decimal fractions. Decimal fractions such as $1/3$ or $1/10$ that have a denominator that is odd or has an odd factor can never be represented exactly by a sum of fractions that all have an even denominator.

The `while` Loop

A second kind of loop in C++ is the `while` loop. Where the `for` loop is primarily used to repeat a statement or a block for a prescribed number of iterations, the `while` loop is used to execute a statement or block of statements as long as a specified condition is true. The general form is:

```
while(condition)
    loop_statement;
```

Here `loop_statement` is executed repeatedly, as long as the `condition` expression has the value `true`. After the condition becomes `false`, the program continues with the statement following the loop. As always, a block of statements between braces could replace the single `loop_statement`.

The logic of the `while` loop is shown in Figure 3-5.




FIGURE 3-5

TRY IT OUT Using the while Loop

You could rewrite the earlier example that computes averages (Ex3_10.cpp) to use the `while` loop.

```

// Ex3_12.cpp
// Using a while loop to compute an average
#include <iostream>

using std::cin;
using std::cout;
using std::endl;

int main()
{
    double value(0.0);                      // Value entered stored here
    double sum(0.0);                        // Total of values accumulated here
    int i(0);                                // Count of number of values
    char indicator('y');                     // Continue or not?

    while('y' == indicator)                  // Loop as long as y is entered
    {
        cout << endl
            << "Enter a value: ";
        cin >> value;                         // Read a value
        ++i;                                  // Increment count
        sum += value;                          // Add current input to total

        cout << endl
            << "Do you want to enter another value (enter y or n)? ";
        cin >> indicator;                     // Read indicator
    }

    cout << endl
  
```

```
<< "The average of the " << i
<< " values you entered is " << sum/i << "."
<< endl;
return 0;
}
```

How It Works

For the same input, this version of the program produces the same output as before. One statement has been updated, and another has been added — they are highlighted in the code. The `for` loop statement has been replaced by the `while` statement, and the test for `indicator` in the `if` has been deleted, as this function is performed by the `while` condition. You have to initialize `indicator` with '`y`', in place of the '`n`' which appeared previously — otherwise the `while` loop terminates immediately. As long as the condition in the `while` returns `true`, the loop continues.

You can use any expression resulting in `true` or `false` as a `while` loop condition. The example would be better if the loop condition was extended to allow '`Y`' to be entered to continue the loop, as well as '`y`'. You could modify the `while` as follows to do the trick:

```
while(('y' == indicator) || ('Y' == indicator))
```

You can also create a `while` loop that potentially executes indefinitely, by using a condition that is always `true`. This can be written as follows:

```
while(true)
{
...
}
```


You could also write the loop control expression as the integer value `1`, which would be converted to the `bool` value `true`. Naturally, the same requirement applies here as in the case of the indefinite `for` loop: namely, you must provide some way of exiting the loop within the loop block. You'll see other ways to use the `while` loop in Chapter 4.

The do-while Loop

The `do-while` loop is similar to the `while` loop in that the loop continues as long as the specified loop condition remains `true`. The main difference is that the condition is checked at the end of the loop — which contrasts with the `while` loop and the `for` loop, where the condition is checked at the beginning. Consequently, the `do-while` loop statement is always executed at least once. The general form of the `do-while` loop is:

```
do
{
    loop_statements;
}while(condition);
```

The logic of this form of loop is shown in Figure 3-6.

**FIGURE 3-6**

You could replace the `while` loop in the last version of the program to calculate an average with a `do-while` loop:

```

do
{
    cout << endl
        << "Enter a value: ";
    cin >> value;           // Read a value
    ++i;                   // Increment count
    sum += value;          // Add current input to total

    cout << "Do you want to enter another value (enter y or n)?";
    cin >> indicator;     // Read indicator
} while(('y' == indicator) || ('Y' == indicator));
  
```

There's little difference between the two versions of the loop, except that this version doesn't depend on the initial value set in `indicator` for correct operation. As long as you want to enter at least one value, which is not unreasonable for the calculation in question, this version is preferable.

The Range-Based for Loop

I am introducing this loop here so all the loops that you have available appear together. The range-based `for` loop enables you to iterate over each of the items in a collection of items in a very simple way. You have not met any collections to which you can apply this loop so far, but you will meet arrays in the next chapter where you can use this loop. I'll discuss how the range-based `for` loop works in more detail then, and you will learn about other kinds of collections that you can apply the range-based `for` loop to in Chapter 10.

Nested Loops

You can nest one loop inside another. The usual application for this will become more apparent in Chapter 4 — it's typically applied to repeating actions at different levels of classification. An example might be calculating the total marks for each student in a class, and then repeating the process for each class in a school.

TRY IT OUT Nested Loops

You can see the effects of nesting one loop inside another by calculating the values of a simple formula. A factorial of an integer is the product of all the integers from 1 to the integer in question; the factorial of 3, for example, is 1 times 2 times 3, which is 6. The following program computes the factorial of integers that you enter (until you've had enough):

```
// Ex3_13.cpp
// Demonstrating nested loops to compute factorials
#include <iostream>

using std::cin;
using std::cout;
using std::endl;

int main()
{
    char indicator('n');
    long value(0L), factorial(0L);

    do
    {
        cout << endl << "Enter an integer value: ";
        cin >> value;

        factorial = 1L;
        for(long i = 2L; i <= value; i++)
            factorial *= i;

        cout << "Factorial " << value << " is " << factorial;
        cout << endl << "Do you want to enter another value (y or n)? ";
        cin >> indicator;
    } while('y' == indicator) || ('Y' == indicator));

    return 0;
}
```

If you compile and execute this example, the typical output produced is:

```
Enter an integer value: 5
Factorial 5 is 120
Do you want to enter another value (y or n)? y

Enter an integer value: 10
Factorial 10 is 3628800
```

```

Do you want to enter another value (y or n)? y

Enter an integer value: 13
Factorial 13 is 1932053504
Do you want to enter another value (y or n)? y

Enter an integer value: 22
Factorial 22 is -522715136
Do you want to enter another value (y or n)? n

```

How It Works

Factorial values grow very fast. In fact, 12 is the largest input value for which this example produces a correct result. The factorial of 13 is actually 6,227,020,800, not 1,932,053,504 as the program tells you. If you run it with even larger input values, leading digits are lost in the result stored in the variable `factorial`, and you may well get negative values for the factorial, as you do when you ask for the factorial of 22.

This situation doesn't cause any error messages, so it is of paramount importance that you are sure that the values you're dealing with in a program can be contained in the permitted range of the type of variable you're using. You also need to consider the effects of incorrect input values. Errors of this kind, which occur silently, can be very hard to find.

The outer of the two nested loops is the `do-while` loop, which controls when the program ends. As long as you keep entering `y` or `Y` at the prompt, the program continues to calculate factorial values. The factorial for the integer entered is calculated in the inner `for` loop. This is executed `value-1` times, to multiply the variable `factorial` (with an initial value of 1) with successive integers from 2 to `value`.

TRY IT OUT Another Nested Loop

Nested loops can be a little confusing, so let's try another example. This program generates a multiplication table of a given size:

```

// Ex3_14.cpp
// Using nested loops to generate a multiplication table
#include <iostream>
#include <iomanip>

using std::cout;
using std::endl;
using std::setw;

int main()
{
    const int size(12);           // Size of table
    int i(0), j(0);             // Loop counters

    cout << endl                // Output table title
    << size << " by " << size << " Multiplication Table" << endl << endl;

```

```

cout << endl << "    | ";
for(i = 1; i <= size; i++)           // Loop to output column headings
    cout << setw(3) << i << " ";
cout << endl;                      // Newline for underlines
for(i = 0; i <= size; i++)          // Underline each heading
    cout << "____";
for(i = 1; i <= size; i++)          // Outer loop for rows
{
    cout << endl
        << setw(3) << i << " | ";   // Output row label
    for(j = 1; j <= size; j++)      // Inner loop for the rest of the row
        cout << setw(3) << i*j << " "; // End of inner loop
}
cout << endl;                      // End of outer loop
return 0;
}

```

The output from this example is:

12 by 12 Multiplication Table

	1	2	3	4	5	6	7	8	9	10	11	12
1	1	2	3	4	5	6	7	8	9	10	11	12
2	2	4	6	8	10	12	14	16	18	20	22	24
3	3	6	9	12	15	18	21	24	27	30	33	36
4	4	8	12	16	20	24	28	32	36	40	44	48
5	5	10	15	20	25	30	35	40	45	50	55	60
6	6	12	18	24	30	36	42	48	54	60	66	72
7	7	14	21	28	35	42	49	56	63	70	77	84
8	8	16	24	32	40	48	56	64	72	80	88	96
9	9	18	27	36	45	54	63	72	81	90	99	108
10	10	20	30	40	50	60	70	80	90	100	110	120
11	11	22	33	44	55	66	77	88	99	110	121	132
12	12	24	36	48	60	72	84	96	108	120	132	144

How It Works

The table title is produced by the first output statement in the program. The next output statement, combined with the loop following it, generates the column headings. Each column is five characters wide, so the heading value is displayed in a field width of three, specified by the `setw(3)` manipulator, followed by two spaces. The output statement preceding the loop outputs four spaces and a vertical bar above the first column, which contains the row headings. A series of underline characters is then displayed beneath the column headings.

The nested loop generates the main table contents. The outer loop repeats once for each row, so `i` is the row number. The output statement

```
cout << endl
<< setw(3) << i << " |"; // Output row label
```

goes to a new line for the start of a row, and then outputs the row heading given by the value of `i` in a field width of three, followed by a space and a vertical bar.

A row of values is generated by the inner loop:

```
for(j = 1; j <= size; j++) // Inner loop for the rest of the row
    cout << setw(3) << i*j << " "; // End of inner loop
```

This loop outputs values `i*j`, corresponding to the product of the current row value `i`, and each of the column values in turn by varying `j` from 1 to `size`. So, for each iteration of the outer loop, the inner loop executes `size` iterations. The values are positioned in the same way as the column headings. When the outer loop is completed, the `return` is executed to end the program.

SUMMARY

In this chapter, you learned all the essential mechanisms for making decisions in C++ programs. The ability to compare values and change the course of program execution is what differentiates a computer from a simple calculator. You need to be comfortable with all of the decision-making statements I have discussed because they are all used very frequently. You have also gone through all the facilities for repeating a group of statements. Loops are a fundamental programming technique that you will need to use in every program of consequence that you write. You will find you use the `for` loop most often in C++, closely followed by the `while` loop.

EXERCISES

1. Write a program that reads numbers from `cin` and then sums them, stopping when 0 has been entered. Construct three versions of this program, using the `while`, `do-while`, and `for` loops.
2. Write a program to read characters from the keyboard and count the vowels. Stop counting when a Q (or a q) is encountered. Use a combination of an indefinite loop to get the characters, and a `switch` statement to count them.
3. Write a program to print out the multiplication tables from 2 to 12, in columns.
4. Imagine that in a program you want to set a ‘file open mode’ variable based on two attributes: the file type, which can be text or binary, and the way in which you want to open the file to read or write it, or append data to it. Using the bitwise operators (`&` and `|`) and a set of flags, devise a method to allow a single integer variable to be set to any combination of the two attributes. Write a program that sets such a variable and then decodes it, printing out its setting, for all possible combinations of the attributes.

► WHAT YOU LEARNED IN THIS CHAPTER

TOPIC	CONCEPT
Relational operators	The relational operators allow you to combine logical values or expressions that result in a logical value. They yield a <code>bool</code> value — <code>true</code> or <code>false</code> — as the result that you can use in an <code>if</code> statement.
Decisions based on numerical values	You can make decisions based on conditions that return non- <code>bool</code> values. Any non-zero value is cast to <code>true</code> when a condition is tested; zero casts to <code>false</code> .
Statements for decision-making	The <code>if</code> statement provides the primary decision-making capability in C++. Further flexibility is provided by the <code>switch</code> statement and the conditional operator.
Loop statements	There are four basic methods for repeating a block of statements: the <code>for</code> loop, the <code>while</code> loop, the <code>do-while</code> loop, and the range-based <code>for</code> loop. The <code>for</code> loop allows the loop to repeat a given number of times. The <code>while</code> loop allows a loop to continue as long as a specified condition returns <code>true</code> . The <code>do-while</code> executes the loop at least once and allows continuation of the loop as long as a specified condition returns <code>true</code> . The range-based <code>for</code> loop enables you to iterate over all the items in a collection.
Nested loops	Any kind of loop may be nested within any other kind of loop.
The <code>continue</code> keyword	The keyword <code>continue</code> allows you to skip the remainder of the current iteration in a loop and go straight to the next iteration.
The <code>break</code> keyword	The keyword <code>break</code> provides an immediate exit from a loop. It also provides an exit from a <code>switch</code> at the end of statements in a <code>case</code> .

4

Arrays, Strings, and Pointers

WHAT YOU WILL LEARN IN THIS CHAPTER:

- How to use arrays
- How to declare and initialize arrays of different types
- How to use the range-based `for` loop with an array
- How to declare and use multidimensional arrays
- How to use pointers
- How to declare and initialize pointers of different types
- The relationship between arrays and pointers
- How to declare references and some initial ideas on their uses

WROX.COM CODE DOWNLOADS FOR THIS CHAPTER

You can find the wrox.com code downloads for this chapter on the Download Code tab at www.wrox.com/remtitle.cgi?isbn=9781118368084. The code is in the Chapter 4 download and individually named according to the names throughout the chapter.

HANDLING MULTIPLE DATA VALUES OF THE SAME TYPE

You already know how to declare and initialize variables of various types that each holds a single item of information; I'll refer to single items of data as *data elements*. The most obvious extension to the idea of a variable is to be able to reference several data elements of a particular type with a single variable name. This would enable you to handle applications of a much broader scope.

Let's consider an example of where you might need this. Suppose that you needed to write a payroll program. Using a separately named variable for each individual's pay, their tax liability, and so on, would be an uphill task to say the least. A much more convenient way to handle such a problem would be to reference an employee by some kind of generic name — `employeeName` to take an imaginative example — and to have other generic names for the kinds of data related to each employee, such as `pay`, `tax`, and so on. Of course, you would also need some means of picking out a particular employee from the whole bunch, together with the data from the generic variables associated with them. This kind of requirement arises with any collection of like entities that you want to handle in your program, whether they're baseball players or battleships. Naturally, C++ provides you with a way to deal with this.

Arrays

The basis for the solution to all of these problems is provided by the *array*. An array is simply a number of memory locations called *array elements* or simply *elements*, each of which can store an item of data of the same given data type, and which are all referenced through the same variable name. The employee names in a payroll program could be stored in one array, the pay for each employee in another, and the tax due for each employee could be stored in a third array.

You select a particular element in an array using an index value, which is simply an integer representing the sequence number of the element in the array. The first element has the sequence number 0, the second 1, and so on. You can also envisage the index value of an array element as being an offset from the first element in an array. The first element has an offset of 0 and therefore an index of 0, and an index value of 3 will refer to the fourth element of an array.

The basic structure of an array is illustrated in Figure 4-1.




FIGURE 4-1

Figure 4-1 shows an array with the name `height` that has six elements, each storing a different value. These might be the heights of the members of a family, for instance, recorded to the nearest inch. Because there are six elements, the index values run from 0 through 5. To refer to a particular element, you write the array name, followed by the index value of the particular element between

square brackets. The third element is referred to as `height[2]`, for example. If you think of the index as being the offset from the first element, it's easy to see that the index value for the fourth element will be 3.

The amount of memory required to store each element is determined by its type, and all the elements of an array are stored in a contiguous block of memory.

Declaring Arrays

You declare an array in essentially the same way as you declared the variables that you have seen up to now, the only difference being that the number of elements in the array is specified between square brackets immediately following the array name. For example, you could declare the integer array `height`, shown in the previous figure, with the following declaration statement:

```
long height[6];
```

Because each `long` value occupies 4 bytes in memory, the whole array requires 24 bytes. Arrays can be of any size, subject to the constraints imposed by the amount of memory in the computer on which your program is running.

You can declare arrays to be of any type. For example, to declare arrays intended to store the capacity and power output of a series of engines, you could write the following:

```
double engine_size[10];      // Engine size in cubic inches
double horsepower[10];      // Engine power output
```

If auto mechanics is your thing, this would enable you to store the cubic capacity and power output of up to 10 engines, referenced by index values from 0 to 9. As you have seen before with other variables, you can declare multiple arrays of a given type in a single statement, but in practice it is almost always better to declare variables in separate statements.

TRY IT OUT Using Arrays

As a basis for an exercise in using arrays, imagine that you have kept a record of both the amount of gasoline you have bought for the car and the odometer reading on each occasion. You can write a program to analyze this data to see how the gas consumption looks on each occasion that you bought gas:

```
// Ex4_01.cpp
// Calculating gas mileage
#include <iostream>
#include <iomanip>

using std::cin;
using std::cout;
using std::endl;
using std::setw;

int main()
{
```

```
const int MAX(20);           // Maximum number of values
double gas[ MAX ];          // Gas quantity in gallons
long miles[ MAX ];          // Odometer readings
int count(0);                // Loop counter
char indicator('y');         // Input indicator

while( ('y' == indicator || 'Y' == indicator) && count < MAX )
{
    cout << endl << "Enter gas quantity: ";
    cin >> gas[count];           // Read gas quantity
    cout << "Enter odometer reading: ";
    cin >> miles[count];        // Read odometer value

    ++count;
    cout << "Do you want to enter another(y or n)? ";
    cin >> indicator;
}

if(count <= 1)               // count = 1 after 1 entry completed
{                           // ... we need at least 2
    cout << endl << "Sorry - at least two readings are necessary.";
    return 0;
}

// Output results from 2nd entry to last entry
for(int i = 1; i < count; i++)
{
    cout << endl
        << setw(2) << i << ".           // Output sequence number
        << "Gas purchased = " << gas[i] << " gallons" // Output gas
        << " resulted in "           // Output miles per gallon
        << (miles[i] - miles[i - 1])/gas[i] << " miles per gallon." ;
}
cout << endl;
return 0;
}
```

The program assumes that you fill the tank each time, so the gas bought was the amount consumed by driving the distance recorded. Here's an example of the output produced by this example:

```
Enter gas quantity: 12.8
Enter odometer reading: 25832
Do you want to enter another(y or n)? y

Enter gas quantity: 14.9
Enter odometer reading: 26337
Do you want to enter another(y or n)? y

Enter gas quantity: 11.8

Enter odometer reading: 26598
Do you want to enter another(y or n)? n
```

1.Gas purchased = 14.9 gallons resulted in 33.8926 miles per gallon.
 2.Gas purchased = 11.8 gallons resulted in 22.1186 miles per gallon.

How It Works

Because you need to take the difference between two odometer readings to calculate the miles covered for the gas used, you use only the odometer reading from the first pair of input values — you ignore the gas bought in the first instance as that would have been consumed during miles driven earlier.

During the second period shown in the output, the traffic must have been really bad — or maybe the parking brake was left on.

The dimensions of the two arrays `gas` and `miles` used to store the input data are determined by the value of the constant with the name `MAX`. By changing the value of `MAX`, you can change the program to accommodate a different maximum number of input values. This technique is commonly used to make a program flexible in the amount of information that it can handle. Of course, all the program code must be written to take account of the array dimensions, or of any other parameters being specified by `const` variables. This presents little difficulty in practice, however, so there's no reason why you should not adopt this approach. You'll also see later how to allocate memory for storing data as the program executes, so that you don't need to fix the amount of memory allocated for data storage in advance.

Entering the Data

The data values are read in the `while` loop. Because the loop variable `count` can run from 0 to `MAX - 1`, we haven't allowed the user of our program to enter more values than the array can handle. You initialize the variables `count` and `indicator` to 0 and 'y' respectively, so that the `while` loop is entered at least once. There's a prompt for each input value required and the value is read into the appropriate array element. The element used to store a particular value is determined by the variable `count`, which is 0 for the first input. The array element is specified in the `cin` statement by using `count` as an index, and `count` is then incremented, ready for the next value.

After you enter each value, the program prompts for confirmation that another value is to be entered. The character entered is read into `indicator` and then tested in the loop condition. The loop will terminate unless 'y' or 'Y' is entered and `count` is less than the specified maximum value, `MAX`.

After the input loop ends (by whatever means), the value of `count` contains one more than the index value of the last element entered in each array. (Remember, you increment it after you enter each new element). This is checked in order to verify that at least two pairs of values were entered. If this wasn't the case, the program ends with a suitable message because two odometer values are necessary to calculate a mileage value.

Producing the Results

The output is generated in the `for` loop. The control variable `i` runs from 1 to `count-1`, allowing mileage to be calculated as the difference between the current element, `miles[i]` and the previous element, `miles[i - 1]`. Note that an index value can be any expression evaluating to an integer that represents a legal index for the array in question, which is an index value from 0 to one less than the number of elements in the array.

If the value of an index expression lies outside of the range corresponding to legitimate array elements, you will reference a spurious data location that may contain other data, garbage, or even program code. If the reference to such an element appears in an expression, you will use some arbitrary data value in the calculation, which certainly produces a result that you did not intend. If you are storing a result in an array element using an illegal index value, you will overwrite whatever happens to be in that location. When this is part of your program code, the results are catastrophic. If you use illegal index values, there are no warnings produced either by the compiler or at run time. The only way to guard against this is to code your program to prevent it happening.

The output is generated by a single `cout` statement for all values entered, except for the first. A line number is also generated for each line of output using the loop control variable `i`. Miles per gallon is calculated directly in the output statement. You can use array elements in exactly the same way as any other variables in an expression.

Initializing Arrays

To initialize an array in its declaration, you put the initializing values, separated by commas, between braces, and you place the set of initial values following an equals sign after the array name. Here's an example:

```
int engine_size[5] = { 200, 250, 300, 350, 400 };
```

The array has the name `engine_size` and has five elements that each store a value of type `int`. The values in the initializing list between the braces correspond to successive index values of the array, so in this case `engine_size[0]` has the value 200, `engine_size[1]` the value 250, `engine_size[2]` the value 300, and so on.

You must not specify more initializing values than there are elements in the array, but you can include fewer. If there *are* fewer, the values are assigned to successive elements, starting with the first element — which is the one corresponding to the index value 0. The array elements for which you didn't provide an initial value are initialized with zero. This isn't the same as supplying no initializing list. Without an initializing list, the array elements contain junk values. Also, if you include an initializing list, there must be at least one initializing value in it; otherwise the compiler generates an error message. I can illustrate this with the following, rather limited, example.

TRY IT OUT Initializing an Array

This example demonstrates that you'll have junk values in arrays that you don't initialize:

```
// Ex4_02.cpp
// Demonstrating array initialization
#include <iostream>
#include <iomanip>

using std::cout;
using std::endl;
```

```

using std::setw;

int main()
{
    int value[5] = { 1, 2, 3 };
    int junk [5];

    cout << endl;
    for(int i = 0; i < 5; i++)
        cout << setw(12) << value[i];

    cout << endl;
    for(int i = 0; i < 5; i++)
        cout << setw(12) << junk[i];

    cout << endl;
    return 0;
}

```

In this example, you declare two arrays, `value` and `junk`. You initialize `value` in part, and you don't initialize `junk` at all. The program generates two lines of output, which on my computer look like this:

1	2	3	0	0
-858993460	-858993460	-858993460	-858993460	-858993460

The second line (corresponding to values of `junk[0]` to `junk[4]`) may well be different on your computer.

How It Works

The first three values of the array `value` are the initializing values, and the last two have the default value of 0. In the case of `junk`, all the values are spurious because you didn't provide any initial values at all. The array elements contain whatever values were left there by the program that last used these memory locations.

A convenient way to initialize a whole array to zero is simply to specify a single initializing value as 0. For example:

```
long data[100] = {0};           // Initialize all elements to zero
```

This statement declares the array `data`, with all one hundred elements initialized with 0. The first element is initialized by the value you have between the braces, and the remaining elements are initialized to zero because you omitted values for these.

You can also omit the dimension of an array of numeric type, provided you supply initializing values. The number of elements in the array is determined by the number of initializing values you specify. For example, the array declaration

```
int value[] = { 2, 3, 4 };
```

defines an array with three elements that have the initial values 2, 3, and 4.

NOTE The C++ 11 standard defines a new uniform way of expressing a list of initial values that is the same for all objects that are initialized in this way. This includes Standard Template library containers that you will learn about in Chapter 10 as well as arrays. You initialize an array using the new syntax like this:

```
int value[] { 2, 3, 4 };
```

With this syntax the = operator is unnecessary. At the time of writing, Visual C++ that comes with Visual Studio 2012 does not support this syntax. However, Microsoft has indicated that it intends to support this in a later interim release of the product, so by the time you are reading this it may be supported — which is why I am mentioning it here!

Using the Range-Based for Loop

You have seen that you can use a `for` loop to iterate over all the elements in an array. The range-based `for` loop makes this even easier. The loop is easy to understand through an example:

```
double temperatures[] = {65.5, 68.0, 75.0, 77.5, 76.4, 73.8, 80.1};
double sum = 0.0;
int count = 0;
for(double t : temperatures)
{
    sum += t;
    ++count;
}
double average = sum/count;
```

This calculates the average of the values stored in the `temperatures` array. The parentheses following the `for` keyword contain two things separated by a colon; the first specifies the variable that will access each of the values from the collection specified by the second. The `t` variable will be assigned the value of each element in the `temperatures` array in turn before executing the loop body. This is used to accumulate the sum of all the elements in the array. The loop also accumulates the total number of array elements in `count` so the average temperature can be calculated after the loop.

You could also write the loop using the `auto` keyword:

```
for(auto temperature : temperatures)
{
    sum += temperature;
    ++count;
}
```

The `auto` keyword tells the compiler to determine the type for the local variable that holds the current value from the array. The compiler knows that the array elements are of type `double`, so `t` will be of type `double`.

NOTE The C++ library provides the `_countof()` macro that you can use to obtain the number of elements in an array. You just put the array name between the parentheses.

Character Arrays and String Handling

An array of type `char` is called a character array and is generally used to store a character string. A character string is a sequence of characters with a special character appended to indicate the end of the string. The string-terminating character indicates the end of the string; this character is defined by the escape sequence '`\0`', and is sometimes referred to as a *null character*, since it's a byte with all bits as zero. A string of this form is often referred to as a *C-style string* because defining a string in this way was introduced in the C language from which C++ was developed by Bjarne Stroustrup (you can find his home page at <http://www.research.att.com/~bs/>).

This is not the only representation of a string that you can use — you'll meet others that are much safer representations later in the book. You should avoid using C-style strings in new code.

NOTE Each character in a non-Unicode string occupies one byte, so together with the terminating null character, a string requires a number of bytes that is one greater than the number of characters contained in the string.

You can declare a character array and initialize it with a string literal. For example:

```
char movie_star[15] = "Marilyn Monroe";
```

Note that the terminating '`\0`' is supplied automatically by the compiler. If you include one explicitly in the string literal, you end up with two of them. You must, however, allow for the terminating null in the number of elements that you allot to the array.

You can let the compiler work out the length of an initialized array for you. Here's an example:

```
char president[] = "Ulysses Grant";
```

Because the dimension is unspecified, the compiler allocates space for enough elements to hold the initializing string, plus the terminating null character. In this case it allocates 14 elements for the array `president`. Of course, if you want to use this array later for storing a different string, its length (including the terminating null character) must not exceed 14 bytes. In general, it is your responsibility to ensure that the array is large enough for any string you might subsequently want to store.

You can also create strings that comprise Unicode characters, the characters in the string being of type `wchar_t`. Here's a statement that creates a Unicode string:

```
wchar_t president[] = L"Ulysses Grant";
```

The `L` prefix indicates that the string literal is a wide character string, so each character in the string, including the terminating null character, will occupy two bytes. Of course, indexing the string references characters, not bytes, so `president[2]` corresponds to the character `L'y`.

String Input

The `iostream` header file contains definitions of a number of functions for reading characters from the keyboard. The one that you'll look at here is the function `getline()`, which reads a sequence of characters entered through the keyboard and stores it in a character array as a string terminated by '`\0`'. You typically use the `getline()` function statements like this:

```
const int MAX(80);           // Maximum string length including \0
char name[MAX];            // Array to store a string
cin.getline(name, MAX, '\n'); // Read input line as a string
```

These statements first declare a `char` array `name` with `MAX` elements and then read characters from `cin` using the function `getline()`. The source of the data, `cin`, is written as shown, with a period separating it from the function name. The period indicates that the `getline()` function you are calling is the one belonging to the `cin` object. You will learn more about this form of syntax when classes are discussed later on. Meanwhile, just take it for granted as you use it in an example. The significance of the arguments to the `getline()` function is shown in Figure 4-2.




FIGURE 4-2

Because the last argument to the `getline()` function is '`\n`' (newline or end line character) and the second argument is `MAX`, characters are read from `cin` until the '`\n`' character is read, or when `MAX - 1` characters have been read, whichever occurs first. The maximum number of characters read is `MAX - 1` rather than `MAX` to allow for the '`\0`' character to be appended to the sequence of characters stored in the array. The '`\n`' character is generated when you press the Return key on your keyboard and is therefore usually the most convenient character to end input. You can, however, specify something else by changing the last argument. The '`\n`' isn't stored in the input array `name`, but as I said, a '`\0`' is added at the end of the input string in the array.

TRY IT OUT Programming with Strings

You now have enough knowledge to write a simple program to read a string and then count how many characters it contains.

```
// Ex4_03.cpp
// Counting string characters
#include <iostream>
using std::cin;
using std::cout;
using std::endl;

int main()
{
    const int MAX(80);           // Maximum array dimension
    char buffer[MAX];           // Input buffer
    int count(0);                // Character count

    cout << "Enter a string of less than "
        << MAX << " characters:\n";
    cin.getline(buffer, MAX, '\n'); // Read a string until \n

    while(buffer[count] != '\0') // Increment count as long as
        count++;                // the current character is not null

    cout << endl
        << "The string \" " << buffer
        << "\" has " << count << " characters.";
    cout << endl;
    return 0;
}
```

Typical output from this program is as follows:

```
Enter a string of less than 80 characters:
Radiation fades your genes
The string "Radiation fades your genes" has 26 characters.
```

How It Works

This program declares a character array `buffer` and reads a character string into the array from the keyboard after displaying a prompt for the input. Reading from the keyboard ends when the user presses *Return*, or when `MAX - 1` characters have been read.

A while loop is used to count the number of characters read. The loop continues as long as the current character referenced with `buffer[count]` is not '`\0`'. This sort of checking on the current character while stepping through an array is a common technique in native C++. The only action in the loop is to increment `count` for each non-null character.

There is a library function, `strlen()`, that will do what this loop does; you'll learn about it later in this chapter.

Finally, in the example, the string and the character count is displayed with a single output statement. Note the use of the escape sequence '`\"`' to output a double quote.

Using the Range-Based for Loop with Strings

You have seen that you can use an array of type `char[]` to store a string. You can therefore use a range-based `for` loop to access the characters in a string:

```
char text[] = "Exit signs are on the way out.";
int count = 0;
cout << "The string contains the following characters:" << endl;
for (auto ch : text)
{
    ++count;
    cout << ch << " ";
}
cout << endl << "The string contains " << (count-1) << " characters." << endl;
```

The loop outputs each character from the string, including the null at the end, and accumulates a count of the total number of characters. The count includes the null that terminates the string so its value is reduced by 1 before output.

Multidimensional Arrays

The arrays that you have defined so far with one index are referred to as *one-dimensional arrays*. An array can also have more than one index value, in which case it is called a *multidimensional array*. Suppose you have a field in which you are growing bean plants in rows of 10, and the field contains 12 such rows (so there are 120 plants in all). You could declare an array to record the weight of beans produced by each plant using the following statement:

```
double beans[12][10];
```

This declares the two-dimensional array `beans`, the first index being the row number, and the second index the number within the row. To refer to any particular element requires two index values. For example, you could set the value of the element reflecting the fifth plant in the third row with the following statement:

```
beans[2][4] = 10.7;
```

Remember that the index values start from zero, so the row index value is 2 and the index for the fifth plant within the row is 4.


Being a successful bean farmer, you might have several identical fields planted with beans in the same pattern. Assuming that you have eight fields, you could use a three-dimensional array to record data about these, declared thus:

```
double beans[8][12][10];
```

This records production for all of the plants in each of the fields, the leftmost index referencing a particular field. If you ever get to bean farming on an international scale, you are able to use a

four-dimensional array, with the extra dimension designating the country. Assuming that you're as good a salesman as you are a farmer, growing this quantity of beans to keep up with the demand may well start to affect the ozone layer.

Arrays are stored in memory in a way such that the rightmost index value varies most rapidly. Thus, the array `data[3][4]` is three one-dimensional arrays of four elements each. The arrangement of this array is illustrated in Figure 4-3.



Array elements are stored in contiguous locations in memory.

FIGURE 4-3

The elements of the array are stored in a contiguous block of memory, as indicated by the arrows in Figure 4-3. The first index selects a particular row within the array, and the second index selects an element within the row.

Note that a two-dimensional array is really a one-dimensional array of one-dimensional arrays. An array with three dimensions is actually a one-dimensional array of elements where each element is a one-dimensional array of one-dimensional arrays. This is not something you need to worry about most of the time. It implies that for the array in Figure 4-3, the expressions `data[0]`, `data[1]`, and `data[2]` reference one-dimensional arrays.

Initializing Multidimensional Arrays

To initialize a multidimensional array, you use an extension of the method used for a one-dimensional array. For example, you can initialize a two-dimensional array, `data`, with the following declaration:

```
long data[2][4] = {
    { 1, 2, 3, 5 },
    { 7, 11, 13, 17 }
};
```

The initializing values for each row of the array are contained within their own pair of braces. Because there are four elements in each row, there are four initializing values in each group, and because there are two rows, there are two groups between braces, each group of initializing values being separated from the next by a comma.

You can omit initializing values in any row, in which case the remaining array elements in the row are zero. For example:

```
long data[2][4] = {  
    { 1, 2, 3 },  
    { 7, 11 }  
};
```

I have spaced out the initializing values to show where values have been omitted. The elements `data[0][3]`, `data[1][2]`, and `data[1][3]` have no initializing values and are therefore zero.

If you wanted to initialize the whole array with zeros you could simply write:

```
long data[2][4] = {0};
```

If you are initializing arrays with even more dimensions, remember that you need as many nested braces for groups of initializing values as there are dimensions in the array — unless you're initializing the array with zeros.

TRY IT OUT Storing Multiple Strings

You can use a single two-dimensional array to store several C-style strings. You can see how this works with an example:

```
// Ex4_04.cpp  
// Storing strings in an array  
#include <iostream>  
using std::cout;  
using std::cin;  
using std::endl;  
  
int main()  
{  
    char stars[6][80] = { "Robert Redford",  
                          "Hopalong Cassidy",  
                          "Lassie",  
                          "Slim Pickens",  
                          "Boris Karloff",  
                          "Oliver Hardy"  
    };  
    int dice(0);  
  
    cout << endl  
        << "Pick a lucky star!"  
        << "Enter a number between 1 and 6: ";
```

```

    cin >> dice;

    if(dice >= 1 && dice <= 6)           // Check input validity
        cout << endl                  // Output star name
        << "Your lucky star is " << stars[dice - 1];
    else
        cout << endl                  // Invalid input
        << "Sorry, you haven't got a lucky star.";

    cout << endl;
    return 0;
}

```

How It Works

Apart from its incredible inherent entertainment value, the main point of interest in this example is the declaration of the array `stars`. It is a two-dimensional array of elements of type `char` that can hold up to six strings, each of which can be up to 80 characters long (including the terminating null character that is automatically added by the compiler). The initializing strings for the array are enclosed between braces and separated by commas.

One disadvantage of using arrays in this way is the memory that is almost invariably left unused. All of the strings are fewer than 80 characters, and the surplus elements in each row of the array are wasted.

You can also let the compiler work out how many strings you have by omitting the first array dimension and declaring it as follows:

```

char stars[][80] = { "Robert Redford",
                     "Hopalong Cassidy",
                     "Lassie",
                     "Slim Pickens",
                     "Boris Karloff",
                     "Oliver Hardy"
};

```

This causes the compiler to define the first dimension to accommodate the number of initializing strings that you have specified. Because you have six, the result is exactly the same, but it avoids the possibility of an error. Here, you can't omit both array dimensions. With an array of two or more dimensions, the rightmost dimension must always be defined.

NOTE Remember the semicolon at the end of the declaration. It's easy to forget it when there are initializing values for an array.

Where you need to reference a string for output in the following statement, you need only specify the first index value:

```

cout << endl                  // Output star name
<< "Your lucky star is " << stars[dice - 1];

```

A single index value selects a particular 80-element sub-array, and the output operation displays the contents up to the terminating null character. The index is specified as `dice - 1` as the `dice` values are from 1 to 6, whereas the index values clearly need to be from 0 to 5.

INDIRECT DATA ACCESS

The variables that you have dealt with so far provide you with the ability to name a memory location in which you can store data of a particular type. The contents of a variable are either entered from an external source, such as the keyboard, or calculated from other values that are entered. There is another kind of variable that does not store data that you normally enter or calculate, but greatly extends the power and flexibility of your programs. This kind of variable is called a *pointer*.

What Is a Pointer?

Each memory location that you use to store a data value has an address. The address provides the means for your PC hardware to reference a particular data item. A pointer is a variable that stores the address of another variable of a particular type. A pointer has a variable name just like any other variable and also has a type that designates what kind of variables its contents refer to. Note that the type of a pointer variable includes the fact that it's a pointer. A variable that is a pointer, that can hold addresses of locations in memory containing values of type `int`, is of type ‘pointer to `int`’.

Declaring Pointers

The declaration for a pointer is similar to that of an ordinary variable, except that the pointer name has an asterisk in front of it to indicate that it's a variable that is a pointer. For example, to declare a pointer `pnumber` of type `long`, you could use the following statement:

```
long* pnumber;
```

This declaration has been written with the asterisk close to the type name. If you want, you can also write it as:

```
long *pnumber;
```

The compiler won't mind at all; however, the type of the variable `pnumber` is ‘pointer to `long`’, which is often indicated by placing the asterisk close to the type name. Whichever way you choose to write a pointer type, be consistent.

You can mix declarations of ordinary variables and pointers in the same statement. For example:

```
long* pnumber, number(99);
```

This declares the pointer `pnumber` of type ‘pointer to `long`’ as before, and also declares the variable `number`, of type `long`. On balance, it's probably better to declare pointers separately from other

variables; otherwise, the statement can appear misleading as to the type of the variables declared, particularly if you prefer to place the * adjacent to the type name. The following statements certainly look clearer, and putting declarations on separate lines enables you to add comments for them individually, making for a program that is easier to read:

```
long number(99);           // Declaration and initialization of long variable
long* pnumber;             // Declaration of variable of type pointer to long
```

It's a common convention in C++ to use variable names beginning with p to denote pointers. This makes it easier to see which variables in a program are pointers, which in turn can make a program easier to follow.

Let's take an example to see how this works, without worrying about what it's for. I will get to how you use pointers very shortly. Suppose you have the long integer variable number containing the value 99 because you declared it in the preceding code. You also have the pointer pnumber of type pointer to long, which you could use to store the address of the variable number. But how do you obtain the address of a variable?

The Address-Of Operator

What you need is the *address-of operator*, &. This is a unary operator that obtains the address of a variable. It's also called the reference operator, for reasons I will discuss later in this chapter. To set up the pointer that I have just discussed, you could write this assignment statement:

```
pnumber = &number;           // Store address of number in pnumber
```

The result of this operation is illustrated in Figure 4-4.




FIGURE 4-4

The operator & obtains the address of any variable, but you need a pointer of the appropriate type to store it. To store the address of a double variable, for example, the pointer must have been declared as type `double*`, which is type 'pointer to double'.

Using Pointers

Taking the address of a variable and storing it in a pointer is all very well, but the really interesting aspect is how you can use it. Fundamental to using a pointer is accessing the data value in the variable to which a pointer points. This is done using the indirection operator `*`.

The Indirection Operator

You use the *indirection operator*, `*`, with a pointer to access the contents of the variable that it points to. The name “indirection operator” stems from the fact that the data is accessed indirectly. It is also called the *dereference operator*, and the process of accessing the data in the variable pointed to by a pointer is termed *de-referencing the pointer*.

One aspect of this operator that can seem confusing is the fact that you now have several different uses for the same symbol, `*`. It is the multiply operator, it serves as the indirection operator, and it is used in the declaration of a pointer. Each time you use `*`, the compiler is able to distinguish its meaning by the context. When you multiply two variables, `A*B` for instance, there’s no meaningful interpretation of this expression for anything other than a multiply operation.

Why Use Pointers?

A question that usually springs to mind at this point is, “Why use pointers at all?” After all, taking the address of a variable you already know and sticking it in a pointer so that you can dereference it seems like overhead you can do without. There are several reasons why pointers are important.

As you will see shortly, you can use pointer notation to operate on data stored in an array, which often executes faster than if you use array notation. Also, when you get to define your own functions later in the book, you will see that pointers are used extensively for enabling access within a function to large blocks of data, such as arrays, that are defined outside the function. Most importantly, however, you will also see that you can allocate space for variables dynamically — that is, during program execution. This sort of capability allows your program to adjust its use of memory depending on the input to the program. Because you don’t know in advance how many variables you are going to create dynamically, a primary way you have for doing this is using pointers — so make sure you get the hang of this bit.

Initializing Pointers

Using pointers that aren’t initialized is extremely hazardous. You can easily overwrite random areas of memory through an uninitialized pointer. The resulting damage depends on how unlucky you are, so it’s more than just a good idea to initialize your pointers. It’s very easy to initialize a pointer to the address of a variable that has already been defined. Here you can see that I have initialized the pointer `pnumber` with the address of the variable `number` just by using the operator `&` with the variable name:

```
int number(0);           // Initialized integer variable
int* pnumber(&number);  // Initialized pointer
```

When initializing a pointer with the address of another variable, remember that the variable must already have been declared prior to the pointer declaration.

Of course, you may not want to initialize a pointer with the address of a specific variable when you declare it. In this case, you can initialize it with the pointer equivalent of zero. The literal `nullptr` is a pointer that does not point to anything so you can declare and initialize a pointer using the following statement:

```
int* pnumber(nullptr); // Pointer not pointing to anything
```

This ensures that the pointer doesn't contain an address that will be accepted as valid, and provides the pointer with a value that you can check in an `if` statement, such as:

```
if(pnumber == nullptr)
    cout << endl << "pnumber does not point to anything.";
```

Before `nullptr` was added to the C++ language, 0 or `NULL` (which is a macro for which the compiler will substitute 0) was used to initialize a pointer, and of course, these still work. However, it is much better to use `nullptr` to initialize your pointers.

NOTE *The reason for introducing `nullptr` into the C++ language was to remove potential confusion between the literal 0 as an integral value and 0 as a pointer. Having a dual meaning for the literal 0 caused problems in some circumstances. `nullptr` is of type `std::nullptr_t` and cannot be confused with a value of any other type. `nullptr` can be implicitly converted to any pointer type but cannot be implicitly converted to any integral type except type `bool`.*

Because the literal `nullptr` can be implicitly converted to type `bool`, you can check the status of the pointer `pnumber` like this:

```
if(!pnumber)
    cout << endl << "pnumber does not point to anything.";
```

`nullptr` converts to the `bool` value `false`, and any other pointer value converts to `true`. Thus, if `pnumber` contains `nullptr`, the `if` expression will be `true` and will cause the message to be written to the output stream.

TRY IT OUT Using Pointers

You can try out various aspects of pointer operations with an example:

```
// Ex4_05.cpp
// Exercising pointers
#include <iostream>
using std::cout;
using std::endl;
using std::hex;
using std::dec;
```

```
int main()
{
    long* pnumber(nullptr);           // Pointer declaration & initialization
    long number1(55), number2(99);

    pnumber = &number1;                // Store address in pointer
    *pnumber += 11;                  // Increment number1 by 11
    cout << endl
        << "number1 = " << number1
        << "    &number1 = " << hex << pnumber;

    pnumber = &number2;                // Change pointer to address of number2
    number1 = *pnumber*10;            // 10 times number2

    cout << endl
        << "number1 = " << dec << number1
        << "    pnumber = " << hex << pnumber
        << "    *pnumber = " << dec << *pnumber;

    cout << endl;
    return 0;
}
```

You should compile and execute the release version of this example. The debug version will add extra bytes, used for debugging purposes that will cause the variables to be separated by 12 bytes instead of 4. On my computer, this example generates the following output:

```
number1 = 66    &number1 = 003CF7F0
number1 = 990    pnumber = 003CF7F4    *pnumber = 99
```

How It Works

There is no input to this example. All operations are carried out with the initializing values for the variables. After storing the address of `number1` in the pointer `pnumber`, the value of `number1` is incremented indirectly through the pointer in this statement:

```
*pnumber += 11;                      // Increment number1 by 11
```

The indirection operator determines that you are adding 11 to the contents of the variable pointed to by `pnumber`, which is `number1`. If you forgot the `*` in this statement, you would be attempting to add 11 to the address stored in the pointer.

The values of `number1`, and the address of `number1` that is stored in `pnumber`, are displayed. You use the `hex` manipulator to generate the address output in hexadecimal notation.

You can obtain the value of ordinary integer variables as hexadecimal output by using the manipulator `hex`. You send it to the output stream in the same way as `endl`, with the result that all following output is in hexadecimal notation. If you want the following output to be decimal, you use the manipulator `dec` in the next output statement to switch the output back to decimal mode again.

After the first line of output, the contents of pnumber is set to the address of number2. The variable number1 is then changed to the value of 10 times number2:

```
number1 = *pnumber*10;           // 10 times number2
```

This is calculated by accessing the contents of number2 indirectly through the pointer. The second line of output shows the results of these calculations.

The address values you see in your output may well be different from those shown in the output here since they reflect where the program is loaded in memory, which depends on how your operating system is configured.

Note that the addresses &number1 and pnumber (when it contains &number2) differ by four bytes. This shows that number1 and number2 occupy adjacent memory locations, as each variable of type long occupies four bytes. The output demonstrates that everything is working as you would expect.

Pointers to char

A pointer of type `char*` has the interesting property that it can be initialized with a string literal. For example, you can declare and initialize such a pointer with the statement:

```
char* proverb ("A miss is as good as a mile.");
```

This looks similar to initializing a `char` array, but it's slightly different. This creates a string literal (actually an array of type `const char`) with the character string appearing between the quotes and terminating with '`\0`', and stores the address of the literal in the pointer `proverb`. The address of the literal will be the address of its first character. This is shown in Figure 4-5.

char* proverb ("A miss is as good as a mile.");

1. The pointer **proverb** is created.




FIGURE 4-5

TRY IT OUT Lucky Stars with Pointers

You could rewrite the lucky stars example using pointers instead of an array to see how that would work:

```
// Ex4_06.cpp
// Initializing pointers with strings
#include <iostream>
using std::cin;
```

```
using std::cout;
using std::endl;

int main()
{
    char* pstr1("Robert Redford");
    char* pstr2("Hopalong Cassidy");
    char* pstr3("Lassie");
    char* pstr4("Slim Pickens");
    char* pstr5("Boris Karloff");
    char* pstr6("Oliver Hardy");
    char* pstr("Your lucky star is ");

    int dice(0);

    cout << endl
        << "Pick a lucky star!"
        << "Enter a number between 1 and 6: ";
    cin >> dice;

    cout << endl;
    switch(dice)
    {
        case 1: cout << pstr << pstr1;
                   break;
        case 2: cout << pstr << pstr2;
                   break;
        case 3: cout << pstr << pstr3;
                   break;
        case 4: cout << pstr << pstr4;
                   break;
        case 5: cout << pstr << pstr5;
                   break;
        case 6: cout << pstr << pstr6;
                   break;

        default: cout << "Sorry, you haven't got a lucky star.";
    }

    cout << endl;
    return 0;
}
```

How It Works

The array in `Ex4_04.cpp` has been replaced by the six pointers, `pstr1` to `pstr6`, each initialized with a name. You have also declared an additional pointer, `pstr`, initialized with the phrase that you want to use at the start of a normal output line. Because you have discrete pointers, it is easier to use a `switch` statement to select the appropriate output message rather than an `if`, as you did in the original version. Any incorrect values entered are all taken care of by the `default` option of the `switch`.

Outputting the string pointed to by a pointer couldn't be easier. As you can see, you simply write the pointer name. It may cross your mind at this point that in `Ex4_05.cpp` you wrote a pointer name in the output statement, and the address that it contained was displayed. Why is it different here? The answer

is in the way the output operation views a pointer of type ‘pointer to char.’ It treats a pointer of this type in a special way, in that it regards it as a string (which is an array of `char`), and so outputs the string itself, rather than its address.

Using pointers in the example has eliminated the waste of memory that occurred with the array version of this program, but the program seems a little long-winded now. There must be a better way. Indeed there is — using an array of pointers.

TRY IT OUT Arrays of Pointers

With an array of pointers of type `char`, each element can point to an independent string, and the lengths of each of the strings can be different. You can declare an array of pointers in the same way that you declare a normal array. Let’s go straight to rewriting the previous example using a pointer array:

```
// Ex4_07.cpp
// Initializing pointers with strings
#include <iostream>
using std::cin;
using std::cout;
using std::endl;

int main()
{
    char* pstr[] = { "Robert Redford",      // Initializing a pointer array
                     "Hopalong Cassidy",
                     "Lassie",
                     "Slim Pickens",
                     "Boris Karloff",
                     "Oliver Hardy"
                 };
    char* pstart("Your lucky star is ");

    int dice(0);

    cout << endl
        << "Pick a lucky star!"
        << "Enter a number between 1 and 6: ";
    cin >> dice;

    cout << endl;
    if(dice >= 1 && dice <= 6)           // Check input validity
        cout << pstart << pstr[dice - 1]; // Output star name
    else
        cout << "Sorry, you haven't got a lucky star."; // Invalid input

    cout << endl;
    return 0;
}
```

How It Works

In this case, you are nearly getting the best of all possible worlds. You have a one-dimensional array of pointers to type `char` declared, such that the compiler works out what the dimension should be from the number of initializing strings. The memory usage that results from this is illustrated in Figure 4-6.

Compared to using a ‘normal’ array, the pointer array generally carries less overhead in terms of space. With an array, you would need to make each row the length of the longest string, and six rows of seventeen bytes each is 102 bytes, so by using a pointer array you have saved a whole -1 bytes! What’s gone wrong? The simple truth is that for this small number of relatively short strings, the size of the extra array of pointers is significant. You would make savings if you were dealing with more strings that were longer and had more variable lengths.

Space saving isn’t the only advantage that you get by using pointers. In a lot of circumstances you save time, too. Think of what happens if you want to move “Oliver Hardy” to the first position and “Robert Redford” to the end. With the pointer array as in `Ex4_07.cpp`, you just need to swap the pointers — the strings themselves stay where they are. If you had stored these simply as strings as you did in `Ex4_04.cpp`, a great deal of copying would be necessary — you’d need to copy the whole string “Robert Redford” to a temporary location while you copied “Oliver Hardy” in its place, and then you’d need to copy “Robert Redford” to the end position. This requires significantly more computer time to execute.

Because you are using `pstr` as the name of the array, the variable holding the start of the output message needs to be different; it is called `pstart`. You select the string that you want to output by means of a very simple `if` statement, similar to that of the original version of the example. You either display a star selection or a suitable message if the user enters an invalid value.




FIGURE 4-6

One weakness of the way the program is written is that the code assumes there are six options, even though the compiler is allocating the space for the pointer array from the number of initializing strings that you supply. So if you add a string to the list, you have to alter other parts of the program to take account of this. It would be nice to be able to add strings and have the program automatically adapt to however many strings there are.

The `sizeof` Operator

A new operator can help us here. The `sizeof` operator produces an integer value of type `size_t` that gives the number of bytes occupied by its operand, where `size_t` is a type defined by the standard library. Many standard library functions return a value of type `size_t`, and the `size_t` type is defined within the standard library using a `typedef` statement to be equivalent to one of the fundamental types, usually `unsigned int`. The reason for using `size_t` rather than a fundamental type directly is that it allows flexibility in what the actual type is in different C++ implementations. The C++ standard permits the range of values accommodated by a fundamental type to vary, to make the best of a given hardware architecture, and `size_t` can be defined to be the equivalent of the most suitable fundamental type in the current machine environment.

Look at this statement that refers to the variable `dice` from the previous example:

```
cout << sizeof dice;
```

The value of the expression `sizeof dice` is 4 because `dice` was declared as type `int` and therefore occupies 4 bytes. Thus, this statement outputs the value 4.

The `sizeof` operator can be applied to an element in an array or to the whole array. When the operator is applied to an array name by itself, it produces the number of bytes occupied by the whole array, whereas when it is applied to a single element with the appropriate index value or values, it results in the number of bytes occupied by that element. Thus, in the last example, you could output the number of elements in the `pstr` array with the expression:

```
cout << (sizeof pstr)/(sizeof pstr[0]);
```

The expression `(sizeof pstr)/(sizeof pstr[0])` divides the number of bytes occupied by the whole pointer array, by the number of bytes occupied by the first element of the array. Because each element in the array occupies the same amount of memory, the result is the number of elements in the array. The code fragment you saw earlier that computed the average for an array of temperatures could be written like this:

```
double temperatures[] = {65.5, 68.0, 75.0, 77.5, 76.4, 73.8, 80.1};
double sum = 0.0;
for(auto t : temperatures)
    sum += t;
double average = sum/((sizeof temperatures)/(sizeof temperatures[0]));
```

You no longer need to accumulate the element count within the loop so this code will be faster.

You could use `_countof()` to obtain the number of array elements in the loop:

```
for(auto t : temperatures)
    sum += t;
double average = sum/_countof(temperatures);
```

NOTE Remember that `pstr` is an array of pointers — using the `sizeof` operator on the array or on individual elements will not tell us anything about the memory occupied by the text strings. `pstr[0]` is a pointer to a character array and thus occupies just 4 bytes in 32-bit code, or 8 bytes when compiled as 64-bit code.

You can also apply the `sizeof` operator to a type name rather than a variable, in which case the result is the number of bytes occupied by a variable of that type. In this case, the type name should be enclosed in parentheses. For example, after executing the statement,

```
size_t long_size(sizeof(long));
```

the variable `long_size` will be initialized with the value 4. The variable `long_size` is declared to be of type `size_t` to match the type of the value produced by the `sizeof` operator. Using a different integer type for `long_size` may result in a warning message from the compiler.

TRY IT OUT Using the `sizeof` Operator

You can amend the last example to use the `sizeof` operator so that the code automatically adapts to an arbitrary number of string values from which to select:

```
// Ex4_08.cpp
// Flexible array management using sizeof
#include <iostream>
using std::cin;
using std::cout;
using std::endl;

int main()
{
    char* pstr[] = { "Robert Redford",           // Initializing a pointer array
                    "Hopalong Cassidy",
                    "Lassie",
                    "Slim Pickens",
                    "Boris Karloff",
                    "Oliver Hardy"
                };
    char* pstart("Your lucky star is ");

    int count((sizeof pstr)/(sizeof pstr[0])); // Number of array elements

    int dice(0);
```

```

cout << endl
    << " Pick a lucky star!"
    << " Enter a number between 1 and " << count << ": ";
cin >> dice;

cout << endl;
if(dice >= 1 && dice <= count)           // Check input validity
    cout << pstart << pstr[dice - 1];      // Output star name
else
    cout << "Sorry, you haven't got a lucky star."; // Invalid input

cout << endl;
return 0;
}

```

How It Works

As you can see, the changes required in the example are very simple. You just calculate the number of elements in the pointer array `pstr` and store the result in `count`. Then, wherever the total number of elements in the array was referenced as 6, you just use the variable `count`. You could now just add a few more names to the list of lucky stars, and everything affected in the program is adjusted automatically.

Constant Pointers and Pointers to Constants

The array `pstr` in the last example is clearly not intended to be modified in the program, and nor are the strings being pointed to, nor is the variable `count`. It would be a good idea to ensure that these didn't get modified by mistake in the program. You could very easily protect the variable `count` from accidental modification by writing this:

```
const int count = (sizeof pstr)/(sizeof pstr[0]);
```

However, the array of pointers deserves closer examination. You declared the array like this:

```

char* pstr[] = { "Robert Redford",    // Initializing a pointer array
                 "Hopalong Cassidy",
                 "Lassie",
                 "Slim Pickens",
                 "Boris Karloff",
                 "Oliver Hardy"
               };

```

Each pointer in the array is initialized with the address of a string literal, "Robert Redford", "Hopalong Cassidy", and so on. The type of a string literal is 'array of const char', so you are storing the address of a const array in a non-const pointer. The compiler allows us to use a string literal to initialize an element of an array of `char*` for reasons of backward compatibility with existing code.

If you try to alter the character array with a statement like this:

```
*pstr[0] = "Stan Laurel";
```

the program does not compile.

If you were to reset one of the elements of the array to point to a character using a statement like this:

```
*pstr[0] = 'X';
```

the program compiles, but crashes when this statement is executed.

You don't really want to have unexpected behavior, like the program crashing at run time, and you can prevent it. A far better way of writing the declaration is as follows:

```
const char* pstr[] = { "Robert Redford",      // Array of pointers
                      "Hopalong Cassidy",  // to constants
                      "Lassie",
                      "Slim Pickens",
                      "Boris Karloff",
                      "Oliver Hardy"
};
```

In this case, there is no ambiguity about the `const`-ness of the strings pointed to by the elements of the pointer array. If you now attempt to change these strings, the compiler flags this as an error at compile time.

However, you could still legally write this statement:

```
pstr[0] = pstr[1];
```

Those lucky individuals due to be awarded Mr. Redford would get Mr. Cassidy instead because both pointers now point to the same name. Note that this isn't changing the values of the objects pointed to by the pointer array element — it is changing the value of the pointer stored in `pstr[0]`. You should therefore inhibit this kind of change as well, because some people may reckon that good old Hoppy may not have the same sex appeal as Robert. You can do this with the following statement:

```
// Array of constant pointers to constants
const char* const pstr[] = { "Robert Redford",
                            "Hopalong Cassidy",
                            "Lassie",
                            "Slim Pickens",
                            "Boris Karloff",
                            "Oliver Hardy"
};
```

To summarize, you can distinguish three situations relating to `const`, pointers, and the objects to which they point:

- A pointer to a constant object
- A constant pointer to an object
- A constant pointer to a constant object

In the first situation, the object pointed to cannot be modified, but you can set the pointer to point to something else:

```
const char* pstring("Some text");
```

In the second, the address stored in the pointer can't be changed, but the object pointed to can be:

```
char* const pstring("Some text");
```

Finally, in the third situation, both the pointer and the object pointed to have been defined as constant and, therefore, neither can be changed:

```
const char* const pstring("Some text");
```

NOTE Of course, all this applies to pointers that point to any type. A pointer to type `char` is used here purely for illustrative purposes. In general, to interpret more-complex types correctly, you just read them from right to left. The type `const char*` is a pointer to characters that are `const` and the type `char* const` is a `const` pointer to characters.

Pointers and Arrays

Array names can behave like pointers under some circumstances. In most situations, if you use the name of a one-dimensional array by itself, it is automatically converted to a pointer to the first element of the array. Note that this is not the case when the array name is used as the operand of the `sizeof` operator.

If you have these declarations,

```
double* pdata(nullptr);
double data[5];
```

you can write this assignment:

```
pdata = data;           // Initialize pointer with the array address
```

This is assigning the address of the first element of the array `data` to the pointer `pdata`. Using the array name by itself refers to the address of the array. If you use the array name `data` with an index value, it refers to the contents of the element corresponding to that index value. So, if you want to store the address of that element in the pointer, you have to use the address-of operator:

```
pdata = &data[1];
```

Here, the pointer `pdata` contains the address of the second element of the array.

Pointer Arithmetic

You can perform arithmetic operations with pointers. You are limited to addition and subtraction in terms of arithmetic, but you can also perform comparisons of pointer values to produce a logical result. Arithmetic with a pointer implicitly assumes that the pointer points to an array, and that the arithmetic operation is on the address contained in the pointer. For the pointer `pdata`, for example, you could assign the address of the third element of the array `data` to a pointer with this statement:

```
pdata = &data[2];
```

In this case, the expression `pdata+1` would refer to the address of `data[3]`, the fourth element of the `data` array, so you could make the pointer point to this element by writing this statement:

```
pdata += 1;           // Increment pdata to the next element
```

This increments the address contained in `pdata` by the number of bytes occupied by one element of the `data` array. In general, `pdata+n`, where `n` can be any expression resulting in an integer, adds `n*sizeof(double)` to the address in `pdata`, because it was declared to be of type pointer to `double`. This is illustrated in Figure 4-7.

In other words, incrementing or decrementing a pointer works in terms of the type of the object pointed to. Increasing a pointer to `long` by one changes its contents to the next `long` address, and so increments the address by four. Similarly, incrementing a pointer to `short` by one increments the address by two. The more common notation for incrementing a pointer is using the increment operator. For example:

```
pdata++;           // Increment pdata to the next element
```

This is equivalent to (and more common than) the `+=` operator. However, I used `+=` earlier to make it clear that although the increment value is actually specified as one, except for the case of a pointer to type `char` the effect is an address increment greater than one.




FIGURE 4-7

NOTE The address resulting from an arithmetic operation on a pointer can be a value ranging from the address of the first element of the array to the address that is one beyond the last element. Accessing an address that does not refer to an element within the array results in undefined behavior; this includes one beyond the last element of course.

You can, of course, dereference a pointer on which you have performed arithmetic (there wouldn't be much point to it otherwise). For example, assuming that `pdata` is still pointing to `data[2]`, this statement,

```
* (pdata + 1) = * (pdata + 2);
```

is equivalent to this:

```
data[3] = data[4];
```

The parentheses are necessary when you want to dereference a pointer after incrementing the address it contains because the precedence of the indirection operator is higher than that of the arithmetic operators, + and -. If you write the expression `*pdata+1`, instead of `* (pdata+1)`, this adds one to the value stored at the address contained in `pdata`, which is equivalent to executing `data[2]+1`. Because this isn't an lvalue, its use in the previous assignment statement would cause the compiler to generate an error message.

You can use an array name as though it were a pointer for addressing elements of an array. If you have the same one-dimensional array as before, declared as

```
long data[5];
```

using pointer notation, you can refer to the element `data[3]`, for example, as `* (data+3)`. This kind of notation can be applied generally so that, corresponding to the elements `data[0]`, `data[1]`, `data[2]`, you can write `*data`, `*(data+1)`, `*(data+2)`, and so on.

TRY IT OUT Array Names as Pointers

You can practice this aspect of array addressing with a program to calculate prime numbers (a prime number is divisible only by itself and one):

```
// Ex4_09.cpp
// Calculating primes
#include <iostream>
#include <iomanip>
using std::cout;
using std::endl;
using std::setw;

int main()
{
    const int MAX(100);           // Number of primes required
    long primes[MAX] = { 2,3,5 }; // First three primes defined
    long trial(5);               // Candidate prime
    int count(3);                // Count of primes found
    bool found(false);            // Indicates when a prime is found

    do
    {
        trial += 2;              // Next value for checking
        found = false;             // Set found indicator

        for(int i = 0; i < count; i++) // Try division by existing primes
        {
            found = (trial % *(primes + i)) == 0; // True for exact division
            if(found)                  // If division is exact
                break;                  // it's not a prime
        }
    }
```

```
if (!found)                                // We got one...
    *(primes + count++) = trial; // ...so save it in primes array
}while(count < MAX);

// Output primes 5 to a line
for(int i = 0; i < MAX; i++)
{
    if(i % 5 == 0)                      // New line on 1st, and every 5th line
        cout << endl;
    cout << setw(10) << *(primes + i);
}
cout << endl;

return 0;
}
```

If you compile and execute this example, you should get the following output:

2	3	5	7	11
13	17	19	23	29
31	37	41	43	47
53	59	61	67	71
73	79	83	89	97
101	103	107	109	113
127	131	137	139	149
151	157	163	167	173
179	181	191	193	197
199	211	223	227	229
233	239	241	251	257
263	269	271	277	281
283	293	307	311	313
317	331	337	347	349
353	359	367	373	379
383	389	397	401	409
419	421	431	433	439
443	449	457	461	463
467	479	487	491	499
503	509	521	523	541

How It Works

You have the usual `#include` statements for the `iostream` header file for input and output, and for `iomanip`, because you will use a stream manipulator to set the field width for output.

You use the constant `MAX` to define the number of primes that you want the program to produce. The `primes` array, which stores the results, has the first three primes already defined to start the process off. All the work is done in two loops: the outer `do-while` loop, which picks the next value to be checked and adds the value to the `primes` array if it is prime, and the inner `for` loop that actually checks the value to see whether it's prime or not.

The algorithm in the `for` loop is very simple and is based on the fact that if a number is not a prime, it must be divisible by one of the primes found so far — all of which are less than the number in question

because all numbers are either prime or a product of primes. In fact, only division by primes less than or equal to the square root of the number in question need to be checked, so this example isn't as efficient as it might be.

```
found = (trial % *(primes + i)) == 0; // True for exact division
```

This statement sets the variable `found` to `true` if there's no remainder from dividing the value in `trial` by the current prime `*(primes + i)` (remember that this is equivalent to `primes[i]`), and to `false` otherwise. The `if` statement causes the `for` loop to be terminated if `found` has the value `true` because the candidate in `trial` can't be a prime in that case.

After the `for` loop ends (for whatever reason), it's necessary to decide whether or not the value in `trial` was prime. This is indicated by the value in the indicator variable `found`.

```
*(primes + count++) = trial; // ...so save it in primes array
```

If `trial` does contain a prime, this statement stores the value in `primes[count]` and then increments `count` through the postfix increment operator.

After `MAX` number of primes have been found, they are output with a field width of 10 characters, 5 to a line, as a result of this statement:

```
if(i % 5 == 0) // New line on 1st, and every 5th line
    cout << endl;
```

This starts a new line when `i` has the values 0, 5, 10, and so on.

TRY IT OUT Counting Characters Revisited

To see how handling strings works in pointer notation, you could produce a version of the program you looked at earlier for counting the characters in a string:

```
// Ex4_10.cpp
// Counting string characters using a pointer
#include <iostream>
using std::cin;
using std::cout;
using std::endl;

int main()
{
    const int MAX(80); // Maximum array dimension
    char buffer[MAX]; // Input buffer
    char* pbuffer(buffer); // Pointer to array buffer

    cout << endl // Prompt for input
        << "Enter a string of less than "
        << MAX << " characters:"
        << endl;
```

```
    cin.getline(buffer, MAX, '\n');      // Read a string until \n

    while(*pbuffer)                  // Continue until \0
        pbuffer++;

    cout << endl
        << "The string \" " << buffer
        << "\"" has " << pbuffer - buffer << " characters.";
    cout << endl;

    return 0;
}
```

Here's an example of typical output from this example:

```
Enter a string of less than 80 characters:
The tigers of wrath are wiser than the horses of instruction.
The string "The tigers of wrath are wiser than the horses of
instruction." has 61 characters.
```

How It Works

Here, the program operates using the pointer `pbuffer` rather than the array name `buffer`. You don't need the `count` variable because the pointer is incremented in the `while` loop until '`\0`' is found. When the '`\0`' character is found, `pbuffer` will contain the address of that position in the string. The count of the number of characters in the string entered is therefore the difference between the address stored in the pointer `pbuffer`, and the address of the beginning of the array denoted by `buffer`.

You could also have incremented the pointer in the loop by writing the loop like this:

```
while(*pbuffer++);                      // Continue until \0
```

Now the loop contains no statements, only the test condition. This would work adequately, except for the fact that the pointer would be incremented after '`\0`' was encountered, so the address would be one more than the last position in the string. You would therefore need to express the count of the number of characters in the string as `pbuffer-buffer-1`.

Note that you can't use the array name here in the same way that you have used the pointer. The expression `buffer++` is strictly illegal because you can't modify the address value that an array name represents. Even though you can use an array name in an expression as though it is a pointer, it isn't a pointer, because the address value that it represents is fixed.

Using Pointers with Multidimensional Arrays

Using a pointer to store the address of a one-dimensional array is relatively straightforward, but with multidimensional arrays, things can get a little complicated. If you don't intend to use pointers with multidimensional arrays, you can skip this section, as it's a little obscure; however, if you have previous experience with C, this section is worth a glance.

If you have to use a pointer with multidimensional arrays, you need to keep clear in your mind what is happening. By way of illustration, you can use an array `beans`, declared as follows:

```
double beans[3][4];
```

You can declare and assign a value to the pointer `pbeans`, as follows:

```
double* pbeans;
pbeans = &beans[0][0];
```

Here, you are setting the pointer to the address of the first element of the array, which is of type `double`. You could also set the pointer to the address of the first row in the array with the statement:

```
pbeans = beans[0];
```

This is equivalent to using the name of a one-dimensional array, which is replaced by its address. You used this in the earlier discussion; however, because `beans` is a two-dimensional array, you cannot set an address in the pointer with the following statement:

```
pbeans = beans; // Will cause an error!!
```

The problem is one of type. The type of the pointer you have defined is `double*`, but the array is of type `double[3][4]`. A pointer to store the address of this array must be of type `double*[4]`. C++ associates the dimensions of the array with its type, and the preceding statement is only legal if the pointer has been declared with the dimension required. This is done with a slightly more complicated notation than you have seen so far:

```
double (*pbeans)[4];
```

The parentheses here are essential; otherwise, you would be declaring an array of pointers. Now the previous statement is legal, but this pointer can only be used to store addresses of an array with the dimensions shown.

Pointer Notation with Multidimensional Arrays

You can use pointer notation with an array name to reference elements of the array. You can reference each element of the array `beans` that you declared earlier, which had three rows of four elements, in two ways:

- Using the array name with two index values
- Using the array name in pointer notation

Therefore, the following two statements are equivalent:

```
beans[i][j]
*(beans + i) + j
```

Let's look at how these work. The first line uses normal array indexing to refer to the element with offset *j* in row *i* of the array.

You can determine the meaning of the second line by working from the inside outwards. *beans* refers to the address of the first row of the array, so *beans + i* refers to row *i* of the array. The expression **(beans + i)* is the address of the first element of row *i*, so **(beans + i) + j* is the address of the element in row *i* with offset *j*. The whole expression therefore refers to the value of that element.

If you really want to be obscure — and it isn't recommended that you should be — the following two statements, where you have mixed array and pointer notation, are also legal references to the same element of the array:

```
*(beans[i] + j)  
(*(beans + i))[j]
```

There is yet another aspect to the use of pointers that is really the most important of all: the ability to allocate memory for variables dynamically. You'll look into that next.

DYNAMIC MEMORY ALLOCATION

Working with a fixed set of variables in a program can be very restrictive. You will often want to decide the amount of space to be allocated for storing different types of variables at execution time, depending on the input data for the program. Any program that involves reading and processing a number of data items that is not known in advance can take advantage of the ability to allocate memory to store the data at run time. For example, if you need to implement a program to store information about the students in a class, the number of students is not fixed, and their names will vary in length, so to deal with the data most efficiently, you'll want to allocate space dynamically at execution time.

Obviously, because dynamically allocated variables can't have been defined at compile time, they can't be named in your source program. When they are created, they are identified by their address in memory, which is contained within a pointer. With the power of pointers, and the dynamic memory management tools in Visual C++, writing your programs to have this kind of flexibility is quick and easy.

The Free Store, Alias the Heap

In most instances, when your program is executed, there is unused memory in your computer. This unused memory is called the *heap* in C++, or sometimes the *free store*. You can allocate space within the free store for a new variable of a given type using a special operator in C++ that returns the address of the space allocated. This operator is *new*, and it's complemented by the operator *delete*, which de-allocates memory previously allocated by *new*.

You can allocate space in the free store for some variables in one part of a program, and then release the allocated space and return it to the free store after you have finished with it. This makes the memory available for reuse by other dynamically allocated variables, later in the same program. This can be a powerful technique; it enables you to use memory very efficiently, and in many cases, it results in programs that can handle much larger problems, involving considerably more data than otherwise might be possible.

The new and delete Operators

Suppose that you need space for a `double` variable. You can define a pointer to type `double` and then request that the memory be allocated at execution time. You can do this using the operator `new` with the following statements:

```
double* pvalue=nullptr;
pvalue = new double; // Request memory for a double variable
```

This is a good moment to recall that *all pointers should be initialized*. Using memory dynamically typically involves a number of pointers floating around, so it's important that they should not contain spurious values. You should try to arrange for a pointer not containing a legal address value to be set to `nullptr`.

The `new` operator in the second line of code should return the address of the memory in the free store allocated to a `double` variable, and this address is stored in the pointer `pvalue`. You can then use this pointer to reference the variable using the indirection operator, as you have seen. For example:

```
*pvalue = 9999.0;
```

Of course, the memory may not have been allocated because the free store had been used up, or because the free store is fragmented by previous usage — meaning that there isn't a sufficient number of contiguous bytes to accommodate the variable for which you want to obtain space. You don't have to worry too much about this, however. The `new` operator will throw an *exception* if the memory cannot be allocated for any reason, which terminates your program. Exceptions are a mechanism for signaling errors in C++; you learn about these in Chapter 6.

You can also initialize a variable created by `new`. Taking the example of the `double` variable that was allocated by `new` and the address stored in `pvalue`, you could have set the value to 999.0, as it was created with this statement:

```
pvalue = new double(999.0); // Allocate a double and initialize it
```

Of course, you could create the pointer and initialize it in a single statement, like this:

```
double* pvalue(new double(999.0));
```

When you no longer need a variable that has been dynamically allocated, you can free up the memory that it occupies in the free store with the `delete` operator:

```
delete pvalue; // Release memory pointed to by pvalue
```

This ensures that the memory can be used subsequently by another variable. If you don't use `delete`, and subsequently store a different address value in the pointer `pvalue`, it will be impossible to free up the memory or to use the variable that it contains, because access to the address is lost. In this situation, you have what is referred to as a memory leak, especially when it recurs in your program.

You should also set the value of a pointer to `nullptr` when you delete the memory to which it points. If you don't, you have what is called a *dangling pointer*, through which you might attempt to access the memory that has been freed.

NOTE In Chapter 10 I'll explain smart pointers, which is an alternative to the pointers I have discussed in this chapter. When you are allocating memory dynamically, especially for arrays or more complex objects, it is better to use a smart pointer. A smart pointer takes care of deleting the memory, when it is no longer required, automatically so you no longer have to worry about it. I deferred discussion of smart pointers until Chapter 10 because there are several things you need to learn about before you can understand smart pointers.

Allocating Memory Dynamically for Arrays

Allocating memory for an array dynamically is very straightforward. If you wanted to allocate an array of type `char`, assuming `pstr` is a pointer to `char`, you could write the following statement:

```
pstr = new char[20];      // Allocate a string of twenty characters
```

This allocates space for a `char` array of 20 characters and stores its address in `pstr`.

To remove the array that you have just created in the free store, you must use the `delete` operator. The statement would look like this:

```
delete [] pstr;          // Delete array pointed to by pstr
```

Note the use of square brackets to indicate that what you are deleting is an array. When removing arrays from the free store, you should always include the square brackets, or the results will be unpredictable. Note also that you do not specify any dimensions here, simply `[]`.

Of course, the `pstr` pointer now contains the address of memory that may already have been allocated for some other purpose, so it certainly should not be used. When you use the `delete` operator to discard some memory that you previously allocated, you should always reset the pointer, like this:

```
pstr = nullptr;
```

This ensures that you do not attempt to access the memory that has been deleted.

NOTE In Chapter 10 I'll also explain containers, which you can use to store collections of items in a much more flexible way than standard arrays.

TRY IT OUT Using Free Store

You can see how dynamic memory allocation works in practice by rewriting the program that calculates an arbitrary number of primes, this time using memory in the free store to store the primes:

```
// Ex4_11.cpp
// Calculating primes using dynamic memory allocation
#include <iostream>
#include <iomanip>
using std::cin;
using std::cout;
using std::endl;
using std::setw;

int main()
{
    long* pprime(nullptr);           // Pointer to prime array

    long trial(5);                 // Candidate prime
    int count(3);                  // Count of primes found
    bool found(false);             // Indicates when a prime is found
    int max(0);                    // Number of primes required

    cout << endl
        << "Enter the number of primes you would like (at least 4): ";
    cin >> max;                   // Number of primes required

    if(max < 4)                   // Test the user input, if less than 4
        max = 4;                   // ensure it is at least 4

    pprime = new long[max];

    *pprime = 2;                  // Insert three
    *(pprime + 1) = 3;            // seed primes
    *(pprime + 2) = 5;

    do
    {
        trial += 2;               // Next value for checking
        found = false;            // Set found indicator

        for(int i = 0; i < count; i++) // Division by existing primes
        {
            found = (trial % *(pprime + i)) == 0; // True for exact division
            if(found)                // If division is exact
                break;                // it's not a prime
        }

        if (!found)                // We got one...
            *(pprime + count++) = trial; // ...so save it in primes array
    } while(count < max);

    // Output primes 5 to a line
    for(int i = 0; i < max; i++)

```

```
{  
    if(i % 5 == 0) // New line on 1st, and every 5th line  
        cout << endl;  
    cout << setw(10) << *(pprime + i);  
}  
  
delete [] pprime; // Free up memory  
pprime = nullptr; // and reset the pointer  
cout << endl;  
return 0;  
}
```

Here's an example of the output from this program:

```
Enter the number of primes you would like (at least 4): 20  
      2      3      5      7      11  
     13     17     19     23     29  
     31     37     41     43     47  
     53     59     61     67     71
```

How It Works

The program is similar to the previous version. After receiving the number of primes required in the `int` variable `max`, you allocate an array of that size in the free store using the operator `new`. Note that you have made sure that `max` can be no less than 4. This is because the program requires space to be allocated in the free store for at least the three seed primes, plus one new one. You specify the size of the array that is required by putting the variable `max` between the square brackets following the array type specification:

```
pprime = new long[max];
```

You store the address of the memory area that is allocated by `new` in the pointer `pprime`. The program would terminate at this point if the memory could not be allocated.

After the memory that stores the prime values has been successfully allocated, the first three array elements are set to the values of the first three primes:

```
*pprime = 2; // Insert three  
*(pprime + 1) = 3; // seed primes  
*(pprime + 2) = 5;
```

You are using the dereference operator to access the first three elements of the array. As you saw earlier, the parentheses in the second and third statements are there because the precedence of the `*` operators is higher than that of the `+` operator.

You can't specify initial values for elements of an array that you allocate dynamically. You have to use explicit assignment statements if you want to set initial values for elements of the array.

The calculation of the prime numbers is exactly as before; the only change is that the name of the pointer you have here, `pprime`, is substituted for the array name, `primes`, that you used in the previous version. Equally, the output process is the same. Acquiring space dynamically is really not a problem at all. After it has been allocated, it in no way affects how the computation is written.

After you finish with the array, you remove it from the free store using the `delete` operator, remembering to include the square brackets to indicate that it is an array you are deleting:

```
delete [] pprime;           // Free up memory
```

Although it's not essential here, you also reset the pointer:

```
pprime = nullptr;           // and reset the pointer
```

All memory allocated in the free store is released when your program ends, but it is good to get into the habit of resetting pointers to `nullptr` when they no longer point to valid memory areas.

Dynamic Allocation of Multidimensional Arrays

Allocating memory in the free store for a multidimensional array involves using the `new` operator in a slightly more complicated form than is used for a one-dimensional array. Suppose that you declare the pointer `pbeans` like this:

```
double (*pbeans) [4] (nullptr);
```

To obtain the space for the array `beans [3] [4]` that you used earlier in this chapter, you could write this:

```
pbeans = new double [3][4];           // Allocate memory for a 3x4 array
```

You just specify both array dimensions between square brackets after the type name for the array elements.

Allocating space for a three-dimensional array simply requires that you specify the extra dimension with `new`, as in this example:

```
auto pBigArray = new double [5][10][10]; // Allocate memory for a 5x10x10 array
```

However many dimensions there are in the array that has been created, to destroy it and release the memory back to the free store, you write the following:

```
delete [] pBigArray;           // Release memory for array
pBigArray = nullptr;
```

You always use just one pair of square brackets following the `delete` operator, regardless of the dimensionality of the array with which you are working.

You have already seen that you can use a variable as the specification of the dimension of a one-dimensional array to be allocated by `new`. This extends to two or more dimensions, but with the restriction that only the leftmost dimension may be specified by a variable. All the other dimensions must be constants or constant expressions. So, you could write this:

```
pBigArray = new double[max][10][10];
```

where `max` is a variable; however, specifying a variable for any dimension other than the leftmost causes an error message to be generated by the compiler.

USING REFERENCES

A *reference* appears to be similar to a pointer in many respects, which is why I'm introducing it here, but it really isn't the same thing at all. The real importance of references becomes apparent only when you get to explore their use with functions, particularly in the context of object-oriented programming. Don't be misled by their simplicity and what might seem to be a trivial concept. As you will see later, references provide some extraordinarily powerful facilities, and, in some contexts, enable you to achieve results that would be impossible without them.

What Is a Reference?

There are two kinds of references: *lvalue references* and *rvalue references*. Essentially, a reference is a name that can be used as an alias for something else.

An lvalue reference is an alias for another variable; it is called an lvalue reference because it refers to a persistent storage location that can appear on the left of an assignment operation. Because an lvalue reference is an alias and not a pointer, the variable for which it is an alias has to be specified when the reference is declared; unlike a pointer, a reference cannot be altered to represent another variable.

An rvalue reference can be used as an alias for a variable, just like an lvalue reference, but it differs from an lvalue reference in that it can also reference an rvalue, which is a temporary value that is essentially transient.

Declaring and Initializing Lvalue References

Suppose that you have declared a variable as follows:

```
long number(0L);
```

You can declare an lvalue reference for this variable using the following declaration statement:

```
long& rnumber(number); // Declare a reference to variable number
```

The ampersand following the type name `long` and preceding the variable name `rnumber`, indicates that an lvalue reference is being declared, and that the variable name it represents, `number`, is specified as the initializing value between the parentheses; therefore, the variable `rnumber` is of type ‘reference to `long`’. You can now use the reference in place of the original variable name. For example, this statement,

```
rnumber += 10L;
```

has the effect of incrementing the variable `number` by 10.

Note that you cannot write:

```
int& refData = 5;           // Will not compile!
```

The literal 5 is constant and cannot be changed. To protect the integrity of constant values, you must use a `const` reference:

```
const int& refData = 5;      // OK
```

Now you can access the literal 5 through the `refData` reference. Because you declare `refData` as `const`, it cannot be used to change the value it references.

Let's contrast the lvalue reference `rnumber` defined in the previous code with the pointer `pnumber`, declared in this statement:

```
long* pnumber(&number);      // Initialize a pointer with an address
```

This declares the pointer `pnumber`, and initializes it with the address of the variable `number`. This then allows the variable `number` to be incremented with a statement such as:

```
*pnumber += 10L;            // Increment number through a pointer
```

There is a significant distinction between using a pointer and using a reference. The pointer needs to be dereferenced, and whatever address it contains is used to access the variable to participate in the expression. With a reference, there is no need for de-referencing. In some ways, a reference is like a pointer that has already been dereferenced, although it can't be changed to reference something else. An lvalue reference is the complete equivalent of the variable for which it is a reference.

Using References in a Range-Based for Loop

Earlier in this chapter you saw a code snippet using a range-based `for` loop to iterate over an array of temperatures:

```
for(auto t : temperatures)
{
    sum += t;
    ++count;
}
```

The `t` variable does not reference an array element, only its value, so you cannot use it to modify the element. However, you can do this by using a reference type:

```
const double FtoC = 5.0/9.0;          // Convert Fahrenheit to Centigrade
for(auto& t : temperatures)
    t = (t - 32)*FtoC;
for(auto& t : temperatures)
    cout << " " << t;
cout << endl;
```

The variable `t` will now be of type `double&` and will reference each of the array elements in turn directly. This loop changes the values in the array from Fahrenheit to Centigrade.

Using a reference in a range-based `for` loop to access items from a collection is particularly valuable when you are working with collections of objects. Copying some objects can be expensive on time, so avoiding copying by using a reference type will make your code more efficient. You will learn about collections of objects in Chapter 10 when the range-based `for` loop comes into its own.

Rvalue References

I am introducing rvalue references here because the concept is related to that of lvalue references, but I cannot go into the significance of rvalue references here. Rvalue references are important in the context of functions, which you will learn about in Chapter 5. You'll also learn more about rvalue references in subsequent chapters.

As you know, every expression in C++ is either an rvalue or an lvalue. A variable is an lvalue because it represents a location in memory. An rvalue is different. It represents the result of evaluating an expression. Thus, an rvalue reference is a reference to a variable that has a name, and allows the contents of the memory that the variable represents to be accessed through an lvalue reference. An rvalue reference is a reference to the memory containing the result of evaluating an expression.

You specify an rvalue reference type using two ampersands following the type name. Here's an example:

```
int x(5);
int&& rExpr = 2*x + 3;                      // rvalue reference
cout << rExpr << endl;
int& rx(x);                                // lvalue reference
cout << rx << endl;
```

Here, the rvalue reference is initialized to reference the result of evaluating the expression `2*x + 3`, which is a temporary value — an rvalue. The output will be 13. You cannot do this with an lvalue reference. Is this useful? In this case, no, indeed it is not recommended at all; but in a different context, it is very useful.

WARNING *The preceding code fragment will compile and execute, but it is definitely not the way to use an rvalue reference. This is just by way of illustrating what an rvalue reference is.*

While the code fragments relating to references illustrate how lvalue and rvalue reference variables *can* be defined and initialized, this is not how they are typically used. The primary application for both types of references is in defining functions where they can be of immense value; you'll learn more about using rvalue references in functions later in the book, starting in Chapter 5.

LIBRARY FUNCTIONS FOR STRINGS

The standard library provides the `cstring` header that contains functions that operate on null-terminated strings. These are a set of functions that are specified in the C++ standard. There are also alternatives to some of these functions that are not standard, but which provide a more secure implementation of the function than the original versions. In general, I'll mention both where they exist in the `cstring` header, but I'll use the more secure versions in examples. Let's explore some of the most useful functions provided by the `cstring` header.

NOTE The string standard header for native C++ defines the `string` and `wstring` classes that represent character strings. The `string` class represents strings of characters of type `char` and the `wstring` class represents strings of characters of type `wchar_t`. Both are defined in the `string` header as template classes that are instances of the `basic_string<T>` class template. A class template is a parameterized class (with parameter `T` in this case) that you can use to create new classes to handle different types of data. I won't be discussing templates and the `string` and `wstring` classes until Chapter 8, but I am mentioning them here because they are much better and safer to use.

Finding the Length of a Null-Terminated String

The `strlen()` function returns the length of the argument string of type `char*` as a value of type `size_t`. The type `size_t` is an implementation-defined type that corresponds to an unsigned integer type that is used generally to represent the lengths of sequences of various kinds. The `wcslen()` function does the same thing for strings of type `wchar_t*`.

Here's how you use the `strlen()` function:

```
char* str("A miss is as good as a mile.");
cout << "The string contains " << strlen(str) << " characters." << endl;
```

The output produced when this fragment executes is:

```
The string contains 28 characters.
```

As you can see from the output, the length value that is returned does not include the terminating null. It is important to keep this in mind, especially when you are using the length of one string to create another of the same length.

Both `strlen()` and `wcslen()` find the length by looking for the null at the end. If there isn't one, the functions will happily continue beyond the end of the string, checking throughout memory in the hope of finding a null. For this reason, these functions represent a security risk when you are working with data from an untrusted external source. In this situation you can use the `strnlen()` and `wcsnlen()` functions, both of which require a second argument that specifies the length of the buffer in which the string specified by the first argument is stored.

Joining Null-Terminated Strings

The `strcat()` function concatenates two null-terminated strings. The string specified by the second argument is appended to the string specified by the first argument. Here's an example of how you might use it:

```
char str1[30]= "Many hands";
char* str2(" make light work.");
strcat(str1, str2);
cout << str1 << endl;
```

Note that the first string is stored in the array `str1` of 30 characters, which is far more than the length of the initializing string, "Many hands". The string specified by the first argument must have sufficient space to accommodate the two strings when they are joined. If it doesn't, disaster will surely result because the function will then try to overwrite the area beyond the end of the first string.

As Figure 4-8 shows, the first character of the string specified by the second argument overwrites the terminating null of the first argument, and all the remaining characters of the second string are copied across, including the terminating null. Thus, the output from the fragment will be:

```
Many hands make light work.
```

The `strcat()` function returns the pointer that is the first argument, so you could combine the last two statements in the previous fragment into one:

```
cout << strcat(str1, str2) << endl;
```

The `wcsconcat()` function concatenates wide-character strings, but otherwise works exactly the same as the `strcat()` function.




FIGURE 4-8

With the `strncat()` function you can append part of one null-terminated string to another. The first two arguments are the destination and source strings respectively, and the third argument is a count of the number of characters from the source string that are to be appended. With the strings as defined in Figure 4-8, here's an example of using `strncat()`:

```
cout << strncat(str1, str2, 11) << endl;
```

After executing this statement, `str1` contains the string "Many hands make light". The operation appends 11 characters from `str2` to `str1`, overwriting the terminating '\0' in `str1`, and then appends a final '\0' character. The `wcsncat()` provides the same capability as `strncat()` but for wide-character strings.

All the functions for concatenating strings that I have introduced up to now rely on finding the terminating nulls in the strings to work properly, so they are also insecure when it comes to dealing with untrusted data. The `strcat_s()`, `wcscat_s()`, `strncat_s()`, and `wcsncat_s()` functions in `<cstring>` provide secure alternatives. Just to take one example, here's how you could use `strcat_s()` to carry out the operation shown in Figure 4-8:

```
const size_t count = 30;
char str1[count] = "Many hands";
char* str2(" make light work.");

errno_t error = strcat_s(str1, count, str2);

if(error == 0)
    cout << " Strings joined successfully." << endl;

else if(error == EINVAL)
    cout << "Error! Source or destination string address is a null pointer." << endl;

else if(error == ERANGE)
    cout << " Error! Destination string too small." << endl;
```

For convenience, I defined the array size as the constant `count`. The first argument to `strcat_s()` is the destination string to which the source string specified by the third argument is to be appended. The second argument is the total number of bytes available at the destination. The function returns an integer value of type `errno_t` to indicate how things went. The error return value will be zero if the operation is successful, `EINVAL` if the source or destination is `nullptr`, or `ERANGE` if the destination length is too small. In the event of an error occurring, the destination will be left unchanged. The error code values `EINVAL` and `ERANGE` are defined in the `cerrno` header, so you need an `#include` directive for this, as well as for `cstring`, to compile the preceding fragment correctly. Of course, you are not obliged to test for the error codes that the function might return, and if you don't, you won't need the `#include` directive for `cerrno`.

Copying Null-Terminated Strings

The standard library function `strcpy()` copies a string from a source location to a destination. The first argument is a pointer to the destination location, and the second argument is a pointer to the source string; both arguments are of type `char*`. The function returns a pointer to the destination string. Here's an example of how you use it:

```
const size_t LENGTH = 22;
const char source[LENGTH] = "The more the merrier!";
char destination[LENGTH];
cout << "The destination string is: " << strcpy(destination, source)
    << endl;
```

The source string and the destination buffer can each accommodate a string containing 21 characters plus the terminating null. You copy the source string to destination in the last statement. The output statement makes use of the fact that the `strcpy()` function returns a pointer to the destination string, so the output is:

```
The destination string is: The more the merrier!
```

You must ensure that the destination string has sufficient space to accommodate the source string. If you don't, something will get overwritten in memory, and disaster is the likely result.

The `strcpy_s()` function is a more secure version of `strcpy()`. It requires an extra argument between the destination and source arguments that specifies the size of the destination string buffer. The `strcpy_s()` function returns an integer value of type `errno_t` that indicates whether an error occurred. Here's how you might use this function:

```
const size_t LENGTH(22);
const char source[LENGTH] = "The more the merrier!";
char destination[LENGTH];

errno_t error = strcpy_s(destination, LENGTH, source);

if(error == EINVAL)
    cout << "Error. The source or the destination address is a null pointer." << endl;
else if(error == ERANGE)
    cout << "Error. The destination is too small." << endl;
else
    cout << "The destination string is: " << destination << endl;
```

You need to include the `cstring` and `cerrno` headers for this to compile. The `strcpy_s()` function verifies that the source and destination are not `nullptr` and that the destination buffer has sufficient space to accommodate the source string. When either or both the source and destination are `nullptr`, the function returns the value `EINVAL`. If the destination buffer is too small, the function returns `ERANGE`. If the copy is successful, the return value is 0.

You have analogous wide-character versions of these copy functions; these are `wcsncpy()` and `wcsncpy_s()`.

Comparing Null-Terminated Strings

The `strcmp()` function compares two null-terminated strings that you specify by arguments that are pointers of type `char*`. The function returns a value of type `int` that is less than zero, zero, or greater than zero, depending on whether the string pointed to by the first argument is less than, equal to, or greater than the string pointed to by the second argument. Here's an example:

```
char* str1("Jill");
char* str2("Jacko");
int result = strcmp(str1, str2);
if(result < 0)
    cout << str1 << " is less than " << str2 << '.' << endl;
else if(0 == result)
```

```

    cout << str1 << " is equal to " << str2 << '.' << endl;
else
    cout << str1 << " is greater than " << str2 << '.' << endl;

```

This fragment compares the strings `str1` and `str2`, and uses the value returned by `strcmp()` to execute one of three possible output statements.

Comparing the strings works by comparing the character codes of successive pairs of corresponding characters. The first pair of characters that are different determines whether the first string is less than or greater than the second string. Two strings are equal if they contain the same number of characters, and the corresponding characters are identical. Of course, the output is:

```
Jill is greater than Jacko.
```

The `wcsncmp()` function is the wide-character string equivalent of `strcmp()`.

Searching Null-Terminated Strings

The `strspn()` function searches a string for the first character that is not contained in a given set and returns the index of the character found. The first argument is a pointer to the string to be searched, and the second argument is a pointer to a string containing the set of characters. You could search for the first character that is not a vowel like this:

```

char* str = "I agree with everything.";
char* vowels = "aeiouAEIOU ";
size_t index = strspn(str, vowels);
cout << "The first character that is not a vowel is '" << str[index]
    << "' at position " << index << endl;

```

This searches `str` for the first character that is not contained in `vowels`. Note that I included a space in the `vowels` set, so a space will be ignored so far as the search is concerned. The output from this fragment is:

```
The first character that is not a vowel is 'g' at position 3
```

Another way of looking at the value the `strspn()` function returns is that it represents the length of the substring, starting from the first character in the first argument string that consists entirely of characters in the second argument string. In the example it is the first three characters "I a".

The `wcsspn()` function is the wide-character string equivalent of `strspn()`.

The `strstr()` function returns a pointer to the position in the first argument of a substring specified by the second argument. Here's a fragment that shows this in action:

```

char* str = "I agree with everything.";
char* substring = "ever";

```

```

char* psubstr = strstr(str, substring);

if(!psubstr)
    cout << "\"" << substring << "\"" not found in "\"" << str << "\"" << endl;
else
    cout << "The first occurrence of \""
        << substring
        << "\" in \""
        << str << "\" is at position "
        << psubstr-str << endl;

```

The third statement calls the `strstr()` function to search `str` for the first occurrence of the substring. The function returns a pointer to the position of the substring if it is found, or `nullptr` when it is not found. The `if` statement outputs a message, depending on whether or not `substring` was found in `str`. The expression `psubstr-str` gives the index position of the first character in the substring. The output produced by this fragment is:

The first occurrence of "ever" in "I agree with everything." is at position 13

TRY IT OUT Searching Null-Terminated Strings

This example searches a given string to determine the number of occurrences of a given substring:

```

// Ex4_12.cpp
// Searching a string
#include <iostream>
#include <cstring>
using std::cout;
using std::endl;
using std::strlen;
using std::strstr;

int main()
{
    char* str("Smith, where Jones had had \"had had\" had had \"had\"."
              "\n\"Had had\" had had the examiners' approval.");
    char* word("had");
    cout << "The string to be searched is: "
        << endl << str << endl;

    int count(0);                      // Number of occurrences of word in str
    char* pstr(str);                  // Pointer to search start position
    char* found(nullptr);             // Pointer to occurrence of word in str

    while(true)
    {
        found = strstr(pstr, word);
        if(!found)
            break;
        ++count;
        pstr = found+strlen(word);   // Set next search start as 1 past the word found
    }
}

```

```

    }

    cout << "\"" << word << "\"" was found "
        << count << " times in the string." << endl;
    return 0;
}

```

The output from this example is:

```

The string to be searched is: Smith, where Jones had had "had had" had had "had".
"Had had" had had the examiners' approval.
"had" was found 10 times in the string.

```

How It Works

All the action takes place in the indefinite `while` loop:

```

while(true)
{
    found = strstr(pstr, word);
    if(!found)
        break;
    ++count;
    pstr = found+strlen(word);      // Set next search start as 1 past the word found
}

```

The first step is to search the string for `word` starting at position `pstr`, which initially is the beginning of the string. You store the address that `strstr()` returns in `found`; this will be `nullptr` if `word` was not found in `pstr`, so the `if` statement ends the loop in that case.

If `found` is not `nullptr`, you increment the count of the number of occurrences of `word`, and update the `pstr` pointer so that it points to one character past the `word` instance that was found in `pstr`. This will be the starting point for the search on the next loop iteration.

From the output, you can see that `word` was found ten times in `str`. Of course, “Had” doesn’t count because it starts with an uppercase letter.

SUMMARY

You are now familiar with all of the basic types of values in C++, how to create and use arrays of those types, and how to create and use pointers. You have also been introduced to the idea of a reference. However, we have not exhausted all of these topics. I’ll come back to arrays, pointers, and references later in the book.

The pointer mechanism is sometimes a bit confusing because it can operate at different levels within the same program. Sometimes it is operating as an address, and at other times it can be operating with the value stored at an address. It’s very important that you feel at ease with the way pointers are used, so if you find that they are in any way unclear, try them out with a few examples of your own until you feel confident about applying them.

EXERCISES

1. Write a program that allows an unlimited number of values to be entered and stored in an array allocated in the free store. The program should then output the values, five to a line, followed by the average of the values entered. The initial array size should be five elements. The program should create a new array with five additional elements, when necessary, and copy values from the old array to the new.
2. Repeat the previous exercise but use pointer notation throughout instead of arrays.
3. Declare a character array, and initialize it to a suitable string. Use a loop to change every other character to uppercase.

Hint: In the ASCII character set, values for uppercase characters are 32 less than their lowercase counterparts.

4. Define an array of elements of type `double` that contains twelve arbitrary values that represent monthly average temperatures in Fahrenheit. Use a range-based `for` loop to convert the values to Centigrade and find and output the maximum, minimum, and average Centigrade temperatures.
-

► WHAT YOU LEARNED IN THIS CHAPTER

TOPIC	CONCEPT
Arrays	An array allows you to manage a number of variables of the same type using a single name. Each dimension of an array is defined between square brackets, following the array name in the declaration of the array.
Array dimensions	Each dimension of an array is indexed starting from zero. Thus, the fifth element of a one-dimensional array has the index value 4.
Initializing arrays	Arrays can be initialized by placing the initializing values between curly braces in the declaration.
Range <code>for</code> loop	You can use the range-based <code>for</code> loop to iterate over each of the elements in an array.
Pointers	A pointer is a variable that contains the address of another variable. A pointer is declared as a ‘pointer to type’ and may only be assigned addresses of variables of the given type.
Pointers to <code>const</code> and <code>const</code> pointers	A pointer can point to a constant object. Such a pointer can be reassigned to another object. A pointer may also be defined as <code>const</code> , in which case it can’t be reassigned.
References	A reference is an alias for another variable, and can be used in the same places as the variable it references. A reference must be initialized in its declaration. A reference can’t be reassigned to another variable.
The <code>sizeof</code> operator	The operator <code>sizeof</code> returns the number of bytes occupied by the object specified as its argument. Its argument may be a variable or a type name between parentheses.
The <code>new</code> operator	The operator <code>new</code> allocates memory dynamically in the free store. When memory has been assigned as requested, it returns a pointer to the beginning of the memory area provided. If memory cannot be assigned for any reason, an exception is thrown that by default causes the program to terminate.
The <code>delete</code> operator	You use the <code>delete</code> operator to release memory that you previously allocated using the <code>new</code> operator.

5

Introducing Structure into Your Programs

WHAT YOU WILL LEARN IN THIS CHAPTER:

- How to declare and write your own C++ functions
- How function arguments are defined and used
- How to pass arrays to and from a function
- What pass-by-value means
- How to pass pointers to functions
- How to use references as function arguments, and what pass-by-reference means
- How the `const` modifier affects function arguments
- How to return values from a function
- How to use recursion

WROX.COM CODE DOWNLOADS FOR THIS CHAPTER

You can find the wrox.com code downloads for this chapter on the Download Code tab at www.wrox.com/remtitle.cgi?isbn=9781118368084. The code is in the Chapter 5 download and individually named according to the names throughout the chapter.

UNDERSTANDING FUNCTIONS

Up to now, you haven't really been able to structure your program code in a modular fashion, because you only know how to construct a program as a single function, `main()`; but you *have* been using library functions of various kinds as well as functions belonging to objects.

Whenever you write a C++ program, you should have a modular structure in mind from the outset, and as you'll see, a good understanding of how to implement functions is essential to object-oriented programming.

There's quite a lot to structuring your C++ programs, so to avoid indigestion, you won't try to swallow the whole thing in one gulp. After you have chewed over and gotten the full flavor of these morsels, you move on to the next chapter, where you get further into the meat of the topic.

First, I'll explain the broad principles of how a function works. A function is a self-contained block of code with a specific purpose. A function has a name that both identifies it and is used to call it for execution in a program. The name of a function is global if it is not defined within a namespace, otherwise the name is qualified by the namespace name. The name of a function is not necessarily unique, as you'll see in the next chapter; however, functions that perform different actions should generally have different names.

The name of a function is governed by the same rules as those for a variable. A function name is, therefore, a sequence of letters and digits, the first of which is a letter, where an underscore (`_`) counts as a letter. The name of a function should generally reflect what it does, so, for example, you might call a function that counts beans `count_beans()`.

You pass information to a function by means of *arguments* specified when you invoke it. These arguments must correspond with *parameters* that appear in the definition of the function.

The arguments that you specify replace the parameters used in the definition of the function when the function executes. The code in the function then executes as though it were written using your argument values. Figure 5-1 illustrates the relationship between arguments in the function call and the parameters you specify in the definition of the function.




FIGURE 5-1

In Figure 5-1, the `add_ints()` function returns the sum of the two arguments passed to it. In general, a function returns either a single value to the point in the program where it was called, or nothing at all, depending on how you define the function. You might think that returning a single value from a function is a constraint, but the single value returned can be a pointer that could contain the address of an array, for example. You will learn more about how data is returned from a function a little later in this chapter.

Why Do You Need Functions?

One major advantage that a function offers is that it can be executed as many times as necessary from different points in a program. Without the ability to package a block of code into a function, programs would end up being much larger, because you would typically need to replicate the same code at various points in them. You also use functions to break up a program into easily manageable chunks for development and testing; a program of significant size and complexity that consists of several small blocks of code is much easier to understand and test than if it were written as one large chunk.

Imagine a really big program — let's say a million lines of code. A program of this size would be virtually impossible to write and debug without functions. Functions enable you to segment the program so that you can write the code piecemeal. You can test each piece independently before bringing it together with the other pieces. This approach also allows the development work to be divided among members of a programming team, with each team member taking responsibility for a tightly specified piece of the program that has a well-defined, functional interface to the rest of the code.

Structure of a Function

As you have seen when writing the function `main()`, a function consists of a *function header* that identifies the function, followed by the *body* of the function between braces that makes up the executable code for the function. Let's look at an example. You could write a function to raise a value to a given power; that is, to compute the result of multiplying the value `x` by itself `n` times, which is x^n :

```
// Function to calculate x to the power n, with n greater than or
// equal to 0
double power(double x, int n)           // Function header
{                                         // Function body starts here...
    double result(1.0);                  // Result stored here
    for(int i = 1; i <= n; i++)
        result *= x;

    return result;                      // ...and ends here
}
```

The Function Header

Let's first examine the function header in this example. The following is the first line of the function:

```
double power(double x, int n)           // Function header
```

It consists of three parts:

- The type of the *return value* (`double`, in this case)
- The name of the function (`power`, in this case)
- The parameters of the function enclosed between parentheses (`x` and `n`, in this case, of types `double` and `int`, respectively)

The return value is returned to the calling function when the function is executed, so when the function is called, it results in a value of type `double` in the expression in which it appears.

Our function has two parameters: `x`, the value to be raised to a given power, which is of type `double`, and the value of the power, `n`, which is of type `int`. The computation that the function performs is written using these parameter variables together with another variable, `result`, declared in the body of the function. The parameter names and any variables defined in the body of the function are local to the function.

NOTE No semicolon is required at the end of the function header or after the closing brace for the function body.

The General Form of a Function Header

The general form of a function header can be written as follows:

```
return_type function_name(parameter_list)
```

The `return_type` can be any legal type. If the function does not return a value, the return type is specified by the keyword `void`. The keyword `void` is also used to indicate the absence of parameters, so a function that has no parameters and doesn't return a value would have the following function header.

```
void my_function(void)
```

An empty parameter list also indicates that a function takes no arguments, so you could omit the keyword `void` between the parentheses like:

```
void my_function()
```

NOTE A function with a return type specified as `void` should not be used in an expression in the calling program. Because it doesn't return a value, it can't sensibly be part of an expression, so using it in this way causes the compiler to generate an error message.

The Function Body

The desired computation in a function is performed by the statements in the function body that follow the function header. The first of these in our `power()` example declares a variable `result` that is initialized with the value 1.0. The variable `result` is local to the function, as are all automatic variables that you declare within the function body. This means that the variable `result` ceases to exist after the function has completed execution. What might immediately strike you is that if `result` ceases to exist on completing execution of the function, how is it returned? The answer is that a copy of the value to be returned is made automatically, and this copy is made available to the return point in the program.

The calculation in `power()` is performed in the `for` loop. A loop control variable `i` is declared in the `for` loop, which assumes successive values from 1 to `n`. The variable `result` is multiplied by `x` once for each loop iteration, so this occurs `n` times to generate the required value. If `n` is 0, the statement in the loop won't be executed at all because the loop continuation condition immediately fails, and so `result` is left as 1.0.

As I've said, the parameters and all the variables declared within the body of a function are local to the function. There is nothing to prevent you from using the same names for variables in other functions for quite different purposes. Indeed, it's just as well this is so because it would be extremely difficult to ensure variables' names were always unique within a program containing a large number of functions, particularly if the functions were not all written by the same person.

The scope of variables declared within a function is determined in the same way that I have already discussed. A variable is created at the point at which it is defined and ceases to exist at the end of the block containing it. There is one type of variable that is an exception to this — variables declared as `static`. I'll discuss static variables a little later in this chapter.

NOTE Take care not to mask global variables with local variables of the same name. You first met this situation back in Chapter 2, where you saw how you could use the scope resolution operator `::` to access global variables.

The return Statement

The `return` statement returns the value of `result` to the point where the function was called. The general form of the `return` statement is

```
return expression;
```

where `expression` must evaluate to a value of the type specified in the function header for the return value. The expression can be any expression you want, as long as you end up with a value of the required type. It can include function calls — even a call of the same function in which it appears, as you'll see later in this chapter.

If the type of return value has been specified as `void`, there must be no expression appearing in the return statement. It must be written simply as:

```
return;
```

You can also omit the `return` statement when it is the last statement in the function body and there is no return value.

Alternative Function Syntax

The C++ 11 introduces an alternative syntax for writing the function header. Here's an example of the `power()` function that you saw earlier defined using the alternative syntax:

```
auto power(double x, int n)-> double // Function header
{
    double result(1.0);                // Function body starts here...
    for(int i = 1; i <= n; i++)
        result *= x;

    return result;                    // ...and ends here
}
```

This will work in exactly the same way as the previous version of the function. The return type of the function appears following the `->` in the header. This is referred to as a `trailing return type`. The `auto` keyword at the beginning indicates to the compiler that the return type is determined later.

So why was it necessary to introduce the alternative syntax? Isn't the old syntax good enough? The answer is no. In the next chapter you'll learn about *function templates*, where situations can arise when you need to allow for the return type from a function to vary depending on the result of executing the body of the function. You can specify that with the old syntax. The alternative function syntax does allow you to do that, as you'll see in Chapter 6.

Using a Function

At the point at which you use a function in a program, the compiler must know something about it to compile the function call. It needs enough information to be able to identify the function, and to verify that you are using it correctly. If the definition of the function that you intend to use does not appear earlier in the same source file, you must declare the function using a statement called a *function prototype*.

Function Prototypes

The prototype of a function provides the basic information that the compiler needs to check that you are using the function correctly. It specifies the parameters to be passed to the function, the function name, and the type of the return value — basically, it contains the same information as appears in the function header, with the addition of a semicolon. Clearly, the number of parameters and their types must be the same in the function prototype as they are in the function header in the definition of the function.

A prototype or a definition for each function that you call from within another function must appear before the statements doing the calling. Prototypes are usually placed at the beginning of the program source file. The header files that you've been including for standard library functions contain the prototypes of the functions provided by the library, amongst other things.

For the `power()` function example, you could write the prototype as:

```
double power(double value, int index);
```

NOTE *Don't forget that a semicolon is required at the end of a function prototype. Without it, you get error messages from the compiler.*

Note that I have specified names for the parameters in the function prototype that are different from those I used in the function header when I defined the function. This is just to indicate that it's possible. Most often, the same names are used in the prototype and in the function header in the definition of the function, but this doesn't *have* to be so. You can use longer, more expressive parameter names in the function prototype to aid understanding of the significance of the parameters, and then use shorter parameter names in the function definition where the longer names would make the code in the body of the function less readable.

If you like, you can even omit the names altogether in the prototype, and just write:

```
double power(double, int);
```

This provides enough information for the compiler to do its job; however, it's better practice to use some meaningful name in a prototype because it aids readability and, in some cases, makes all the difference between clear code and confusing code. If you have a function with two parameters of the same type (suppose our index was also of type `double` in the function `power()`, for example), the use of suitable names indicates clearly which parameter appears first and which second. Without parameter names it would be impossible to tell.

TRY IT OUT Using a Function

You can see how all this goes together in an example that exercises the `power()` function:

```
// Ex5_01.cpp
// Declaring, defining, and using a function
#include <iostream>
using std::cout;
using std::endl;

double power(double x, int n); // Function prototype

int main(void)
{
```

```
int index();           // Raise to this power
double x(3.0);        // Different x from that in function power
double y(0.0);

y = power(5.0, 3);    // Passing constants as arguments
cout << endl << "5.0 cubed = " << y;

cout << endl << "3.0 cubed = "
    << power(3.0, index); // Outputting return value

x = power(x, power(2.0, 2.0)); // Using a function as an argument
cout << endl                  // with auto conversion of 2nd parameter
    << "x = " << x;

cout << endl;
return 0;
}

// Function to compute positive integral powers of a double value
// First argument is value, second argument is power index
double power(double x, int n)
{
    // Function body starts here...
    double result(1.0); // Result stored here
    for(int i = 1; i <= n; i++)
        result *= x;
    return result;
} // ...and ends here
```

This program shows some of the ways in which you can use the function `power()`, specifying the arguments to the function in a variety of ways. If you run this example, you get the following output:

```
5.0 cubed = 125
3.0 cubed = 27
x = 81
```

How It Works

After the usual `#include` statement for input/output and the `using` declarations, you have the prototype for the function `power()`. If you were to delete this and try recompiling the program, the compiler wouldn't be able to process the calls to the function in `main()` and would instead generate a whole series of error messages:

```
error C3861: 'power': identifier not found
```

In a change from previous examples, I've used the keyword `void` in the function `main()` where the parameter list would usually appear to indicate that no parameters are to be supplied. Previously, I left the parentheses enclosing the parameter list empty, which is also interpreted in C++ as indicating that there are no parameters. Using `void` in this way is a remnant from the practice in C but you won't see it very often in C++. As you saw, the keyword `void` is used as the return type for a function to indicate that no value is returned. If you specify the return type of a function as `void`, you must not place a value in any `return` statement within the function; otherwise, you get an error message from the compiler.

You gathered from some of the previous examples that using a function is very simple. To use the function `power()` to calculate 5.0^3 and store the result in a variable `y` in our example, you have the following statement:

```
y = power(5.0, 3);
```

The values 5.0 and 3 here are the arguments to the function. They happen to be constants, but you can use any expression as an argument, as long as a value of the correct type is ultimately produced. The arguments to the `power()` function substitute for the parameters `x` and `n`, which were used in the definition of the function. The computation is performed using these values, and then, a copy of the result, 125, is returned to the calling function, `main()`, which is then stored in `y`. You can think of the function as having this value in the statement or expression in which it appears. You then output the value of `y`:

```
cout << endl << "5.0 cubed = " << y;
```

The next call of the function is used within the output statement:

```
cout << endl << "3.0 cubed = "
    << power(3.0, index);           // Outputting return value
```

Here, the value returned by the function is transferred directly to the output stream. Because you haven't stored the returned value anywhere, it is otherwise unavailable to you. The first argument in the call of the function here is a constant; the second argument is a variable.

The function `power()` is used next in this statement:

```
x = power(x, power(2.0, 2.0));      // Using a function as an argument
```

Here, the `power()` function is called twice. The first call to the function is the rightmost in the expression, and the result supplies the value for the second argument to the leftmost call. Although the arguments in the sub-expression `power(2.0, 2.0)` are both specified as the `double` literal 2.0, the function is actually called with the first argument as 2.0 and the second argument as the integer literal, 2. The compiler converts the `double` value specified for the second argument to type `int`, because it knows from the function prototype (shown again here) that the type of the second parameter has been specified as `int`.

```
double power(double x, int n);        // Function prototype
```

The `double` result 4.0 is returned by the first call to the `power()` function, and after conversion to type `int`, the value 4 is passed as the second argument in the next call of the function, with `x` as the first argument. Because `x` has the value 3.0, the value of 3.0^4 is computed and the result, 81.0, stored in `x`. This sequence of events is illustrated in Figure 5-2.

This statement involves two implicit conversions from type `double` to type `int` that were inserted by the compiler. There's a possible loss of data when converting from type `double` to type `int`, so the compiler issues warning messages when this occurs, even though the compiler itself has inserted this conversion. Generally, relying on automatic conversions where there is potential for data loss is a dangerous programming practice, and it is not at all obvious from the code that this conversion

is intended. It is far better to be explicit in your code by using the `static_cast` operator when necessary. The statement in the example is much better written as:

```
x = power(x, static_cast<int>(power(2.0, 2)));
```

Coding the statement like this avoids both the compiler warning messages that the original version caused. Using a static cast does not remove the possibility of losing data in the conversion of data from one type to another. Because you specified it, though, it is clear that this is what you intended, recognizing that data loss might occur.

You could write the loop in the `power()` function like this:

```
for(auto i = 1; i <= n; i++)
    result *= x;
```

The compiler will deduce the appropriate type for `i` from the initial value. I prefer to explicitly specify the type as `int` in this instance because I think it makes the code more readily understood.




FIGURE 5-2

PASSING ARGUMENTS TO A FUNCTION

It's very important to understand how arguments are passed to a function, because it affects how you write functions and how they ultimately operate. There are also a number of pitfalls to be avoided, so we'll look at the mechanism for this quite closely.

The arguments you specify when a function is called should usually correspond in type and sequence to the parameters that appear in the definition of the function. As you saw in the last example, if the type of an argument you specify in a function call doesn't correspond with the type of the parameter in the function definition, the compiler arranges for the argument to be converted to the required type, obeying the same rules as those for converting operands that I discussed in Chapter 2. If the conversion is not possible, you get an error message from the compiler. However, even if the conversion is possible and the code compiles, it could result in the loss of data (for example, a conversion from type `long` to type `short`) and should therefore be avoided.

There are two mechanisms used to pass arguments to functions. The first mechanism applies when you specify the parameters in the function definition as ordinary variables (*not* references). This is called the *pass-by-value* method of transferring data to a function, so let's look into that first.

The Pass-by-Value Mechanism

With this mechanism, the variables, constants, or expression values that you specify as arguments are not passed to a function at all. Instead, copies of the argument values are created, and these copies are used as the values to be transferred to the function. Figure 5-3 shows this in a diagram using the example of our power() function.

```
int index(2);
double value(10.0);
double result(power(value, index));
```




FIGURE 5-3

In Figure 5-3, the value returned by **power()** is used to initialize **result**. Each time you call the **power()** function, the compiler arranges for copies of the arguments to be stored in a temporary location in memory. During execution of the function, all references to the function parameters are mapped to these temporary copies of the arguments.

TRY IT OUT**Passing-by-Value**

One consequence of the pass-by-value mechanism is that a function can't directly modify the arguments passed to it. You can demonstrate this by deliberately trying to do so in an example:

```
// Ex5_02.cpp
// A futile attempt to modify caller arguments
#include <iostream>
using std::cout;
using std::endl;

int incr10(int num);           // Function prototype

int main(void)
{
    int num(3);

    cout << endl << "incr10(num) = " << incr10(num) << endl
        << "num = " << num << endl;
    return 0;
}

// Function to increment a variable by 10
int incr10(int num)           // Using the same name might help...
{
    num += 10;                 // Increment the caller argument - hopefully
    return num;                // Return the incremented value
}
```

Of course, this program is doomed to failure. If you run it, you get this output:

```
incr10(num) = 13
num = 3
```

How It Works

The output confirms that the original value of `num` remains untouched. The copy of `num` that was generated and passed as the argument to the `incr10()` function was incremented and was eventually discarded on exiting from the function.

Clearly, the pass-by-value mechanism provides you with a high degree of protection from having your caller arguments mauled by a rogue function, but it is conceivable that you might actually want to arrange to modify caller arguments. Of course, there is a way to do this. Didn't you just know that pointers would turn out to be incredibly useful?

Pointers as Arguments to a Function

When you use a pointer as an argument, the pass-by-value mechanism still operates as before; however, a pointer is an address of another variable, and if you take a copy of this address, the copy still points to the same variable. This is how specifying a pointer as a parameter enables your function to get at a caller argument.

TRY IT OUT Pass-by-Pointer

You can change the last example to use a pointer to demonstrate the effect:

```
// Ex5_03.cpp
// A successful attempt to modify caller arguments
#include <iostream>
using std::cout;
using std::endl;

int incr10(int* num); // Function prototype

int main(void)
{
    int num(3);

    int* pnum(&num); // Pointer to num

    cout << endl << "Address passed = " << pnum;

    int result = incr10(pnum);
    cout << endl << "incr10(pnum) = " << result;

    cout << endl << "num = " << num << endl;
    return 0;
}

// Function to increment a variable by 10
int incr10(int* num) // Function with pointer argument
{
    cout << endl << "Address received = " << num;

    *num += 10; // Increment the caller argument
    // - confidently
    return *num; // Return the incremented value
}
```

The output from this example is:

```
Address passed = 0012FF6C
Address received = 0012FF6C
incr10(pnum) = 13
num = 13
```

The address values produced by your computer may be different from those shown here, but the two values should be identical to each other.

How It Works

In this example, the principal alterations from the previous version relate to passing a pointer, `pnum`, in place of the original variable, `num`. The prototype for the function now has the parameter type specified as a pointer to `int`, and the `main()` function has the pointer `pnum` declared and initialized with the address of `num`. The function `main()`, and the function `incr10()`, output the address sent and

the address received, respectively, to verify that the same address is indeed being used in both places. Because the `incr10()` function is writing to `cout`, you now call it before the output statement and store the return value in `result`:

```
int result = incr10(pnum);
cout << endl << "incr10(pnum) = " << result;
```

This ensures proper sequencing of the output. The output shows that this time, the variable `num` has been incremented and has a value that's now identical to that returned by the function.

In the rewritten version of the function `incr10()`, both the statement incrementing the value passed to the function and the `return` statement now de-reference the pointer to use the value stored.

Passing Arrays to a Function

You can also pass an array to a function, but in this case, the array is not copied, even though a pass-by-value method of passing arguments still applies. The array name is converted to a pointer, and a copy of the pointer to the beginning of the array is passed by value to the function. This is quite advantageous because copying large arrays is very time-consuming. As you may have worked out, however, elements of the array may be changed within a function, and thus, an array is the only type that cannot be passed by value.

TRY IT OUT Passing Arrays

You can illustrate the ins and outs of this by writing a function to compute the average of a number of values passed to a function in an array:

```
// Ex5_04.cpp
// Passing an array to a function
#include <iostream>
using std::cout;
using std::endl;

double average(double array[], int count);           //Function prototype

int main(void)
{
    double values[] = { 1.0, 2.0, 3.0, 4.0, 5.0, 6.0, 7.0, 8.0, 9.0, 10.0 };

    cout << endl << "Average = "

        << average(values, (sizeof values)/(sizeof values[0])) << endl;
    return 0;
}

// Function to compute an average
double average(double array[], int count)
{
    double sum(0.0);                                // Accumulate total in here
```

```

        for(int i = 0; i < count; i++)
            sum += array[i];           // Sum array elements

        return sum/count;          // Return average
    }

```

The program produces the following output:

```
Average = 5.5
```

How It Works

The `average()` function is designed to work with an array of any length. As you can see from the prototype, it accepts two arguments: the array and a count of the number of elements. The function is called in `main()` in this statement:

```

cout << endl << "Average = "
<< average(values, (sizeof values)/(sizeof values[0])) << endl;

```

The function is called with the first argument as the array name, `values`, and the second argument as an expression that evaluates to the number of elements in the array.

You'll recall this expression, using the operator `sizeof`, from when you looked at arrays in Chapter 4.

Within the body of the function, the computation is expressed in the way you would expect. There's no significant difference between this and the way you would write the same computation if you implemented it directly in `main()`.

The output confirms that everything works as we anticipated.

TRY IT OUT Using Pointer Notation When Passing Arrays

You haven't exhausted all the possibilities here. As you determined at the outset, the array name is passed as a pointer — to be precise, as a copy of a pointer — so within the function, you are not obliged to work with the data as an array at all. You could modify the function in the example to work with pointer notation throughout, in spite of the fact that you are using an array.

```

// Ex5_05.cpp
// Handling an array in a function as a pointer
#include <iostream>
using std::cout;
using std::endl;

double average(double* array, int count);      //Function prototype

int main(void)
{
    double values[] = { 1.0, 2.0, 3.0, 4.0, 5.0, 6.0, 7.0, 8.0, 9.0, 10.0 };

    cout << endl << "Average = "

```

```
    << average(values, (sizeof values)/(sizeof values[0])) << endl;
    return 0;
}

// Function to compute an average
double average(double* array, int count)
{
    double sum(0.0);                                // Accumulate total in here
    for(int i = 0; i < count; i++)                  // Sum array elements
        sum += *array++;

    return sum/count;                                // Return average
}
```

The output is exactly the same as in the previous example.

How It Works

As you can see, the program needed very few changes to make it work with the array as a pointer. The prototype and the function header have been changed, although neither change is absolutely necessary. If you change both back to the original version, with the first parameter specified as a `double` array, and leave the function body written in terms of a pointer, it works just as well. The most interesting aspect of this version is the body of the `for` loop statement:

```
sum += *array++;                                // Sum array elements
```

Here, you apparently break the rule about not being able to modify an address specified as an array name because you are incrementing the address stored in `array`. In fact, you aren't breaking the rule at all. Remember that the pass-by-value mechanism makes a copy of the original array address and passes that to the function, so you are just modifying the copy here — the original array address is quite unaffected. As a result, whenever you pass a one-dimensional array to a function, you are free to treat the value passed as a pointer in every sense, and change the address in any way that you want.

NOTE An array records no information about its size, so you cannot use the range-based `for` loop with an array passed as an argument to a function.

Passing Multidimensional Arrays to a Function

Passing a multidimensional array to a function is quite straightforward. The following statement declares a two-dimensional array, `beans`:

```
double beans[2][4];
```

You could then write the prototype of a hypothetical function, `yield()`, like this:

```
double yield(double beans[2][4]);
```

NOTE You may be wondering how the compiler knows that this is defining an array of the dimensions shown as a parameter, and not a single array element. The answer is simple — you can't write a single array element as a parameter in a function definition or prototype, although you can pass one as an argument when you call a function. For a parameter accepting a single element of an array as an argument, the parameter would have just a variable name and its type. The array context doesn't apply.

When you are defining a multidimensional array as a parameter, you can also omit the first dimension value. Of course, the function needs some way of knowing the extent of the first dimension. For example, you could write this:

```
double yield(double beans[][4], int index);
```

Here, the second parameter provides the necessary information about the first dimension. The function can operate with a two-dimensional array, with the value for the first dimension specified by the second argument to the function and with the second dimension fixed at 4.

TRY IT OUT Passing Multidimensional Arrays

You define such a function in the following example:

```
// Ex5_06.cpp
// Passing a two-dimensional array to a function
#include <iostream>
using std::cout;
using std::endl;

double yield(double array[][4], int n);

int main(void)
{
    double beans[3][4] = { { 1.0, 2.0, 3.0, 4.0 },
                           { 5.0, 6.0, 7.0, 8.0 },
                           { 9.0, 10.0, 11.0, 12.0 } };

    cout << endl << "Yield = " << yield(beans, sizeof beans/sizeof beans[0])
        << endl;
    return 0;
}

// Function to compute total yield
double yield(double beans[][4], int count)
{
    double sum(0.0);
```

```
for(int i = 0; i < count; i++)      // Loop through number of rows
    for(int j = 0; j < 4; j++)      // Loop through elements in a row
        sum += beans[i][j];
return sum;
}
```

The output from this example is:

```
Yield = 78
```

How It Works

I have used different names for the parameters in the function header from those in the prototype, just to remind you that this is possible — but in this case, it doesn't really improve the program at all. The first parameter is defined as an array of an arbitrary number of rows, each row having four elements. You actually call the function using the array `beans` with three rows. The second argument is specified by dividing the total size of the array in bytes by the size of the first row. This evaluates to the number of rows in the array.

The computation in the function is simply a nested `for` loop with the inner loop summing elements of a single row and the outer loop repeating this for each row.

Using a pointer in a function rather than a multidimensional array as an argument doesn't really apply particularly well in this example. When the array is passed, it passes an address value that points to an array of four elements (a row). This doesn't lend itself to an easy pointer operation within the function. You would need to modify the statement in the nested `for` loop to the following:

```
sum += *(*(beans + i) + j);
```

So the computation is probably clearer in array notation.

References as Arguments to a Function

We now come to the second of the two mechanisms for passing arguments to a function. Specifying a parameter to a function as a reference changes the method of passing data for that parameter.

The method used is not *pass-by-value*, where an argument is copied before being transferred to the function, but *pass-by-reference*, where the parameter acts as an alias for the argument passed. This eliminates any copying of the argument supplied and allows the function to access the caller argument directly. It also means that the de-referencing, which is required when passing and using a pointer to a value, is also unnecessary.

Using reference parameters to a function has particular significance when you are working with objects of a class type. Objects can be large and complex, in which case, the copying process can be very time-consuming. Using reference parameters in these situations can make your code execute considerably faster.

TRY IT OUT Pass-by-Reference

Let's go back to a revised version of a very simple example, `Ex5_03.cpp`, to see how it would work using reference parameters:

```
// Ex5_07.cpp
// Using an lvalue reference to modify caller arguments
#include <iostream>
using std::cout;
using std::endl;

int incr10(int& num); // Function prototype

int main(void)
{
    int num(3);
    int value(6);

    int result = incr10(num);
    cout << endl << "incr10(num) = " << result
        << endl << "num = " << num;

    result = incr10(value);
    cout << endl << "incr10(value) = " << result
        << endl << "value = " << value << endl;
    return 0;
}

// Function to increment a variable by 10
int incr10(int& num) // Function with reference argument
{
    cout << endl << "Value received = " << num;
    num += 10; // Increment the caller argument
                // - confidently
    return num; // Return the incremented value
}
```

This program produces the output:

```
Value received = 3
incr10(num) = 13
num = 13
Value received = 6
incr10(value) = 16
value = 16
```

How It Works

You should find the way this works quite remarkable. This is essentially the same as `Ex5_03.cpp`, except that the function uses an lvalue reference as a parameter. The prototype has been changed to reflect this. When the function is called, the argument is specified just as though it were a pass-by-value operation, so it's used in the same way as the earlier version. The argument value isn't passed to

the function. The function parameter is *initialized* with the address of the argument, so whenever the parameter `num` is used in the function, it accesses the caller argument directly.

Just to reassure you that there's nothing fishy about the use of the identifier `num` in `main()` as well as in the function, the function is called a second time with the variable `value` as the argument. At first sight, this may give you the impression that it contradicts what I said was a basic property of a reference — that after being declared and initialized, it couldn't be reassigned to another variable. The reason it isn't contradictory is that a reference as a function parameter is created and initialized each time the function is called, and is destroyed when the function ends, so you get a completely new reference created each time you use the function.

Within the function, the value received from the calling program is displayed onscreen. Although the statement is essentially the same as the one used to output the address stored in a pointer, because `num` is now a reference you obtain the data value rather than the address.

This clearly demonstrates the difference between a reference and a pointer. A reference is an alias for another variable, and therefore can be used as an alternative way of referring to it. It is equivalent to using the original variable name. The output shows that the `incr10()` function is directly modifying the variable passed as a caller argument.

You will find that if you try to use a numeric value, such as 20, as an argument to `incr10()`, the compiler outputs an error message. This is because the compiler recognizes that a reference parameter can be modified within a function, and the last thing you want is to have your constants changing value now and again. This would introduce a kind of excitement into your programs that you could probably do without. You also cannot use an expression for an argument corresponding to an lvalue reference parameter unless the expression is an lvalue. Essentially, the argument for an lvalue reference parameter must result in a persistent memory location in which something can be stored.

NOTE *I'm sure that you remember that there is another type of reference called an rvalue reference that I mentioned in Chapter 4. A parameter of an rvalue reference type allows an expression that is an rvalue to be passed to a function. You'll learn more about this later in this chapter.*

The security you get by using an lvalue reference parameter is all very well, but if the function didn't modify the value, you wouldn't want the compiler to create all these error messages every time you passed a reference argument that was a constant. Surely, there ought to be some way to accommodate this? As Ollie would have said, "There most certainly is, Stanley!"

Use of the `const` Modifier

You can apply the `const` modifier to a parameter to a function to tell the compiler that you don't intend to modify it in any way. This causes the compiler to check that your code indeed does not modify the argument, and there are no error messages when you use a constant argument.

TRY IT OUT**Passing a const**

You can modify the previous program to show how the `const` modifier changes the situation:

```
// Ex5_08.cpp
// Using a reference to modify caller arguments

#include <iostream>
using std::cout;
using std::endl;

int incr10(const int& num);           // Function prototype

int main(void)
{
    const int num(3);      // Declared const to test for temporary creation
    int value(6);

    int result = incr10(num);
    cout << endl << "incr10(num) = " << result
        << endl << "num = " << num;

    result = incr10(value);
    cout << endl << "incr10(value) = " << result;
    cout << endl << "value = " << value;

    cout << endl;
    return 0;
}

// Function to increment a variable by 10
int incr10(const int& num)           // Function with const reference argument
{
    cout << endl << "Value received = " << num;
    // num += 10;                  // this statement would now be illegal
    // return num+10;              // Return the incremented value
}
```

The output when you execute this is:

```
Value received = 3
incr10(num) = 13
num = 3
Value received = 6
incr10(value) = 16
value = 6
```

How It Works

You declare the variable `num` in `main()` as `const` to show that when the parameter to the function `incr10()` is declared as `const`, you no longer get a compiler message when passing a `const` object.

It has also been necessary to comment out the statement that increments `num` in the function `incr10()`. If you uncomment this line, you'll find the program no longer compiles, because the compiler won't allow `num` to appear on the left side of an assignment. When you specified `num` as `const` in the function header and prototype, you promised not to modify it, so the compiler checks that you kept your word. Everything works as before, except that the variables in `main()` are no longer changed by the function.

By using lvalue reference parameters, you now have the best of both worlds. On one hand, you can write a function that can access caller arguments directly and avoid the copying that is implicit in the pass-by-value mechanism. On the other hand, where you don't intend to modify an argument, you can get all the protection against accidental modification you need by using a `const` modifier with an lvalue reference type.

Rvalue Reference Parameters

I'll now illustrate briefly how parameters that are rvalue reference types differ from parameters that are lvalue reference types. Keep in mind that this won't be how rvalue references are intended to be used. You'll learn about that later in the book. Let's look at an example that is similar to `Ex5_07.cpp`.

TRY IT OUT Using rvalue Reference Parameters

Here's the code for this example:

```
// Ex5_09.cpp
// Using an rvalue reference parameter

#include <iostream>
using std::cout;
using std::endl;

int incr10(int&& num);           // Function prototype

int main(void)
{
    int num(3);
    int value(6);
    int result(0);
/*
    result = incr10(num);           // Increment num
    cout << endl << "incr10(num) = " << result
        << endl << "num = " << num;

    result = incr10(value);         // Increment value
    cout << endl << "incr10(value) = " << result
        << endl << "value = " << value;
*/
    result = incr10(value+num);      // Increment an expression
    cout << endl << "incr10(value+num) = " << result
```

```

        << endl << "value = " << value;

result = incr10(5);                                // Increment a literal
cout << endl << "incr10(5) = " << result
<< endl << "5 = " << 5;

cout << endl;
return 0;
}

// Function to increment a variable by 10
int incr10(int&& num)           // Function with rvalue reference argument
{
    cout << endl << "Value received = " << num;
    num += 10;
    return num;                  // Return the incremented value
}

```

Compiling and executing this produces the output:

```

Value received = 9
incr10(value+num) = 19
value = 6
Value received = 5
incr10(5) = 15
5 = 5

```

How It Works

The `incr10()` function now has an rvalue reference parameter type. In `main()`, you call the function with the expression `value+num` as the argument. The output shows that the function returns the value of the expression incremented by 10. Of course, you saw earlier that if you try to pass an expression as the argument for an lvalue reference parameter, the compiler will not allow it.

Next, you pass the literal, `5`, as the argument, and again, the value returned shows the incrementing works. The output also shows that the literal `5` has not been changed, but why not? The argument in this case is an expression consisting of just the literal `5`. The expression has the value `5` when it is evaluated, and this is stored in a temporary location that is referenced by the function parameter.

If you uncomment the statements at the beginning of `main()`, the code will not compile. A function that has an rvalue reference parameter can only be called with an argument that is an rvalue. Because `num` and `value` are lvalues, the compiler flags the statements that pass these as arguments to `incr10()` as errors.

While this example shows that you can pass an expression as the argument corresponding to an rvalue reference, and that within the function, the temporary location holding the value of the expression can be accessed and changed, this serves no purpose in this context. You will see when we get to look into defining classes that in some circumstances, rvalue reference parameters offer significant advantages.

NOTE An important point to keep in mind is that even though an rvalue reference parameter may refer to an rvalue — the result of an expression that is temporary — the rvalue reference parameter itself is not an rvalue, it is an lvalue. There are circumstances where you will want to convert the rvalue reference parameter from an lvalue to an rvalue. You will see in Chapter 8 how this can arise and how you can use the `std::move()` library function to convert an lvalue to an rvalue.

Arguments to main()

You can define `main()` with no parameters or you can specify a parameter list that allows the `main()` function to obtain values from the command line from the execute command for the program. Values passed from the command line as arguments to `main()` are always interpreted as strings. If you want to get data into `main()` from the command line, you must define it like this:

```
int main(int argc, char* argv[])
{
    // Code for main()...
}
```

The first parameter is the count of the number of strings found on the command line, including the program name, and the second parameter is an array that contains pointers to these strings plus an additional element that is null. Thus, `argc` is always at least 1, because you at least must enter the name of the program. The number of arguments received depends on what you enter on the command line to execute the program. For example, suppose that you execute the `DoThat` program with the command:

```
DoThat.exe
```

There is just the name of the .exe file for the program, so `argc` is 1 and the `argv` array contains two elements — `argv[0]` pointing to the string "DoThat.exe", and `argv[1]` that contains `nullptr`.

Suppose you enter this on the command line:

```
DoThat or else "my friend" 999.9
```

Now `argc` is 5 and `argv` contains six elements, the last element being `nullptr` and the first five pointing to the strings:

```
"DoThat" "or" "else" "my friend" "999.9"
```

You can see from this that if you want to have a string that includes spaces received as a single string, you must enclose it between double quotes. You can also see that numerical values are read as strings, so if you want conversion to the numerical value, that is up to you.

Let's see it working.

TRY IT OUT**Receiving Command-Line Arguments**

This program just lists the arguments it receives from the command line:

```
// Ex5_10.cpp
// Reading command line arguments
#include <iostream>
using std::cout;
using std::endl;

int main(int argc, char* argv[])
{
    cout << endl << "argc = " << argc << endl;
    cout << "Command line arguments received are:" << endl;
    for(int i = 0; i < argc; i++)
        cout << "argument " << (i+1) << ":" << argv[i] << endl;
    return 0;
}
```

You have two choices as to how you enter the command-line arguments. After you build the example, you can open a command window at the folder containing the .exe file, and then enter the program name followed by the command-line arguments. Alternatively, you can specify the command-line arguments in the IDE before you execute the program. Just open the project properties window by selecting Project → Properties from the main menu and then extend the Configuration Properties tree in the left pane by clicking the arrow. Click the Debugging folder and enter the items to be passed to the application as values for the Command Arguments property.

I enter the following in the command window with the current directory containing the .exe file for the program:

```
Ex5_10 trying multiple "argument values" 4.5 0.0
```

Here is the output from resulting from my input:

```
argc = 6
Command line arguments received are:
argument 1: Ex5_10
argument 2: trying
argument 3: multiple
argument 4: argument values
argument 5: 4.5
argument 6: 0.0
```

How It Works

The program first outputs the value of argc and then the values of each argument from the argv array in the for loop. You can see from the output that the first argument value is the program name. "argument values" is treated as a single argument because of the enclosing double quotes.

You could make use of the fact that the last element in `argv` is `nullptr` and code the output of the command-line argument values like this:

```
int i(-1);
while(argv[++i] != nullptr)
    cout << "argument " << (i+1) << ":" << argv[i] << endl;
```

The while loop ends when `argv[argc]` is reached because that element contains `nullptr`.

Accepting a Variable Number of Function Arguments

You can define a function so that it allows any number of arguments to be passed to it. You indicate that a variable number of arguments can be supplied by placing an ellipsis (which is three periods, ...) at the end of the parameter list in the function definition. For example:

```
int sumValues(int first,...)
{
    //Code for the function
}
```

There must be at least one ordinary parameter, but you can have more. The ellipsis must always be placed at the end of the parameter list.

Obviously, there is no information about the type or number of arguments in the variable list, so your code must figure out what is passed to the function when it is called. The C++ library defines `va_start`, `va_arg`, and `va_end` macros in the `cstdarg` header to help you do this. It's easiest to show how these are used with an example.

TRY IT OUT Receiving a Variable Number of Arguments

This program uses a function that just sums the values of a variable number of arguments passed to it:

```
// Ex5_11.cpp
// Handling a variable number of arguments
#include <iostream>
#include <cstdarg>
using std::cout;
using std::endl;

int sum(int count, ...)
{
    if(count <= 0)
        return 0;

    va_list arg_ptr;           // Declare argument list pointer
    va_start(arg_ptr, count); // Set arg_ptr to 1st optional argument

    int sum(0);
    for(int i = 0; i<count; i++)
```

```

        sum += va_arg(arg_ptr, int);           // Add int value from arg_ptr and increment
        va_end(arg_ptr);                   // Reset the pointer to null
    return sum;
}

int main(int argc, char* argv[])
{
    cout << sum(6, 2, 4, 6, 8, 10, 12) << endl;
    cout << sum(9, 11, 22, 33, 44, 55, 66, 77, 66, 99) << endl;
    return 0;
}

```

This example produces the following output:

```

42
473

```

How It Works

The `main()` function calls the `sum()` function in the two output statements, in the first instance with seven arguments and in the second with ten arguments. The first argument in each case specifies the number of arguments that follow. It's important not to forget this, because if you omit the count argument, the result will be rubbish.

The `sum()` function has a single normal parameter of type `int` that represents the count of the number of arguments that follow. The ellipsis in the parameter list indicates that an arbitrary number of arguments can be passed. Basically, you have two ways of determining how many arguments there are when the function is called — you can require that the number of arguments is specified by a fixed parameter, as in the case of `sum()`, or you can require that the last argument has a special marker value that you can check for and recognize.

To start processing the variable argument list, you declare a pointer of type `va_list`:

```

va_list arg_ptr;                      // Declare argument list pointer

```

The `va_list` type is defined in the `cstdarg` header file, and the pointer is used to point to each argument in turn.

The `va_start` macro is used to initialize `arg_ptr` so that it points to the first argument in the list:

```

va_start(arg_ptr, count);            // Set arg_ptr to 1st optional argument

```

The second argument to the macro is the name of the fixed parameter that precedes the ellipsis in the parameter list, and this is used by the macro to determine where the first variable argument is.

You retrieve the values of the arguments in the list in the `for` loop:

```

int sum();
for(int i = 0 ; i<count; i++)
    sum += va_arg(arg_ptr, int);      // Add int value from arg_ptr and increment
}

```

The `va_arg` macro returns the value of the argument at the location specified by `arg_ptr` and increments `arg_ptr` to point to the next argument value. The second argument to the `va_arg` macro is the argument type, and this determines the value that you get as well as how `arg_ptr` increments, so if this is not correct, you get chaos; the program probably executes, but the values you retrieve are rubbish, and `arg_ptr` is incremented incorrectly to access more rubbish.

When you are finished retrieving argument values, you reset `arg_ptr` with the statement:

```
va_end(arg_ptr); // Reset the pointer to null
```

The `va_end` macro resets the pointer of type `va_list` that you pass as the argument to it to null. It's a good idea to always do this because after processing the arguments, `arg_ptr` points to a location that does not contain valid data.

RETURNING VALUES FROM A FUNCTION

All the example functions that you have created have returned a single value. Is it possible to return anything other than a single value? Well, not directly, but as I said earlier, the single value returned need not be a numeric value; it could also be an address, which provides the key to returning any amount of data. You simply use a pointer. Unfortunately, this also is where the pitfalls start, so you need to keep your wits about you for the adventure ahead.

Returning a Pointer

Returning a pointer value is easy. A pointer value is just an address, so if you want to return the address of some variable `value`, you can just write the following:

```
return &value; // Returning an address
```

As long as the function header and function prototype indicate the return type appropriately, you have no problem — or at least, no apparent problem. Assuming that the variable `value` is of type `double`, the prototype of a function called `treble`, which might contain the preceding `return` statement, could be as follows:

```
double* treble(double data);
```

I have defined the parameter list arbitrarily here.

So let's look at a function that returns a pointer. It's only fair that I warn you in advance — this function doesn't work, but it is educational. Let's assume that you need a function that returns a pointer to a memory location containing three times its argument value. Our first attempt to implement such a function might look like this:

```
// Function to treble a value - mark 1
double* treble(double data)
{
```

```

        double result(0.0);
        result = 3.0*data;
        return &result;
    }
}

```

TRY IT OUT Returning a Bad Pointer

You could create a little test program to see what happens (remember that the `treble` function won't work as expected):

```

// Ex5_12.cpp
#include <iostream>
using std::cout;
using std::endl;

double* treble(double); // Function prototype

int main(void)
{
    double num(5.0); // Test value
    double* ptr(nullptr); // Pointer to returned value

    ptr = treble(num);

    cout << endl << "Three times num = " << 3.0*num;

    cout << endl << "Result = " << *ptr; // Display 3*num

    cout << endl;
    return 0;
}

// Function to treble a value - mark 1
double* treble(double data)
{
    double result(0.0);
    result = 3.0*data;
    return &result;
}

```

There's a hint that everything is not as it should be, because compiling this program results in a warning from the compiler:

```
warning C4172: returning address of local variable or temporary
```

The output that I got from executing the program was:

```
Three times num = 15
Result = 4.10416e-230
```

How It Works (or Why It Doesn't)

The function `main()` calls `treble()` and stores the address returned in the pointer `ptr`, which should point to a value that is three times the argument, `num`. It then displays the result of computing three times `num`, followed by the value at the address returned from the function.

Clearly, the second line of output doesn't reflect the correct value of 15, but where's the error? Well, it's not exactly a secret because the compiler gives fair warning of the problem. The error arises because the variable `result` in the function `treble()` is created when the function begins execution, and is destroyed on exiting from the function — so the memory that the pointer is pointing to no longer contains the original variable value. The memory previously allocated to `result` becomes available for other purposes, and here, it has evidently been used for something else.

A Cast-Iron Rule for Returning Addresses

There is an absolutely cast-iron rule for returning addresses:

Never, ever, return the address of a local automatic variable from a function.

You obviously can't use a function that doesn't work, so what can you do to rectify that? You could use a reference parameter and modify the original variable, but that's not what you set out to do. You are trying to return a pointer to some useful data so that, ultimately, you can return more than a single item of data. One answer lies in dynamic memory allocation (you saw this in action in the previous chapter). With the operator `new`, you can create a new variable in the free store that continues to exist until it is eventually destroyed by `delete` — or until the program ends. With this approach, the function looks like this:

```
// Function to treble a value - mark 2
double* treble(double data)
{
    double* result(new double(0.0));
    *result = 3.0*data;
    return result;
}
```

Rather than declaring `result` to be type `double`, you now declare it to be of type `double*` and store in it the address returned by the operator `new`. Because the `result` is a pointer, the rest of the function is changed to reflect this, and the address contained in the `result` is finally returned to the calling program. You could exercise this version by replacing the function in the last working example with this version.

You need to remember that with dynamic memory allocation from within a function such as this, more memory is allocated each time the function is called. The onus is on the calling program to delete the memory when it's no longer required. It's easy to forget to do this in practice, with the result that the free store is gradually eaten up until, at some point, it is exhausted and the program fails. As mentioned before, this sort of problem is referred to as a *memory leak*.

Here you can see how the function would be used. The only necessary change to the original code is to use `delete` to free the memory as soon as you have finished with the pointer returned by the `treble()` function.

```
#include <iostream>

using std::cout;
using std::endl;

double* treble(double); // Function prototype

int main(void)
{
    double num(5.0); // Test value
    double* ptr(nullptr); // Pointer to returned value

    ptr = treble(num);

    cout << endl << "Three times num = " << 3.0*num;

    cout << endl << "Result = " << *ptr; // Display 3*num
    delete ptr; // Don't forget to free the memory
    ptr = nullptr;
    cout << endl;
    return 0;
}

// Function to treble a value - mark 2
double* treble(double data)
{
    double* result(new double(0.0));
    *result = 3.0*data;
    return result;
}
```

NOTE In Chapter 10 you'll learn about smart pointers that eliminate the need to use `delete` to free memory you have allocated with `new`. By using smart pointers you can remove the risk of memory leaks too.

Returning a Reference

You can also return an lvalue reference from a function. This is just as fraught with potential errors as returning a pointer, so you need to take care with this, too. Because an lvalue reference has no existence in its own right (it's always an alias for something else), you must be sure that the object that it refers to still exists after the function completes execution. It's very easy to forget this when you use references in a function because they appear to be just like ordinary variables.

References as return types are of primary significance in the context of object-oriented programming. As you will see later in the book, they enable you to do things that would be impossible without them. (This particularly applies to “operator overloading,” which I’ll come to in Chapter 8.) Returning an lvalue reference from a function means that you can use the result of the function on the left side of an assignment statement.

TRY IT OUT Returning a Reference

Let’s look at an example that illustrates the use of reference return types, and also demonstrates how a function can be used on the left of an assignment operation when it returns an lvalue. This example assumes that you have an array containing a mixed set of values. Whenever you want to insert a new value into the array, you want to replace the element with the lowest value.

```
// Ex5_13.cpp
// Returning a reference
#include <iostream>
#include <iomanip>
using std::cout;
using std::endl;
using std::setw;

double& lowest(double values[], const int& length); // Function prototype

int main(void)
{
    double data[] = { 3.0, 10.0, 1.5, 15.0, 2.7, 23.0,
                      4.5, 12.0, 6.8, 13.5, 2.1, 14.0 };
    int len(__countof(data));                                // Number of elements
    for(auto value : data)
        cout << setw(6) << value;

    lowest(data, len) = 6.9;                                // Change lowest to 6.9
    lowest(data, len) = 7.9;                                // Change lowest to 7.9

    cout << endl;
    for(auto value : data)
        cout << setw(6) << value;

    cout << endl;
    return 0;
}

// Function returning a reference
double& lowest(double a[], const int& len)
{
    int j(0);                                              // Index of lowest element
    for(int i = 1; i < len; i++)
        if(a[j] > a[i])                                    // Test for a lower value...
            j = i;                                         // ...if so update j
    return a[j];                                           // Return reference to lowest element
}
```

The output from this example is:

3	10	1.5	15	2.7	23	4.5	12	6.8	13.5	2.1	14
3	10	6.9	15	2.7	23	4.5	12	6.8	13.5	7.9	14

How It Works

Let's first take a look at how the function is implemented. The prototype for the function `lowest()` uses `double&` as the specification of the return type, which is therefore of type "reference to `double`." You write a reference type return value in exactly the same way as you have seen for variable declarations, by appending the `&` to the data type. The function has two parameters specified — a one-dimensional array of type `double` and a parameter of type `int` that specifies the length of the array.

The body of the function has a straightforward `for` loop to determine which element of the array passed contains the lowest value. The index, `j`, of the array element with the lowest value is arbitrarily set to 0 at the outset, and then modified within the loop if the current element, `a[i]`, is less than `a[j]`. Thus, on exit from the loop, `j` contains the index value corresponding to the array element with the lowest value. The `return` statement is as follows:

```
return a[j]; // Return reference to lowest element
```

In spite of the fact that this looks identical to the statement that would return a value, because the return type was declared as a reference, this returns a reference to the array element `a[j]` rather than the value that the element contains. The address of `a[j]` is used to initialize the reference to be returned. This reference is created by the compiler because the return type was declared as a reference.

Don't confuse returning `&a[j]` with returning a reference. If you write `&a[j]` as the return value, you are specifying the address of `a[j]`, which is a *pointer*. If you do this after having specified the return type as a *reference*, you get an error message from the compiler. Specifically, you get this:

```
error C2440: 'return' : cannot convert from 'double *' to 'double &'
```

The function `main()`, which exercises the `lowest()` function, is very simple. An array of type `double` is declared and initialized with 12 arbitrary values, and an `int` variable `len` is initialized to the length of the array using the `_countof()` macro. The initial values in the array are output for comparison purposes.

Again, the program uses the stream manipulator `setw()` to space the values uniformly, requiring the `#include` directive for `iomanip`.

The function `main()` then calls the function `lowest()` on the left side of an assignment to change the lowest value in the array. This is done twice to show that it does actually work and is not an accident. The contents of the array are then output to the display again, with the same field width as before, so corresponding values line up.

As you can see from the output with the first call to `lowest()`, the third element of the array, `data[2]`, contained the lowest value, so the function returned a reference to it and its value was changed to 6.9. Similarly, on the second call, `data[10]` was changed to 7.9. This demonstrates quite clearly that returning a reference allows the use of the function on the left side of an assignment statement. The effect is as if the variable specified in the `return` statement appeared on the left of the assignment.

Of course, if you want to, you can also use it on the right side of an assignment, or in any other suitable expression. If you had two arrays, `x` and `y`, with the number of array elements specified by `lenx` and `leny`, respectively, you could set the lowest element in the array `x` to twice the lowest element in the array `y` with this statement:

```
lowest(x, lenx) = 2.0*lowest(y, leny);
```

This statement would call your `lowest()` function twice — once with arguments `y` and `leny` in the expression on the right side of the assignment, and once with arguments `x` and `lenx` to obtain the address where the result of the right-hand expression is to be stored.

A Teflon-Coated Rule: Returning References

A similar rule to the one concerning the return of a pointer from a function also applies to returning references:

Never, ever, return a reference to a local variable from a function.

I'll leave the topic of returning a reference from a function for now, but I haven't finished with it yet. I will come back to it again in the context of user-defined types and object-oriented programming, when you will unearth a few more magical things that you can do with references.

Static Variables in a Function

There are some things you can't do with automatic variables within a function. You can't count how many times a function is called, for example, because you can't accumulate a value from one call to the next. There's more than one way to get around this if you need to. For instance, you could use a reference parameter to update a count in the calling program, but this wouldn't help if the function was called from lots of different places within a program. You could use a global variable that you incremented from within the function, but globals are risky things to use. Because globals can be accessed from anywhere in a program, it is very easy to change them accidentally.

Global variables are also risky in applications that have multiple threads of execution that access them, and you must take special care to manage how globals are accessed from different threads. The basic problem that has to be addressed when more than one thread can access a global variable is that one thread can change the value of a global variable while another thread is working with it. The best solution in such circumstances is to avoid the use of global variables altogether.

To create a variable whose value persists from one call of a function to the next, you can declare a variable within a function as `static`. You use exactly the same form of declaration for a `static` variable that you saw in Chapter 2. For example, to declare a variable `count` as `static`, you could use this statement:

```
static int count(0);
```

This also initializes the variable to zero.

NOTE Initialization of a static variable within a function only occurs the first time that the function is called. In fact, on the first call of a function, the static variable is created and initialized. It then continues to exist for the duration of program execution, and whatever value it contains when the function is exited is available when the function is next called.

TRY IT OUT Using Static Variables in Functions

You can demonstrate how a static variable behaves in a function with the following simple example:

```
// Ex5_14.cpp
// Using a static variable within a function
#include <iostream>
using std::cout;
using std::endl;

void record(void);      // Function prototype, no arguments or return value

int main(void)
{
    record();

    for(int i = 0; i <= 3; i++)
        record();

    cout << endl;
    return 0;
}

// A function that records how often it is called
void record(void)
{
    static int count(0);
    cout << endl << "This is the " << ++count;
    if((count > 3) && (count < 21))           // All this....
        cout <<"th";
    else
        switch(count%10)                      // is just to get...
    {
        case 1: cout << "st";
                   break;
        case 2: cout << "nd";
                   break;
        case 3: cout << "rd";
                   break;
        default: cout << "th";      // the right ending for...
                  // 1st, 2nd, 3rd, 4th, etc.
    }
    cout << " time I have been called";
    return;
}
```

Our function here serves only to record the fact that it was called. If you build and execute it, you get this output:

```
This is the 1st time I have been called  
This is the 2nd time I have been called  
This is the 3rd time I have been called  
This is the 4th time I have been called  
This is the 5th time I have been called
```

How It Works

You initialize the static variable `count` with 0 and increment it in the first output statement in the function. Because the increment operator is prefixed, the incremented value is displayed by the output statement. It will be 1 on the first call, 2 on the second, and so on. Because `count` is static, it continues to exist and retain its value from one call of the function to the next.

The remainder of the function is concerned with working out when "st", "nd", "rd", or "th" should be appended to the value of `count` that is displayed. It's surprisingly irregular.

Note the `return` statement. Because the return type of the function is `void`, to include a value would cause a compiler error. You don't actually need to put a `return` statement in this particular case, because running off the closing brace for the body of the function is equivalent to executing a `return` statement without a value. The program would compile and run without error even if you didn't include the `return`.

RECURSIVE FUNCTION CALLS

When a function contains a call to itself, it's referred to as a *recursive function*. A recursive function call can also be indirect, where a function `fun1` calls a function `fun2`, which, in turn, calls `fun1`.

Recursion may seem to be a recipe for an indefinite loop, and if you aren't careful, it certainly can be. An indefinite loop will lock up your machine and require *Ctrl+Alt+Del* to end the program, which is always a nuisance. A prerequisite for avoiding an indefinite loop is that the function contains some means of stopping the process.

Unless you have come across the technique before, the sort of things to which recursion may be applied may not be obvious. In physics and mathematics, there are many things that can be thought of as involving recursion. A simple example is the factorial of an integer, which, for a given integer N , is the product $1 \times 2 \times 3 \dots \times N$. This is very often the example given to show recursion in operation. Recursion can also be applied to the analysis of programs during the compilation process; however, you will look at something even simpler.

TRY IT OUT A Recursive Function

At the start of this chapter (see `Ex5_01.cpp`), you produced a function to compute the integral power of a value; that is, to compute x^n . This is equivalent to x multiplied by itself n times. You can implement this as a recursive function as an elementary illustration of recursion in action. You can also improve the implementation of the function to deal with negative index values, where x^n is equivalent to $1/x^{-n}$.

```

// Ex5_15.cpp (based on Ex5_01.cpp)
// A recursive version of x to the power n
#include <iostream>
using std::cout;
using std::endl;

double power(double x, int n);      // Function prototype

int main(void)
{
    double x(2.0);                  // Different x from that in function power
    double result(0.0);

    // Calculate x raised to powers -3 to +3 inclusive
    for(int index = -3; index <= 3; index++)
        cout << x << " to the power " << index << " is " << power(x, index) << endl;

    return 0;
}

// Recursive function to compute integral powers of a double value
// First argument is value, second argument is power index
double power(double x, int n)
{
    if(n < 0)
    {
        x = 1.0/x;
        n = -n;
    }
    if(n > 0)
        return x*power(x, n-1);
    else
        return 1.0;
}

```

The output from this program is:

```

2 to the power -3 is 0.125
2 to the power -2 is 0.25
2 to the power -1 is 0.5
2 to the power 0 is 1
2 to the power 1 is 2
2 to the power 2 is 4
2 to the power 3 is 8

```

How It Works

The function now supports positive and negative powers of x, so the first action is to check whether the value for the power that x is to be raised to, n, is negative:

```

if(n < 0)
{
    x = 1.0/x;
    n = -n;
}

```

Supporting negative powers is easy; the code just uses the fact that x^{-n} can be evaluated as $(1/x)^n$. Thus, if n is negative, you set x to be $1.0/x$ and change the sign of n so it's positive.

The next `if` statement decides whether or not the `power()` function should call itself once more:

```
if(n > 0)
    return x*power(x, n-1);
else
    return 1.0;
```

The `if` statement provides for the value 1.0 being returned if n is zero, and in all other cases, it returns the result of the expression, `x*power(x, n-1)`. This causes a further call to the function `power()` with the index value reduced by 1. Thus, the `else` clause in the `if` statement provides the essential mechanism necessary to avoid an indefinite sequence of recursive function calls.

Clearly, if the value of n is other than zero within the function `power()`, a further call to the function `power()` occurs. In fact, for any given value of n other than 0, the function calls itself n times, ignoring the sign of n . Figure 5-4 shows the mechanism when the index argument is 3.




FIGURE 5-4

As you see, the `power()` function is called a total of four times to generate x^3 , three of the calls being recursive where the function is calling itself.

Using Recursion

Unless you have a problem that particularly lends itself to using recursive functions, or if you have no obvious alternative, it's generally better to use a different approach, such as a loop, because it will be much more efficient than using recursive function calls. Think about what happens with our last example to evaluate a simple product, x multiplied by itself n times. On each call, the compiler generates copies of the two arguments to the function, and also has to keep track of the location to return to when each `return` is executed. It's also necessary to arrange to save the contents of various registers in your computer so that they can be used within the function `power()`, and, of course, these need to be restored to their original state at each return from the function. With a quite modest depth of recursive call, the overhead will be considerably greater than if you use a loop.

This is not to say you should never use recursion. Where the problem suggests the use of recursive function calls as a solution, it can be an immensely powerful technique, greatly simplifying the code. You'll see an example where this is the case in the next chapter.

SUMMARY

In this chapter, you learned about the basics of program structure. You should have a good grasp of how functions are defined, how data can be passed to a function, and how results are returned to a calling program. Functions are fundamental to programming in C++, so everything you do from here on will involve using multiple functions in a program.

The use of references as arguments is a very important concept, so make sure you are confident about using them. You'll see a lot more about references as arguments to functions when you look into object-oriented programming.

EXERCISES

1. The *factorial* of 4 (written as $4!$) is $4 \times 3 \times 2 \times 1 = 24$, and $3!$ is $3 \times 2 \times 1 = 6$, so it follows that $4!$ is $4 \times 3!$, or more generally:

```
fact(n) = n*fact(n - 1)
```

The limiting case is when n is 1, in which case, $1! = 1$. Because of this, $0!$ is defined to be 1. Write a recursive function that calculates factorials, and test it.

2. Write a function that swaps two integers, using pointers as arguments. Write a program that uses this function and test that it works correctly.
3. The trigonometry functions (`sin()`, `cos()`, and `tan()`) in the standard `cmath` library take arguments in radians. Write three equivalent functions, called `sind()`, `cosd()`, and `tand()`, which take arguments in degrees. All arguments and return values should be type `double`.

4. Write a program that reads a number (an integer) and a name (less than 15 characters) from the keyboard. Design the program so that the data entry is done in one function, and the output in another. Store the data in the `main()` function. The program should end when zero is entered for the number. Think about how you are going to pass the data between functions — by value, by pointer, or by reference?
 5. (Advanced) Write a function that, when passed a string consisting of words separated by single spaces, returns the first word; calling it again with an argument of `nullptr` returns the second word, and so on, until the string has been processed completely, when `nullptr` is returned. This is a simplified version of the way the C++ run-time library routine `strtok()` works. So, when passed the string "one two three", the function returns "one" after the first call, then "two" after the second, and finally "three". Passing it a new string results in the current string being discarded before the function starts on the new string.
-

► WHAT YOU LEARNED IN THIS CHAPTER

TOPIC	CONCEPT
Functions	Functions should be compact units of code with a well-defined purpose. A typical program will consist of a large number of small functions, rather than a small number of large functions.
Function prototypes	Always provide a function prototype for each function defined in your program, positioned before you call that function.
Reference parameters	Passing values to a function using a reference can avoid the copying implicit in the pass-by-value transfer of arguments. Parameters that are not modified in a function should be specified as <code>const</code> .
Returning references or pointers	When returning a reference or a pointer from a function, ensure that the object being returned has the correct scope. Never return a pointer or a reference to an object that is local to a function.
static variables in a function	A static variable that is defined within the body of a function retains its value from one function call to the next.

A large, bold, dark gray number '6' is centered on a light gray background with a subtle hexagonal grid pattern.

More about Program Structure

WHAT YOU WILL LEARN IN THIS CHAPTER:

- What a pointer to a function is
- How to define and use pointers to functions
- How to define and use arrays of pointers to functions
- What an exception is and how to write exception handlers that deal with them
- How to write multiple functions with a single name to handle different kinds of data automatically
- What function templates are and how to define and use them
- How to write a substantial program using several functions

WROX.COM CODE DOWNLOADS FOR THIS CHAPTER

You can find the wrox.com code downloads for this chapter on the Download Code tab at www.wrox.com/remtitle.cgi?isbn=9781118368084. The code is in the Chapter 6 download and individually named according to the names throughout the chapter.

POINTERS TO FUNCTIONS

A pointer stores an address value that, up to now, has been the address of another variable. This has provided considerable flexibility in allowing you to use different variables at different times through a single pointer. A pointer can also point to the address of a function. This enables you to call a function through a pointer, which will be the function at the address that was last assigned to the pointer.

Obviously, a pointer to a function must contain the memory address of the function that you want to call. To work properly, the pointer must also maintain information about the parameter list for the function it points to, as well as the return type. Therefore, the type for a pointer to a function must incorporate the parameter types and the return type of the functions to which it can point. Clearly, this is going to restrict what you can store in a particular pointer to a function.

If you have declared a pointer to functions that accept one argument of type `int` and return a value of type `double`, you can only store the address of a function that has exactly this form. If you want to store the address of a function that accepts two arguments of type `int` and returns type `char`, you must define another pointer with a type that includes these characteristics.

Declaring Pointers to Functions

You can declare a pointer `pfun` that you can use to point to functions that take two arguments, of type `char*` and `int`, and return a value of type `double` like this:

```
double (*pfun)(char*, int); // Pointer to function declaration
```

At first, you may find that the parentheses make this look a little weird. This declares a pointer with the name `pfun` that can point to functions that accept two arguments, one of type pointer to `char` and another of type `int`, and return a value of type `double`. The parentheses around the pointer name, `pfun`, and the asterisk are essential; without them, the statement would be a function declaration rather than a pointer declaration. In this case, it would look like this:

```
double *pfun(char*, int); // Prototype for a function, pfun,  
// returning type double*
```

This is a prototype for a function `pfun()` that has two parameters, and returns a pointer to a `double` value. The general form of a declaration of a pointer to a function looks like this:

```
return_type (*pointer_name)(list_of_parameter_types);
```

The declaration of a pointer to a function consists of three components:

- The return type of the functions that can be pointed to
- The pointer name preceded by an asterisk to indicate it is a pointer
- The parameter types of the functions that can be pointed to

NOTE *The pointer can only point to functions with the same `return_type` and `list_of_parameter_types` specified in the declaration. If you attempt to assign a function to a pointer that does not conform to the types in the pointer declaration, the compiler generates an error message.*

You can initialize a pointer to a function with the name of a function within the declaration of the pointer. The following is an example of this:

```
long sum(long num1, long num2);           // Function prototype
long (*pfun)(long, long) = sum;          // Pointer to function points to sum()
```

In general, you can set the `pfun` pointer that you declared here to point to any function that accepts two arguments of type `long` and returns a value of type `long`. In the first instance, you initialized it with the address of the `sum()` function that has the prototype given by the first statement.

When you initialize a pointer to a function in the declaration, you can use the `auto` keyword for the type. You can write the previous declaration as:

```
auto pfun = sum;
```

As long as the prototype or definition for `sum()` precedes this statement in the source file, the compiler can work out the pointer type.

Of course, you can also initialize a pointer to a function by using an assignment statement. Assuming the pointer `pfun` has been declared as in the preceding code, you could set the value of the pointer to a different function with these statements:

```
long product(long, long);           // Function prototype
...
pfun = product;                   // Set pointer to function product()
```

As with pointers to variables, you must ensure that a pointer to a function is initialized before you use it to call a function. Without initialization, catastrophic failure of your program is guaranteed.

TRY IT OUT Pointers to Functions

To get a proper feeling for these newfangled pointers and how they perform in action, try one out in a program:

```
// Ex6_01.cpp
// Exercising pointers to functions
#include <iostream>
using std::cout;
using std::endl;

long sum(long a, long b);           // Function prototype
long product(long a, long b);      // Function prototype

int main(void)
{
    long (*pdo_it)(long, long);     // Pointer to function declaration

    pdo_it = product;
    cout << endl
        << "3*5 = " << pdo_it(3, 5); // Call product thru a pointer

    pdo_it = sum;                  // Reassign pointer to sum()
    cout << endl
```

```
<< "3*(4 + 5) + 6 = "
<< pdo_it(product(3, pdo_it(4, 5)), 6); // Call thru a pointer,
// twice
cout << endl;
return 0;
}

// Function to multiply two values
long product(long a, long b)
{
    return a*b;
}

// Function to add two values
long sum(long a, long b)
{
    return a + b;
}
```

This example produces the output:

```
3*5 = 15
3*(4 + 5) + 6 = 33
```

How It Works

This is hardly a useful program, but it does show very simply how a pointer to a function is declared, assigned a value, and subsequently used to call a function.

After the usual preamble, you declare a pointer to a function, `pdo_it`, which can point to either of the other two functions that you have defined, `sum()` or `product()`. The pointer is given the address of the function `product()` in this assignment statement:

```
pdo_it = product;
```

You just supply the name of the function as the initial value for the pointer, and no parentheses or other adornments are required. The function name is automatically converted to an address, which is stored in the pointer. You could replace the first two statements in `main()` with this statement:

```
auto pdo_it = product;
```

This declares and initializes `pdo_it` with the address of the `product()` function.

The function `product()` is called indirectly through the pointer `pdo_it` in the output statement.

```
cout << endl
<< "3*5 = " << pdo_it(3, 5); // Call product thru a pointer
```

You use the name of the pointer just as if it was a function name, followed by the arguments between parentheses exactly as they would appear if you were using the original function name directly.

Just to show that you can, you change the pointer to point to `sum()`:

```
pdo_it = sum; // Reassign pointer to sum()
```

You then use it again in a ludicrously convoluted expression to do some simple arithmetic:

```
cout << endl
    << "3*(4 + 5) + 6 = "
    << pdo_it(product(3, pdo_it(4, 5)), 6); // Call thru a pointer,
                                                // twice
```

This shows that you can use a pointer to a function in exactly the same way as the function that it points to. The sequence of actions in the expression is shown in Figure 6-1.




FIGURE 6-1

A Pointer to a Function as an Argument

Because “pointer to a function” is a perfectly reasonable type, a function can also have a parameter that is of a pointer to a function type. The function can then call the function pointed to by the argument. The pointer can point to different functions in different circumstances, which allows the particular function that is to be called from inside a function to be determined in the calling

program. You can pass a function name explicitly as the argument for a parameter that is of a pointer to function type.

TRY IT OUT Passing a Function Pointer

Suppose you need a function that processes an array of values by producing the sum of the squares of each of the elements on some occasions, and the sum of the cubes on other occasions. One way of achieving this is by using a pointer to a function as a parameter.

```
// Ex6_02.cpp
// A pointer to a function as an argument
#include <iostream>
using std::cout;
using std::endl;

// Function prototypes
double squared(double);
double cubed(double);
double sumarray(double data[], int len, double (*pfun)(double));

int main(void)
{
    double data[] = { 1.5, 2.5, 3.5, 4.5, 5.5, 6.5, 7.5 };
    int len(_countof(data));

    cout << endl << "Sum of squares = " << sumarray(data, len, squared);
    cout << endl << "Sum of cubes = " << sumarray(data, len, cubed);
    cout << endl;
    return 0;
}

// Function for a square of a value
double squared(double x)
{
    return x*x;
}

// Function for a cube of a value
double cubed(double x)
{
    return x*x*x;
}

// Function to sum functions of array elements
double sumarray(double data[], int len, double (*pfun)(double))
{
    double total(0.0); // Accumulate total in here

    for(int i = 0; i < len; i++)
        total += pfun(data[i]);

    return total;
}
```

If you compile and run this code, you should see the following output:

```
Sum of squares = 169.75
Sum of cubes = 1015.88
```

How It Works

The first statement of interest is the prototype for the function `sumarray()`. Its third parameter is a pointer to a function that has a parameter of type `double`, and returns a value of type `double`.

```
double sumarray(double array[], int len, double (*pfun)(double));
```

The function `sumarray()` processes each element of the array passed as its first argument with whatever function is pointed to by its third argument. The function then returns the sum of the processed array elements. The third argument must be a function that returns a `double` value and accepts an argument of type `double`.

You call `sumarray()` twice in `main()`, the first time with the function name `squared` as the third argument, and the second time using `cubed`. In each case, the address corresponding to the function name that you use as the argument is substituted for the function pointer in the body of the function `sumarray()`, so the appropriate function is called within the `for` loop.

There are obviously easier ways of achieving what this example does, but using a pointer to a function provides you with a lot of generality. You could pass any function to `sumarray()` that you care to define as long as it takes one `double` argument and returns a value of type `double`.

Arrays of Pointers to Functions

In the same way as with regular pointers, you can declare an array of pointers to functions. You can also initialize them in the declaration. Here is an example:

```
double sum(const double, const double);           // Function prototype
double product(const double, const double);       // Function prototype
double difference(const double, const double);    // Function prototype
double (*pfun[])(const double, const double) =   {
    { sum, product, difference } };               // Array of function pointers
```

Each of the elements in the array is initialized by the corresponding function address appearing in the initializing list between braces. The array length is determined by the number of initial values in the list. You cannot use `auto` to deduce an array type, so you must put the specific type here.

To call `product()` using the second element of the pointer array, you would write:

```
pfun[1](2.5, 3.5);
```

The square brackets that select the function pointer array element appear immediately after the array name and before the arguments to the function being called. Of course, you can place a function call through an element of a function pointer array in any appropriate expression that the

original function might legitimately appear in, and the index value selecting the pointer can be any expression producing a valid index value.

INITIALIZING FUNCTION PARAMETERS

With all the functions you have used up to now, you have had to take care to provide an argument corresponding to each parameter in a function call. It can be quite handy to be able to omit one or more arguments in a function call and have some default values supplied automatically for the arguments that you leave out. You can arrange this by providing initial values for the parameters to a function in its prototype.

Suppose that you write a function to display a message, where the message is passed as the argument. Here is the definition of such a function:

```
void showit(const char message[])
{
    cout << endl
        << message;
    return;
}
```

You can specify a default value for the parameter to this function by specifying the initializing string in the function prototype, as follows:

```
void showit(const char message[] = "Something is wrong.");
```

The default value for the `message` parameter is the string literal shown. If you omit the argument when you call the function, the default value is used.

TRY IT OUT Omitting Function Arguments

Leaving out the function argument when you call the function executes it with the default value. If you supply the argument, it replaces the default value. You can use the `showit()` function to output a variety of messages.

```
// Ex6_03.cpp
// Omitting function arguments
#include <iostream>
using std::cout;
using std::endl;

void showit(const char message[] = "Something is wrong.");

int main(void)
{
    const char mymess[] = "The end of the world is nigh.";

    showit();                                // Display the basic message
    showit("Something is terribly wrong!");    // Display an alternative
```

```

showit();
showit(mymess); // Display the default again
// Display a predefined message

cout << endl;
return 0;
}

void showit(const char message[])
{
    cout << endl
        << message;
    return;
}

```

If you execute this example, it produces the following apocalyptic output:

```

Something is wrong.
Something is terribly wrong!
Something is wrong.
The end of the world is nigh.

```

How It Works

As you see, you get the default message specified in the function prototype whenever the argument is left out; otherwise, the function behaves normally.

If you have a function with several arguments, you can provide initial values for as many of them as you like. If you want to omit more than one argument to take advantage of a default value, all arguments to the right of the leftmost argument that you omit must also be left out. For example, suppose you have this function:

```
int do_it(long arg1 = 10, long arg2 = 20, long arg3 = 30, long arg4 = 40);
```

and you want to omit one argument in a call to it. You can omit only the last one, `arg4`. If you want to omit `arg3`, you must also omit `arg4`. If you omit `arg2`, `arg3` and `arg4` must also be omitted, and if you want to use the default value for `arg1`, you have to omit all of the arguments.

You can conclude from this that you need to put the arguments which have default values in the function prototype together in sequence at the end of the parameter list, with the argument most likely to be omitted appearing last.

EXCEPTIONS

If you've had a go at the exercises that appear at the end of the previous chapters, you've more than likely come across compiler errors and warnings, as well as errors that occur while the program is running. *Exceptions* are a way of flagging errors or unexpected conditions that occur in your programs, and you already know that the `new` operator throws an exception if the memory you request cannot be allocated.

So far, you have typically handled error conditions by using an `if` statement to test some expression, and then executing some specific code to deal with the error. C++ provides another, more general mechanism for handling errors that allows you to separate the code that deals with these conditions from the code that executes when such conditions do not arise. It is important to realize that exceptions are not intended to be used as an alternative to the normal data checking and validating that you might do in a program. The code that is generated when you use exceptions carries quite a bit of overhead with it, so exceptions are really intended to be applied in the context of exceptional, near-catastrophic conditions that might arise, but are not normally expected to occur in the normal course of events. An error reading from a disk might be something that you use exceptions for. An invalid data item being entered is not a good candidate for using exceptions.

The exception mechanism uses three new keywords:

- `try`—Identifies a code block in which an exception can occur. A `try` block must be immediately followed by at least one `catch` block.
- `throw`—Causes an exception condition to be originated and throws an exception of a particular type.
- `catch`—Identifies a block of code that handles the exception. A `catch` block is executed when an exception is thrown in the preceding `try` block that is of the type that is specified between parentheses following the `catch` keyword. A `try` block may be followed by several `catch` blocks, each catching a different type of exception.

In the following Try It Out, you can see how they work in practice.

TRY IT OUT Throwing and Catching Exceptions

You can easily see how exception handling operates by working through an example. Let's use a very simple context for this. Suppose that you are required to write a program that calculates the time it takes in minutes to make a part on a machine. The number of parts made in each hour is recorded, but you must keep in mind that the machine breaks down regularly and may not make any parts.

You could code this using exception handling as follows:

```
// Ex6_04.cpp  Using exception handling
#include <iostream>
using std::cout;
using std::endl;

int main(void)
{
    int counts[] = {34, 54, 0, 27, 0, 10, 0};
    int time(60);                                // One hour in minutes
    int hour(0);                                 // Current hour

    for(auto& count : counts)
    {
        try
        {
            cout << endl << "Hour " << ++hour;
            cout << endl << "Time " << time;
            cout << endl << "Count " << count;
        }
        catch (exception e)
        {
            cout << endl << "Exception caught";
        }
    }
}
```

```

        if(0 == count)
            throw "Zero count - calculation not possible.';

        cout << " minutes per item: " << static_cast<double>(time)/count;
    }
catch(const char aMessage[])
{
    cout << endl << aMessage << endl;
}
}
return 0;
}

```

If you run this example, the output is:

```

Hour 1 minutes per item: 1.76471
Hour 2 minutes per item: 1.11111
Hour 3
Zero count - calculation not possible.

Hour 4 minutes per item: 2.22222
Hour 5
Zero count - calculation not possible.

Hour 6 minutes per item: 6
Hour 7
Zero count - calculation not possible.

```

How It Works

The code in the `try` block is executed in the normal sequence. The `try` block serves to define where an exception can be raised. You can see from the output that when an exception is thrown, the sequence of execution continues with the `catch` block. The `catch` block will execute when an exception of type `const char[]` is thrown. After the code in the `catch` block has been executed, execution continues with the next loop iteration. Of course, when no exception is thrown, the `catch` block is not executed.

The division is carried out in the output statement that follows the `if` statement checking the divisor. When a `throw` statement is executed, control passes immediately to the first statement in the `catch` block, so the statement that performs the division is bypassed when an exception is thrown. After the statement in the `catch` block executes, the loop continues with the next iteration, if there is one.

Throwing Exceptions

You can throw an exception anywhere within a `try` block using a `throw` statement, and the `throw` statement operand determines the type of the exception. The exception thrown in the example is a string literal and, therefore, of type `const char[]`. The operand following the `throw` keyword can be any expression, and the type of the result of the expression determines the type of exception thrown. There must be a `catch` block to catch an exception of the type that may be thrown.

Exceptions can also be thrown in functions that are called from within a `try` block and can be caught by a `catch` block following the `try` block if they are not caught within the function. You could add a function to the previous example to demonstrate this, with the definition:

```
void testThrow(void)
{
    throw "Zero count - calculation not possible.";
}
```

You place a call to this function in the previous example in place of the `throw` statement:

```
if(0 == count)
    testThrow(); // Call a function that throws an exception
```

The exception is thrown by the `testThrow()` function and caught by the `catch` block whenever the array element is zero, so the output is the same as before. Don't forget the function prototype if you add the definition of `testThrow()` to the end of the source code.

Catching Exceptions

The `catch` block following the `try` block in our example catches any exception of type `const char[]`. This is determined by the parameter specification that appears in parentheses following the keyword `catch`. You must supply at least one `catch` block for a `try` block, and the `catch` blocks must immediately follow the `try` block. A `catch` block catches all exceptions (of the specified type) that occur anywhere in the code in the immediately preceding `try` block, including those thrown and not caught in any functions called directly or indirectly within the `try` block.

If you want to specify that a `catch` block is to handle any exception thrown in a `try` block, you put an ellipsis (...) between the parentheses enclosing the exception declaration:

```
catch (...)
{
    // code to handle any exception
}
```

This `catch` block catches exceptions of any type. It must appear last if you have other `catch` blocks defined for the `try` block.

Here's how a `try` block followed by two `catch` blocks looks:

```
try
{
    ...
}
catch (const type1& ex)
{
    ...
}
catch (type2 ex)
{
    ...
}
```

When an exception is thrown in a try block with more than one catch block, the catch blocks are checked in sequence until a match for the exception type is found. The code in the first catch block that matches will be executed.

TRY IT OUT Nested try Blocks

You can nest `try` blocks one within another. With this situation, if an exception is thrown from within an inner `try` block that is not followed by a `catch` block corresponding to the type of exception thrown, the catch handlers for the outer `try` block are searched. You can demonstrate this with the following example:

```
// Ex6_05.cpp
// Nested try blocks
#include <iostream>
using std::cin;
using std::cout;
using std::endl;

int main(void)
{
    int height(0);
    const int minHeight(9);                                // Minimum height in inches
    const int maxHeight(100);                             // Maximum height in inches
    const double inchesToMeters(0.0254);
    char ch('y');

    try                                         // Outer try block
    {
        while('y' == ch || 'Y' == ch)
        {
            cout << "Enter a height in inches: ";
            cin >> height;
                                    // Read the height to be
                                    // converted

            try
            {
                if(height > maxHeight)
                    throw "Height exceeds maximum";          // Exception thrown
                if(height < minHeight)
                    throw height;                            // Exception thrown

                cout << static_cast<double>(height)*inchesToMeters
                    << " meters" << endl;
            }
            catch(const char aMessage[])
            {
                cout << aMessage << endl;
            }
            cout << "Do you want to continue(y or n)?";
            cin >> ch;
        }
    }
}
```

```
    catch(int badHeight)
    {
        cout << badHeight << " inches is below minimum" << endl;
    }
    return 0;
}
```

How It Works

There is a `try` block enclosing the `while` loop and an inner `try` block in which two different types of exception may be thrown. The exception of type `const char[]` is caught by the `catch` block for the inner `try` block, but the exception of type `int` has no `catch` handler associated with the inner `try` block; therefore, the `catch` handler in the outer `try` block is executed. In this case, the program ends immediately because the statement following the `catch` block is a `return`.

Rethrowing Exceptions

It may be that when you catch an exception, you want to pass it on the calling program for some additional action, rather than handling it entirely in the `catch` block. In this case you can rethrow the exception for onward processing. For example:

```
try
{
    ...
}
catch (const type1& ex)
{
    ...
}
catch (type2 ex)
{
    // Process the exception...
    throw;           // Rethrow the exception for processing by the caller
}
```

Using `throw` without an operand causes the exception that is being handled to be rethrown. You can only use `throw` without an operand within a `catch` block. Rethrowing the exception terminates execution of the function and throws the exception to be caught by the caller of this function. The calling function must place its call to this function in a `try` block to catch the rethrown exception.

Exception Handling in the MFC

This is a good point to raise the question of MFC and exceptions because they are used to some extent. If you browse the documentation that came with Visual C++, you may come across `TRY`, `THROW`, and `CATCH` in the index. These are macros defined within the MFC that were created before exception handling was implemented in the C++ language. They mimic the operation of `try`, `throw`, and `catch` in C++, but the language facilities for exception handling really render these obsolete, so you should not use them. They are, however, still there for two reasons. There are large numbers of

programs still around that use these macros, and it is important to ensure that, as far as possible, old code still compiles. Also, most of the MFC that throws exceptions was implemented in terms of these macros. In any event, any new programs should use the `try`, `throw`, and `catch` keywords because they work with the MFC.

There is one slight anomaly you need to keep in mind when you use MFC functions that throw exceptions. The MFC functions that throw exceptions generally throw exceptions of class types — you will find out about class types before you get to use the MFC. Even though the exception that an MFC function throws is of a given class type — `CDBException`, say — you need to catch the exception as a pointer, not as the type of the exception. So, with the exception thrown being of type `CDBException`, the type that appears as the `catch` block parameter is `CBDEception*`. If you are not rethrowing the exception, you must also delete the exception object in the catch block by calling its `Delete()` function. For example:

```
try
{
    // Execute some code that might throw an MFC exception...
}
catch (CException* ex)
{
    // Handle the exception here...
    ex->Delete();                                // Delete the exception object
}
```

You should not use `delete` to delete the exception object because the object may not be allocated on the heap. `CException` is the base class for all MFC exceptions so the catch block here will catch MFC exceptions of any type.

HANDLING MEMORY ALLOCATION ERRORS

When you used the `new` operator to allocate memory (as you saw in Chapters 4 and 5), you ignored the possibility that the memory might not be allocated. If the memory isn't allocated, an exception is thrown that results in the termination of the program. Ignoring this exception is quite acceptable in most situations because having no memory left is usually a terminal condition for a program that you can usually do nothing about. However, there can be circumstances where you might be able to do something about it if you had the chance, or you might want to report the problem in your own way. In this situation, you can catch the exception that the `new` operator throws. Let's contrive an example to show this happening.

TRY IT OUT Catching an Exception Thrown by the `new` Operator

The exception that the `new` operator throws when memory cannot be allocated is of type `bad_alloc`. `bad_alloc` is a class type defined in the `new` standard header file, so you'll need an `#include` directive for that. Here's the code:

```
// Ex6_06.cpp
// Catching an exception thrown by new
#include<new>                                // For bad_alloc type
```

```
#include<iostream>
using std::bad_alloc;
using std::cout;
using std::endl;

int main( )
{
    char* pdata(nullptr);
    size_t count(~static_cast<size_t>(0)/2);
    try
    {
        pdata = new char[count];
        cout << "Memory allocated." << endl;
    }
    catch(bad_alloc &ex)
    {
        cout << "Memory allocation failed." << endl
            << "The information from the exception object is: "
            << ex.what() << endl;
    }
    delete[] pdata;
    return 0;
}
```

On my machine, this example produces the following output:

```
Memory allocation failed.
The information from the exception object is: bad allocation
```

How It Works

The example allocates memory dynamically for an array of type `char[]` where the length is specified by the `count` variable that you define as:

```
size_t count(~static_cast<size_t>(0)/2);
```

The size of an array is an integer of type `size_t`, so you declare `count` to be of this type. The value for `count` is generated by a somewhat complicated expression. The value 0 is type `int`, so the value produced by the expression `static_cast<size_t>(0)` is a zero of type `size_t`. Applying the `~` operator to this flips all the bits so you then have a `size_t` value with all the bits as 1, which corresponds to the maximum value you can represent as `size_t`, because `size_t` is an unsigned type. This value exceeds the maximum amount of memory that the `new` operator can allocate in one go, so you divide by 2 to bring it within the bounds of what is possible. This is still a very large value, so, unless your machine is exceptionally well endowed with memory, the allocation request will fail.

The allocation of the memory takes place in the `try` block. If the allocation succeeds, you'll see a message to that effect, but if, as you expect, it fails, an exception of type `bad_alloc` will be thrown by the `new` operator. This causes the code in the `catch` block to be executed. Calling the `what()` function for the `bad_alloc` object reference `ex` returns a string describing the problem that caused the exception, and you see the result of this call in the output. Most exception classes implement the `what()` function to provide a string describing why the exception was thrown.

To handle out-of-memory situations with some positive effect, clearly, you must have some means of returning memory to the free store. In most practical cases, this involves some serious work on the program to manage memory, so it is not often undertaken.

FUNCTION OVERLOADING

Suppose you have written a function that determines the maximum value in an array of values of type `double`:

```
// Function to generate the maximum value in an array of type double
double maxdouble(double data[], const int& len)
{
    double maximum(data[0]);

    for(int i = 1; i < len; i++)
        if(maximum < data[i])
            maximum = data[i];

    return maximum;
}
```

You now want to create a function that produces the maximum value from an array of type `long`, so you write another function similar to the first, with this prototype:

```
long maxlong(long data[], const int& len);
```

You have chosen the function name to reflect the particular task in hand, which is OK for two functions, but you may also need the same function for several other types of argument. It seems a pity that you have to keep inventing names. Ideally, you would use the same function name `max()` regardless of the argument type, and have the appropriate version executed. It probably won't be any surprise to you that you can, indeed, do this, and the C++ mechanism that makes it possible is called *function overloading*.

What Is Function Overloading?

Function overloading allows you to use several functions with the same name as long as they each have different parameter lists. When one of the functions is called, the compiler chooses the correct version for the job based on the list of arguments. Obviously, the compiler must always be able to decide unequivocally which function should be selected in any particular instance of a function call, so the parameter list for each function in a set of overloaded functions must be unique. Following on from the `max()` function example, you could create overloaded functions with the following prototypes:

```
int max(int data[], const int& len);                                // Prototypes for
long max(long data[], const int& len);                               // a set of overloaded
double max(double data[], const int& len);                           // functions
```

These functions share a common name, but have different parameter lists. Overloaded functions that have the same number of parameters must have at least one parameter with a unique type. An overloaded function can have a different number of parameters from the others in the set.

Note that a different return type does not distinguish a function adequately. You can't add the following function to the previous set:

```
double max(long data[], const int& len);           // Not valid overloading
```

The reason is that this function would be indistinguishable from the function that has this prototype:

```
long max(long data[], const int& len);
```

If you define functions like this, it causes the compiler to complain with the following error:

```
error C2556: 'double max(long [],const int&)' :
overloaded function differs only by return type from 'long max(long [],const
int&)'
```

This may seem slightly unreasonable, until you remember that you can write statements such as these:

```
long numbers[] = {1, 2, 3, 3, 6, 7, 11, 50, 40};
int len(_countof(numbers));
max(numbers, len);
```

The call for the `max()` function doesn't make much sense here because you discard the result, but this does not make it illegal. If the return type were permitted as a distinguishing feature, the compiler would be unable to decide whether to choose the version with a `long` or a `double` return type. For this reason, the return type is not considered to be a differentiating feature of overloaded functions.

Every function — not just overloaded functions — is said to have a *signature*, where the signature of a function is determined by its name and its parameter list. All functions in a program must have unique signatures, otherwise the program does not compile.

TRY IT OUT Using Overloaded Functions

You can exercise the overloading capability with the function `max()` that you have already defined. Try an example that includes the three versions for `int`, `long`, and `double` arrays.

```
// Ex6_07.cpp
// Using overloaded functions
#include <iostream>
using std::cout;
using std::endl;

int max(int data[],const int& len);           // Prototypes for
long max(long data[],const int& len);          // a set of overloaded
double max(double data[],const int& len);       // functions
```

```

int main(void)
{
    int small[] = {1, 24, 34, 22};
    long medium[] = {23, 245, 123, 1, 234, 2345};
    double large[] = {23.0, 1.4, 2.456, 345.5, 12.0, 21.0};

    int lensmall(_countof(small));
    int lenmedium(_countof(medium));
    int lenlarge(_countof(large));

    cout << endl << max(small, lensmall);
    cout << endl << max(medium, lenmedium);
    cout << endl << max(large, lenlarge);

    cout << endl;
    return 0;
}

// Maximum of ints
int max(int x[],const int& len)
{
    int maximum(x[0]);
    for(int i = 1; i < len; i++)
        if(maximum < x[i])
            maximum = x[i];
    return maximum;
}

// Maximum of longs
long max(long x[],const int& len)
{
    long maximum (x[0]);
    for(int i = 1; i < len; i++)
        if(maximum < x[i])
            maximum = x[i];
    return maximum;
}

// Maximum of doubles
double max(double x[],const int& len)
{
    double maximum(x[0]);
    for(int i = 1; i < len; i++)
        if(maximum < x[i])
            maximum = x[i];
    return maximum;
}

```

The example works as you would expect and produces this output:

34
2345
345.5

How It Works

You have three prototypes for the three overloaded versions of the function `max()`. In each of the three output statements, the appropriate version of the function `max()` is selected by the compiler based on the argument list types. This works because each of the versions of `max()` has a unique signature, because each parameter list is different from that of the others.

Reference Types and Overload Selection

When you use reference types for parameters in overloaded functions, you must take care to ensure the compiler can select an appropriate overload. Suppose you define functions with the following prototype:

```
void f(int n);  
void f(int& rn);
```

These functions are differentiated by the type of the parameter, but code using these will not compile. When you call `f()` with an argument of type `int`, the compiler has no means of determining which function should be selected because either function is equally applicable. In general, you cannot overload on a given type, `type`, and an lvalue reference to that type, `type&`.

However, the compiler can distinguish the overloaded functions with the following prototypes:

```
void f(int& arg);           // Lvalue reference parameter  
void f(int&& arg);         // Rvalue reference parameter
```

Even though for some argument types, either function could apply, the compiler adopts a preferred choice. The `f(int&)` function will always be selected when the argument is an lvalue. The `f(int&&)` version will be selected only when the argument is an rvalue. For example:

```
int num(5);  
f(num);           // Calls f(int&)  
f(2*num);        // Calls f(int&&)  
f(25);           // Calls f(int&&)  
f(num++);        // Calls f(int&&)  
f(++num);         // Calls f(int&)
```

Only the first and last statements call the overload with the lvalue reference parameter, because the other statements call the function with arguments that are rvalues.

NOTE The rvalue reference type parameter is intended primarily for addressing specific problems that you'll learn about when you look into defining classes.

When to Overload Functions

Function overloading provides you with the means of ensuring that a function name describes the function being performed and is not confused by extraneous information such as the type of data being processed. This is akin to what happens with basic operations in C++. To add two numbers, you use the same operator, regardless of the types of the operands. Our overloaded function `max()` has the same name, regardless of the type of data being processed. This helps to make the code more readable and makes these functions easier to use.

NOTE *The intent of function overloading is clear: to enable the same operation to be performed with different operands using a single function name. So, whenever you have a series of functions that do essentially the same thing, but with different types of arguments, you should overload them and use a common function name, or write a function template, which is coming up next.*

FUNCTION TEMPLATES

The last example was somewhat tedious in that you had to repeat essentially the same code for each function, but with different variable and parameter types. However, there is a way of avoiding this. You have the possibility of creating a recipe that will enable the compiler to automatically generate functions with various parameter types. The code defining the recipe for generating a particular group of functions is called a *function template*.

A function template has one or more *type parameters*, and you generate a particular function by supplying a concrete type argument for each of the template's parameters. Thus, the functions generated by a function template all have the same basic code, but customized by the type arguments that you supply. You can see how this works in practice by defining a function template for the function `max()` in the previous example.

Using a Function Template

You can define a template for the function `max()` as follows:

```
template<class T> T max(T x[], const int& len)
{
    T maximum(x[0]);
    for(int i = 1; i < len; i++)
        if(maximum < x[i])
            maximum = x[i];
    return maximum;
}
```

The `template` keyword identifies this as a template definition. The angled brackets following the `template` keyword enclose the type parameters that are used to create a particular instance of the function separated by commas; in this instance, you have just one type parameter, `T`. The

class keyword before the T indicates that the T is the type parameter for this template, class being the generic term for type. Later in the book, you will see that defining a class is essentially defining your own data type. Consequently, you have fundamental types in C++, such as type int and type char, and you also have the types that you define yourself. You can use the keyword typename instead of class to identify the parameters in a function template, in which case, the template definition would look like this:

```
template<typename T> T max(T x[], const int& len)
{
    T maximum(x[0]);
    for(int i = 1; i < len; i++)
        if(maximum < x[i])
            maximum = x[i];
    return maximum;
}
```

Some programmers prefer to use the typename keyword as the class keyword tends to connote a user-defined type, whereas typename is more neutral and, therefore, is more readily understood to imply fundamental types as well as user-defined types. In practice, you'll see both used widely.

Wherever T appears in the definition of a function template, it is replaced by the specific type argument, such as long, that you supply when you create an instance of the template. If you try this out manually by plugging in long in place of T in the template, you'll see that this generates a perfectly satisfactory function for calculating the maximum value from an array of type long:

```
long max(long x[], const int& len)
{
    long maximum(x[0]);
    for(int i = 1; i < len; i++)
        if(maximum < x[i])
            maximum = x[i];
    return maximum;
}
```

The creation of a particular function instance is referred to as *instantiation*. Each time you use max() in your program, the compiler checks to see if a function corresponding to the type of arguments that you have used in the function call already exists. If the function required does not exist, the compiler creates one by substituting the argument type that you have used in your function call in place of the parameter T throughout the template definition.

NOTE The compiler will only process a template definition if you use it in your code. This means that errors in the template will not be identified if you don't use it.

You could exercise the template for the max() function with the same main() function that you used in the previous example.

TRY IT OUT Using a Function Template

Here's a version of the previous example modified to use a template for the `max()` function:

```
// Ex6_08.cpp
// Using function templates

#include <iostream>
using std::cout;
using std::endl;

// Template for function to compute the maximum element of an array
template<typename T> T max(T x[], const int& len)
{
    T maximum(x[0]);
    for(int i = 1; i < len; i++)
        if(maximum < x[i])
            maximum = x[i];
    return maximum;
}

int main(void)
{
    int small[] = { 1, 24, 34, 22 };
    long medium[] = { 23, 245, 123, 1, 234, 2345 };
    double large[] = { 23.0, 1.4, 2.456, 345.5, 12.0, 21.0 };

    int lensmall(_countof(small));
    int lenmedium(_countof(medium));
    int lenlarge(_countof(large));

    cout << endl << max(small, lensmall);
    cout << endl << max(medium, lenmedium);
    cout << endl << max(large, lenlarge);

    cout << endl;
    return 0;
}
```

This program produces exactly the same output as the previous example.

How It Works

For each of the statements outputting the maximum value in an array, a new version of `max()` is instantiated using the template. Of course, if you add another statement calling the function `max()` with one of the types used previously, no new version of the template code is generated.

Using a template doesn't reduce the size of your compiled program in any way. The compiler generates a version of the source code for each unique function that you require. In fact, using templates can generally *increase* the size of your program, as functions may be created even though an existing version might satisfactorily be used by casting the argument. You can force the creation of particular instances of a template by explicitly including a declaration for it. For example, if you wanted to ensure

that an instance of the template for the function `max()` was created corresponding to the type `float`, you could place the following declaration after the definition of the template:

```
float max(float, const int&);
```

This forces the creation of this version of the function template. It does not have much value in the case of our program example, but it can be useful when you know that several versions of a template function might be generated, but you want to force the generation of a subset that you plan to use, with arguments cast to the appropriate type where necessary.

USING THE DECLTYPE OPERATOR

You use the `decltype` operator to obtain the type of an expression, so `decltype(exp)` is the type of the value that results from evaluating the expression `exp`. For example, you could write the following statements:

```
double x(100.0);
int n(5);
decltype(x*n) result(x*n);
```

The last statement specifies the type of `result` to be the type of the expression `x*n`, which is type `double`. While this shows the mechanics of what the `decltype` operator does, the primary use for the `decltype` operator is in defining function templates. Occasionally, the return type of a template function with multiple type parameters may depend on the types used to instantiate the template. Suppose you want to write a template function to multiply corresponding elements of two arrays, possibly of different types, and return the sum of these products. Because the types of the two arrays may be different, the type of the result will depend on the actual types of the array arguments, so you cannot specify a particular return type. The function template might notionally look like this:

```
template<class T1, class T2>
return_type f(T1 v1[], T2 v2[], const size_t& count)
{
    decltype(v1[0]*v2[0]) sum(0);
    for(size_t i = 0; i<count; i++) sum += v1[i]*v2[i];
    return sum;
}
```

`return_type` needs to be the type of the result of multiplying corresponding elements of the array arguments. The `decltype` operator can help, but unfortunately the following will not compile:

```
template<class T1, class T2>
decltype(v1[0]*v2[0]) f(T1 v1[], T2 v2[], size_t count) // Will not compile!
{
    decltype(v1[0]*v2[0]) sum(0);
    for(size_t i = 0; i<count; i++) sum += v1[i]*v2[i];
    return sum;
}
```

This specifies what you want, but the compiler cannot compile this because `v1` and `v2` are not defined at the point where the return type specification is processed.

It requires a different syntax to take care of it:

```
template<class T1, class T2>
auto f(T1 v1[], T2 v2[], const size_t& count) -> decltype(v1[0]*v2[0])
{
    decltype(v1[0]*v2[0]) sum(0);
    for(size_t i = 0; i<count; i++) sum += v1[i]*v2[i];
    return sum;
}
```

As you saw in Chapter 5, this is referred to as a *trailing return type*. You specify the return type using the `auto` keyword. The actual return type can be determined by the compiler when an instance of the template is created because, at that point, the parameters `v1` and `v2` have been parsed. The `decltype` expression following the `->` determines the return type for any instance of the template. Let's see if it works.

TRY IT OUT Using the decltype Operator

Here's a simple example to exercise the template you have just seen:

```
// Ex6_09.cpp Using the decltype operator
#include <iostream>
using std::cout;
using std::endl;

template<class T1, class T2>
auto product(T1 v1[], T2 v2[], const size_t& count) -> decltype(v1[0]*v2[0])
{
    decltype(v1[0]*v2[0]) sum(0);
    for(size_t i = 0; i<count; i++) sum += v1[i]*v2[i];
    return sum;
}

int main()
{
    double x[] = {100.5, 99.5, 88.7, 77.8};
    short y[] = {3, 4, 5, 6};
    long z[] = {11L, 12L, 13L, 14L};
    size_t n = 4;
    cout << "Result type is " << typeid(product(x, y, n)).name() << endl;
    cout << "Result is " << product(x, y, n) << endl;
    auto result = product(z, y, n);
    cout << "Result type is " << typeid(result).name() << endl;
    cout << "Result is " << result << endl;

    return 0;
}
```

This produces the following output:

```
Result type is double
Result is 1609.8
Result type is long
Result is 230
```

How It Works

The return types for functions generated from the `product()` function template are determined by the expression `decltype(v1[0]*v2[0])`. The first instantiations of the template in `main()` are due to the statements:

```
cout << "Result type is " << typeid(product(x, y, n)).name() << endl;
cout << "Result is " << product(x, y, n) << endl;
```

You can see from the output that the type of the value returned by the `product()` function instance is `type double` when the first two arguments are arrays of type `double` and type `short`, respectively, which is as it should be. Executing the next three statements shows that the type for the value returned is `type long` when the arguments are arrays of type `short` and `long`. You obtain the type of `result` where the `auto` keyword determines the type of the variable to be that of the value returned by `product()`. Clearly, the `decltype` operator is working exactly as advertised.

NOTE Of course, you can use the trailing return type syntax for any function so you can also use it when you define templates that do not require the use of `decltype`. For example, you could define the template for `max()` like this:

```
template<class T> auto max(T x[], const int& len) -> T
{
    T maximum(x[0]);
    for(int i = 1; i < len; i++)
        if(maximum < x[i])
            maximum = x[i];
    return maximum;
}
```

AN EXAMPLE USING FUNCTIONS

You have covered a lot of ground in C++ up to now and a lot on functions in this chapter alone. After wading through a varied menu of language capabilities, it's not always easy to see how they relate to one another. Now would be a good point to see how some of this goes together to produce something with more meat than a simple demonstration program.

Let's work through a more realistic example to see how a problem can be broken down into functions. The process involves defining the problem to be solved, analyzing the problem to see how it can be implemented in C++, and, finally, writing the code. The approach here is aimed at

illustrating how various functions go together to make up the final result, rather than providing a tutorial on how to develop a program.

Implementing a Calculator

Suppose you need a program that acts as a calculator; not one of these fancy devices with lots of buttons and gizmos designed for those who are easily pleased, but one for people who know where they are going, arithmetically speaking. You can really go for it and enter a calculation from the keyboard as a single arithmetic expression, and have the answer displayed immediately. An example of the sort of thing that you might enter is:

```
2*3.14159*12.6*12.6 / 2 + 25.2*25.2
```

To avoid unnecessary complications for the moment, you won't allow parentheses in the expression and the whole computation must be entered in a single line; however, to allow the user to make the input look attractive, you *will* allow spaces to be placed anywhere. The expression may contain the operators multiply, divide, add, and subtract represented by *, /, +, and -, respectively, and it will be evaluated with normal arithmetic rules, so that multiplication and division take precedence over addition and subtraction.

The program should allow as many successive calculations to be performed as required, and should terminate if an empty line is entered. It should also have helpful and friendly error messages.

Analyzing the Problem

A good place to start is with the input. The program reads in an arithmetic expression of any length on a single line, which can be any construction within the terms given. Because nothing is fixed about the elements making up the expression, you have to read it as a string of characters and then work out within the program how it's made up. You can decide arbitrarily that you will handle a string of up to 80 characters, so you could store it in an array declared within these statements:

```
const int MAX(80);           // Maximum expression length including '\0'  
char buffer[MAX];          // Input area for expression to be evaluated
```

To change the maximum length of the string processed by the program, you will only need to alter the initial value of `MAX`.

NOTE In Chapter 8 you'll learn about the `string` class that enables you to handle strings of any length without having to decide the length in advance.

You'll need to analyze the basic structure of the information that appears in the input string, so let's break it down step by step.

You will want to make sure that the input is as uncluttered as possible when you are processing it, so before you start analyzing the input string, you will get rid of any spaces in it. You can call the function that will do this `eatspaces()`. This function can work by stepping through the input

buffer — which is the array `buffer[]` — and shuffling characters up to overwrite any spaces. This process uses two indexes to the buffer array, `i` and `j`, which start out at the beginning of the buffer; in general, you'll store element `j` at position `i`. As you progress through the array elements, each time you find a space, you increment `j` but not `i`, so the space at position `i` gets overwritten by the next character you find at index position `j` that is not a space. Figure 6-2 illustrates the logic of this.




FIGURE 6-2

This process is one of copying the contents of the `buffer` array to itself, excluding any spaces. Figure 6-2 shows the `buffer` array before and after the copying process, and the arrows indicate which characters are copied and the position to which each character is copied.

When you have removed spaces from the input, you are ready to evaluate the expression. You define the `expr()` function that returns the value that results from evaluating the whole expression in the input buffer. To decide what goes on inside the `expr()` function, you need to look into the structure of the input in more detail. The add and subtract operators have the lowest precedence and so are evaluated last. You can think of the input string as comprising one or more *terms* connected by operators, which can be either the operator `+` or the operator `-`. You can refer to either operator as an `addop`. With this terminology, you can represent the general form of the input expression like this:

```
expression: term addop term ... addop term
```

The expression contains at least one `term` and can have an arbitrary number of following `addop term` combinations. In fact, assuming that you have removed all the blanks, there are only three legal possibilities for the character that follows each `term`:

- The next character is '`\0`', so you are at the end of the string.
- The next character is '`-`', in which case you should subtract the next `term` from the value accrued for the expression up to this point.
- The next character is '`+`', in which case you should add the value of the next `term` to the value of the expression accumulated so far.

If anything else follows a `term`, the string is not what you expect, so you'll throw an exception. Figure 6-3 illustrates the structure of a sample expression.




FIGURE 6-3

Next, you need a more detailed and precise definition of a `term`. A `term` is simply a series of numbers connected by either the operator `*` or the operator `/`. Therefore, a `term` (in general) looks like this:

```
term: number multop number ... multop number
```

`multop` represents either a multiply or a divide operator. You could define a `term()` function to return the value of a `term`. This needs to scan the string to a number first and then to look for a `multop` followed by another number. If a character is found that isn't a `multop`, the `term()` function assumes that it is an `addop` and returns the value that has been found up to that point.

The last thing you need to figure out before writing the program is how you recognize a number. To minimize the complexity of the code, you'll only recognize unsigned numbers; therefore, a number consists of a series of digits that optionally may be followed by a decimal point and some more digits. To determine the value of a number, you step through the buffer looking for digits. If you find anything that isn't a digit, you check whether it's a decimal point. If it's not a decimal point, it has nothing to do with a number, so you return what you have got. If you find a decimal point, you look for more digits. As soon as you find anything that's not a digit, you have the complete number and you return that. Imaginatively, you'll call the function to recognize a number and return its value `number()`. Figure 6-4 shows an example of how an expression breaks down into terms and numbers.




FIGURE 6-4

You now have enough understanding of the problem to write some code. You can work through the functions you need and then write a `main()` function to tie them all together. The first and, perhaps, easiest function to write is `eatspaces()`, which will eliminate spaces from the input string.

Eliminating Blanks from a String

You can write the prototype for the `eatspaces()` function as follows:

```
void eatspaces(char* str);           // Function to eliminate blanks
```

The function doesn't need to return any value because spaces can be eliminated from the string *in situ*, modifying the original string directly through the pointer that is passed as the argument. The process for eliminating spaces is very simple. You copy the string to itself, overwriting any spaces, as you saw earlier in this chapter.

You can define the function to do this as follows:

```
// Function to eliminate spaces from a string
void eatspaces(char* str)
{
    int i(0);                                // 'Copy to' index to string
    int j(0);                                // 'Copy from' index to string

    while((*(str + i) = *(str + j++)) != '\0') // Loop while character is not \0
        if(*(str + i) != ' ')
            i++;                                // Increment i as long as
                                            // character is not a space
    return;
}
```

How the Function Functions

All the action is in the `while` loop. The loop condition copies the string by moving the character at position `j` to the character at position `i`, and then increments `j` to the next character. If the character copied was '`\0`', you have reached the end of the string and you're done.

The only action in the loop statement is to increment `i` to the next character if the last character copied was not a blank. If it *is* a blank, `i` is not to be incremented and the blank can therefore be overwritten by the character copied on the next iteration.

That wasn't hard, was it? Next, you can try writing the function that returns the result of evaluating the expression.

Evaluating an Expression

The `expr()` function returns the value of the expression specified in a string that is supplied as an argument, so you can write its prototype as:

```
double expr(char* str);           // Function evaluating an expression
```

The function declared here accepts a string as an argument and returns the result as type double. Based on the structure for an expression that you worked out earlier, you can draw a logic diagram for the process of evaluating an expression, as shown in Figure 6-5.




FIGURE 6-5

Using this basic definition of the logic, you can now write the function:

```
// Function to evaluate an arithmetic expression
double expr(char* str)
{
    double value(0.0);                                // Store result here
    int index(0);                                     // Keeps track of current character position

    value = term(str, index);                         // Get first term

    for(;;)                                         // Indefinite loop, all exits inside
    {
        switch(*(str + index++))                   // Choose action based on current character
        {
            case '\0':                           // We're at the end of the string
                return value;                     // so return what we have got

            case '+':                           // + found so add in the
                value += term(str, index);       // next term
                break;

            case '-':                           // - found so subtract
                value -= term(str, index);       // the next term
                break;

            default:                          // If we reach here the string is junk
                char message[38] = "Expression evaluation error. Found: ";
                strncat_s(message, str + index - 1, 1); // Append the character
                throw message;
                break;
        }
    }
}
```

How the Function Functions

Considering this function is analyzing any arithmetic expression that you care to throw at it (as long as it uses our operator subset), it's not a lot of code. You define a variable `index` of type `int`, which keeps track of the current position in the string where you are working, and you initialize it to 0, which corresponds to the index position of the first character in the string. You also define a variable `value` of type `double` in which you'll accumulate the value of the expression that is passed to the function in the `char` array `str`.

Because an expression must have at least one term, the first action in the function is to get the value of the first term by calling the function `term()`, which you have yet to write. This actually places three requirements on the function `term()`:

- 1.** It should accept a `char*` and an `int` parameter, the second parameter being an index to the first character of the term in the string supplied through the first parameter.
- 2.** It should update the `index` value passed so that it references the string character following the last character of the term found.
- 3.** It should return the value of the term as type `double`.

The rest of the program is an indefinite `for` loop. Within the loop, the action is determined by a `switch` statement, which is controlled by the current character in the string. If it is a '+', you call the `term()` function to get the value of the next term in the expression and add it to the variable `value`. If it is a '-', you subtract the value returned by `term()` from the variable `value`. If it is a '\0', you are at the end of the string, so you return the current contents of the variable `value` to the calling program. If it is any other character, it shouldn't be there, so throw an exception. The exception is a string that has the offending character appended.

As long as either a '+' or a '-' is found, the loop continues. Each call to `term()` moves the value of the `index` variable to the character following the term that was evaluated, and this should be either another '+' or '-', or the end-of-string character '\0'. Thus, the function either terminates normally when '\0' is reached, or abnormally by throwing an exception.

You could also analyze an arithmetic expression using a recursive function. If you think about the definition of an expression slightly differently, you could specify it as being either a term, or a term followed by an expression. The definition here is recursive (i.e., the definition involves the item being defined), and this approach is very common in defining programming language structures. This definition provides just as much flexibility as the first, but using it as the base concept, you could arrive at a recursive version of `expr()` instead of using a loop as you did in the implementation of `expr()`. You might want to try this alternative approach as an exercise after you have completed the first version.

Getting the Value of a Term

The `term()` function returns a value for a term as type `double` and receives two arguments: the string being analyzed and an index to the current position in the string. There are other ways of doing this, but this arrangement is quite straightforward. The prototype of the function `term()` is:

```
double term(char* str, int& index);           // Function analyzing a term
```

The second parameter is a reference. This is because you want the function to be able to modify the value of the `index` variable in the calling program to position it at the character following the last character of the term found in the input string. You could return `index` as a value, but then you would need to return the value of the term in some other way, so this arrangement seems quite natural.

The logic for analyzing a term is going to be similar to that for an expression. A term is a number, potentially followed by one or more combinations of a multiply or a divide operator and another number. You can write the definition of the `term()` function as:

```
// Function to get the value of a term
double term(char* str, int& index)
{
    double value(0.0);                      // Somewhere to accumulate
                                                // the result

    value = number(str, index);              // Get the first number in the term

    // Loop as long as we have a good operator
    while(true)
```

```
{  
    if(*(str + index) == '*')           // If it's multiply,  
        value *= number(str, ++index); // multiply by next number  
  
    else if(*(str + index) == '/')      // If it's divide,  
        value /= number(str, ++index); // divide by next number  
    else  
        break;  
}  
return value;                         // We've finished, so return what  
                                      // we've got  
}
```

How the Function Functions

You first declare a local `double` variable, `value`, in which you'll accumulate the value of the current term. Because a term must contain at least one number, the first action is to obtain the value of the first number by calling the `number()` function and storing the result in `value`. The code implicitly assumes that `number()` accepts the string and an index to a position in the string as arguments, and returns the value of the number found. Because the `number()` function must also update the index to the string to the position after a number is found, you'll again specify the second parameter for the function as a reference.

The rest of the `term()` function is a `while` loop that continues as long as the next character is '*' or '/'. Within the loop, if the character found at the current position is '*', you increment `index` to position it at the beginning of the next number, call the function `number()` to get the value of the next number, and then multiply the contents of `value` by the value returned. In a similar manner, if the current character is '/', you increment `index` and divide the contents of `value` by the value returned from `number()`. Because `number()` automatically alters the value of `index` to the character following the number found, `index` is already set to select the next available character in the string on the next iteration. The loop terminates when a character other than a multiply or divide operator is found, whereupon the current value of the term accumulated in the variable `value` is returned to the calling program.

The last analytical function that you require is `number()`, which determines the numerical value of any number appearing in the string.

Analyzing a Number

Based on the way you have used the `number()` function within the `term()` function, you need to declare it with this prototype:

```
double number(char* str, int& index); // Function to recognize a number
```

The specification of the second parameter as a reference allows the function to update the argument in the calling program directly, which is what you require.

You can make use of a function provided by the standard library here. The `cctype` header file provides definitions for a range of functions for testing single characters. These functions return

values of type `int` where nonzero values correspond to `true` and zero corresponds to `false`. Four of these functions are shown in the following table:

FUNCTIONS	DESCRIPTION
<code>int isalpha(int c)</code>	Returns nonzero if the argument is alphabetic; otherwise, returns 0
<code>int isupper(int c)</code>	Returns nonzero if the argument is an uppercase letter; otherwise, returns 0.
<code>int islower(int c)</code>	Returns nonzero if the argument is a lowercase letter; otherwise, returns 0.
<code>int isdigit(int c)</code>	Returns nonzero if the argument is a digit; otherwise, returns 0.

NOTE A number of other functions are provided by the `cctype` header but I won't grind through all the details. If you're interested, you can look them up in the Visual C++ Help. A search on "is routines" should find them.

You only need the last of the functions shown in the table in the program. Remember that `isdigit()` is testing a character, such as the character '9' (ASCII character 57 in decimal notation) for instance, not a numeric 9, because the input is a string. You can define the function `number()` as:

```
// Function to recognize a number in a string
double number(char* str, int& index)
{
    double value(0.0);                                // Store the resulting value

    // There must be at least one digit...
    if(!isdigit(*(str + index)))
    { // There's no digits so input is junk...
        char message[31] = "Invalid character in number: ";
        strncat_s(message, str+index, 1); // Append the character
        throw message;
    }

    while(isdigit(*(str + index)))                  // Loop accumulating leading digits
        value = 10*value + (*str + index++) - '0';

        // Not a digit when we get to here
        if(*(str + index) != '.')                  // so check for decimal point
```

```
    return value;                                // and if not, return value

    double factor(1.0);                         // Factor for decimal places
    while(isdigit(*(str + (++index))))          // Loop as long as we have digits
    {
        factor *= 0.1;                          // Decrease factor by factor of 10
        value = value + (*(str + index) - '0')*factor; // Add decimal place
    }

    return value;                                // On loop exit we are done
}
```

How the Function Functions

You declare the local variable `value` as type `double` that holds the value of the number that is found. You initialize it with 0.0 because you add in the digit values as you go along. There must always be at least one digit present for the number to be valid, so the first step is to verify that this is the case. If there is no initial digit, the input is badly formed, so you throw an exception that identifies the problem and the erroneous character.

A number in the string is a series of digits as ASCII characters so the function steps through the string accumulating the value of the number digit by digit. This occurs in two phases — the first phase accumulates digits before the decimal point; then, if you find a decimal point, the second phase accumulates the digits after it.

The first step is in the `while` loop that continues as long as the current character selected by the variable `index` is a digit. The value of the digit is extracted and added to the variable `value` in the loop statement:



```
value = 10*value + (*(str + index++) - '0');
```

The way this is constructed bears a closer examination. A digit character has an ASCII value between 48, corresponding to the digit 0, and 57, corresponding to the digit 9. Thus, if you subtract the ASCII code for '0' from the code for a digit, you convert it to its equivalent numeric digit value from 0 to 9. You have parentheses around the subexpression:

```
*(str + index++) - '0'
```

These are not essential, but they do make what's going on a little clearer. The contents of `value` are multiplied by 10 to shift the value one decimal place to the left before adding in the digit value, because you'll find digits from left to right — that is, the most significant digit first. This process is illustrated in Figure 6-6.

As soon as you come across something other than a digit, it is either a decimal point or something else. If it's not a decimal point, you've finished, so you return the current contents of `value` to the calling program. If it is a decimal point, you accumulate the digits corresponding to the fractional part of the number in the second loop. In this loop, you use the `factor` variable, which has the initial value 1.0, to set the decimal place for the current digit, and, consequently, `factor` is multiplied by 0.1 for each digit found. Thus, the first digit after the decimal point is multiplied by 0.1, the second by 0.01, the third by 0.001, and so on. This process is illustrated in Figure 6-7.

**FIGURE 6-6****FIGURE 6-7**

As soon as you find a non-digit character, you are done, so after the second loop you return `value`. You almost have the whole thing now. You just need a `main()` function to read the input and drive the process.

Putting the Program Together

You can collect the `#include` statements together and assemble the function prototypes at the beginning of the program for all the functions used in this program:

```
// Ex6_10.cpp
// A program to implement a calculator

#include <iostream>                                // For stream input/output
#include <cstdlib>                                 // For the exit() function
#include <cctype>                                  // For the isdigit() function
using std::cin;
using std::cout;
using std::cerr;
using std::endl;

void eatspaces(char* str);                         // Function to eliminate blanks
double expr(char* str);                           // Function evaluating an expression
double term(char* str, int& index);               // Function analyzing a term
double number(char* str, int& index);              // Function to recognize a number

const int MAX(80);                                // Maximum expression length,
                                                // including '\0'
```

You have also defined a global variable `MAX`, which is the maximum number of characters in the expression processed by the program (including the terminating '`\0`' character).

Now, you can add the definition of the `main()` function, and your program is complete. The `main()` function should read a string and exit if it is empty; otherwise, call the function `expr()` to evaluate the input and display the result. This process should repeat indefinitely. That doesn't sound too difficult, so let's give it a try.

```
int main()
{
    char buffer[MAX] = {0};      // Input area for expression to be evaluated

    cout << endl
        << "Welcome to your friendly calculator."
        << endl
        << "Enter an expression, or an empty line to quit."
        << endl;

    for(;)

    {
        cin.getline(buffer, sizeof buffer);          // Read an input line
        eatspaces(buffer);                          // Remove blanks from input

        if(!buffer[0])                            // Empty line ends calculator
            return 0;

        try
        {
            cout << "\t= " << expr(buffer)           // Output value of expression
            << endl << endl;
        }
    }
}
```

```

        catch( const char* pEx)
    {
        cerr << pEx << endl;
        cerr << "Ending program." << endl;
        return 1;
    }
}
}
}

```

How the Function Functions

In `main()`, you set up the `char` array, `buffer`, to accept an expression up to 80 characters long (including the string termination character). The expression is read within the indefinite `for` loop using the `getline()` function. After obtaining the input, spaces are removed from the string by calling the function `eatspaces()`.

All the other things that `main()` provides for are also within the loop. It checks for an empty string, which consists of just the null character, '`\0`', in which case the program ends. It also outputs the value returned by the `expr()` function. The statement that does this is in a `try` block, because both the `expr()` function and the `number()` function that it calls indirectly can throw an exception when things go wrong. The exception thrown by both functions is of the same type. The `catch` block will catch exceptions of type `const char*` so it will catch an exception thrown by either function. When an exception is thrown, the `catch` block outputs the string that is the exception and ends the program.

After you add all the function definitions to the code and compile and run it, you should get output similar to the following:

```

2 * 35
      = 70
2/3 + 3/4 + 4/5 + 5/6 + 6/7
      = 3.90714
1 + 2.5 + 2.5*2.5 + 2.5*2.5*2.5
      = 25.375

```

You can enter as many calculations as you like, and when you are fed up with it, just press Enter to end the program. If you want to see the error handling in action, just enter an invalid expression. Be sure to execute the release version of the program when you are doing this, otherwise you will get an error reported by the debug code.

Extending the Program

Now that you have got a working calculator, you can start to think about extending it. Wouldn't it be nice to be able to handle parentheses in an expression? It can't be that difficult, can it? Let's give it a try.

Think about the relationship between something in parentheses that might appear in an expression and the kind of expression analysis that you have made so far. Look at an example of the kind of expression you want to handle:

$$2*(3 + 4) / 6 - (5 + 6) / (7 + 8)$$

Notice that an expression between parentheses always forms part of a `term` in our original parlance. Whatever sort of computation you come up with, this is always true. In fact, if you could substitute

the value of the expressions within parentheses back into the original string, you would have something that you can already deal with. This indicates a possible approach to handling parentheses. You might be able to treat an expression in parentheses as just another number, and modify the `number()` function to sort out the value of whatever appears between the parentheses.

That sounds like a good idea, but “sorting out” the expression in parentheses requires a bit of thought: the clue to success is in the terminology used here. An expression that appears within parentheses is a perfectly good example of a full-blown expression, and you already have the `expr()` function that will return the value of an expression. If you can get the `number()` function to work out what lies between the parentheses and extract those from the string, you could pass the substring that results to the `expr()` function, and recursion would really simplify the problem. What’s more, you don’t need to worry about nested parentheses. Any set of parentheses contains what you have defined as an expression, so nested parentheses are taken care of automatically. Recursion wins again.

Let’s take a stab at rewriting `number()` to recognize an expression between parentheses:

```
// Function to recognize an expression in parentheses
// or a number in a string
double number(char* str, int& index)
{
    double value(0.0);                                // Store the resulting value

    if(*(str + index) == '(')                         // Start of parentheses
    {
        char* psubstr(nullptr);                      // Pointer for substring
        psubstr = extract(str, ++index);             // Extract substring in brackets
        value = expr(psubstr);                       // Get the value of the substring
        delete[] psubstr;                            // Clean up the free store
        return value;                               // Return substring value
    }

    // There must be at least one digit...
    if(!isdigit(*(str + index)))
    { // There's no digits so input is junk...
        char message[31] = "Invalid character in number: ";
        strncat_s(message, str+index, 1); // Append the character
        throw message;
    }

    while(isdigit(*(str + index)))                  // Loop accumulating leading digits
        value = 10*value + (*(str + index++) - '0');
        // Not a digit when we get to here
    if(*(str + index)!='.')
        // so check for decimal point
        // and if not, return value
        return value;

    double factor(1.0);                            // Factor for decimal places
    while(isdigit(*(str + (++index))))           // Loop as long as we have digits
    {
        factor *= 0.1;                           // Decrease factor by factor of 10
        value = value + (*(str + index) - '0')*factor; // Add decimal place
    }
    return value;                                 // On loop exit we are done
}
```

This is not yet complete, because you still need the `extract()` function, but you'll fix that in a moment.

How the Function Functions

Very little has been changed to support parentheses. I suppose it is a bit of a cheat, because you use the `extract()` function that you haven't written yet, but for one extra function, you get as many levels of nested parentheses as you want. This really is icing on the cake, and it's all down to the magic of recursion!

The first thing that `number()` does now is to test for a left parenthesis. If it finds one, it calls another function, `extract()` to extract the substring between the parentheses from the original string. The address of this new substring is stored in the pointer `psubstr`, so you then apply the `expr()` function to the substring by passing this pointer as an argument. The result is stored in `value`, and after releasing the memory allocated on the free store in the `extract()` function (as you will eventually implement it), you return the value obtained for the substring as though it were a regular number. Of course, if there is no left parenthesis to start with, the function `number()` continues exactly as before.

Extracting a Substring

You now need to write the `extract()` function. It's not difficult, but it's also not trivial. The main complication comes from the fact that the expression within parentheses may also contain other sets of parentheses, so you can't just go looking for the first right parenthesis after you find a left parenthesis. You must watch out for more left parentheses as well, and for every one that you find, ignore the corresponding right parenthesis. You can do this by maintaining a count of left parentheses as you go along, adding one to the count for each left parenthesis you find. If the left parenthesis count is not zero, you subtract one for each right parenthesis. Of course, if the left parenthesis count is zero and you find a right parenthesis, you're at the end of the substring. The mechanism for extracting a parenthesized substring is illustrated in Figure 6-8.




FIGURE 6-8

Because the string you extract here contains subexpressions between parentheses, eventually `extract()` is called again to deal with those.

The `extract()` function also needs to allocate memory for the substring and return a pointer to it. Of course, the index to the current position in the original string must end up selecting the character following the substring, so the parameter for that should be specified as a reference. Thus the prototype of `extract()` is:

```
char* extract(char* str, int& index); //Function to extract a substring
```

You can now have a shot at the definition of the function:

```
// Function to extract a substring between parentheses
// (requires cstring header file)
char* extract(char* str, int& index)
{
    char* pstr(nullptr);           // Pointer to new string for return
    int numL(0);                  // Count of left parentheses found
    int bufindex(index);          // Save starting value for index

    do
    {
        switch(*(str + index))
        {
            case ')':
                if(0 == numL)
                {
                    ++index;
                    pstr = new char[index - bufindex];
                    if(!pstr)
                    {
                        throw "Memory allocation failed.";
                    }
                    // Copy substring to new memory
                    strncpy_s(pstr, index-bufindex, str+bufindex, index-bufindex-1);

                    return pstr;           // Return substring in new memory
                }
                else
                {
                    numL--;             // Reduce count of '(' to be matched
                    break;
                }
            case '(':
                numL++;              // Increase count of '(' to be
                // matched
                break;
        }
    } while(* (str + index++) != '\0'); // Loop - don't overrun end of string

    throw "Ran off the end of the expression, must be bad input.";
}
```

How the Function Functions

You declare a pointer to a string, `pstr`, that will eventually point to the substring that you will return. You declare a counter `numL` to keep track of left parentheses in the substring. The initial value of `index` (when the function begins execution) is stored in the variable `bufindex`. You use this in combination with incremented values of `index` to determine the range of characters to be extracted from `str` and returned.

The executable part of the function is basically one big `do-while` loop that walks through `str` looking for parentheses. You check for left or right parentheses during each cycle. If a left parenthesis is found, `numL` is incremented, and if a right parenthesis is found and `numL` is non-zero, it is decremented. When you find a right parenthesis and `numL` is zero, you have found the end of the substring. Sufficient memory is obtained on the heap to hold the substring and the address is stored in `pstr`. The substring that you want from `str` is then copied to the memory that you obtained through the operator `new` by using the `strncpy_s()` function that is declared in the `cstring` header. This function copies the string specified by the third argument, `str+bufindex`, to the address specified by the first argument, `pstr`. `str+bufindex` is a pointer to the character in `str` where the substring starts. The second argument is the length of the destination string, `pstr` and the fourth argument is the number of characters to be copied from the source string.

If you fall through the bottom of the loop, it means that you hit the '`\0`' at the end of the expression in `str` without finding the complementary right bracket, so you throw an exception that will be caught in `main()`.

Running the Modified Program

After replacing the `number()` function in the old version of the program, adding the `#include` directive for `cstring`, and incorporating the prototype and the definition for the new `extract()` function you have just written, you're ready to roll with an all-singing, all-dancing calculator. If you have assembled all that without error, you can get output like this:

```
Welcome to your friendly calculator.
Enter an expression, or an empty line to quit.
1/(1+1/(1+1/(1+1)))
    = 0.6
(1/2-1/3)*(1/3-1/4)*(1/4-1/5)
    = 0.000694444
3.5*(1.25-3/(1.333-2.1*1.6))-1
    = 8.55507
2,4-3.4
Arrrgh!*#! There's an error
```

The friendly and informative error message in the last output line is due to the use of the comma instead of the decimal point in the expression above it, in what should be 2.4. As you can see, you get nested parentheses to any depth with a relatively simple extension of the program, all due to the amazing power of recursion.

SUMMARY

You now have a reasonably comprehensive knowledge of writing and using functions, and you have used overloading to implement a set of functions providing the same operation with different types of parameters. You have also seen how you can define function templates that you can use to generate different versions of essentially the same function. You'll see more about overloading functions in the following chapters.

You also got some experience of using several functions in a program by working through the calculator example. But remember that all the uses of functions up to now have been in the context of a traditional procedural approach to programming. When you come to look at object-oriented programming, you will still use functions extensively, but with a very different approach to program structure and to the design of the solution to a problem.

EXERCISES

1. Consider the following function:

```
int ascVal(size_t i, const char* p)
{
    // Return the ASCII value of the char
    if (!p || i > strlen(p))
        return -1;
    else
        return p[i];
}
```

Write a program that will call this function through a pointer and verify that it works. You'll need an `#include` directive for the `cstring` header in your program to use the `strlen()` function.

2. Write a family of overloaded functions called `equal()`, which take two arguments of the same type, returning 1 if the arguments are equal, and 0 otherwise. Provide versions having `char`, `int`, `double`, and `char*` arguments. (Use the `strcmp()` function from the runtime library to test for equality of strings. If you don't know how to use `strcmp()`, search for it in the online help. You'll need an `#include` directive for the `cstring` header file in your program.) Write test code to verify that the correct versions are called.
3. At present, when the calculator hits an invalid input character, it prints an error message, but doesn't show you where the error was in the line. Write an error routine that prints out the input string, putting a caret (^) below the offending character, like this:

```
12 + 4,2*3
^
```
4. Add an exponentiation operator, `^`, to the calculator, fitting it in alongside `*` and `/`. What are the limitations of implementing it in this way, and how can you overcome them?

5. (Advanced) Extend the calculator so it can handle trig and other math functions, allowing you to input expressions such as:

```
2 * sin(0.6)
```

The math library functions all work in radians; provide versions of the trigonometric functions so that the user can use degrees, for example:

```
2 * sind(30)
```

► WHAT YOU LEARNED IN THIS CHAPTER

TOPIC	CONCEPT
Pointers to functions	A pointer to a function stores the address of a function, plus information about the number and types of parameters and return type for a function.
Exceptions	An exception is a way of signaling an error in a program so that the error handling code can be separated from the code for normal operations.
Throwing exceptions	You throw an exception with a statement that uses the keyword <code>throw</code> .
try blocks	Code that may throw exceptions should be placed in a <code>try</code> block, and the code to handle a particular type of exception is placed in a <code>catch</code> block immediately following the <code>try</code> block. There can be several <code>catch</code> blocks following a <code>try</code> block, each catching a different type of exception.
Overloaded functions	Overloaded functions are functions with the same name, but with different parameter lists.
Calling an overloaded function	When you call an overloaded function, the function to be called is selected by the compiler based on the number and types of the arguments that you specify.
Function templates	A function template is a recipe for generating overloaded functions automatically.
Function template parameters	A function template has one or more parameters that are type variables. An instance of the function template — that is, a function definition — is created by the compiler for each function call that corresponds to a unique set of type arguments for the template.
Function template instances	You can force the compiler to create a particular instance from a function template by specifying the function you want in a prototype declaration.
The decltype operator	You use the <code>decltype</code> operator to determine the type of the result of an expression.
Trailing return types	When a function template has a return type that depends on the arguments types, you can specify the return type using the <code>auto</code> keyword and define the return type using the <code>decltype</code> operator following <code>-></code> after the function header.

7

Defining Your Own Data Types

WHAT YOU WILL LEARN IN THIS CHAPTER:

- How structures are used
- How classes are used
- The basic components of a class and how you define class types
- How to create, and use, objects of a class
- How to control access to members of a class
- How to create constructors
- The default constructor
- References in the context of classes
- How to implement the copy constructor

WROX.COM CODE DOWNLOADS FOR THIS CHAPTER

You can find the wrox.com code downloads for this chapter on the Download Code tab at www.wrox.com/remtitle.cgi?isbn=9781118368084. The code is in the Chapter 7 download and individually named according to the names throughout the chapter.

THE STRUCT IN C++

This chapter is about creating your own data types to suit your particular problem. It's also about creating objects, the building blocks of object-oriented programming. An object can seem a bit mysterious to the uninitiated, but as you will see in this chapter, an object can be just an instance of one of your own data types.

A structure is a user-defined type that you define using the `struct` keyword so it is often referred to as a struct. The `struct` originated back in the C language, and C++ incorporates and expands on the C `struct`. A `struct` in C++ is functionally replaceable by a class insofar as anything you can do with a `struct`, you can also achieve by using a class; however, because Windows was written in C before C++ became widely used, the `struct` appears pervasively in Windows programming. It is also widely used today, so you really need to know something about structs. You'll first take a look at (C-style) structs in this chapter before exploring the more extensive capabilities offered by classes.

What Is a struct?

Almost all the variables that you have seen up to now have been able to store a single type of entity — a number of some kind, a character, or an array of elements of the same type. The real world is a bit more complicated than that, and just about any physical object you can think of needs several items of data to describe it even minimally. Think about the information that might be needed to describe something as simple as a book. You might consider title, author, publisher, date of publication, number of pages, price, topic or classification, and ISBN number, just for starters, and you can probably come up with a few more without too much difficulty. You could specify separate variables to contain each of the parameters that you need to describe a book, but ideally, you would want to have a single data type, `BOOK`, say, which embodied all of these parameters. I'm sure you won't be surprised to hear that this is exactly what a `struct` can do for you.

Defining a struct

Let's stick with the notion of a book, and suppose that you just want to include the title, author, publisher, and year of publication within your definition of a book. You could declare a structure to accommodate this as follows:

```
struct BOOK
{
    char Title[80];
    char Author[80];
    char Publisher[80];
    int Year;
};
```

This doesn't define any variables, but it does define a new type for variables, and the name of the type is `BOOK`. The `struct` keyword defines `BOOK` as such, and the elements making up an object of this type are defined within the braces. Note that each line defining an element in the `struct` is terminated by a semicolon, and that a semicolon also appears after the closing brace. The elements of a `struct` can be of any type, except the same type as the `struct` being defined. You couldn't have an element of type `BOOK` included in the structure definition for `BOOK`, for example. You may think this is a limitation, but note that you could include a pointer of type `BOOK*`, as you'll see a little later on.

The elements `Title`, `Author`, `Publisher`, and `Year` enclosed between the braces in the preceding definition are referred to as *members* or *fields* of the `BOOK` structure. An object of type `BOOK` is called an *instance* of the class type. Every object of type `BOOK` contains its own set of the members

Title, Author, Publisher, and Year. You can now create variables of type BOOK in exactly the same way as you create variables of any other type:

```
BOOK Novel; // Declare variable Novel of type BOOK
```

This declares a variable with the name Novel that you can now use to store information about a book. All you need now is to understand how you get data into the various members that make up a variable of type BOOK.

Initializing a struct

The first way to get data into the members of a struct object is to define initial values for them in the declaration of the object. Suppose you wanted to initialize Novel to contain the data for one of your favorite books, *Paneless Programming*, published in 1981 by the Gutter Press. This is a story of a guy performing heroic code development while living in an igloo, and, as you probably know, inspired the famous Hollywood box office success, *Gone with the Window*. It was written by I.C. Fingers, who is also the author of that seminal three-volume work, *The Connoisseur's Guide to the Paper Clip*. With this wealth of information, you can write the declaration for Novel as:

```
BOOK Novel =
{
    "Paneless Programming", // Initial value for Title
    "I.C. Fingers", // Initial value for Author
    "Gutter Press", // Initial value for Publisher
    1981 // Initial value for Year
};
```

The initializing values appear between braces and separated by commas, in much the same way that you defined initial values for elements of an array. As with arrays, the sequence of initial values obviously needs to be the same as the sequence of the members of the struct in its definition. Each member of the Novel structure has the corresponding initial value assigned to it, as indicated in the comments.

Accessing the Members of a struct

To access individual members of a struct, you use the *member selection operator*, which is a period; this is sometimes referred to as the *member access operator*. To refer to a member, you write the struct variable name, followed by a period, followed by the name of the member. To change the Year member of the Novel structure, you could write:

```
Novel.Year = 1988;
```

This sets the value of the Year member to 1988. You can use a member of a struct in exactly the same way as any other variable of the same type as the member. To increment the member year by two, for example, you can write:

```
Novel.Year += 2;
```

This increments the value of the year member of Novel, just like any other variable.

TRY IT OUT Using structs

This example shows how referencing the members of a `struct` works. Suppose you want to write a program to deal with some of the things you might find in a yard, such as those illustrated in the professionally landscaped yard in Figure 7-1.




FIGURE 7-1

I have arbitrarily assigned the coordinates 0,0 to the top-left corner of the yard. The bottom-right corner has the coordinates 100,120. Thus, the first coordinate value is a measure of the horizontal position relative to the top-left corner, with values increasing from left to right, and the second coordinate is a measure of the vertical position from the same reference point, with values increasing from top to bottom. Figure 7-1 also shows the position of the pool and those of the two huts relative to the top-left

corner of the yard. Because the yard, huts, and pool are all rectangular, you could define a `struct` type to represent any of these objects:

```
struct RECTANGLE
{
    int Left;                      // Top-left point
    int Top;                        // coordinate pair

    int Right;                     // Bottom-right point
    int Bottom;                    // coordinate pair
};
```

The first two members of the `RECTANGLE` structure type correspond to the coordinates of the top-left point of a rectangle, and the next two to the coordinates of the bottom-right point. You can use this in an elementary example representing rectangular objects in the yard:

```
// Ex7_01.cpp
// Exercising structures in the yard
#include <iostream>
using std::cout;
using std::endl;

// Definition of a struct to represent rectangles
struct RECTANGLE
{
    int Left;                      // Top-left point
    int Top;                        // coordinate pair

    int Right;                     // Bottom-right point
    int Bottom;                    // coordinate pair
};

// Prototype of function to calculate the area of a rectangle
long Area(const RECTANGLE& aRect);

// Prototype of a function to move a rectangle
void MoveRect(RECTANGLE& aRect, const int& x, const int& y);

int main(void)
{
    RECTANGLE Yard = { 0, 0, 100, 120 };
    RECTANGLE Pool = { 30, 40, 70, 80 };
    RECTANGLE Hut1, Hut2;

    Hut1.Left = 70;
    Hut1.Top = 10;
    Hut1.Right = Hut1.Left + 25;
    Hut1.Bottom = 30;

    Hut2 = Hut1;                  // Define Hut2 the same as Hut1
    MoveRect(Hut2, 10, 90);       // Now move it to the right position

    cout << endl
```

```
<< "Coordinates of Hut2 are "
<< Hut2.Left << "," << Hut2.Top << " and "
<< Hut2.Right << "," << Hut2.Bottom;

cout << endl
    << "The area of the yard is " << Area(Yard);

cout << endl
    << "The area of the pool is " << Area(Pool) << endl;

return 0;
}

// Function to calculate the area of a rectangle
long Area(const RECTANGLE& aRect)
{
    return (aRect.Right - aRect.Left)*(aRect.Bottom - aRect.Top);
}

// Function to Move a Rectangle
void MoveRect(RECTANGLE& aRect, const int& x, const int& y)
{
    int length(aRect.Right - aRect.Left);           // Get length of rectangle
    int width(aRect.Bottom - aRect.Top);            // Get width of rectangle

    aRect.Left = x;                                // Set top-left point
    aRect.Top = y;                                 // to new position
    aRect.Right = x + length;                      // Get bottom-right point as
    aRect.Bottom = y + width;                      // increment from new position
    return;
}
```

The output from this example is:

```
Coordinates of Hut2 are 10,90 and 35,110
The area of the yard is 12000
The area of the pool is 1600
```

How It Works

Note that the `struct` definition appears at global scope in this example. You'll be able to see it in the Class View tab for the project. Putting the definition of the `struct` at global scope allows you to declare a variable of type `RECTANGLE` anywhere in the `.cpp` file. In a larger program, such definitions would be stored in an `.h` file that would be added to each `.cpp` file where necessary using an `#include` directive.

You have defined two functions to process `RECTANGLE` objects. The `Area()` function calculates the area of the `RECTANGLE` object that you pass as a reference argument as the product of the length and the width, where the length is the difference between the horizontal positions of the defining points, and the width is the difference between the vertical positions of the defining points. The parameter is `const`

because the function does not change the argument that is passed to it. By passing a reference, the code runs a little faster because the argument is not copied. The `MoveRect()` function modifies the defining points of a `RECTANGLE` object to position it at the coordinates `x`, `y`, which are passed as reference arguments.

The position of a `RECTANGLE` object is assumed to be the position of the `Left`, `Top` point. Because the `RECTANGLE` object is passed as a reference, the function can modify the members of the `RECTANGLE` object directly. After calculating the length and width of the `RECTANGLE` object passed, the `Left` and `Top` members are set to `x` and `y`, respectively, and the new `Right` and `Bottom` members are calculated by incrementing `x` and `y` by the length and width of the original `RECTANGLE` object.

In the `main()` function, you initialize the `Yard` and `Pool` variables with their coordinate positions, as shown in Figure 7-1. The `Hut1` variable represents the hut at the top-right in the illustration, and its members are set to the appropriate values using assignment statements. The `Hut2` variable, corresponding to the hut at the bottom-left of the yard, is first set to be the same as `Hut1` in the assignment statement:


```
Hut2 = Hut1; // Define Hut2 the same as Hut1
```

This copies the values of the members of `Hut1` to the corresponding members of `Hut2`. You can only assign a `struct` of a given type to another of the same type. You can't increment a `struct` directly or use a `struct` in an arithmetic expression.

To alter the position of `Hut2` to its place at the bottom-left of the yard, you call the `MoveRect()` function with the coordinates of the required position as arguments. This roundabout way of getting the coordinates of `Hut2` is totally unnecessary, and serves only to show how you can use a `struct` as an argument to a function.

IntelliSense Assistance with Structures

The editor in Visual C++ is quite intelligent — it knows the types of variables, for instance. This is because of the IntelliSense feature. If you hover the mouse cursor over a variable name in the editor window, it pops up a little box showing its type. It also can help a lot with structures (and classes, as you will see) because not only does it know the types of ordinary variables, it also knows the members that belong to a variable of a particular structure type. As you type the member selection operator following a structure variable name, the editor pops up a window showing the list of members. If you click one of the members, it shows the member definition including the comment that appeared in the original definition of the structure, so you know what it is. This is shown in Figure 7-2, using a fragment of the previous example.

**FIGURE 7-2**

Now, there's a real incentive to add comments, and to keep them short and to the point. If you double-click on a member in the list or press the Enter key when the item is highlighted, it is automatically inserted after the member selection operator, thus eliminating one source of typos in your code. Great, isn't it?

You can turn any or all of the IntelliSense features off. To turn the IntelliSense features on or off, first select Options from the Tools menu. Expand the Text Editor tree in the left pane of the dialog that displays by clicking the [unfilled] symbol, then click the [unfilled] symbol alongside C/C++. Click on the Advanced option and you will see the IntelliSense options displayed in the right pane. Setting an option to false turns it off. One feature I recommend that you do change is the one named Member List Commit Characters. With the default list of characters as the value for this feature, you'll find that normal entry of code will have spurious things inserted. For example, typing the sequence `i = n;` will result in `i = namespace;` which can be irritating to say the least. I suggest that you delete the entire set of characters in the value column for this feature.

The editor also shows the parameter list for a function when you are typing the code to call it — it pops up as soon as you enter the left parenthesis for the argument list. This is particularly helpful with library functions, as it's tough to remember the parameter list for all of them. Of course, the `#include` directive for the header file must already be there in the source code for this to work. Without it, the editor has no idea what the library function is. Also, beware of omitting the `std` namespace prefix when you have also failed to include a `using` statement for a library function; the editor won't recognize the function. You will see more things that the editor can help with as you learn more about classes.

After that interesting little diversion, let's get back to structures.

The struct RECT

Rectangles are used a great deal in Windows programs. For this reason, there is a `RECT` structure predefined in the `winddef.h` header file that is included into `windows.h`. Its definition is essentially the same as the structure that you defined in the last example:

```
struct RECT
{
    LONG left;                      // Top-left point
    LONG top;                       // coordinate pair

    LONG right;                     // Bottom-right point
    LONG bottom;                    // coordinate pair
};
```

Type `LONG` is a Windows type that is equivalent to the fundamental type `long`. This `struct` is usually used to define rectangular areas on your display for a variety of purposes. Because `RECT` is used so extensively, `windows.h` also contains prototypes for a number of functions to manipulate and modify rectangles. For example, it declares the `InflateRect()` function that increases the size of a rectangle, and the `EqualRect()` function that compares two rectangles.

The MFC also defines a `CRect` class, which is the equivalent of a `RECT` structure. After you understand classes, you will be using this rather than the `RECT` structure. The `CRect` class provides a very extensive range of functions for manipulating rectangles, and you'll use many of these when you are writing Windows programs using the MFC.

Using Pointers with a struct

You can create a pointer to a variable of a structure type. In fact, many of the functions declared in `windows.h` that work with `RECT` objects require pointers to a `RECT` as arguments, because this avoids the copying of the whole structure when a `RECT` argument is passed to a function. To define a pointer to a `RECT` object, for example, the declaration is what you might expect:

```
RECT* pRect(nullptr);                                // Define a pointer to a RECT
```

Assuming that you have defined a `RECT` object, `aRect`, you can set the pointer to the address of this variable in the normal way:

```
pRect = &aRect;                                     // Set pointer to the address of aRect
```

As you saw when I introduced the idea of a `struct`, a `struct` can't contain a member of the same type as the `struct` being defined, but it can contain a pointer to a `struct`, including a pointer to a `struct` of the same type. For example, you could define a structure like this:

```
struct ListElement
{
    RECT aRect;                           // RECT member of structure
    ListElement* pNext;                  // Pointer to a list element
};
```

The first element of the `ListElement` structure is of type `RECT`, and the second element is a pointer to a structure of type `ListElement` — the same type as that being defined. (Remember that this element isn't of type `ListElement`, it's of type “pointer to `ListElement`.”) This allows objects of type `ListElement` to be daisy-chained together, where each `ListElement` can contain the address of the next `ListElement` object in a chain, the last in the chain having the pointer as `nullptr`. This is illustrated in Figure 7-3.




FIGURE 7-3

Each box in the diagram represents an object of type `ListElement`, and the `pNext` member of each object stores the address of the next object in the chain, except for the last object, where `pNext` is `nullptr`. This kind of arrangement is referred to as a *linked list*. It has the advantage that as long as you know the address of the first element in the list, you can find all the others. This is particularly useful when many objects are created dynamically, because you can use a linked list to keep track of them. Every time you create a new object, you can add it to the end of the list by storing its address in the `pNext` member of the last object in the chain.

Accessing Structure Members through a Pointer

Consider the following statements:

```
RECT aRect = {0, 0, 100, 100};
RECT* pRect(&aRect);
```

The first declares and defines the `aRect` object to be of type `RECT` with the first pair of members initialized to (0, 0) and the second pair to (100, 100). The second statement declares `pRect` as a pointer to type `RECT` and initializes it with the address of `aRect`. You can now access the members of `aRect` through the pointer with a statement such as this:

```
(*pRect).top += 10; // Increment the Top member by 10
```

The parentheses around the dereferenced pointer here are essential because the member access operator takes precedence over the dereferencing operator. Without the parentheses, you would be

attempting to treat the pointer as a `struct` and trying to dereference the member, so the statement would not compile. After executing this statement, the `top` member will have the value 10 and, of course, the remaining members will be unchanged.

The syntax that you used to access the member of a `struct` through a pointer looks rather clumsy. Because this kind of operation crops up very frequently, C++ includes a special operator that expresses the same thing in a much more readable and intuitive form, so let's look at that next.

The Indirect Member Selection Operator

The *indirect member selection operator*, `->`, is specifically for accessing members of a `struct` or a class through a pointer; this operator is also referred to as the *indirect member access operator*. The operator looks like a little arrow (`->`) and is formed from a minus sign (`-`) followed by the symbol for greater than (`>`). You could use it to rewrite the statement to access the `top` member of `aRect` through the pointer `pRect`, as follows:

```
pRect->top += 10; // Increment the top member by 10
```

This is much more expressive of what is going on, isn't it? You'll see a lot more of the indirect member selection operator throughout the rest of the book.

TYPES, OBJECTS, CLASSES, AND INSTANCES

Before I get into the language, syntax, and programming techniques for classes, I'll first explain how your existing knowledge relates to the concept of classes. So far, you've learned that C++ lets you create variables that can be any of a range of fundamental data types: `int`, `long`, `double`, and so on. You have also seen how you can use the `struct` keyword to define a structure type that you can then use as the type for a variable representing a composite of several other variables.

The variables of the fundamental types don't allow you to model real-world objects (or even imaginary objects) adequately. It's hard to model a box in terms of an `int`, for example; however, you can use the members of a `struct` to define a set of attributes for such an object. You could define variables `length`, `width`, and `height` to represent the dimensions of the box and bind them together as members of a `Box` structure, as follows:

```
struct Box
{
    double length;
    double width;
    double height;
};
```

With this definition of a new data type called `Box`, you can define variables of this type just as you did with variables of the basic types. You can then create, manipulate, and destroy as many `Box` objects as you need to in your program. This means that you can model objects using `structs` and write your programs around them.

So — that's object-oriented programming all wrapped up, then? Well, not quite. Object-oriented programming (OOP) is based on three basic concepts relating to object types (*encapsulation*, *polymorphism*, and *inheritance*), and what you have seen so far doesn't quite fit the bill. Don't worry about what these terms mean for the moment — you'll explore that in the rest of this chapter and throughout the book.

The notion of a `struct` in C++ goes far beyond the original concept of a `struct` in C — it incorporates the object-oriented notion of a `class`. This idea of classes, from which you can create your own data types and use them just like the native types, is fundamental to C++, and the `class` keyword was introduced into the language to describe this concept. The keywords `struct` and `class` are almost identical in effect. They differ in the access control to the members, which you find out more about later in this chapter. The `struct` keyword is maintained in C++ for backwards compatibility with C, but everything that you can do with a `struct`, and more, you can achieve with a `class`.

Take a look at how you might define a class representing boxes:

```
class CBox
{
public:
    double m_Length;
    double m_Width;
    double m_Height;
};
```

When you define `CBox` as a class, you are essentially defining a new data type, similar to when you defined the `Box` structure. The only differences here are the use of the keyword `class` instead of `struct`, and the use of the `public` keyword followed by a colon that precedes the definition of the members of the class. The variables that you define as part of the class are called *data members* of the class, because they are variables that store data.

The `public` keyword is a clue as to the difference between a structure and a class. It just specifies that the members of the class that follow the keyword are generally accessible, in the same way as the members of a structure are. By default, the members of a class are not generally accessible and are said to be *private*, and to make members accessible, you must precede their definitions with the `public` keyword. The members of a `struct`, on the other hand, are public by default. The reason that class members are private by default is because, in general, an object of a class should be a self-contained entity such that the data that make the object what it is should be *encapsulated* and only changed under controlled circumstances. Public data members should be very much the exception. As you'll see a little later in the chapter, though, it's also possible to place other restrictions on the accessibility of members of a class.

I have also called the class `CBox` instead of `Box`. I could have called the class `Box`, but the MFC adopts the convention of using the prefix `C` for all class names, so you might as well get used to it. The MFC also prefixes data members of classes with `m_` to distinguish them from other variables, so I'll use this convention, too. Remember, though, that in other contexts where you might use C++ without the MFC, this will not be the case; in some instances, the convention for naming classes and their members may be different, and in others, there may be no particular convention for naming entities.

You can declare a variable, `bigBox`, which represents an instance of the `CBox` class type like this:

```
CBox bigBox;
```

This is exactly the same as declaring a variable for a `struct`, or, indeed, for any other variable type. After you have defined the `CBox` class, declarations for variables of this type are quite standard.

First Class

The notion of class was invented by an Englishman to keep the general population happy. It derives from the theory that people who know their place and function in society are much more secure and comfortable in life than those who do not. The famous Dane, Bjarne Stroustrup, who invented C++, undoubtedly acquired a deep knowledge of class concepts while at Cambridge University in England and appropriated the idea very successfully for use in his new language.

Class in C++ is similar to the English concept, in that each class usually has a very precise role and a permitted set of actions. However, it differs from the English idea because class in C++ has largely socialist overtones, concentrating on the importance of working classes. Indeed, in some ways it is the reverse of the English ideal because working classes in C++ often live on the backs of classes that do nothing at all.

Operations on Classes

You can define new data types as classes to represent whatever kinds of objects you like. Classes (and structures) aren't limited to just holding data; you can also define member functions or even operations that act on objects of your classes using the standard C++ operators. You can define the `CBox` class, for example, so that the following statements work and have the meanings you want them to have:

```
CBox box1;
CBox box2;

if(box1 > box2)           // Fill the larger box
    box1.fill();
else
    box2.fill();
```

You could also implement operations as part of the `CBox` class for adding, subtracting or even multiplying boxes — in fact, almost any operation to which you could ascribe a sensible meaning in the context of boxes.

I'm talking about incredibly powerful medicine here, and it constitutes a major change in the approach that you take to programming. Instead of breaking down a problem in terms of what are essentially computer-related data types (integers, floating-point numbers, and so on) and then writing a program, you can program in terms of problem-related data types, in other words, classes. These classes might be named `CEmployee`, or `CCowboy`, or `CCheese`, or `CChutney`, each defined specifically for the kind of problem that you want to solve, complete with the functions and operators that are necessary to manipulate instances of your new types.

Object-oriented program design starts with deciding what application-specific data types you need to solve the problem in hand, defining those as classes and writing the program in terms of operations on the specific types that the problem is concerned with, be they `CCoffins` or `CCowpokes`.

Terminology

I'll first summarize some of the terminology that I will be using when discussing classes:

- A *class* is a user-defined data type.
- *Object-oriented programming* (OOP) is the programming style based on the idea of defining your own data types as classes, where the data types are specific to the domain of the problem you intend to solve.
- Declaring an object of a class type is sometimes referred to as *instantiation* because you are creating an *instance* of a class.
- Instances of a class type are referred to as *objects*.
- The idea of an object containing the data implicit to its definition, together with the functions that operate on that data, is referred to as *encapsulation*.

When I get into the details of object-oriented programming, it may seem a little complicated in places, but getting back to the basics of what you're doing can often help to make things clearer, so always keep in mind what objects are really about. They are about writing programs in terms of the objects that are specific to the domain of your problem. All the facilities around classes are there to make this as comprehensive and flexible as possible. Let's get down to the business of understanding classes.

UNDERSTANDING CLASSES

A class is a specification of a data type that you define. It can contain data elements that can either be variables of the fundamental types or of other user-defined types. The data elements may be single data items, arrays, pointers, arrays of pointers of almost any kind, or objects of other class types, so you have a lot of flexibility. A class typically contains functions that operate on objects of the class type by accessing the data elements that they include. So, a class combines both the definition of the elementary data that makes up an object and the means of manipulating the data that belongs to objects of the class type.

The data and functions within a class are called *members* of the class. Oddly enough, the members of a class that are data items are called *data members* and the members that are functions are called *function members* or *member functions*. The member functions of a class are also sometimes referred to as *methods*; I will not use this term, in general, in this book, but it will turn up in Chapter 18.

When you define a class, you define a blueprint for objects of that type. This doesn't actually define any data, but it does define what the class name means, that is, what an object of the class type will consist of and what operations can be performed on such an object. It's much the same as if you wrote a description of the basic type `double`. This wouldn't be an actual variable of type `double`,

but a definition of how it's made up and what you can do with it. To create a variable of a basic data type, you need to use a declaration statement. It's exactly the same with a class type.

Defining a Class

Take a look again at the class example you saw earlier — a class of boxes. The `CBox` data type was defined as:

```
class CBox
{
    public:
        double m_Length;           // Length of a box in inches
        double m_Width;            // Width of a box in inches
        double m_Height;           // Height of a box in inches
};
```

The name of the class type follows the `class` keyword, and the three data members are defined between the curly braces. The data members are defined for the class using the declaration statements that you already know and love, and the whole class definition is terminated with a semicolon. The names of all the members of a class are local to the class. You can, therefore, use the same names elsewhere in a program, including other class definitions, without causing any problems.

Access Control in a Class

The `public` keyword determines the access attributes of the members of the class that follow it. Specifying the members as `public` means that they can be accessed anywhere within the scope of the class object to which they belong. You can also specify the members of a class as `private` or `protected`, which I'll explain later. If you omit the access specification altogether, the members have the default access attribute, `private`. (This is the only difference between a class and a struct — the default access specifier for a struct is `public`.)

All you have defined so far is the `CBox` class, which is a data type. You haven't declared any objects of the class type. When I talk about accessing a class member, say `m_Height`, I'm talking about accessing the data member of a particular object, and that object needs to be defined somewhere.

Declaring Objects of a Class

You declare objects of a class with exactly the same sort of declaration that you use to declare variables of fundamental types, so you could declare objects of the `CBox` class type with these statements:

```
CBox box1;                                // Declare box1 of type CBox
CBox box2;                                // Declare box2 of type CBox
```

Both of these objects will, of course, have their own data members. This is illustrated in Figure 7-4.




FIGURE 7-4

The object name, `box1`, embodies the whole object, including its three data members. They are not initialized to anything — the data members of each object will simply contain junk values, so let's look at how you access them for the purpose of setting them to some specific values.

Accessing the Data Members of a Class

You can refer to the data members of a class object using the *direct member selection operator* that you used to access members of a struct. To set the value of the data member `m_Height` of the object `box2` to 18.0, you could write this assignment statement:

```
box2.m_Height = 18.0; // Setting the value of a data member
```

You can access the data member in this way in a function that is outside the class because the `m_Height` member was specified as having `public` access. If it wasn't defined as `public`, this statement would not compile. You'll see more about this shortly.

TRY IT OUT Your First Use of Classes

Verify that you can use your class in the same way as the structure. Try it out in the following console application:

```
// Ex7_02.cpp
// Creating and using boxes
#include <iostream>
using std::cout;
using std::endl;

class CBox // Class definition at global scope
{
public:
    double m_Length; // Length of a box in inches
    double m_Width; // Width of a box in inches
    double m_Height; // Height of a box in inches
};

int main()
{
    CBox box1; // Declare box1 of type CBox
    CBox box2; // Declare box2 of type CBox

    double boxVolume(0.0); // Stores the volume of a box
```

```

box1.m_Height = 18.0;           // Define the values
box1.m_Length = 78.0;           // of the members of
box1.m_Width = 24.0;            // the object box1

box2.m_Height = box1.m_Height - 10; // Define box2
box2.m_Length = box1.m_Length/2.0; // members in
box2.m_Width = 0.25*box1.m_Length; // terms of box1

// Calculate volume of box1
boxVolume = box1.m_Height*box1.m_Length*box1.m_Width;

cout << endl
    << "Volume of box1 = " << boxVolume;

cout << endl
    << "box2 has sides which total "
    << box2.m_Height+ box2.m_Length+ box2.m_Width
    << " inches.';

cout << endl           // Display the size of a box in memory
    << "A CBox object occupies "
    << sizeof box1 << " bytes.";

cout << endl;
return 0;
}

```

As you type in the code for `main()`, you should see the editor prompting you with a list of member names whenever you enter a member selection operator following the name of a class object. You can then select the member you want from the list by double-clicking it. You can also use the arrow keys on the keyboard to move through the list of members and press Enter when you reach the one you want. Hovering the mouse cursor for a moment over any variable in your code will result in the type being displayed.

How It Works

Everything here works, as you would have expected from your experience with structures. The definition of the class appears outside of `main()` and therefore has global scope. This enables you to declare `CBox` objects anywhere in the source file and the class shows up in the Class View tab.

You declare two objects of type `CBox` within `main(): box1 and box2`. Of course, as with variables of the basic types, the objects `box1` and `box2` are local to `main()`. Objects of a class type obey the same rules with respect to scope as variables of the fundamental types.

The first three assignment statements set the values of the data members of `box1`. You define the values of the data members of `box2` in terms of the data members of `box1` in the next three assignment statements.

You then have a statement that calculates the volume of `box1` as the product of its three data members, and you output this value. Next, you output the sum of the data members of `box2` by writing the expression for the sum directly in the output statement. The final action in the program is to output the number of bytes occupied by `box1`, which is produced by the `sizeof` operator.

If you run this program, you should get this output:

```
Volume of box1 = 33696
box2 has sides which total 66.5 inches.
A CBox object occupies 24 bytes.
```

The last line shows that `box1` occupies 24 bytes, which is a result of having three data members of 8 bytes each. The statement that produced the last line of output could equally well have been written like this:

```
cout << endl // Display the size of a box in memory
<< "A CBox object occupies "
<< sizeof(CBox) << " bytes. ";
```

I have used the type name between parentheses as the operand for the `sizeof` operator, rather than a specific object name. You'll remember from Chapter 4 that this is standard syntax for the `sizeof` operator.

This example has demonstrated the mechanism for accessing the `public` data members of a class. It also shows that they can be used in exactly the same way as ordinary variables. You are now ready to break new ground by taking a look at *member functions* of a class.

Member Functions of a Class

A member function of a class is a function that has its definition or prototype within the class definition. It operates on any object of the class of which it is a member, and can access all the members of an object.

TRY IT OUT Adding a Member Function to CBox

This example extends the `CBox` class to include a member function that calculates the volume of a `CBox` object. This will demonstrate how you access the members of the class from within a member function.

```
// Ex7_03.cpp
// Calculating the volume of a box with a member function
#include <iostream>
using std::cout;
using std::endl;

class CBox // Class definition at global scope
{
public:
    double m_Length; // Length of a box in inches
    double m_Width; // Width of a box in inches
    double m_Height; // Height of a box in inches

    // Function to calculate the volume of a box
    double Volume()
```

```

    {
        return m_Length*m_Width*m_Height;
    }

};

int main()
{
    CBox box1;                                // Declare box1 of type CBox
    CBox box2;                                // Declare box2 of type CBox

    double boxVolume(0.0);                     // Stores the volume of a box

    box1.m_Height = 18.0;                      // Define the values
    box1.m_Length = 78.0;                      // of the members of
    box1.m_Width = 24.0;                       // the object box1

    box2.m_Height = box1.m_Height - 10;         // Define box2
    box2.m_Length = box1.m_Length/2.0;          // members in
    box2.m_Width = 0.25*box1.m_Length;          // terms of box1

    boxVolume = box1.Volume();                  // Calculate volume of box1
    cout << endl
        << "Volume of box1 = " << boxVolume;

    cout << endl
        << "Volume of box2 = "
        << box2.Volume();

    cout << endl
        << "A CBox object occupies "
        << sizeof box1 << " bytes.";

    cout << endl;
    return 0;
}

```

How It Works

The new code that you add to the `CBox` class definition is shaded. It's just the definition of the `Volume()` function, which is a member function of the class. It has the same access attribute as the data members, `public`, because every class member that you declare following an access attribute will have that access attribute, until another access attribute appears within the class definition. The `Volume()` function returns the volume of a `CBox` object as a value of type `double`. The expression in the `return` statement is just the product of the three data members.

There's no need to qualify the names of the class members in any way when you access them in member functions. The unqualified member names automatically refer to the members of the object that is current when the member function is executed.

The `Volume()` function is used in the highlighted statements in `main()`, after initializing the data members. You can call a member function for a particular object by writing the name of the object to be processed, followed by a period, followed by the member function name. The function automatically

accesses the data members of the object for which it was called, so the first use of `Volume()` calculates the volume of `box1`. Using only the name of a member will always refer to the member of the object for which the member function has been called.

The member function is used a second time directly in the output statement to produce the volume of `box2`. If you execute this example, it produces this output:

```
Volume of box1 = 33696  
Volume of box2 = 6084  
A CBox object occupies 24 bytes.
```

Note that the `CBox` object still occupies the same number of bytes. Adding a function member to a class doesn't affect the size of the objects. Obviously, a member function has to be stored in memory somewhere, but there's only one copy regardless of how many class objects you create, and the memory occupied by member functions isn't counted when the `sizeof` operator produces the number of bytes that an object occupies.

NOTE *Adding a virtual function to a class, which you will learn about in Chapter 9, will increase the size of a class object.*

The names of the class data members in the member function automatically refer to the data members of the specific object used to call the function, and the function can only be called for a particular object of the class. In this case, this is done by using the direct member access operator with the name of an object.

NOTE *If you try to call a member function without specifying an object name, your program will not compile.*

Positioning a Member Function Definition

You are not obliged to put the definition of a member function inside the class definition. If you want to put it outside the class definition, you just put the prototype inside the class. If you rewrite the previous class with the function definition outside, the class definition looks like this:

```
class CBox // Class definition at global scope  
{  
public:  
    double m_Length; // Length of a box in inches  
    double m_Width; // Width of a box in inches  
    double m_Height; // Height of a box in inches  
    double Volume(); // Member function prototype  
};
```

Now, you need to write the function definition, but because it appears outside the definition of the class, there has to be some way of telling the compiler that the function belongs to the CBox class. This is done by prefixing the function name with the name of the class and separating the two with the scope resolution operator. The function definition would now look like this:

```
// Function to calculate the volume of a box
double CBox::Volume()
{
    return m_Length*m_Width*m_Height;
}
```

The function produces the same output as the last example; however, the program isn't exactly the same. In the second case, all calls to the function are treated in the way that you're already familiar with. However, when you define a function within the class definition, as in `Ex7_03.cpp`, the compiler implicitly treats the function as an *inline function*.

Inline Functions

With an inline function, the compiler tries to expand the code in the body of the function in place of a call to the function. This avoids much of the overhead of calling the function and speeds up your code. This is illustrated in Figure 7-5.




FIGURE 7-5

NOTE Of course, the compiler ensures that expanding a function inline doesn't cause any problems with variable name conflicts or scope.

The compiler may not always be able to insert the code for a function inline (such as with recursive functions or functions for which you have obtained an address), but generally, it will work. It's best used for very short, simple functions, such as our `Volume()` function in the `CBox` class, because such functions will execute faster inline and inserting the body code in place of each call does not significantly increase the size of the executable module.

When you define a member function outside of the class, you can tell the compiler that you would like the function to be considered as inline by placing the keyword `inline` at the beginning of the function header:

```
// Function to calculate the volume of a box
inline double CBox::Volume()
{
    return m_Length*m_Width*m_Height;
}
```

With this function definition, the program would be exactly the same as the original. This enables you to put the member function definitions outside of the class if you so choose, and still retain the execution performance benefits of inlining.

You can apply the `inline` keyword to ordinary functions in your program that have nothing to do with classes and get the same effect. Remember, however, that it's best used for short, simple functions.

You now need to understand a little more about what happens when you declare an object of a class.

CLASS CONSTRUCTORS

In the previous program example, you declared the `CBox` objects, `box1` and `box2`, and then laboriously worked through each of the data members for each object in order to assign an initial value to it. This is unsatisfactory from several points of view. First of all, it would be easy to overlook initializing a data member, particularly with a class that had many more data members than our `CBox` class. Initializing the data members of several objects of a complex class could involve pages of assignment statements. The final constraint on this approach arises when you get to defining data members of a class that don't have the attribute `public` — you won't be able to access them from outside the class at all. There has to be a better way and, of course, there is — it's known as the *class constructor*.

What Is a Constructor?

A class constructor is a special function in a class that is responsible for creating new objects. A constructor, therefore, provides the opportunity to initialize objects as they are created and to ensure that data members only contain valid values. A class may have several constructors, enabling you to create objects in various ways.

You have no leeway in naming the constructors in a class — they all have the same name as the class in which they are defined. The `CBox()` function, for example, is a constructor for our `CBox` class. A constructor has no return type. It's wrong to specify a return type for a constructor; you must not even write it as `void`. The primary purpose of a constructor is to assign initial values to the data

elements of the class, and no return type is necessary or permitted. If you inadvertently specify a return type for a constructor, the compiler will report it as an error.

TRY IT OUT Adding a Constructor to the CBox class

Let's extend our CBox class to incorporate a constructor:

```
// Ex7_04.cpp
// Using a constructor
#include <iostream>
using std::cout;
using std::endl;

class CBox                                // Class definition at global scope
{
public:
    double m_Length;                      // Length of a box in inches
    double m_Width;                       // Width of a box in inches
    double m_Height;                      // Height of a box in inches

    // Constructor definition
    CBox(double lv, double bv, double hv)
    {
        cout << endl << "Constructor called.";
        m_Length = lv;                     // Set values of
        m_Width = bv;                     // data members
        m_Height = hv;
    }

    // Function to calculate the volume of a box
    double Volume()
    {
        return m_Length* m_Width* m_Height;
    }
};

int main()
{
    CBox box1(78.0,24.0,18.0);           // Declare and initialize box1
    CBox cigarBox(8.0,5.0,1.0);          // Declare and initialize cigarBox

    double boxVolume(0.0);                // Stores the volume of a box

    boxVolume = box1.Volume();            // Calculate volume of box1
    cout << endl
        << "Volume of box1 = " << boxVolume;

    cout << endl
        << "Volume of cigarBox = "
        << cigarBox.Volume();

    cout << endl;
    return 0;
}
```

How It Works

The `CBox()` constructor has three parameters of type `double`, corresponding to the initial values for the `m_Length`, `m_Width`, and `m_Height` members of an object. The first statement in the constructor outputs a message so that you can tell when it's been called. You wouldn't do this in production programs, but it's very helpful in showing when a constructor is called, so it's often used when testing a program. I'll use it regularly for the purposes of illustration. The code in the body of the constructor is very simple. It just assigns the arguments that you pass to the constructor when you call it to the corresponding data members. If necessary, you could also include checks that valid, non-negative arguments are supplied and, in a real context, you probably would want to do this, but our primary interest here is in seeing how the mechanism works.

Within `main()`, you declare the `box1` object with initializing values for the data members `m_Length`, `m_Width`, and `m_Height`, in sequence. These are in parentheses following the object name. This is using the functional notation for initialization that you have applied to initializing ordinary variables of basic types. You also declare a second object of type `CBox`, called `cigarBox`, which also has initializing values.

The volume of `box1` is calculated using the `Volume()` member as in the previous example, and is then output. You also output the value of the volume of `cigarBox`. The output from the example is:

```
Constructor called.  
Constructor called.  
Volume of box1 = 33696  
Volume of cigarBox = 40
```

The first two lines are from the two calls of the `CBox` constructor, once for each object declared. The constructor that you have supplied is automatically called when a `CBox` object is declared, so both `CBox` objects are initialized with the initializing values appearing in the declaration. These are passed to the constructor as arguments in the sequence that they are written in the declaration. As you can see, the volume of `box1` is the same as before and `cigarBox` has a volume looking suspiciously like the product of its dimensions, which is quite a relief.

The Default Constructor

Try modifying the last example by adding the declaration for `box2` that you had previously in `Ex7_03.cpp`:

```
CBox box2; // Declare box2 of type CBox
```

Here, you've left `box2` without initializing values. When you rebuild this version of the program, you get the error message:

```
error C2512: 'CBox': no appropriate default constructor available
```

This means that the compiler is looking for a *default constructor* for `box2` (also referred to as the *noarg* constructor because it doesn't require arguments when it is called) because you haven't supplied any initializing values for the data members. A default constructor can be either a constructor

that has no parameters specified in the constructor definition, or one whose arguments all have default values defined. This statement was perfectly satisfactory in `Ex7_02.cpp`, so why doesn't it work now?

The answer is that the previous example used a default no-argument constructor that was supplied by the compiler, and the compiler provided this constructor because you didn't supply one. In this example you *did* supply a constructor so the compiler assumes that you are taking care of everything needed to create objects and so it didn't supply the default. If you want to use declarations for `CBox` objects that aren't initialized, you have to include a definition for the default constructor yourself. What exactly does the default constructor look like? In the simplest case, it doesn't need to do anything:

```
CBox()
{
    // Default constructor
    // Totally devoid of statements
```

You can see such a constructor in action.

TRY IT OUT Supplying a Default Constructor

Let's add our default constructor to the last example, along with the declaration for `box2`, plus the original assignments for the data members of `box2`. You can enlarge the default constructor just enough to show that it is called. Here is the next version of the program:

```
// Ex7_05.cpp
// Supplying and using a default constructor
#include <iostream>
using std::cout;
using std::endl;

class CBox                                // Class definition at global scope
{
public:
    double m_Length;                      // Length of a box in inches
    double m_Width;                        // Width of a box in inches
    double m_Height;                       // Height of a box in inches

    // Constructor definition
    CBox(double lv, double bv, double hv)
    {
        cout << endl << "Constructor called.";
        m_Length = lv;                     // Set values of
        m_Width = bv;                     // data members
        m_Height = hv;
    }

    // Default constructor definition
    CBox()
    {
        cout << endl << "Default constructor called.";
    }

    // Function to calculate the volume of a box
    double Volume()
```

```
{  
    return m_Length*m_Width*m_Height;  
}  
};  
  
int main()  
{  
    CBox box1(78.0,24.0,18.0);           // Declare and initialize box1  
    CBox box2;                      // Declare box2 - no initial values  
    CBox cigarBox(8.0, 5.0, 1.0);        // Declare and initialize cigarBox  
  
    double boxVolume(0.0);              // Stores the volume of a box  
  
    boxVolume = box1.Volume();          // Calculate volume of box1  
    cout << endl  
        << "Volume of box1 = " << boxVolume;  
  
    box2.m_Height = box1.m_Height - 10; // Define box2  
    box2.m_Length = box1.m_Length / 2.0; // members in  
    box2.m_Width = 0.25*box1.m_Length; // terms of box1  
  
    cout << endl  
        << "Volume of box2 = "  
        << box2.Volume();  
  
    cout << endl  
        << "Volume of cigarBox = "  
        << cigarBox.Volume();  
  
    cout << endl;  
    return 0;  
}
```

How It Works

Now that you have included your own version of the default constructor, there are no error messages from the compiler and everything works. The program produces this output:

```
Constructor called.  
Default constructor called.  
Constructor called.  
Volume of box1 = 33696  
Volume of box2 = 6084  
Volume of cigarBox = 40
```

The default constructor just displays a message. Evidently, it was called when you declared the object `box2`. You also get the correct value for the volumes of all three `CBox` objects, so the rest of the program is working as it should.

You now know that you can overload constructors just as you overloaded functions in Chapter 6. You have just executed an example with two constructors that differ only in their parameter list. One has three parameters of type `double` and the other has no parameters at all.

Default Parameter Values

You have seen how you can specify default values for the parameters to a function in the function prototype. You use the same syntax for class member functions, including constructors. If you put the definition of the member function inside the class, you can put the default values for the parameters in the function header. If you include only the prototype of a function in the class definition, the default parameter values should go in the prototype, not in the function definition.

If you decided that the default size for a `CBox` object was a unit box with all sides of length 1, you could alter the class in the last example to this:

```
class CBox                                // Class definition at global scope
{
public:
    double m_Length;                      // Length of a box in inches
    double m_Width;                       // Width of a box in inches
    double m_Height;                      // Height of a box in inches

    // Constructor definition
    CBox(double lv = 1.0, double bv = 1.0, double hv = 1.0)
    {
        cout << endl << "Constructor called.";
        m_Length = lv;                    // Set values of
        m_Width = bv;                   // data members
        m_Height = hv;
    }

    // Default constructor definition
    CBox()
    {
        cout << endl << "Default constructor called.";
    }

    // Function to calculate the volume of a box
    double Volume()
    {
        return m_Length*m_Width*m_Height;
    }
};
```

If you make this change to the last example, what happens? You get another error message from the compiler, of course. Amongst a lot of other stuff, you get these useful comments from the compiler:

```
warning C4520: 'CBox': multiple default constructors specified
error C2668: 'CBox::CBox': ambiguous call to overloaded function
```

This means that the compiler can't work out which of the two constructors to call — the one for which you have set default values for the parameters or the constructor that doesn't accept any parameters. The declaration of `box2` requires a constructor without parameters and either constructor can now be called without parameters. The obvious solution to this is to get rid of the constructor that has no parameters. This is actually beneficial. Without this constructor, any `CBox` object declared without being explicitly initialized will automatically have its members initialized to 1.

TRY IT OUT**Supplying Default Values for Constructor Arguments**

You can demonstrate this with the following simplified example:

```
// Ex7_06.cpp
// Supplying default values for constructor arguments
#include <iostream>
using std::cout;
using std::endl;

class CBox                                // Class definition at global scope
{
public:
    double m_Length;                      // Length of a box in inches
    double m_Width;                       // Width of a box in inches
    double m_Height;                      // Height of a box in inches

    // Constructor definition
    CBox(double lv = 1.0, double bv = 1.0, double hv = 1.0)
    {
        cout << endl << "Constructor called.";
        m_Length = lv;                     // Set values of
        m_Width = bv;                     // data members
        m_Height = hv;
    }

    // Function to calculate the volume of a box
    double Volume()
    {
        return m_Length*m_Width*m_Height;
    }
};

int main()
{
    CBox box2;                            // Declare box2 - no initial values

    cout << endl
        << "Volume of box2 = "
        << box2.Volume();

    cout << endl;
    return 0;
}
```

How It Works

You only declare a single uninitialized `CBox` variable — `box2` — because that's all you need for demonstration purposes. This version of the program produces the following output:

```
Constructor called.
Volume of box2 = 1
```

This shows that the constructor with default parameter values is doing its job of setting the values of objects that have no initializing values specified.

You should not assume from this that this is the only, or even the recommended, way of implementing the default constructor. There will be many occasions where you won't want to assign default values in this way, in which case, you'll need to write a separate default constructor. There will even be times when you don't want to have a default constructor operating at all, even though you have defined another constructor. This would ensure that all declared objects of a class must have initializing values explicitly specified in their declaration.

Using an Initialization List in a Constructor

Previously, you initialized the members of an object in the class constructor using explicit assignments. You could also have used a different technique called an *initialization list*. I can demonstrate this with an alternative version of the constructor for the CBox class:

```
// Constructor definition using an initialization list
CBox(double lv = 1.0, double bv = 1.0, double hv = 1.0):
    m_Length(lv), m_Width(bv), m_Height(hv)
{
    cout << endl << "Constructor called.";
}
```

The way this constructor definition is written assumes that it appears within the body of the class definition. The values of the data members are not set in assignment statements in the body of the constructor. As in a declaration, they are specified as initializing values using functional notation and appear in the initializing list as part of the function header. The member `m_Length` is initialized by the value of `lv`, for example. This is more efficient than using assignments as you did in the previous version. If you substitute this version of the constructor in the previous example, you will see that it works just as well.

Note that the initializing list for the constructor is separated from the parameter list by a colon, and the initializers are separated by a comma. This technique for initializing parameters in a constructor is important, because, as you will see later, it's the only way of setting values for certain types of data members. The MFC also relies heavily on the initialization list technique.

NOTE I mentioned in Chapter 4 that Microsoft has indicated that it will support the uniform initialization feature from the C++ 11 standard in an interim release of Visual C++ 11. When this feature is supported, you will be able to use it when you create class objects. You will then be able to create a CBox object like this:

```
CBox box{10,20,30};
```

The initializing values are between braces. This is equivalent to:

```
CBox box(10,20,30);
```

Making a Constructor Explicit

If you define a constructor with a single parameter, the compiler will use this constructor for implicit conversions, which may not be what you want. For example, suppose you define a constructor for the `CBox` class like this:

```
CBox(double side): m_Length(side), m_Width(side), m_Height(side) {}
```

This is a handy constructor to have when you want to define a `CBox` object that is a cube, where all the dimensions are the same. Because this constructor has a single parameter, the compiler will use it for implicit conversions when necessary. For example, consider the following code fragment:

```
CBox box;  
box = 99.0;
```

The first statement calls the default constructor to create `box`, so this must be present in the class. The second statement will call the constructor `CBox(double)` with the argument as `99.0`, so you are getting an implicit conversion from a value of type `double` to type `CBox`. This may be what you want, but there will be many classes with single argument constructors where you don't want this to happen. In these situations, you can use the `explicit` keyword in the definition of the constructor to prevent it:

```
explicit CBox(double side): m_Length(side), m_Width(side), m_Height(side) {}
```

With the constructor declared as `explicit`, it will only be called when it is explicitly invoked, and it will not be used for implicit conversions. With the constructor declared as `explicit`, the statement assigning the value `99.0` to the `box` object will not compile. In general, unless you want your single-parameter constructors to be used as implicit-type conversions, it is best to declare all such constructors as `explicit`.

With the explicit `CBox` constructor in the previous statement, this will not compile:

```
CBox box = 4.0;
```

This statement implies a conversion of the value, `4.0`, of type `double` to type `CBox` and the compiler will not allow it. This will compile though:

```
CBox box(4.0);
```

This is not a conversion. This is an explicit call for the constructor with a single parameter.

There's another way you can get implicit conversions that you may not intend. In the previous version of the `CBox` class, the constructor has default values for all three parameters. This is how it looks using an initialization list:

```
CBox(double lv = 1.0, double bv = 1.0, double hv = 1.0):  
    m_Length(lv), m_Width(bv), m_Height(hv)  
{  
    cout << endl << "Constructor called.";  
}
```

Because there are default values for the second and third parameters, the following statements will compile:

```
CBox box;
box = 99.0;
```

This time, you will get an implicit call to the previous version of the constructor with the first argument value as 99.0, and the other two arguments with default values. This is unlikely to be what you want. To prevent this, make the constructor explicit:

```
explicit CBox(double lv = 1.0, double bv = 1.0, double hv = 1.0):
    m_Length(lv), m_Width(bv), m_Height(hv)
{
    cout << endl << "Constructor called.";
}
```

PRIVATE MEMBERS OF A CLASS

Having a constructor that sets the values of the data members of a class object, but still admits the possibility of any part of a program being able to mess with what are essentially the guts of an object, is almost a contradiction in terms. To draw an analogy, after you have arranged for a brilliant surgeon whose skills were honed over years of training to do things to your insides with a sharp knife, letting the local plumber or bricklayer have a go is a bit risky. You need some protection for your class data members.

You can get the security you need by using the `private` keyword when you define the class members. Data and function members of a class that are `private` can, in general, be accessed only by member functions of a class. There's one exception, but we'll worry about that later. A normal function has no direct means of accessing the `private` members of a class. This is shown in Figure 7-6.




FIGURE 7-6

Having the possibility of specifying class members as `private` also enables you to separate the *interface* to the class from its internal implementation. The interface to a class is composed of the `public` data members and the `public` member functions, in particular, because they can provide indirect access to all the members of a class, including the `private` members. By keeping the internals of a class `private`, you can later modify them to improve performance for example, without necessitating changes to code that uses the class through its public interface. To keep the data and function members of a class safe from unnecessary meddling, it's good practice to declare those that don't need to be exposed as `private`. Only make `public` what is essential to the use of your class.

TRY IT OUT Private Data Members

You can rewrite the `CBox` class to make its data members `private`.

```
// Ex7_07.cpp
// A class with private members
#include <iostream>
using std::cout;
using std::endl;

class CBox                                // Class definition at global scope
{
public:
    // Constructor definition using an initialization list
    explicit CBox(double lv = 1.0, double bv = 1.0, double hv = 1.0):
        m_Length(lv), m_Width(bv), m_Height(hv)
    {
        cout << endl << "Constructor called.";
    }

    // Function to calculate the volume of a box
    double Volume()
    {
        return m_Length*m_Width*m_Height;
    }

private:
    double m_Length;                         // Length of a box in inches
    double m_Width;                          // Width of a box in inches
    double m_Height;                        // Height of a box in inches
};

int main()
{
    CBox match(2.2, 1.1, 0.5);             // Declare match box
    CBox box2;                            // Declare box2 - no initial values

    cout << endl
        << "Volume of match = "
        << match.Volume();
```

```
// Uncomment the following line to get an error
// box2.m_Length = 4.0;

cout << endl
    << "Volume of box2 = "
    << box2.Volume();
cout << endl;

return 0;
}
```

How It Works

The CBox constructor is explicit to prevent unwanted implicit conversions. The definition of the CBox class now has two sections. The first is the `public` section containing the constructor and the member function `Volume()`. The second section is specified as `private` and contains the data members. The data members can only be accessed by the member functions of the class. You don't have to modify any of the member functions — they can access all the data members of the class anyway. If you uncomment the statement in `main()` that assigns a value to the `m_Length` member of the `box2` object, you'll get a compiler error message confirming that the data member is inaccessible. If you haven't already done so, take a look at the members of the CBox class in Class View; you'll see that the icon alongside each member indicates its accessibility; a small padlock in the icon shows when a member is `private`.

A point to remember is that using a constructor or a member function is now the only way to get a value into a `private` data member of an object. You have to make sure that all the ways in which you might want to set or modify `private` data members of a class are provided for through member functions.

You can put functions into the `private` section of a class. In this case, they can only be called by other function members of the class. If you put the `Volume()` function in the `private` section, you will get a compiler error from the statements that attempt to use it in `main()`. If you put the constructor in the `private` section, you won't be able to declare any objects of the class type.

The example generates this output:

```
Constructor called.
Constructor called.
Volume of match = 1.21
Volume of box2 = 1
```

The output demonstrates that the class is still working satisfactorily, with its data members defined as having the access attribute `private`. The major difference is that they are now completely protected from unauthorized access and modification.

If you don't specify otherwise, the default access attribute that applies to members of a class is `private`. You could put all your `private` members at the beginning of the class definition and let them default to `private` by omitting the keyword. It's better, however, to take the trouble to explicitly state the access attribute in every case, so there can be no doubt about what you intend.

Of course, you don't have to make all your data members `private`. If the application for your class requires it, you can have some data members defined as `private` and some as `public`. It all depends on

what you're trying to do. If there's no reason to make members of a class `public`, it is better to make them `private`, as it makes the class more secure. Ordinary functions won't be able to access any of the `private` members of your class.

Accessing private Class Members

On reflection, declaring the data members of a class as `private` is rather extreme. It's all very well protecting them from unauthorized modification, but that's no reason to keep their values a secret. What you need is a Freedom of Information Act for `private` members.

You don't have to start writing to your state senator to get it — it's already available to you. You can write a member function to return the value of a data member. Look at this member function for the `CBox` class:

```
inline double CBox::GetLength()
{
    return m_Length;
}
```

Just to show how it looks, I have written this as a member function definition that is external to the class. I've specified it as `inline` because we'll benefit from the speed increase without increasing the size of the code much. With the declaration of the function in the `public` section of the class, you can use it like this:

```
double len = box2.GetLength(); // Obtain data member length
```

You can write a similar function for each data member that you want to make available to the outside world, and their values can be accessed without prejudicing the security of the class. Of course, if you put the function definitions within the class, they will be `inline` by default.

The friend Functions of a Class

There may be circumstances when, for one reason or another, you want certain selected functions that are not members of a class to be able to access all the members of a class — a sort of elite group with special privileges. Such functions are called *friend functions* of a class and are defined using the keyword `friend`. You can either include the prototype of a friend function in the class definition, or you can include the whole function definition. Functions that are friends of a class and are defined within the class definition are also `inline` by default.

NOTE *Friend functions are not members of the class, so the access attributes do not apply to them. They are just ordinary global functions with special privileges.*

Imagine that you want to implement a friend function in the `CBox` class to compute the surface area of a `CBox` object.

TRY IT OUT**Using a friend function to Calculate the Surface Area**

You can see how a friend function works in the following example:

```
// Ex7_08.cpp
// Creating a friend function of a class
#include <iostream>
using std::cout;
using std::endl;

class CBox                                // Class definition at global scope
{
public:

    // Constructor definition
    explicit CBox(double lv = 1.0, double bv = 1.0, double hv = 1.0)
    {
        cout << endl << "Constructor called.";
        m_Length = lv;                      // Set values of
        m_Width = bv;                      // data members
        m_Height = hv;
    }

    // Function to calculate the volume of a box
    double Volume()
    {
        return m_Length*m_Width*m_Height;
    }

private:
    double m_Length;                      // Length of a box in inches
    double m_Width;                       // Width of a box in inches
    double m_Height;                      // Height of a box in inches

    // Friend function
    friend double BoxSurface(const CBox& aBox);
};

// friend function to calculate the surface area of a Box object
double BoxSurface(const CBox& aBox)
{
    return 2.0*(aBox.m_Length*aBox.m_Width +
               aBox.m_Length*aBox.m_Height +
               aBox.m_Height*aBox.m_Width);
}

int main()
{
    CBox match(2.2, 1.1, 0.5);           // Declare match box
    CBox box2;                          // Declare box2 - no initial values

    cout << endl
        << "Volume of match = "
```

```
<< match.Volume();

cout << endl
<< "Surface area of match = "
<< BoxSurface(match);

cout << endl
<< "Volume of box2 = "
<< box2.Volume();

cout << endl
<< "Surface area of box2 = "
<< BoxSurface(box2);

cout << endl;
return 0;
}
```

How It Works

You declare the `BoxSurface()` function as a friend of the `CBox` class by writing the function prototype with the keyword `friend` at the front. The `BoxSurface()` function is a global function so it makes no difference where you put the `friend` declaration within the class definition but it's a good idea to be consistent where you position this sort of declaration. You can see that I have chosen to position it after all the `public` and `private` members of the class. Remember that a friend function isn't a member of the class, so access attributes don't apply.

The function definition follows that of the class. Note that you specify access to the data members of the object within the definition of `BoxSurface()`, using the `CBox` object passed to the function as a parameter. Because a friend function isn't a class member, the data members can't be referenced just by their names. They each have to be qualified by an object name in exactly the same way as an ordinary function accesses public members. A friend function is the same as an ordinary function, except that it can access all the members of the class for which it is a friend, without restriction.

The example produces the following output:

```
Constructor called.
Constructor called.
Volume of match = 1.21
Surface area of match = 8.14
Volume of box2 = 1
Surface area of box2 = 6
```

This is exactly what you would expect. The friend function is computing the surface area of `CBox` objects from the values of the `private` data members.

Placing friend Function Definitions Inside the Class

You could combine the definition of the function with its declaration as a friend of the `CBox` class within the class definition, and the code would run as before. The function definition in the class would be:

```

friend double BoxSurface(const CBox& aBox)
{
    return 2.0*(aBox.m_Length*aBox.m_Width +
                aBox.m_Length*aBox.m_Height +
                aBox.m_Height*aBox.m_Width);
}

```

However, this has a number of disadvantages relating to the readability of the code. Although the function would still have global scope, this might not be obvious to readers of the code, because the function would be hidden in the body of the class definition.

The Default Copy Constructor

Suppose that you declare and initialize a `CBox` object `box1` with this statement:

```
CBox box1(78.0, 24.0, 18.0);
```

You now want to create another `CBox` object, identical to the first. You would like to initialize the second `CBox` object with `box1`. Let's try it.

TRY IT OUT Copying Information Between Instances

The following example shows this in action:

```

// Ex7_09.cpp
// Initializing an object with an object of the same class
#include <iostream>
using std::cout;
using std::endl;

class CBox                                // Class definition at global scope
{
public:
    // Constructor definition
    explicit CBox(double lv = 1.0, double bv = 1.0, double hv = 1.0)
    {
        cout << endl << "Constructor called.";
        m_Length = lv;                      // Set values of
        m_Width = bv;                       // data members
        m_Height = hv;
    }

    // Function to calculate the volume of a box
    double Volume()
    {
        return m_Length*m_Width*m_Height;
    }

private:
    double m_Length;                      // Length of a box in inches
    double m_Width;                       // Width of a box in inches

```

```
    double m_Height;           // Height of a box in inches
};

int main()
{
    CBox box1(78.0, 24.0, 18.0);
    CBox box2 = box1;          // Initialize box2 with box1

    cout << endl
        << "box1 volume = " << box1.Volume()
        << endl
        << "box2 volume = " << box2.Volume();

    cout << endl;
    return 0;
}
```

This example produces the following output:

```
Constructor called.
box1 volume = 33696
box2 volume = 33696
```

How It Works

The program is working as you would want, with both boxes having the same volume. However, as you can see from the output, our constructor was called only once for the creation of `box1`. The question is, how was `box2` created? The mechanism is similar to the one that you experienced when you had no constructor defined and the compiler supplied a default constructor to allow an object to be created. In this instance, the compiler generates a default version of what is referred to as a *copy constructor*.

A copy constructor does exactly what we're doing here — it creates an object of a class by initializing it with the values of the data members of an existing object of the same type. The default version of the copy constructor creates a new object by copying the existing object, member by member.

This is fine for simple classes such as `CBox`, but for many classes — classes that have pointers or arrays as members, for example — it won't work properly. Indeed, with such classes the default copy constructor can create serious errors in your program. In these cases, you must create your own copy constructor. This requires a special approach that you'll look into more fully toward the end of this chapter and again in the next chapter.

THE POINTER `this`

You wrote the `Volume()` member of the `CBox` class in terms of the class member names in the definition of the class. Of course, every `CBox` object that you create contains these members, so there has to be a mechanism for the function to refer to the members of the particular object for which it is called.

When any member function executes, it always contains a hidden pointer with the name `this`, which points to the object used to call the function. Therefore when the `m_Length` member is accessed in the `Volume()` function, it's actually referring to `this->m_Length`, which is the fully specified reference to the object member that is being used. The compiler takes care of adding `this` to the member names in the function.

You can use `this` explicitly within a member function if you need to — when you want to return a pointer to the current object, for example.

TRY IT OUT Explicit Use of this

You can add a public function to the `CBox` class that compares the volumes of two `CBox` objects:

```
// Ex7_10.cpp
// Using the pointer this
#include <iostream>
using std::cout;
using std::endl;

class CBox                                // Class definition at global scope
{
public:
    // Constructor definition
    explicit CBox(double lv = 1.0, double bv = 1.0, double hv = 1.0)
    {
        cout << endl << "Constructor called.";
        m_Length = lv;                      // Set values of
        m_Width = bv;                      // data members
        m_Height = hv;
    }

    // Function to calculate the volume of a box
    double Volume()
    {
        return m_Length*m_Width*m_Height;
    }

    // Function to compare two boxes which returns true
    // if the first is greater than the second, and false otherwise
    bool Compare(CBox& xBox)
    {
        return this->Volume() > xBox.Volume();
    }
private:
    double m_Length;                      // Length of a box in inches
    double m_Width;                       // Width of a box in inches
    double m_Height;                      // Height of a box in inches
};

int main()
```

```
{  
    CBox match(2.2, 1.1, 0.5);           // Declare match box  
    CBox cigar(8.0, 5.0, 1.0);          // Declare cigar box  
  
    if(cigar.Compare(match))  
        cout << endl  
        << "match is smaller than cigar";  
    else  
        cout << endl  
        << "match is equal to or larger than cigar";  
  
    cout << endl;  
    return 0;  
}
```

How It Works

The `Compare()` member returns `true` if the prefixed `CBox` object in the function call has a greater volume than the `CBox` object specified as the argument, and `false` if it doesn't. The parameter to the `Compare()` function is a reference type to avoid unnecessary copying of the argument. In the `return` statement, the prefixed object is referred to through the pointer `this`, using the indirect member access operator, `->`.

Remember that you use the direct member access operator when accessing members through objects and the indirect member access operator when accessing members through pointers to objects. `this` is a pointer, so you use the `->` operator.

The `->` operator works the same for pointers to class objects as it did when you were dealing with a `struct`. Here, using `this` demonstrates that it exists and *does* work, but it's quite unnecessary to use it explicitly in this case. If you change the `return` statement in the `Compare()` function to be:

```
return Volume() > xBox.Volume();
```

you'll find that the program works just as well. Any references to unadorned member names are automatically assumed to be the members of the object pointed to by `this`.

You use the `Compare()` function in `main()` to check the relationship between the volumes of the objects `match` and `cigar`. The output is:

```
Constructor called.  
Constructor called.  
match is smaller than cigar
```

This confirms that the `cigar` object is larger than the `match` object.

It wasn't essential to define the `Compare()` function as a class member. You could just as well have written it as an ordinary function with the objects as arguments. Note that this isn't true of the `Volume()` function because it needs to access the `private` data members of the class. Of course, if you implemented `Compare()` as an ordinary function, it wouldn't have access to the pointer `this`, but it would still be very simple:

```
// Comparing two CBox objects - ordinary function version
bool Compare(CBox& box1, CBox& box2)
{
{
    return box1.Volume() > box2.Volume();
}
```

This has two `CBox` objects as arguments and returns `true` if the volume of the first is greater than the second. You would use this function to perform the same function as in the last example with this statement:

```
if(Compare(cigar, match))
    cout << endl
        << "match is smaller than cigar";
else
    cout << endl
        << "match is equal to or larger than cigar";
```

If anything, this looks slightly better and easier to read than the original version; however, there's a much better way to do this, which you will learn about in the next chapter.

CONST OBJECTS

The `Volume()` function that you defined for the `CBox` class does not alter the object for which it is called; neither does a function such as `getHeight()` that returns the value of the `m_Height` member. Likewise, the `Compare()` function in the previous example didn't change the class objects at all. This may seem at first sight to be a mildly interesting but largely irrelevant observation, but it isn't — it's quite important. Let's think about it.

You will undoubtedly want to create class objects that are fixed from time to time, just like values such as `pi` or `inchesPerFoot` that you might declare as type `const double`. Suppose you wanted to define a `CBox` object as `const` — because it was a very important standard-sized box, for instance. You might define it with the following statement:

```
const CBox standard(3.0, 5.0, 8.0);
```

Now that you have defined your standard box having dimensions $3 \times 5 \times 8$, you don't want it messed about with. In particular, you don't want to allow the values stored in its data members to be altered. How can you be sure they won't be?

Well, you already are. If you declare an object of a class as `const`, the compiler will not allow any member function to be called for it that might alter it. You can demonstrate this quite easily by modifying the declaration for the object, `cigar`, in the previous example to:

```
const CBox cigar(8.0, 5.0, 1.0);           // Declare cigar box
```

If you try recompiling the program with this change, it won't compile. You will see the error message:

```
error C2662: 'cBox::Compare' : cannot convert 'this' pointer
from 'const CBox' to 'CBox &' Conversion loses qualifiers
```

This is produced for the `if` statement that calls the `Compare()` member of `cigar`. An object that you declare as `const` will always have a `this` pointer that is `const`, so the compiler will not allow any member function to be called that does not assume the `this` pointer is `const`. You need to find out how to make the `this` pointer `const` in a member function.

const Member Functions of a Class

To make `this` in a member function `const`, you must declare the function as `const` within the class definition. Here's how you do that with the `Compare()` and `Volume()` members of `CBox`:

```
class CBox                                // Class definition at global scope
{
public:
    // Constructor definition
    explicit CBox(double lv = 1.0, double bv = 1.0, double hv = 1.0)

    {
        cout << endl << "Constructor called.";
        m_Length = lv;                      // Set values of
        m_Width = bv;                      // data members
        m_Height = hv;
    }

    // Function to calculate the volume of a box
    double Volume() const
    {
        return m_Length*m_Width*m_Height;
    }

    // Function to compare two boxes which returns true (1)
    // if the first is greater than the second, and false (0) otherwise
    bool Compare(const CBox& xBox) const
    {
        return this->Volume() > xBox.Volume();
    }

private:
    double m_Length;                     // Length of a box in inches
    double m_Width;                      // Width of a box in inches
    double m_Height;                     // Height of a box in inches
};
```

You can find this code in the download as `Ex7_10A.cpp`. To specify that a member function is `const`, you just append the `const` keyword to the function header. Note that you can only do this with class member functions, not with ordinary global functions. Declaring a function as `const`

is only meaningful in the case of a function that is a member of a class. The effect is to make the `this` pointer in the function `const`. This implies that you cannot write a data member of the class on the left of an assignment within the function definition; it will be flagged as an error by the compiler. A `const` member function cannot call a non-`const` member function of the same class, since this would potentially modify the object. This means that because the `Compare()` function calls `Volume()`, the `Volume()` member must be declared as `const`, too. With the `Volume()` function declared as `const`, you can make the parameter to the `Compare()` function parameter `const`. When `Volume()` was a non-`const` member of the class, making the `Compare()` function parameter `const` would result in a C2662 error message from the compiler. When you declare an object as `const`, the member functions that you call for it must be declared as `const`; otherwise, the program will not compile. The `Compare()` function now works with `const` and non-`const` objects.

Member Function Definitions Outside the Class

When the definition of a `const` member function appears outside the class, the header for the definition must have the keyword `const` added, just as the declaration within the class does. In fact, you should always declare all member functions that do not alter the class object for which they are called as `const`. With this in mind, the `CBox` class could be defined as:

```
class CBox                                // Class definition at global scope
{
public:
    // Constructor
    explicit CBox(double lv = 1.0, double bv = 1.0, double hv = 1.0);

    double Volume() const;           // Calculate the volume of a box
    bool Compare(const CBox& xBox) const; // Compare two boxes

private:
    double m_Length;                // Length of a box in inches
    double m_Width;                 // Width of a box in inches
    double m_Height;                // Height of a box in inches
};
```

This assumes that all function members, including the constructor, are defined outside the class. Both the `Volume()` and `Compare()` members have been declared as `const`. The `Volume()` function is now defined as:

```
double CBox::Volume() const
{
    return m_Length*m_Width*m_Height;
}
```

The `Compare()` function definition is:

```
bool CBox::Compare(const CBox& xBox) const
{
    return this->Volume() > xBox.Volume();
}
```

As you can see, the `const` modifier appears in both definitions. If you leave it out, the code will not compile. A function with a `const` modifier is a different function from one without, even though the name and parameters are exactly the same. Indeed, you can have both `const` and non-`const` versions of a function in a class, and sometimes this can be very useful.

With the class declared as shown, the constructor also needs to be defined separately, like this:

```
CBox::CBox(double lv, double bv, double hv):
    m_Length(lv), m_Width(bv), m_Height(hv)
{
    cout << endl << "Constructor called.";
}
```

ARRAYS OF OBJECTS

You can create an array of objects in exactly the same way as you created an ordinary array of elements of a fundamental type. Each element of an array of objects that you don't initialize causes the default constructor to be called.

TRY IT OUT Arrays of Class Objects

The definition of `CBox` in this example includes a specific default constructor:

```
// Ex7_11.cpp
// Using an array of class objects
#include <iostream>
using std::cout;
using std::endl;

class CBox                                // Class definition at global scope
{
public:
    // Constructor definition
    explicit CBox(double lv, double bv = 1.0, double hv = 1.0)
    {

        cout << endl << "Constructor called.";
        m_Length = lv;                      // Set values of
        m_Width = bv;                       // data members
        m_Height = hv;
    }

    CBox()                               // Default constructor
    {
        cout << endl
            << "Default constructor called.";
        m_Length = m_Width = m_Height = 1.0;
    }

    // Function to calculate the volume of a box
    double Volume() const
```

```

    {
        return m_Length*m_Width*m_Height;
    }

private:
    double m_Length;                      // Length of a box in inches
    double m_Width;                       // Width of a box in inches
    double m_Height;                      // Height of a box in inches

};

int main()
{
    CBox boxes[5];                      // Array of CBox objects declared
    CBox cigar(8.0, 5.0, 1.0);           // Declare cigar box

    cout << endl
        << "Volume of boxes[3] = " << boxes[3].Volume()
        << endl
        << "Volume of cigar = " << cigar.Volume();

    cout << endl;
    return 0;
}

```

The program produces this output:

```

Default constructor called.
Constructor called.
Volume of boxes[3] = 1
Volume of cigar = 40

```

How It Works

You have modified the constructor that accepts arguments so that only two default values are supplied, and you have added a default constructor that initializes the data members to 1 after displaying a message that it was called. You are now able to see *which* constructor was called *when*. The constructors now have quite distinct parameter lists, so there's no possibility of the compiler confusing them.

You can see from the output that the default constructor was called five times, once for each element of the `boxes` array. The other constructor was called to create the `cigar` object. It's clear from the output that the default constructor initialization is working satisfactorily, as the volume of the array element `boxes[3]` is 1.

Of course, you can initialize an array of objects when you declare it. For example:

```
CBox boxes[5] = {CBox(1,2,3),CBox(1,3,2)};
```

The first two elements will be initialized by calling the constructor with three arguments. The remaining three elements will use the default constructor.

STATIC MEMBERS OF A CLASS

Both data members and function members of a class can be declared as `static`. Because the context is a class, there's a little more to it than the effect of the `static` keyword outside a class, so let's look at `static` data members.

Static Data Members

When you declare a data member of a class to be `static`, only one instance of the `static` member is created and this is shared between all objects of the class. Each object gets its own copy of each of the ordinary data members, but only one instance of each `static` data member exists, regardless of how many class objects have been defined. Figure 7-7 illustrates this.




FIGURE 7-7

One use for a `static` data member is to count how many objects have been created. You could add a `static` data member to the `public` section of the `CBox` class by adding the following statement to the class definition:

```
static int objectCount;
```

```
// Count of objects in existence
```

You now have a problem. How do you initialize the static data member?

You can't initialize the static data member in the class definition — that's simply a blueprint for an object and initializing values for members are not allowed. You don't want to initialize it in a constructor, because you want to increment it every time the constructor is called so the count of the number of objects created is accumulated. You can't initialize it in another member function because a member function is associated with an object, and you want it initialized before any objects are created. You can initialize a static data member outside of the class definition though, like this:

```
int CBox::objectCount(0);           // Initialize static member of class CBox
```

Notice that the `static` keyword is not used here; however, you must qualify the member name by using the class name and the scope resolution operator so that the compiler understands that you are referring to a static member of the class. Otherwise, you would simply create a global variable that had nothing to do with the class.

TRY IT OUT Counting Instances of a Class Type

Let's add the static data member and the object-counting capability to the last example.

```
// Ex7_12.cpp
// Using a static data member in a class
#include <iostream>
using std::cout;
using std::endl;

class CBox                         // Class definition at global scope
{
public:
    static int objectCount;          // Count of objects in existence

    // Constructor definition
    explicit CBox(double lv, double bv = 1.0, double hv = 1.0)
    {

        cout << endl << "Constructor called.";
        m_Length = lv;                  // Set values of
        m_Width = bv;                  // data members
        m_Height = hv;
        objectCount++;
    }

    CBox()                          // Default constructor
    {
        cout << endl
            << "Default constructor called.";
        m_Length = m_Width = m_Height = 1.0;
        objectCount++;
    }
}
```

```
// Function to calculate the volume of a box
double Volume() const
{
    return m_Length*m_Width*m_Height;
}

private:
    double m_Length;                      // Length of a box in inches
    double m_Width;                       // Width of a box in inches
    double m_Height;                      // Height of a box in inches
};

int CBox::objectCount(0);                // Initialize static member of CBox class

int main()
{
    CBox boxes[5];                      // Array of CBox objects declared
    CBox cigar(8.0, 5.0, 1.0);           // Declare cigar box

    cout << endl << endl
        << "Number of objects (through class) = "
        << CBox::objectCount;

    cout << endl
        << "Number of objects (through object) = "
        << boxes[2].objectCount;

    cout << endl;
    return 0;
}
```

This example produces the following output:

```
Default constructor called.
Constructor called.
Number of objects (through class) = 6
Number of objects (through object) = 6
```

How It Works

This code shows that it doesn't matter how you refer to the `static` member `objectCount`, whether through the class itself or any of the objects of that class. The value is the same and it is equal to the number of objects that have been created. The six objects are the five elements of the `boxes` array, plus the `cigar` object. It's interesting to note that `static` members of a class exist even though there may be no instances of the class defined. This is evidently the case, because you initialized the `static` member `objectCount` before any class objects were declared.

NOTE Static data members are automatically created when your program begins, and they will be initialized with 0 or its equivalent unless you initialize them with some other value. Thus, you need only to initialize static data members of a class if you want them to start out with a value other than 0. However, you still need to define them. For example:

```
int CBox::objectCount;
```

This defines objectCount but does not initialize it explicitly so the value will be 0 by default.

Static Function Members of a Class

By declaring a function member as `static`, you make it independent of any particular object of the class. Consequently it does not have the pointer `this`. A `static` member function has the advantage that it exists, and can be called, even if no objects of the class exist. In this case, only `static` data members can be accessed because they are the only ones that exist. Thus, you can call a `static` function member of a class to examine `static` data members, even when you do not know for certain that any objects of the class exist. You could, therefore, use a `static` member function to determine whether any objects of the class have been created or how many have been created.

A `static` function might have this prototype:

```
static void Afunction(int n);
```

A `static` function can be called in relation to a particular object by a statement such as the following:

```
aBox.Afunction(10);
```

The function has no access to the non-`static` members of `aBox`. The same function could also be called without reference to an object. In this case, the statement would be:

```
CBox::Afunction(10);
```

where `CBox` is the class name. Using the class name and the scope resolution operator tells the compiler to which class `Afunction()` belongs.

POINTERS AND REFERENCES TO OBJECTS

Using pointers, and particularly references to class objects, is very important in object-oriented programming and in the specification of function parameters. Class objects can involve considerable amounts of data, so using the pass-by-value mechanism for objects can be very time-consuming and inefficient because each object that is passed to a function in this way will be copied. Using reference parameters avoids this overhead and reference parameters are essential to some operations with classes. As you'll see, you can't write a copy constructor without using a reference parameter.

Pointers to Objects

You declare a pointer to an object in the same way that you declare other pointers. For example, a pointer to objects of type `CBox` is declared in this statement:

```
CBox* pBox(nullptr);           // Declare a pointer to CBox
```

You can use this to store the address of a `CBox` object in an assignment in the usual way, using the address operator:

```
pBox = &cigar;                // Store address of CBox object cigar in pBox
```

As you saw when you used the `this` pointer in the `Compare()` member function, you can call a function using a pointer to an object. You can call the `Volume()` function for the pointer `pBox` like this:

```
cout << pBox->Volume();      // Display volume of object pointed to by pBox
```

This uses the indirect member selection operator. This is the typical notation used by most programmers for this kind of operation, so *from now on, I'll use it universally.*

TRY IT OUT Pointers to Classes

Let's try exercising the indirect member access operator a little more. We will use the example `Ex7_13.cpp` as a base, but change it a little:

```
// Ex7_13.cpp
// Exercising the indirect member access operator
#include <iostream>
using std::cout;
using std::endl;

class CBox                      // Class definition at global scope
{
public:
    // Constructor definition
    explicit CBox(double lv = 1.0, double bv = 1.0, double hv = 1.0)
    {
        cout << endl << "Constructor called.";
        m_Length = lv;           // Set values of
        m_Width = bv;            // data members
        m_Height = hv;
    }

    // Function to calculate the volume of a box
    double Volume() const
    {
        return m_Length*m_Width*m_Height;
    }
}
```

```

// Function to compare two boxes which returns true
// if the first is greater than the second, and false otherwise
bool Compare(const CBox* pBox) const
{
    if(!pBox)
        return false;
    return this->Volume() > pBox->Volume();
}

private:
    double m_Length;                      // Length of a box in inches
    double m_Width;                       // Width of a box in inches
    double m_Height;                      // Height of a box in inches
};

int main()
{
    CBox boxes[5];                         // Array of CBox objects declared
    CBox match(2.2, 1.1, 0.5);             // Declare match box
    CBox cigar(8.0, 5.0, 1.0);            // Declare cigar Box
    CBox* pB1(&cigar);                  // Initialize pointer to cigar object address
    CBox* pB2(nullptr);                  // Pointer to CBox initialized to null

    cout << endl
        << "Address of cigar is " << pB1      // Display address
        << endl
        << "Volume of cigar is "
        << pB1->Volume();                  // Volume of object pointed to

    pB2 = &match;
    if(pB2->Compare(pB1))                // Compare via pointers
        cout << endl
            << "match is greater than cigar";
    else
        cout << endl
            << "match is less than or equal to cigar";

    pB1 = boxes;                          // Set to address of array
    boxes[2] = match;                     // Set 3rd element to match
    cout << endl                          // Now access thru pointer
        << "Volume of boxes[2] is " << (pB1 + 2)->Volume();

    cout << endl;
    return 0;
}

```

When you run the example, the output looks something like this:

```

Constructor called.
Constructor called.
Constructor called.
Constructor called.
Constructor called.
Constructor called.

```

```
Constructor called.  
Address of cigar is 0012FE20  
Volume of cigar is 40  
match is less than or equal to cigar  
Volume of boxes[2] is 1.21
```

The address for `cigar` is likely to be different on your PC.

How It Works

The only change to the class definition isn't one of great substance. I have modified the `Compare()` function to accept a pointer to a `CBox` object as an argument. You have an `if` statement added to the function that guards against the possibility for the argument to be null. Now that you know about `const` member functions, you declare `Compare()` as `const` because it doesn't alter the object. The `main()` function merely exercises pointers to `CBox` type objects in various, rather arbitrary, ways.

Within `main()`, you declare two pointers to `CBox` objects after declaring an array, `boxes`, and the `CBox` objects `cigar` and `match`. The first, `pB1`, is initialized with the address of the object `cigar`, and the second, `pB2`, is initialized to `nullptr`. All of this uses the pointer in exactly the same way you would with a pointer to a basic type. The fact that you are using a pointer to a class type makes no difference.

You use `pB1` with the indirect member access operator to generate the volume of the object pointed to, and the result is displayed. You then assign the address of `match` to `pB2` and use both pointers in calling the compare function. Because the parameter for `Compare()` is a pointer to a `CBox` object, the function uses the indirect member selection operator to call the `Volume()` function for the argument.

To demonstrate that you can use address arithmetic on the pointer `pB1` when using it to select a member function, you set `pB1` to the address of the first element of the `CBox` array, `boxes`. In this case, you select the third element of the array and calculate its volume. This is the same as the volume of `match`.

You can see from the output that there were seven constructor calls, five for the `boxes` array, plus one each for the objects `cigar` and `match`.

Overall, there's virtually no difference between using a pointer to a class object and using a pointer to a primitive type, such as `double`.

References to Class Objects

References really come into their own when they are used with classes. As with pointers, there is virtually no difference between the way you declare and use references to class objects and the way in which you have already declared and used references to variables of primitive types. To declare a reference to the object `cigar`, for instance, you would write this:

```
CBox& rcigar(cigar); // Define reference to object cigar
```

To use a reference to calculate the volume of the object `cigar`, you would just use the reference name where the object name would otherwise appear:

```
cout << rcigar.Volume(); // Output volume of cigar thru a reference
```

As you may remember, a reference acts as an alias for the object it refers to, so the usage is exactly the same as using the original object name.

Implementing a Copy Constructor

The importance of references is really in the context of parameters and return values in functions, particularly class member functions. Let's return to the question of the copy constructor as a first toe in the water. For the moment, I'll sidestep the question of *when* you need to write your own copy constructor and concentrate on the problem of *how* you can write one. I'll use the CBox class just to make the discussion more concrete.

The copy constructor is a constructor that creates a new object from an existing object of the same type. It therefore needs to accept an object of the class as an argument. You might consider writing the prototype like this:

```
CBox(CBox initB);
```

Now, think about what happens when this constructor is called. Suppose you write this declaration:

```
CBox myBox(cigar);
```

This generates a call of the copy constructor, as follows:

```
CBox::CBox(cigar);
```

This seems to be no problem, until you realize that the argument is passed by value. So, before *cigar* can be passed to the constructor, the compiler needs to arrange to make a copy of it. Therefore, it calls the copy constructor to make a copy of the argument for the call of the copy constructor. Unfortunately, since it is passed by value, this call also needs a copy of its argument to be made, so the copy constructor is called again, and so on and so on. You end up with an infinite number of calls to the copy constructor.

The solution, as I'm sure you have guessed, is to use a `const` reference parameter. You can write the prototype of the copy constructor like this:

```
CBox(const CBox& initB);
```

Now, the argument to the copy constructor doesn't need to be copied. It is used to initialize the reference parameter so no copying takes place. As you remember from the discussion on references, if a parameter to a function is a reference, no copying of the argument occurs when the function is called. The function accesses the argument in the caller function directly. The `const` qualifier ensures that the argument can't be modified by the function.

NOTE This is another important use of the `const` qualifier. You should always declare a reference parameter of a function as `const` unless the function will modify it.

You could implement the copy constructor as follows:

```
CBox::CBox(const CBox& initB)
{
    m_Length = initB.m_Length;
    m_Width = initB.m_Width;
    m_Height = initB.m_Height;
}
```

This definition assumes that it appears outside of the class definition. The constructor name is qualified with the class name using the scope resolution operator. Each data member of the object being created is initialized with the corresponding member of the object passed as the argument. Of course, you could equally well use the initialization list to set the values of the object.

The `CBox` class is not an example of when you need to write a copy constructor. As you have seen, the default copy constructor works perfectly well with `CBox` objects. I will get to *why* and *when* you need to write your own copy constructor in the next chapter.

SUMMARY

You now understand the basic ideas behind classes in C++. You're going to see more and more about using classes throughout the rest of the book.

EXERCISES

1. Define a struct `Sample` that contains two integer data items. Write a program that declares two objects of type `Sample`, called `a` and `b`. Set values for the data items that belong to `a` and then check that you can copy the values into `b` by simple assignment.
2. Add a `char*` member to struct `Sample` in the previous exercise called `sPtr`. When you fill in the data for `a`, dynamically create a string buffer initialized with "Hello World!" and make `a.sptr` point to it. Copy `a` into `b`. What happens when you change the contents of the character buffer pointed to by `a.sPtr` and then output the contents of the string pointed to by `b.sPtr`? Explain what is happening. How would you get around this?
3. Create a function that accepts a pointer to an object of type `Sample` as an argument and that outputs the values of the members of the object that is passed to it. Test this function by extending the program that you created for the previous exercise.
4. Define a class `CRecord` with two `private` data members that store a name up to 14 characters long and an integer item number. Define a `getRecord()` function member of the `CRecord` class that will set values for the data members by reading input from the keyboard, and a `putRecord()` function member that outputs the values of the data members. Implement the `getRecord()` function so that a calling program can detect when a zero item number is entered. Test your `CRecord` class with a `main()` function that reads and outputs `CRecord` objects until a zero item number is entered.

-
5. Define a class to represent a *push-down stack* of integers. A stack is a list of items that permits adding (“pushing”) or removing (“popping”) items only from one end and works on a last-in, first-out principle. For example, if the stack contained [10 4 16 20], `pop()` would return 10, and the stack would then contain [4 16 20]; a subsequent `push(13)` would leave the stack as [13 4 16 20]. You can’t get at an item that is not at the top without first popping the ones above it. Your class should implement `push()` and `pop()` functions, plus a `print()` function so that you can check the stack contents. Store the list internally as an array, for now. Write a test program to verify the correct operation of your class.
 6. What happens with your solution to the previous exercise if you try to pop more items than you’ve pushed, or save more items than you have space for? Can you think of a robust way to trap this? Sometimes, you might want to look at the number at the top of the stack without removing it; implement a `peek()` function to do this.
-

► WHAT YOU LEARNED IN THIS CHAPTER

TOPIC	CONCEPT
Classes	A class provides a means of defining your own data types. They can reflect whatever types of objects your particular problem requires.
Class members	A class can contain data members and function members. The function members of a class always have free access to the data members of the same class.
Class constructors	Objects of a class are created and initialized using functions called constructors. These are automatically called when an object declaration is encountered. Constructors may be overloaded to provide different ways of initializing an object.
Class member access	Members of a class can be specified as <code>public</code> , in which case, they are freely accessible by any function in a program. Alternatively, they may be specified as <code>private</code> , in which case, they may only be accessed by member functions or friend functions of the class.
Static class members	Members of a class can be defined as <code>static</code> . Only one instance of each <code>static</code> data member of a class exists, which is shared amongst all instances of the class, no matter how many objects of the class are created. Static function members have no <code>this</code> pointer.
The pointer <code>this</code>	Every non-static function of a class contains the pointer <code>this</code> , which points to the current object for which the function was called.
<code>const</code> member functions	A member function that is declared as <code>const</code> has a <code>const this</code> pointer, and therefore cannot modify data members of the class object for which it is called. It also cannot call another member function that is not <code>const</code> .
Calling <code>const</code> member functions	A member function that is declared as <code>const</code> cannot call another member function that is not <code>const</code> . You cannot call a non- <code>const</code> member function for a <code>const</code> object.
Passing objects to a function by reference	Using references to class objects as arguments to function calls can avoid substantial overheads in passing complex objects to a function.
The copy constructor	A copy constructor, which is a constructor for an object initialized with an existing object of the same class, must have its parameter specified as a <code>const</code> reference.

8

More on Classes

WHAT YOU WILL LEARN IN THIS CHAPTER:

- What a destructor is and when and why you need to define it
- How to implement a destructor
- How to create class data members in the free store and how to delete them
- When you must write a copy constructor for a class
- What a union is and how it can be used
- How to make class objects work with operators such as + or *
- How to use rvalue reference parameters to avoid unnecessary copying of class objects
- What class templates are and how you define and use them
- What perfect forwarding is and how you can achieve it
- How to use the standard `string` class for string operations

WROX.COM CODE DOWNLOADS FOR THIS CHAPTER

You can find the wrox.com code downloads for this chapter on the Download Code tab at www.wrox.com/remtitle.cgi?isbn=9781118368084. The code is in the Chapter 8 download and individually named according to the names throughout the chapter.

CLASS DESTRUCTORS

Although this section heading relates to destructors, it's also about dynamic memory allocation. When you allocate memory in the free store for class members, you are invariably obliged to make use of a destructor, in addition to a constructor, of course. As you'll see, dynamically allocating memory for class members will also require you to write a copy constructor.

What Is a Destructor?

A *destructor* is a function that destroys objects when they are no longer required or when they go out of scope. The class destructor is called automatically when an object goes out of scope. Destroying an object involves freeing the memory occupied by the data members of the object (except for static members, which continue to exist even when there are no class objects in existence). The class destructor is a member function with a name that is a tilde (~) followed by the class name. A destructor doesn't return a value and doesn't have parameters. For example, the prototype for the CBox class destructor is:

```
~CBox(); // Class destructor prototype
```

Because a destructor has a specific name and no parameters, there can only ever be one destructor in a class.

NOTE It's an error to specify a return value or parameters for a destructor.

The Default Destructor

All the objects that you have been using up to now have been destroyed automatically by the *default destructor* for the class. The default destructor is always generated automatically by the compiler if you do not define your own destructor. The default destructor doesn't delete objects or object members that have been allocated in the free store. If space for class members has been allocated dynamically in a constructor, then you must define your own destructor that will explicitly use the `delete` operator to release the memory that has been allocated, just as you would with ordinary variables. You need some practice in writing destructors, so let's try it out.

NOTE In Chapter 10 you'll learn about smart pointers that automatically release heap memory when it is no longer required. This can eliminate the need for a destructor in many instances.

TRY IT OUT**A Simple Destructor**

To get an appreciation of when the destructor for a class is called, you can include a destructor in the CBox class. Here's the example:

```
// Ex8_01.cpp
// Class with an explicit destructor
#include <iostream>
using std::cout;
using std::endl;

class CBox           // Class definition at global scope
{
public:
    // Destructor definition
    ~CBox()
    {
        cout << "Destructor called." << endl;
    }

    // Constructor definition
    explicit CBox(double lv = 1.0, double bv = 1.0, double hv = 1.0):
        m_Length(lv), m_Width(bv), m_Height(hv)

    {
        cout << endl << "Constructor called.";
    }

    // Function to calculate the volume of a box
    double Volume() const
    {
        return m_Length*m_Width*m_Height;
    }

    // Function to compare two boxes which returns true
    // if the first is greater than the second, and false otherwise
    bool compare(const CBox* pBox) const

    {
        if(!pBox)
            return false;
        return this->Volume() > pBox->Volume();
    }

private:
    double m_Length;          // Length of a box in inches
    double m_Width;           // Width of a box in inches
    double m_Height;          // Height of a box in inches
};

// Function to demonstrate the CBox class destructor in action
```

```
int main()
{
    CBox boxes[5];           // Array of CBox objects declared
    CBox cigar(8.0, 5.0, 1.0); // Declare cigar box
    CBox match(2.2, 1.1, 0.5); // Declare match box
    CBox* pB1(&cigar);      // Initialize pointer to cigar object address
    CBox* pB2(nullptr);      // Pointer to CBox initialized to null

    cout << endl
        << "Volume of cigar is "
        << pB1->Volume();      // Volume of obj. pointed to

    pB2 = boxes;             // Set to address of array
    boxes[2] = match;        // Set 3rd element to match
    cout << endl
        << "Volume of boxes[2] is "
        << (pB2 + 2)->Volume(); // Now access thru pointer

    cout << endl;
    return 0;
}
```

How It Works

The `CBox` class destructor just displays a message showing that it was called. The output is:

```
Constructor called.
Volume of cigar is 40
Volume of boxes[2] is 1.21
Destructor called.
```

You get one call of the destructor at the end of the program for each of the objects that exist at that time. For each constructor call that occurred, there's a matching destructor call. You don't need to call the destructor explicitly here. The compiler arranges for the destructor to be called when an object needs to be destroyed. In our example, the destructor calls occur after `main()` has finished executing, so it's quite possible for an error in a destructor to cause a program to crash after `main()` has terminated.

Destructors and Dynamic Memory Allocation

You will often want to allocate memory for class data members dynamically. You can use the `new` operator in a constructor to allocate memory for an object member. In such a case, you have the responsibility for releasing the memory when the object is no longer required by providing a suitable destructor (or use a smart pointer, which you will learn about in Chapter 10). Let's first define a simple class where we can do this.

Suppose you define a class where each object is a message of some description — for example, a text string. The class should be as memory-efficient as possible, so, rather than defining a data member as a `char` array big enough to hold the maximum length string that you might require, you'll allocate memory in the free store for the message when an object is created. Here's the class definition:

```
//Listing 08_02_1

class CMessage
{
private:
    char* pmessage; // Pointer to object text string

public:

    // Function to display a message
    void ShowIt() const
    {
        cout << endl << pmessage;
    }

    // Constructor definition
    CMessage(const char* text = "Default message")
    {
        pmessage = new char[strlen(text) + 1]; // Allocate space for text
        strcpy_s(pmessage, strlen(text) + 1, text); // Copy text to new memory
    }

    ~CMessage(); // Destructor prototype
};
```

This class has only one data member defined, `pmessage`, which is a pointer to a string. This is defined in the `private` section of the class, so that it can't be accessed from outside the class.

In the `public` section, you have the `ShowIt()` function that outputs the string for a `CMessage` object. You also have a constructor definition and the prototype for the destructor, `~CMessage()`, which I'll come to in a moment.

The constructor requires a string as an argument, but if none is passed, it uses the default string that is specified for the parameter. The constructor obtains the length of the string supplied as the argument, excluding the terminating null, by using the library function `strlen()`. For the constructor to use this library function, there must be an `#include` directive for the `cstring` header file.

NOTE The `cstring` header declares functions that are from the C runtime library, which is not defined within a namespace, so you can use the function names without qualifying them with a namespace name. Because they are also part of the C++ standard library, the names are also defined within the `std` namespace, so if you want to qualify them with `std`, you can.

The constructor determines the number of bytes of memory necessary to store the string in the free store by adding 1 to the value that the function `strlen()` returns.

NOTE Of course, if the memory allocation fails, an exception will be thrown that will terminate the program. If you wanted to manage such a failure to provide a more graceful end to the program, you would catch the exception within the constructor code. (Chapter 6 explains how you can handle out-of-memory conditions.)

You use the `strcpy_s()` library function that is also declared in the `cstring` header file to copy the string supplied as the constructor argument to the memory allocated for it. `strcpy_s()` copies the string specified by the third argument to the address contained in the first argument. The second argument specifies the length of the destination location.

You must now write a destructor that will free the memory allocated for a message. If you don't provide a destructor, there's no way to delete the memory allocated for an object. If you use this class as it stands in a program where a large number of `CMessage` objects are created, the free store will be gradually eaten away until the program fails. It's easy for this to occur in circumstances where it may not be obvious that it is happening. For example, if you create a temporary `CMessage` object in a function that is called many times in a program, you might assume that the objects are being destroyed at the return from the function. You'd be right about that, of course, but the free store memory will not be released. Thus, for each call of the function, more of the free store will be occupied by memory for discarded `CMessage` objects.

The code for the `CMessage` class destructor is:

```
// Listing 08_02_2
// Destructor to free memory allocated by new
CMessage::~CMessage()
{
    cout << "Destructor called."      // Just to track what happens
        << endl;
    delete[] pmessage;             // Free memory assigned to pointer
}
```

Because you're defining the destructor outside of the class definition, you must qualify the destructor name with the class name, `CMessage`. The destructor displays a message so that you can see when it is called, and then uses the `delete` operator to free the memory pointed to by `pmessage`. Note that you must include the square brackets with `delete` because you're deleting an array (of type `char[]`).

TRY IT OUT Using the `CMessage` Class

You can exercise the `CMessage` class with a little example:

```
// Ex8_02.cpp
// Using a destructor to free memory
#include <iostream>           // For stream I/O
#include <cstring>            // For strlen() and strcpy()
using std::cout;
using std::endl;

// Put the CMessage class definition here (Listing 08_02_1)

// Put the destructor definition here (Listing 08_02_2)

int main()
{
    // Declare object
    CMessage motto("A miss is as good as a mile.");

    // Dynamic object
    CMessage* pM(new CMessage("A cat can look at a queen."));

    motto.ShowIt();           // Display 1st message
    pM->ShowIt();           // Display 2nd message
    cout << endl;

    delete pM;               // Manually delete object created with new

    return 0;
}
```

Don't forget to replace the comments in the code with the `CMessage` class and destructor definitions from the previous section; it won't compile without this (the source code in the download contains all the code for the example).

How It Works

At the beginning of `main()`, you declare and define an initialized `CMessage` object, `motto`, in the usual manner. In the second declaration, you define a pointer to a `CMessage` object, `pM`, and allocate memory for the `CMessage` object that is pointed to by using the operator `new`. The call to `new` invokes the `CMessage` class constructor, which has the effect of calling `new` again to allocate space for the message text pointed to by the data member `pmessage`. If you build and execute this example, it will produce the following output:

```
A miss is as good as a mile.  
A cat can look at a queen.  
Destructor called.  
Destructor called.
```

You have two destructor calls recorded in the output, one for each of the two `CMessage` objects. I said earlier that the compiler doesn't take responsibility for objects created in the free store. The compiler arranged to call your destructor for the object `motto` because this is a normal, automatic object, even though the memory for the data member was allocated in the free store by the constructor. The object pointed to by `pM` is different. You allocated memory for the *object* in the free store, so you have to use `delete` to remove it. If you comment out the statement that appears just before the `return` statement in `main()`:

```
// delete pM; // Manually delete object created with new
```

If you run the code now, it will produce this output:

```
A miss is as good as a mile.  
A cat can look at a queen.  
Destructor called.
```

Now you get just one call of your destructor. This is surprising in a way. Clearly, `delete` is only dealing with the memory allocated by the call to `new` in the function `main()`. It only freed the memory pointed to by `pM`. Because your pointer `pM` points to a `CMessage` object (for which a destructor has been defined), `delete` also calls your destructor to allow you to release the memory for the members of the object. So when you use `delete` for an object created dynamically, it will always call the destructor for the object before releasing the memory that the object occupies. This ensures that any memory allocated dynamically for class members will also be freed.


IMPLEMENTING A COPY CONSTRUCTOR

When you allocate space for class members dynamically, there are demons lurking in the free store. For the `CMessage` class, the default copy constructor is woefully inadequate. Suppose you write these statements:

```
CMessage motto1("Radiation fades your genes.");  
CMessage motto2(motto1); // Calls the default copy constructor
```

The effect of the default copy constructor will be to copy the address that is stored in the pointer member of the class from `motto1` to `motto2` because the copying process implemented by the default copy constructor involves simply copying the values stored in the data members of the original object to the new object. Consequently, there will be only one text string shared between the two objects, as Figure 8-1 illustrates.

```
CMessage motto1("Radiation fades your genes.");
```



```
CMessage motto2(motto1); // Calls the default copy constructor
```




FIGURE 8-1

If the string is changed from either of the objects, it will be changed for the other object as well, because both objects share the same string. If `motto1` is destroyed, the pointer in `motto2` will be pointing at a memory area that has been released, and may now be used for something else, so chaos will surely ensue. Of course, the same problem arises if `motto2` is deleted; `motto1` would then contain a member pointing to a nonexistent string.

The solution is to supply a copy constructor to replace the default version. You could implement this in the `public` section of the class as:

```
CMessage(const CMessage& aMess)
{
    size_t len = strlen(aMess.pmessage)+1;
    pmessage = new char[len];
    strcpy_s(pmessage, len, aMess.pmessage);
}
```

Remember from the previous chapter that to avoid an infinite spiral of calls to a copy constructor, the parameter must be specified as a `const` reference. This copy constructor first allocates enough memory to hold the string in the object `aMess`, stores the address in the data member of the new object, and then copies the string from the initializing object. Now, the new object will be identical to the old one, but quite independent of it.

Just because you don't explicitly initialize one `CMessage` class object with another, don't think that you're safe and need not bother with the copy constructor. Another monster lurks in the free store that can emerge to bite you when you least expect it. Consider the following statements:

```
CMessage thought("Eye awl weighs yews my spell checker.");
DisplayMessage(thought);      // Call a function to output a message
```

Where the function `DisplayMessage()` is defined as:

```
void DisplayMessage(CMessage localMsg)
{
    cout << endl << "The message is: ";
    localMsg.ShowIt();

    return;
}
```

Looks simple enough, doesn't it? What could be wrong with that? A catastrophic error, that's what! What the function `DisplayMessage()` does is actually irrelevant. The problem lies with the parameter. The parameter is a `CMessage` object, so the argument in a call is passed by value. With the default copy constructor, the sequence of events is as follows:

1. The object `thought` is created with the space for the message "Eye awl weighs yews my spell checker" allocated in the free store.
2. The function `DisplayMessage()` is called and, because the argument is passed by value, a copy, `localMsg`, is made using the default copy constructor. Now, the pointer in the copy points to the same string in the free store as the original object.
3. At the end of the function, the local object goes out of scope, so the destructor for the `CMessage` class is called. This deletes the local object (the copy) by deleting the memory pointed to by the pointer `pmessage`.
4. On return from the function `DisplayMessage()`, the pointer in the original object, `thought`, still points to the memory area that has just been deleted. Next time you try to use the original object, your program will behave in weird and mysterious ways.

Any call to a function that passes by value an object of a class that has a member defined dynamically will cause problems. So, out of this, you have an absolutely 100-percent, 24-carat golden rule:

NOTE If you allocate space for a member of a class dynamically, always implement a copy constructor.

SHARING MEMORY BETWEEN VARIABLES

As a relic of the days when 64KB was quite a lot of memory, you have a facility in C++ that allows more than one variable to share the same memory (but, obviously, not at the same time). This is called a *union*, and there are four basic ways in which you can use one:

- You can use it so that a variable, A, occupies a block of memory at one point in a program, which is later occupied by another variable, B, of a different type, because A is no longer required. I recommend that you don't do this. It's not worth the risk of error that is implicit in such an arrangement. You can achieve the same effect by allocating memory dynamically.
- Alternatively, you could have a situation in a program where a large array of data is required, but you don't know in advance of execution what the data type will be — it will be determined by the input data. I also recommend that you don't use unions in this case, since you can achieve the same result using a couple of pointers of different types and, again, allocating the memory dynamically.
- A third possible use for a union is one that you may need now and again — when you want to interpret the same data in two or more different ways. This could happen when you have a variable that is of type long, and you want to treat it as two values of type short. Windows will sometimes package two short values in a single parameter of type long passed to a function. Another instance arises when you want to treat a block of memory containing numeric data as a string of bytes, just to move it around.
- You can use a union as a means of passing an object or a data value around where you don't know in advance what its type is going to be. The union can provide for storing any one of the possible range of types that you might have.

Defining Unions

You define a union using the `union` keyword. It is best understood by taking an example of a definition:

```
union shareLD          // Sharing memory between long and double
{
    double dval;
    long lval;
};
```

This defines a union type `shareLD` that provides for the variables of type `long` and `double` to occupy the same memory. The union type name is usually referred to as a *tag name*. This statement is rather like a class definition, in that you haven't actually defined a union instance yet, so you don't have any variables at this point. Once the union type has been defined, you can define instances of a union in a declaration. For example:

```
shareLD myUnion;
```

This defines an instance of the union type, `shareLD`, that you defined previously. You could also have defined `myUnion` by including it in the union definition statement:

```
union shareLD          // Sharing memory between long and double
{
    double dval;
    long lval;
} myUnion;
```

To refer to a member of the union, you use the direct member selection operator (the period) with the union instance name, just as you have done when accessing class members. You could set the long variable `lval` to 100 in the union instance `myUnion` with this statement:

```
myUnion.lval = 100;           // Using a member of a union
```

Using a similar statement later in a program to initialize the double variable `dval` will overwrite `lval`. The basic problem with using a union to store different types of values in the same memory is that, because of the way a union works, you also need some means of determining which of the member values is current. This is usually achieved by maintaining another variable that acts as an indicator of the type of value stored.

A union is not limited to sharing between two variables. If you wish, you can share the same memory between several variables. The memory occupied by the union will be that which is required by its largest member. For example, suppose you define this union:

```
union shareDLF
{
    double dval;
    long lval;
    float fval;
} uinst = {1.5};
```

An instance of `shareDLF` will occupy 8 bytes, as illustrated in Figure 8-2.

In the example, you defined an instance of the union, `uinst`, as well as the tag name for the union. You also initialized the instance with 1.5.




FIGURE 8-2

NOTE You can only initialize the first member of the union when you declare an instance.

Anonymous Unions

You can define a union without a union type name, in which case, an instance of the union is automatically declared. For example, suppose you define a union like this:

```
union
{
    char* pval;
    double dval;
    long lval;
};
```

This statement defines both a union with no name and an instance of the union with no name. Consequently, you can refer to the variables that it contains just by their names, as they appear in the union definition, `pval`, `dval`, and `lval`. This can be more convenient than a normal union with a type name, but you need to be careful that you don't confuse the union members with ordinary variables. The members of the union will still share the same memory. As an illustration of how the preceding anonymous union works, to use the `double` member, you could write this statement:

```
dval = 99.5; // Using a member of an anonymous union
```

As you can see, there's nothing to distinguish the variable `dval` as a union member. If you need to use anonymous unions, you could use a naming convention to make the members more obvious and thus make your code a little less obscure.

Unions in Classes and Structures

You can include an instance of a union in a class or in a structure. If you intend to store different types of values at different times, this usually necessitates maintaining a class member to indicate what kind of value is stored in the union. There isn't usually a great deal to be gained by using unions as class or struct members.

OPERATOR OVERLOADING

Operator overloading is a very important capability because it enables you to make standard C++ operators, such as `+`, `-`, `*`, and so on, work with objects of your own data types. It allows you to write a function that redefines an operator so that it performs a particular action when it's used with objects of a class type. For example, you could redefine the operator `<` so that when it was used with objects of the `CBox` class, it would return `true` if the first `CBox` argument had a smaller volume than the second.

Operator overloading doesn't allow you to invent new operators, nor can you change operator precedence, so your overloaded version of an operator will have the same priority in the sequence of evaluating an expression as the original operator. You can find the operator precedence table in Chapter 2 of this book and in the MSDN Library.

Although you can't overload all the operators, the restrictions aren't particularly oppressive. These are the operators that you can't overload:

OPERATOR	DEFINITION
<code>::</code>	The scope resolution operator
<code>?:</code>	The conditional operator
<code>.</code>	The direct member selection operator
<code>sizeof</code>	The size-of operator
<code>.*</code>	The de-reference pointer to class member operator

Anything else is fair game, which gives you quite a bit of scope. Obviously, it's a good idea to ensure that your versions of the standard operators are reasonably consistent with their normal usage, or at least reasonably intuitive in their operation. It wouldn't be a very sensible approach to produce an overloaded + operator for a class that performed the equivalent of a multiply on class objects. The best way to understand how operator overloading works is to work through an example, so let's implement what I just referred to, the less-than operator, <, for the CBox class.

Implementing an Overloaded Operator

To implement an overloaded operator for a class, you have to write a special function. Assuming that it is a member of the CBox class, the declaration for the function to overload the < operator within the class definition will be as follows:

```
class CBox
{
public:
    bool operator<(const CBox& aBox) const; // Overloaded 'less than'

    // Rest of the class definition...
};
```

The word `operator` is a keyword. Combined with an operator symbol or name, in this case, <, it defines an operator function. The function name in this case is `operator<`. You can write an operator function with or without a space between the `operator` keyword and the operator itself, as long as there's no ambiguity. The ambiguity arises with operators with names rather than symbols such as `new` or `delete`. If you were to write `operatornew` and `operatordelete` without a space, they are legal names for ordinary functions, so for operator functions with these operators, you must leave a space between the keyword `operator` and the operator name. The strangest-looking name for an overloaded operator function is `operator()()`. This looks like a typing error, but it is, in fact, a function that overloads the function call operator, `()`. You declare `operator<()` as `const` because it doesn't modify the data members of the class.


With the `operator<()` function, the right operand of the operator is defined by the parameter. The left operand is defined implicitly by the pointer `this`. Suppose you have the following `if` statement:

```
if(box1 < box2)
    cout << endl << "box1 is less than box2";
```

The expression between the parentheses in the `if` will call our operator function, so the statement is equivalent to:

```
if(box1.operator<(box2))
    cout << endl << "box1 is less than box2";
```

The correspondence between the CBox objects in the expression and the operator function parameters is illustrated in Figure 8-3.

**FIGURE 8-3**

Let's look at how the code for the `operator<()` function works:

```

// Operator function for 'less than' which
// compares volumes of CBox objects.
bool CBox::operator<(const CBox& aBox) const
{
    return this->Volume() < aBox.Volume();
}

```

You use a reference parameter to avoid unnecessary copying when the function is called. Because the function does not alter the object for which it is called, you can declare the parameter as `const`. If you don't do this, you cannot use the operator with a `const CBox` object as the right operand. You also declare the function to be `const` because it does not modify the `CBox` object for which it is called.

The `return` expression uses the `Volume()` member to calculate the volume of the `CBox` object pointed to by `this`, and compares the result with the volume of `aBox` using the basic operator `<`.

Comparing `CBox` objects for equality is just as easy to implement:

```

bool CBox::operator==(const CBox& aBox) const
{
    return this->Volume() == aBox.Volume();
}

```

This implementation assumes two objects are equal if the volumes are the same. You might want to define equality differently though. A more stringent and perhaps more realistic implementation for equality might be that the objects had identical dimensions, but I'll leave that for you to explore.

TRY IT OUT Operator Overloading

You can exercise the operator functions for CBox objects with an example:

```
// Ex8_03.cpp
// Exercising the overloaded 'less than' and equality operators
#include <iostream> // For stream I/O
using std::cout;
using std::endl;

class CBox // Class definition at global scope
{
public:
    // Constructor definition
    explicit CBox(double lv = 1.0, double wv = 1.0, double hv = 1.0):
        m_Length(lv), m_Width(wv), m_Height(hv)
    {
        cout << endl << "Constructor called.";
    }

    // Function to calculate the volume of a box
    double Volume() const
    {
        return m_Length*m_Width*m_Height;
    }

    bool operator<(const CBox& aBox) const; // Overloaded 'less than'

    // Overloaded equality operator
    bool operator==(const CBox& aBox) const

    {
        return this->Volume() == aBox.Volume();
    }

    // Destructor definition
    ~CBox()
    {
        cout << "Destructor called." << endl;
    }

private:
    double m_Length; // Length of a box in inches
    double m_Width; // Width of a box in inches
    double m_Height; // Height of a box in inches
};

// Operator function for 'less than' that
// compares volumes of CBox objects.
inline bool CBox::operator<(const CBox& aBox) const
{
    return this->Volume() < aBox.Volume();
}

int main()
{
```

```

const CBox smallBox(4.0, 2.0, 1.0);
const CBox mediumBox(10.0, 4.0, 2.0);
CBox bigBox(30.0, 20.0, 40.0);
CBox thatBox(4.0, 2.0, 10.0);

if(mediumBox < smallBox)
    cout << endl << "mediumBox is smaller than smallBox";

if(mediumBox < bigBox)
    cout << endl << "mediumBox is smaller than bigBox";
else
    cout << endl << "mediumBox is not smaller than bigBox";

if(thatBox == mediumBox)
    cout << endl << "thatBox is equal to mediumBox";
else
    cout << endl << "thatBox is not equal to mediumBox";

cout << endl;
return 0;
}

```

How It Works

The prototype of the `operator<()` operator function appears in the `public` section of the class. Because the function definition is outside the class definition, it won't default to `inline` so you specify it explicitly. It's usually a good idea to make simple operator functions `inline` so the code will run faster. The only reason the definition is outside the class is to demonstrate the possibility. You could just as well have put the definition inside the class, like the `operator==()` function. Then you wouldn't need to specify `inline` or to qualify the function name with `CBox`. As you'll remember, the latter is necessary when you define a function member outside the class definition because the compiler needs to know that the function is a member of the `CBox` class.

The `main()` function has two `if` statements using the `<` operator with class members. These automatically invoke the overloaded operator function. If you wanted to get confirmation of this, you could add an output statement to the operator function. There is also a statement using the `==` operator. The output from this example is:

```

Constructor called.
Constructor called.
Constructor called.
Constructor called.
mediumBox is smaller than bigBox
thatBox is equal to mediumBox
Destructor called.
Destructor called.
Destructor called.
Destructor called.

```

The output demonstrates that the `if` statements work fine with our operator functions, and the operator overload works with `const` and non-`const` objects. Being able to express the solution to `CBox` problems directly in terms of `CBox` objects is beginning to be a realistic proposition.

Implementing Full Support for Comparison Operators

With the current version of `operator<()`, there are still a lot of things that you can't do. Specifying a problem solution in terms of `CBox` objects might well involve statements such as the following:

```
if(aBox < 20.0)
    // Do something...
```

Our class won't deal with that. If you try to use an expression comparing a `CBox` object with a numerical value, you'll get an error message. To support this capability, you would need to write another version of the `operator<()` function.

You can quite easily support the type of expression that you've just seen. The definition of the member function within the class would be:

```
// Function to compare a CBox object with a constant
bool CBox::operator<(const double& value) const
{
    return this->Volume() < value;
}
```

The right operand for the `<` operator corresponds to the function parameter. The `CBox` object that is the left operand will be passed as the implicit pointer `this`. This couldn't be much simpler, could it? But you still have a problem using the `<` operator with `CBox` objects. You may well want to write statements such as this:

```
if(20.0 < aBox)
    // do something...
```

You might argue that this could be done by implementing the `operator>()` operator function that accepted a right argument of type `double`, and rewriting the preceding statement to use it, which is quite true. Indeed, implementing the `>` operator is likely to be a requirement for comparing `CBox` objects, anyway, but an implementation of operator support for a type shouldn't artificially restrict the ways in which you can use the objects in an expression. The use of the objects should be as natural as possible. The problem is how to do it.

A member operator function always provides the left argument as the pointer `this`. Because the left argument is of type `double` in this case, you can't implement it as a member function. That leaves you with two choices: an ordinary function or a `friend` function. You don't need to access the private members of the class so it doesn't need to be a `friend` function. You can implement the overloaded `<` operator with a left operand of type `double` as an ordinary function like this:

```
// Function comparing a constant with a CBox object
inline bool operator<(const double& value, const CBox& aBox)
{
    return value < aBox.Volume();
```

As you have seen, an ordinary function (and a `friend` function, too, for that matter) accesses the public members of an object by using the direct member selection operator and the object name. The `Volume()` member is public, so there's no problem using it here.

If the class didn't have the `public` function `Volume()`, you could either declare the operator function a `friend` function that could access the `private` data members directly, or you could provide a set of member functions to return the values of the `private` data members and use those in an ordinary function to implement the comparison.

You still have quite a way to go yet. You still need the `>`, `>=`, `<=`, and `!=` operators. You could plow on and implement all of these yourself. However, the standard library can save you the trouble. The `utility` header defines a set of templates for operator functions as follows:

```
template <class T> bool operator!=(const T& x, const T& y); // Requires ==
template <class T> bool operator>(const T& x, const T& y); // Requires <
template <class T> bool operator<=(const T& x, const T& y); // Requires <
template <class T> bool operator>=(const T& x, const T& y); // Requires <
```

These templates create comparison operator functions for any class. The comments indicate that you must implement `operator<()` and `operator==()` for all these templates to be usable with a class. The templates are defined in the `std::rel_ops` namespace, so you can make the templates available within your source file with the following `using` directive:

```
using namespace std::rel_ops;
```

With that in place, you will get the four additional operator functions in a class for free. Let's try it.

TRY IT OUT Complete Overloading of the Comparison Operators

We can put all this together in an example to show how it works:

```
// Ex8_04.cpp
// Implementing the comparison operators
#include <iostream> // For stream I/O
#include <utility> // For operator overload templates
using std::cout;
using std::endl;
using namespace std::rel_ops;

class CBox // Class definition at global scope
{
public:
    // Constructor definition
    explicit CBox(double lv = 1.0, double wv = 1.0, double hv = 1.0):
        m_Length(lv), m_Width(wv), m_Height(hv)
    {
        cout << endl << "Constructor called.";
    }

    // Function to calculate the volume of a box
    double Volume() const
    {
        return m_Length*m_Width*m_Height;
    }
}
```

```
// Operator function for 'less than' that
// compares volumes of CBox objects.
bool operator<(const CBox& aBox) const
{
    return this->Volume() < aBox.Volume();
}

// 'Less than' operator function to compare a CBox object volume with a constant
bool operator<(const double& value) const
{
    return this->Volume() < value;
}

// 'Greater than' function to compare a CBox object volume with a constant
bool operator>(const double& value) const
{
    return this->Volume() > value;
}

// Overloaded equality operator
bool operator==(const CBox& aBox) const

{
    return this->Volume() == aBox.Volume();
}

// Destructor definition
~CBox()
{ cout << "Destructor called." << endl; }

private:
    double m_Length;                      // Length of a box in inches
    double m_Width;                        // Width of a box in inches
    double m_Height;                       // Height of a box in inches
};

// Function comparing a constant with a CBox object
inline bool operator<(const double& value, const CBox& aBox)
{
    return value < aBox.Volume();
}

int main()
{
    CBox smallBox(4.0, 2.0, 1.0);
    CBox mediumBox(10.0, 4.0, 2.0);
    CBox otherBox(2.0, 1.0, 4.0);

    if(mediumBox != smallBox)
        cout << endl << "mediumBox is not equal to smallBox";

    if(mediumBox > smallBox)
```

```

        cout << endl << "mediumBox is bigger than smallBox";
else
    cout << endl << "mediumBox is not bigger than smallBox";

if(otherBox >= smallBox)
    cout << endl << "otherBox is greater than or equal to smallBox";
else
    cout << endl << "otherBox is smaller than smallBox";

if(otherBox >= mediumBox)

    cout << endl << "otherBox is greater than or equal to mediumBox";
else
    cout << endl << "otherBox is smaller than mediumBox";

if(mediumBox > 50.0)
    cout << endl << "mediumBox capacity is more than 50";
else
    cout << endl << "mediumBox capacity is not more than 50";
if(10.0 < smallBox)
    cout << endl << "smallBox capacity is more than 10";
else
    cout << endl << "smallBox capacity is not more than 10";

cout << endl;
return 0;
}

```

How It Works

Note the position of the definition for the ordinary function version of `operator<()`. It needs to follow the class definition, because it refers to a `CBox` object. If you place it before the class definition, the example will not compile because the `CBox` type has not been defined at that point.

There is a way you could place the function prototype at the beginning of the source file. You can use an *incomplete class declaration*, also called a *forward declaration* of the class type. This would precede the function definition and the code would look like this:

```

class CBox;                                // Incomplete class declaration

inline bool operator<(const double& value, const CBox& aBox); // Prototype

```

The forward declaration identifies `CBox` to the compiler as a class and is sufficient to allow the compiler to process the function prototype properly. It tells the compiler that `CBox` is a user-defined type to be specified later.

This mechanism is essential in circumstances where you have two classes, each of which has a pointer to an object of the other class as a member. They will each require the other to be declared first. It is only possible to resolve such an impasse through the use of an incomplete class declaration.

NOTE You can have forward declarations for enum types as well as class types. For example:

```
enum class Suit;
```

This forward declaration allows you to use the Suit enum type to declare variables after this statement even though the enum type is not yet defined. However, you cannot refer to enumerators of the enum type until you supply the complete definition for the enum:

The output from the example is:

```
Constructor called.  
Constructor called.  
Constructor called.  
mediumBox is not equal to smallBox  
mediumBox is bigger than smallBox  
otherBox is greater than or equal to smallBox  
otherBox is smaller than mediumBox  
mediumBox capacity is more than 50  
smallBox capacity is not more than 10  
Destructor called.  
Destructor called.  
Destructor called.
```

Following the constructor messages due to the declarations of the CBox objects, you have the output lines from the if statements, each of which is working as you would expect. The first of these calls the operator!=() function that is generated by the compiler from the template provided by the utility header. The template requires a definition for the == operator function in the class.

The output demonstrates that all of the template-generated operator functions are working. As it happens, you could have made both the operator functions that you defined as class members ordinary functions, because they only need access to the volume() function, which is public.

You can implement comparison operators for any class type in much the same way as you have implemented them here. They would only differ in the details that depend on the nature of the objects.

```
enum class Suit{Clubs, Diamonds, Hearts, Spades};
```

Overloading the Assignment Operator

You know that if you don't provide an overloaded assignment operator function for your class, the compiler will provide a default. The default version will simply provide a member-by-member copying process, similar to that of the default copy constructor. Don't confuse the default copy constructor with the default assignment operator. The copy constructor is called when you define a

class object that's initialized with an existing object of the same class. It will also be called when you pass an object to a function by value. The assignment operator is called when the left and the right sides of an assignment statement are objects of the same class type.

The default assignment operator works with no problem for the `CBox` class but for any class that has space for members allocated dynamically, you must implement the assignment operator. There will be considerable potential for chaos in your program if you leave the assignment operator out under these circumstances.

Let's return to the `CMessage` class that I used when I was talking about copy constructors. You'll remember it had a member, `pmassage`, that was a pointer to a string. Now, consider the effect that the default assignment operator could have. Suppose you had two instances of the class, `motto1` and `motto2`. You could try setting the members of `motto2` equal to the members of `motto1` using the default assignment operator, as follows:

```
motto2 = motto1;           // Use default assignment operator
```

The effect of using the default assignment operator for this class is essentially the same as using the default copy constructor: disaster will result! Since each object will have a pointer to the same string, if the string is changed for one object, it's changed for both. There is also the problem that when one object is destroyed, its destructor will free the memory used for the string, and the other object will be left with a pointer to memory that may now be used for something else. What you need the assignment operator to do is to copy the text from the source object to a memory area owned by the destination object.

Fixing the Problem

You can fix this with your own assignment operator function, which I will assume is defined within the class definition. Here's a first stab at it, which I'll warn you now is not sufficient for proper operation:

```
// Overloaded assignment operator for CMessage objects
CMessage& operator=(const CMessage& aMess)
{
    // Release memory for 1st operand
    delete[] pmessage;
    pmessage = new char[strlen(aMess.pmessage) + 1];

    // Copy 2nd operand string to 1st
    strcpy_s(this->pmessage, strlen(aMess.pmessage) + 1, aMess.pmessage);

    // Return a reference to 1st operand
    return *this;
}
```

An assignment might seem very simple, but there's a couple of subtleties that need further investigation. First of all, note that you return a *reference* from the assignment operator function. It may not be immediately apparent why this is so — after all, the function does complete the assignment operation entirely, and the object on the right of the assignment will be copied to that on the left. Superficially, this would suggest that you don't need to return anything, but you need to consider in a little more depth how the operator might be used.

You might need to use the result of an assignment operation on the right-hand side of another assignment. Consider this statement:

```
motto1 = motto2 = motto3;
```

The assignment operator is right-associative so the assignment of `motto3` to `motto2` will be carried out first. The statement will translate into the following:

```
motto1 = (motto2.operator=(motto3));
```

The result of the operator function call is on the right of the equals sign, so the statement will finally become this:

```
motto1.operator=(motto2.operator=(motto3));
```

If this is to work, you certainly have to return something from the `operator=()` function. The function call between the parentheses must return an object that can be used as the argument to the other `operator=()` function call. In this case, a return type of either `CMessage` or `CMessage&` would do it, so a reference is not mandatory for this situation, but you must at least return a `CMessage` object.

However, consider the following example:

```
(motto1 = motto2) = motto3;
```

This is perfectly legitimate code — the parentheses serve to make sure the leftmost assignment is carried out first. This translates into the following statement:

```
(motto1.operator=(motto2)) = motto3;
```

When you express the remaining assignment operation as the explicit overloaded function call, this ultimately becomes:

```
(motto1.operator=(motto2)).operator=(motto3);
```

Now, you have a situation where the object returned from the `operator=()` function is used to call the `operator=()` function. If the return type is just `CMessage`, this will not be legal because a temporary copy of the original object is actually returned so it will be an rvalue, and the compiler will not allow a member function call using an rvalue. The only way to ensure this will compile and work correctly is to return a reference, which is an lvalue. The only possible return type if you want to allow fully flexible use of the assignment operator with your class objects is `CMessage&`.

Note that C++ does not enforce any restrictions on the accepted parameter or return types for the assignment operator, but it makes sense to declare the operator in the way I have just described if you want your assignment operator functions to support normal assignment usage.

Another subtlety is that each object already has memory for a string allocated, so the first thing that the operator function has to do is to delete the memory allocated to the first object and reallocate sufficient memory to accommodate the string belonging to the second object. Once this is done, the string from the second object can be copied to the new memory now owned by the first.

There's still a defect in this operator function. What if you were to write the following statement?

```
motto1 = motto1;
```

Obviously, you wouldn't do anything as stupid as this directly, but it could easily be hidden behind a pointer, as in the following statement,

```
motto1 = *pMessage;
```

If the pointer pMessage points to motto1, you essentially have the preceding assignment statement. In this case, the operator function as it stands will delete the memory for motto1, allocate some more memory based on the length of the string that has already been deleted, and try to copy the old memory, which, by then, could well have been corrupted. You can fix this by checking for identical left and right operands at the beginning of the function, so the definition of the operator=() function would become:

```
// Overloaded assignment operator for CMessage objects
CMessage& operator=(const CMessage& aMess)
{
    if(this != &aMess)                                // Check addresses are not equal
    {
        // Release memory for 1st operand
        delete[] pmassage;
        pmassage = new char[strlen(aMess.pmessage) + 1];

        // Copy 2nd operand string to 1st
        strcpy_s(this->pmassage, strlen(aMess.pmessage)+1, aMess.pmessage);

    }
    // Return a reference to 1st operand
    return *this;
}
```

TRY IT OUT Overloading the Assignment Operator

You can put the full operator=() function implementation in a working example. You'll add a Reset() function to the CMessage class that just resets the message to a string of asterisks.

```
// Ex8_05.cpp
// Overloaded assignment operator working well
#include <iostream>
#include <cstring>
using std::cout;
using std::endl;

class CMessage
{
private:
    char* pmassage;                                // Pointer to object text string

public:
    // Function to display a message
    void ShowIt() const
    {
        cout << endl << pmassage;
    }
}
```

```
}

//Function to reset a message to *
void Reset()
{
    char* temp = pmessage;
    while(*temp)
        *(temp++) = '*';
}

// Overloaded assignment operator for CMessage objects
CMessage& operator=(const CMessage& aMess)
{
    if(this != &aMess)                      // Check addresses are not equal
    {
        // Release memory for 1st operand
        delete[] pmessage;
        pmessage = new char[strlen(aMess.pmessage) + 1];

        // Copy 2nd operand string to 1st
        strcpy_s(this->pmessage, strlen(aMess.pmessage)+1, aMess.pmessage);

    }
    // Return a reference to 1st operand
    return *this;
}

// Constructor definition
CMessage(const char* text = "Default message")
{
    pmessage = new char[strlen(text) + 1];      // Allocate space for text
    strcpy_s(pmessage, strlen(text)+1, text);    // Copy text to new memory
}

// Copy constructor definition
CMessage(const CMessage& aMess)
{
    size_t len = strlen(aMess.pmessage)+1;
    pmessage = new char[len];
    strcpy_s(pmessage, len, aMess.pmessage);
}

// Destructor to free memory allocated by new
~CMessage()
{
    cout << "Destructor called."           // Just to track what happens
        << endl;
    delete[] pmessage;                  // Free memory assigned to pointer
}
};

int main()
{
    CMessage motto1("The devil takes care of his own");
    CMessage motto2;
```

```

cout << "motto2 contains - ";
motto2.ShowIt();
cout << endl;

motto2 = motto1;                                // Use new assignment operator

cout << "motto2 contains - ";
motto2.ShowIt();
cout << endl;

motto1.Reset();                                 // Setting motto1 to * doesn't
                                                // affect motto2
cout << "motto1 now contains - ";
motto1.ShowIt();
cout << endl;

cout << "motto2 still contains - ";
motto2.ShowIt();
cout << endl;

return 0;
}

```

You can see from the output that everything works exactly as required, with no linking between the messages of the two objects:

```

motto2 contains -
Default message
motto2 contains -
The devil takes care of his own
motto1 now contains -
*****
motto2 still contains -
The devil takes care of his own
Destructor called.
Destructor called.

```

So you have another golden rule out of all of this:

Always implement an assignment operator function if you allocate space dynamically for a data member of a class.

Having implemented the assignment operator, what happens with operations such as `+=?` Well, they don't work unless you implement them. For each form of `op=` that you want to use with your class objects, you need to write another operator function.

Overloading the Addition Operator

Let's look at overloading the addition operator for our `CBox` class. This is interesting because it involves creating and returning a new object. The new object will be the sum (whatever you define that to mean) of the two `CBox` objects that are its operands.

So what do we want the sum of two boxes to mean? Well, there are quite a few legitimate possibilities, but we'll keep it simple here. Let's define the sum of two CBox objects as a CBox object that is large enough to contain the other two boxes stacked on top of each other. Ideally, you want to join the boxes by combining their shortest dimensions. You can do this by ensuring that the box length is always greater than or equal to the width, and the box width is always greater than or equal to the height. You can then make the new object have an `m_Length` member that is the larger of the `m_Length` members of the objects being added, and an `m_Width` member derived in a similar way. The `m_Height` member will be the sum of the `m_Height` members of the two operand objects, so that the resultant CBox object can contain the other two CBox objects. This isn't necessarily an optimal solution because one or other of the two boxes could be rotated about the height axis for a more efficient combination, but it will be sufficient for our purposes. By altering the constructor, we'll also arrange that the length, width and height of a CBox object are in descending magnitude.

Our version of the addition operation for boxes is easier to explain graphically, so it's illustrated in Figure 8-4.




FIGURE 8-4

Because it needs to access the private members of a `CBox` object, the `operator+()` function will be a member of the class. The declaration of the function within the class definition will be:

```
CBox operator+(const CBox& aBox) const; // Function adding two CBox objects
```

You define the parameter as a reference to avoid unnecessary copying of the right argument when the function is called, and you make it a `const` reference because the function does not modify the argument. If you don't declare the parameter as `const`, the compiler will not allow a `const` object to be passed to the function, so the right operand of `+` could not be a `const CBox` object. You also declare the function as `const` because it doesn't change the object for which it is called. Without this, the left operand of `+` could not be a `const` object.

You can define the function like this:

```
// Function to add two CBox objects
CBox CBox::operator+(const CBox& aBox) const
{
    // New object has larger length and width, and sum of heights
    return CBox(m_Length > aBox.m_Length ? m_Length : aBox.m_Length,
                m_Width > aBox.m_Width ? m_Width : aBox.m_Width,
                m_Height + aBox.m_Height);
}
```

You construct a local `CBox` object from the current object (`*this`) and the `aBox` object that is passed as the argument. Remember that the return process will make a temporary copy of the local `CBox` object you create and that is passed back to the calling function, not the local object, which is discarded on return from the function.

TRY IT OUT Exercising Our Addition Operator

You'll be able to see how the overloaded addition operator in the `CBox` class works in this example:

```
// Ex8_06.cpp
// Adding CBox objects
#include <iostream>                                // For stream I/O
#include <utility>                                 // For operator overload templates
using std::cout;
using std::endl;
using namespace std::rel_ops;

class CBox                                         // Class definition at global scope
{
public:
    // Constructor definition
    explicit CBox(double lv = 1.0, double wv = 1.0, double hv = 1.0): m_Height(hv)
    {
        m_Length = std::max(lv, wv);
        m_Width = std::min(lv, wv);

        // Length is now greater than or equal to width
        if(m_Height > m_Length)
```

```
{  
    m_Height = m_Length;  
    m_Length = hv;  
  
    // m_Height is still greater than m_Width so swap them  
    double temp = m_Width;  
    m_Width = m_Height;  
    m_Height = temp;  
}  
else if( m_Height > m_Width)  
{  
    m_Height = m_Width;  
    m_Width = hv;  
}  
}  
  
// Function to calculate the volume of a box  
double Volume() const  
{  
    return m_Length*m_Width*m_Height;  
}  
  
// Operator function for 'less than' that  
// compares volumes of CBox objects.  
bool operator<(const CBox& aBox) const  
{  
    return this->Volume() < aBox.Volume();  
}  
  
// 'Less than' operator function to compare a CBox object volume with a constant  
bool operator<(const double& value) const  
{  
    return this->Volume() < value;  
}  
  
// 'Greater than' function to compare a CBox object volume with a constant  
bool operator>(const double& value) const  
{  
    return this->Volume() > value;  
}  
  
// Overloaded equality operator  
bool operator==(const CBox& aBox) const  
{  
    return this->Volume() == aBox.Volume();  
}  
  
// Function to add two CBox objects  
CBox operator+(const CBox& aBox) const  
{  
    // New object has larger length & width, and sum of heights  
    return CBox(m_Length > aBox.m_Length ? m_Length : aBox.m_Length,  
               m_Width > aBox.m_Width ? m_Width : aBox.m_Width,  
               m_Height + aBox.m_Height);  
}
```

```

// Function to show the dimensions of a box
void ShowBox() const
{
    cout << m_Length << " " << m_Width << " " << m_Height << endl;
}

private:
    double m_Length;                      // Length of a box in inches
    double m_Width;                       // Width of a box in inches
    double m_Height;                      // Height of a box in inches
};

// Function comparing a constant with a CBox object
inline bool operator>(const double& value, const CBox& aBox)
{
    return value > aBox.Volume();
}

int main()
{
    CBox smallBox(4.0, 2.0, 1.0);
    CBox mediumBox(10.0, 4.0, 2.0);
    CBox aBox;
    CBox bBox;

    cout << "smallBox dimensions are ";
    smallBox.ShowBox();

    cout << "mediumBox dimensions are ";
    mediumBox.ShowBox();

    aBox = smallBox + mediumBox;
    cout << "aBox = smallBox + mediumBox. Dimensions are "
    aBox.ShowBox();

    bBox = aBox + smallBox + mediumBox;
    cout << "bBox = aBox + smallBox + mediumBox. Dimensions are "
    bBox.ShowBox();

    return 0;
}

```

You'll be using the `CBox` class definition again a few pages down the road in this chapter, so note that you'll want to return to this point in the book.

How It Works

I changed the `CBox` class members a little in this example. I deleted the destructor because it isn't necessary for this class, and I modified the constructor to ensure that the `m_Length`, `m_Width`, and `m_Height` members are in descending order of magnitude. This uses the `max()` and `min()` function from the C++ library. I've also added the `ShowBox()` function to output the dimensions of an object. We can use this to verify that our overloaded addition operation is working.

The output from this program is:

```
smallBox dimensions are 4 2 1
mediumBox dimensions are 10 4 2
aBox = smallBox + mediumBox. Dimensions are 10 4 3
bBox = aBox + smallBox + mediumBox. Dimensions are 10 6 4
```

This seems to be consistent with the notion of adding CBox objects that we have defined, and, as you can see, the function also works with multiple add operations in an expression. For the computation of bBox, the overloaded addition operator is called twice. The result shows the combination is not optimum.

You could have implemented the addition operation as a `friend` function. Its prototype would then be:

```
friend CBox operator+(const CBox& aBox, const CBox& bBox);
```

The process for producing the result would be much the same, except that you would use the direct member selection operator to obtain the members for both the arguments to the function.

Overloading the Increment and Decrement Operators

I'll briefly introduce the mechanism for overloading the increment and decrement operators in a class because they have some special characteristics that make them different from other unary operators. You need a way to deal with the fact that the `++` and `--` operators come in a prefix and postfix form, and the effect is different depending on whether the operator is applied in its prefix or postfix form. The overloaded operator is different for the prefix and postfix forms of the increment and decrement operators. Here's how they would be defined in a class with the name `Length`, for example:

```
class Length
{
    private:
        double len;                                // Length value for the class

    public:
        Length& operator++();                      // Prefix increment operator
        const Length operator++(int);               // Postfix increment operator

        Length& operator--();                      // Prefix decrement operator
        const Length operator--(int);               // Postfix decrement operator

    // rest of the class...
};
```

This simple class assumes a length is stored just as a value of type `double`. You would probably make a length class more sophisticated than this but it will serve to illustrate how you overload these operators.

The prefix and postfix forms of the operator functions are differentiated by the parameter list; for the prefix form, there are no parameters and for the postfix form there is a parameter of type `int`. The parameter in the postfix operator function is only there to distinguish it from the prefix form and is unused in the function implementation.

The prefix increment and decrement operators increment or decrement the operand before its value is used in an expression, so you just return a reference to the current object after it has been incremented or decremented. Here's how an implementation of the prefix `operator++()` function would look for the `Length` class:

```
inline Length& Length::operator++()
{
    ++(this->len);
    return *this;
}
```

With the postfix forms, the operand is incremented after its current value is used in an expression. You achieve this by creating a new object that is a copy of the current object before you increment the current object and you return the copy after you have modified the current object. Here's how you might implement the postfix `++` operator for the `Length` class:

```
inline const Length Length::operator++(int)
{
    Length length(*this);           // Copy the current object
    ++*this;                      // Increment the current object
    return length;                // Return the original copy
}
```

After copying the current object, you increment it using the prefix `++` operator for the class. You then return the original, unincremented copy of the current object; it is this value that will be used in the expression in which the operator appears. Specifying the return value as `const` prevents expressions such as `data++++` from compiling.

Overloading the Function Call Operator

The function call operator is `()`, so the function overload for this is `operator()()`. An object of a class that overloads the function call operator is referred to as a *function object* or *functor* because you can use an object name as though it is the name of a function. Let's look at a simple example. Here's a class that overloads the function call operator:

```
class Area
{
public:
    int operator()(int length, int width) { return length*width; }
};
```

The function call operator in this class calculates an area as the product of its integer arguments. To use this operator function, you just need to create an object of type `Area`, for example:

```
Area area;                                // Create function object
int pitchLength(100), pitchWidth(50);
int pitchArea = area(pitchLength, pitchWidth); // Execute function call overload
```

The first statement creates the `area` object that is used in the third statement to call the function call operator for the object. This returns the area of a football pitch, in this case.

Of course, you can pass a function object to another function, just as you would any other object. Look at this function:

```
void printArea(int length, int width, Area& area)
{
    cout << "Area is " << area(length, width);
}
```

Here is a statement that uses this function:

```
printArea(20, 35, Area());
```

This statement calls the `printArea()` function with the first two arguments specifying the length and width of a rectangle. The third argument calls the default `Area` class constructor to create an object that is used in the function to calculate an area. Thus, a function object provides you with a way of passing a function as an argument to another function that is simpler and easier to work with than using pointers to functions.

NOTE In Chapter 10 you'll learn about the `std::function<>` template that provides more flexibility in passing functions around.

Classes that define function objects typically do not need data members and do not have a constructor defined, so there is minimal overhead in creating and using function objects. Function object classes are usually defined as templates because this makes them very flexible, as you'll see later in this chapter.

THE OBJECT COPYING PROBLEM

Copying is implicit in passing arguments by value to a function. This is not a problem when the argument is of a fundamental type, but for arguments that are objects of a class type, it can be. The overhead arising from copying an object can be considerable, especially when the object is large or owns memory that was allocated dynamically. Copying an object is achieved by calling the class copy constructor, so the efficiency of this function is critical to execution performance. As you saw with the `CMessage` class, the assignment operator also involves copying an object. However, there are circumstances where such copy operations are not really necessary, and if you can find a way to avoid them in such situations, execution time can be reduced. Rvalue reference parameters are the key to making this possible.

Avoiding Unnecessary Copy Operations

A modified version of the `CMessage` class from `Ex8_05.cpp` will provide a basis for seeing how this works. Here's a version of the class that implements the addition operator:

```

class CMessage
{
private:
    char* pmessage; // Pointer to object text string

public:
    // Function to display a message
    void ShowIt() const
    {
        cout << endl << pmessage;
    }

    // Overloaded addition operator
    CMessage operator+(const CMessage& aMess) const
    {
        cout << "Add operator function called." << endl;
        size_t len = strlen(pmessage) + strlen(aMess.pmessage) + 1;
        CMessage message;
        message.pmessage = new char[len];
        strcpy_s(message.pmessage, len, pmessage);
        strcat_s(message.pmessage, len, aMess.pmessage);
        return message;
    }

    // Overloaded assignment operator for CMessage objects
    CMessage& operator=(const CMessage& aMess)
    {
        cout << "Assignment operator function called." << endl;
        if(this != &aMess) // Check addresses are not equal
        {
            // Release memory for 1st operand
            delete[] pmessage;
            pmessage = new char[strlen(aMess.pmessage) + 1];

            // Copy 2nd operand string to 1st
            strcpy_s(this->pmessage, strlen(aMess.pmessage)+1, aMess.pmessage);

        }
        return *this; // Return a reference to 1st operand
    }

    // Constructor definition
    CMessage(const char* text = "Default message")
    {
        cout << "Constructor called." << endl;
        pmessage = new char[strlen(text) + 1]; // Allocate space for text
        strcpy_s(pmessage, strlen(text)+1, text); // Copy text to new memory
    }
}

```

```

// Copy constructor definition
CMessage(const CMessage& aMess)
{
    cout << "Copy constructor called." << endl;
    size_t len = strlen(aMess.pmessage)+1;
    pmessage = new char[len];
    strcpy_s(pmessage, len, aMess.pmessage);
}

// Destructor to free memory allocated by new
~CMessage()
{
    cout << "Destructor called."      // Just to track what happens
        << endl;
    delete[] pmessage;             // Free memory assigned to pointer
}
};


```

The changes from the version in `Ex8_05.cpp` are highlighted. There is now output from the constructor and the assignment operator functions to trace when they are called. There is also a copy constructor and the `operator+()` function for adding two `CMessage` objects. You could add versions for concatenating a `CMessage` object with a string literal, but it's not needed here. Let's see how often copying occurs with some simple operations on `CMessage` objects.

TRY IT OUT Tracing Object Copy Operations

Here's the code to exercise the `CMessage` class:

```

// Ex8_07.cpp
// How many copy operations?
#include <iostream>
#include <cstring>
using std::cout;
using std::endl;

// Insert CMessage class definition here...

int main()
{
    CMessage motto1("The devil takes care of his own. ");
    CMessage motto2("If you sup with the devil use a long spoon.\n");
    CMessage motto3;
    cout << " Executing: motto3 = motto1 + motto2 " << endl;
    motto3 = motto1 + motto2;
    cout << " Done!! " << endl << endl;

    cout << " Executing: motto3 = motto3 + motto1 + motto2 " << endl;
    motto3 = motto3 + motto1 + motto2;
    cout << " Done!! " << endl << endl;

    cout << "motto3 contains - ";
    motto3.ShowIt();
}

```

```

    cout << endl;
    return 0;
}

```

This example produces the following output:

```

Constructor called.
Constructor called.
Constructor called.
Executing: motto3 = motto1 + motto2
Add operator function called.
Constructor called.
Copy constructor called.
Destructor called.
Assignment operator function called.
Destructor called.
Done!! 

Executing: motto3 = motto3 + motto1 + motto2
Add operator function called.
Constructor called.
Copy constructor called.
Destructor called.
Add operator function called.
Constructor called.
Copy constructor called.
Destructor called.
Assignment operator function called.
Destructor called.
Destructor called.
Done!! 

motto3 contains -
The devil takes care of his own. If you sup with the devil use a long spoon.
The devil takes care of his own. If you sup with the devil use a long spoon.

Destructor called.
Destructor called.
Destructor called.

```

How It Works

The first statement of interest is:

```

motto3 = motto1 + motto2;           // Use new addition operator

```

This calls `operator+()` to add `motto1` and `motto2`, and the function calls the constructor to create the temporary object to be returned. The returned object is then copied by the copy constructor, and then destroyed, as you can see from the destructor call. The copy is then copied into `motto3` by the `operator=(())` function. Finally, the temporary object that is the right operand for the assignment is destroyed by calling the destructor. There are two operations that copy temporary objects (rvalues) as a result of this statement.

The second statement of interest is:

```
motto3 = motto3 + motto1 + motto2;
```

The `operator+()` function is called to concatenate `motto3` and `motto1`, and the function calls the constructor to create the result that is returned. The object returned is then copied using the copy constructor, and after the original object created within the function is destroyed by the destructor, the copy is concatenated with `motto2` by calling `operator+()` once more, and the sequence of calls is repeated. Finally, the `operator=(())` function is called to store the result. Thus, for this simple statement, we have three copy operations from temporary objects, two from copy constructor calls, and one from the assignment operator.

All of these copy operations could be very expensive in elapsed time if `CMessage` were a really large or complex object. If these copy operations could be avoided, you could improve execution efficiency considerably. Let's look at how you can do this.

Applying Rvalue Reference Parameters

When the source `CMessage` object is a temporary object that is going to be destroyed immediately after a copy operation, the alternative to copying it is to steal the memory that belongs to the temporary object (pointed to by its `pmessage` member) and transfer it to the destination object. If you can do this, you avoid the need to allocate more memory for the destination object, you don't need to copy the data, and there will be no need to release the memory owned by the source object. The source object is going to be destroyed immediately after the operation, so there is no risk in doing this — just faster execution. The key to being able to perform this trick is to detect when the source object in a copy operation is an rvalue. This is exactly what an rvalue reference parameter enables you to do.

You can create an additional overload for the `operator=(())` function like this:

```
CMessage& operator=(CMessage&& aMess)
{
    cout << "Move assignment operator function called." << endl;
    delete[] pmessage;           // Release memory for left operand
    pmessage = aMess.pmessage;   // Steal string from rhs object
    aMess.pmessage = nullptr;    // Null rhs pointer
    return *this;                // Return a reference to 1st operand
}
```

This operator function will be called when the right operand of an assignment is an rvalue — a temporary object. When the right operand is an lvalue, the original function with an lvalue reference parameter will be called. The rvalue reference version of the function deletes the string pointed to by the `pmessage` member of the destination object, and copies the address stored in the `pmessage` member of the source object. The `pmessage` member of the source object is then set to `nullptr`. It is essential that you do this; otherwise, the message would be deleted by the destructor call for the source object. Note that you must not specify the parameter as `const` in this case, because you are modifying it.

You can apply exactly the same logic to copy constructor operations by adding an overloaded copy constructor with an rvalue reference parameter:

```
CMessage(CMessage&& aMess)
{
    cout << "Move copy constructor called." << endl;
    pmessage = aMess.pmessage;
    aMess.pmessage = nullptr;
}
```

Instead of copying the message belonging to the source object to the object being constructed, you simply transfer the address of the message string from the source object to the new object, so, in this case, the copy is just a move operation. As before, you set `pmessage` for the source object to `nullptr` to prevent the message string from being deleted by the destructor.

TRY IT OUT Efficient Object Copy Operations

You can create a new console application, `Ex8_08`, and copy the code from `Ex8_07`. You can then add the overloaded `operator=()` and copy constructor functions that I just discussed to the `CMessage` class definition. This example will produce the following output:

```
Constructor called.
Constructor called.
Constructor called.
Executing: motto3 = motto1 + motto2
Add operator function called.
Constructor called.
Move copy constructor called.
Destructor called.
Move assignment operator function called.
Destructor called.
Done!!

Executing: motto3 = motto3 + motto1 + motto2
Add operator function called.
Constructor called.
Move copy constructor called.
Destructor called.
Add operator function called.
Constructor called.
Move copy constructor called.
Destructor called.
Move assignment operator function called.
Destructor called.
Destructor called.
Done!!

motto3 contains -
The devil takes care of his own. If you sup with the devil use a long spoon.
The devil takes care of his own. If you sup with the devil use a long spoon.
```

```
Destructor called.  
Destructor called.  
Destructor called.
```

How It Works

You can see that all of the operations in the previous example that involved copying an object now execute as move operations. The assignment operator function calls now use the version with the rvalue reference parameter, as do the copy constructor calls. The output shows that `motto3` ends up with the same string as before, so everything is working as it should.

For classes that define complex or large objects, overloading the assignment operator and copy constructor with versions that have an rvalue reference parameter can significantly improve performance.

NOTE If you define the `operator=()` function and the copy constructor in a class with the parameters as non-const rvalue references, make sure you also define the standard versions with const lvalue reference parameters. If you don't, the compiler will supply default versions of these that perform member-by-member copying. This will certainly not be what you want.

Named Objects are Lvalues

When the assignment operator function with the rvalue reference parameter in the `CMessage` class is called, you know for certain that the argument — the right operand — is an rvalue and is, therefore, a temporary object from which you can steal memory. However, within the body of this operator function, the parameter, `aMess`, is an lvalue. This is because any expression that is a named variable is an lvalue. This can result in inefficiencies creeping back in, as I can demonstrate through an example that uses a modified version of the `CMessage` class:

```
class CMessage
{
private:
    CText text; // Object text string

public:
    // Function to display a message
    void ShowIt() const
    {
        text.ShowIt();
    }

    // Overloaded addition operator
    CMessage operator+(const CMessage& aMess) const
    {
        cout << "CMessage add operator function called." << endl;
    }
}
```

```

    CMessage message;
    message.text = text + aMess.text;
    return message;
}

// Copy assignment operator for CMessage objects
CMessage& operator=(const CMessage& aMess)
{
    cout << "CMessage copy assignment operator function called." << endl;
    if(this != &aMess)                                // Check addresses not equal
    {
        text = aMess.text;
    }
    return *this;                                     // Return a reference to 1st operand
}

// Move assignment operator for CMessage objects
CMessage& operator=(CMessage&& aMess)
{
    cout << "CMessage move assignment operator function called." << endl;
    text = aMess.text;
    return *this;                                     // Return a reference to 1st operand
}

// Constructor definition
CMessage(const char* str = "Default message")
{
    cout << "CMessage constructor called." << endl;
    text = CText(str);
}

// Copy constructor definition
CMessage(const CMessage& aMess)
{
    cout << "CMessage copy constructor called." << endl;
    text = aMess.text;
}

// Move constructor definition
CMessage(CMessage&& aMess)
{
    cout << "CMessage move constructor called." << endl;
    text = aMess.text;
}
};


```

The text for the message is now stored as an object of type `CText`, and the member functions of the class have been changed accordingly. Note that the class is kitted out with rvalue reference versions of the copy constructor and the assignment operator, so it should move rather than create new objects when it is feasible to do so. Here's the definition of the `CText` class:

```

class CText
{
private:

```

```
char* pText;

public:
    // Function to display text
    void ShowIt() const
    {
        cout << pText << endl;
    }

    // Constructor
    CText(const char* pStr="No text")
    {
        cout << "CText constructor called." << endl;
        size_t len(strlen(pStr)+1);
        pText = new char[len];                                // Allocate space for text
        strcpy_s(pText, len, pStr);                           // Copy text to new memory
    }

    // Copy constructor definition
    CText(const CText& txt)
    {
        cout << "CText copy constructor called." << endl;
        size_t len(strlen(txt.pText)+1);
        pText = new char[len];
        strcpy_s(pText, len, txt.pText);
    }

    // Move constructor definition
    CText(CText&& txt)
    {
        cout << "CText move constructor called." << endl;
        pText = txt.pText;
        txt.pText = nullptr;
    }

    // Destructor to free memory allocated by new
    ~CText()
    {
        cout << "CText destructor called." << endl;      // Just to track what happens
        delete[] pText;                                    // Free memory
    }

    // Assignment operator for CText objects
    CText& operator=(const CText& txt)
    {
        cout << "CText assignment operator function called." << endl;
        if(this != &txt)                                  // Check addresses not equal
        {
            delete[] pText;                             // Release memory for 1st operand
            size_t len(strlen(txt.pText)+1);
            pText = new char[len];
        }

        // Copy 2nd operand string to 1st
```

```

        strcpy_s(this->pText, len, txt.pText);
    }
    return *this;                                // Return a reference to 1st operand
}

// Move assignment operator for CText objects
CText& operator=(CText&& txt)
{
    cout << "CText move assignment operator function called." << endl;
    delete[] pText;                            // Release memory for 1st operand
    pText = txt.pText;
    txt.pText = nullptr;
    return *this;                                // Return a reference to 1st operand
}

// Overloaded addition operator
CText operator+(const CText& txt) const
{
    cout << "CText add operator function called." << endl;
    size_t len(strlen(pText) + strlen(txt.pText) + 1);
    CText aText;
    aText.pText = new char[len];
    strcpy_s(aText.pText, len, pText);
    strcat_s(aText.pText, len, txt.pText);
    return aText;
}
};


```

It looks like a lot of code, but this is because the class has overloaded versions of the copy constructor and the assignment operator, and it has the `operator+()` function defined. The `CMessage` class makes use of these in the implementation of its member functions. There are also output statements to trace when each function is called. Let's exercise these classes with an example.

TRY IT OUT Creeping Inefficiencies

Here's a simple `main()` function that uses the `CMessage` copy constructor and assignment operator:

```

// Ex8_09.cpp Creeping inefficiencies
#include <iostream>
#include <cstring>
using std::cout;
using std::endl;

// Insert CText class definition here...
// Insert CMessage class definition here...

int main()
{
    CMessage motto1("The devil takes care of his own. ");
    CMessage motto2("If you sup with the devil use a long spoon.\n");

    cout << endl << " Executing: CMessage motto3(motto1+motto2); " << endl;
}


```

```
CMessage motto3(motto1+motto2);
cout << " Done!! " << endl << endl << "motto3 contains - ";
motto3.ShowIt();
CMessage motto4;
cout << endl << " Executing: motto4 = motto3 + motto2; " << endl;
motto4 = motto3 + motto2;
cout << " Done!! " << endl << endl << "motto4 contains - ";
motto4.ShowIt();
cout << endl;
return 0;
}
```

How It Works

It's a lot of output from relatively few statements in `main()`. I'll just discuss the interesting bits. Let's first consider the output arising from executing the statement:

```
CMessage motto3(motto1+motto2);
```

The output looks like this:

```
CMessage add operator function called.
CText constructor called.
CMessage constructor called.
CText constructor called.
CText move assignment operator function called.
CText destructor called.
CText add operator function called.
CText constructor called.
CText move copy constructor called.
CText destructor called.
CText move assignment operator function called.
CText destructor called.
CText constructor called.
CMessage move constructor called.
CText assignment operator function called.
CText destructor called.
```

To see what is happening, you need to relate the output messages to the code in the functions that are called. First, the `operator+()` function for the `CMessage` class is called to concatenate `motto1` and `motto2`. In the body of this function, the `CMessage` constructor is called to create the message object, and within this process, the `CText` constructor is called. Everything is going swimmingly until we get to the second to last line of output, following the line indicating the `CMessage` move constructor is called. When this constructor executes, the argument must have been a temporary — an rvalue — so the assignment statement in the body of the function that stores the value of the `text` member should be a move assignment operation for `CText` objects, not a copy assignment. The problem arises because within the `CMessage` move constructor, the `aMess` parameter is an lvalue because it has a name, in spite of the fact that we know for certain that the argument passed to the function was an rvalue. This means that `aMess.text` is also an lvalue. If it weren't, the `CMessage` copy constructor would be called.

The same problem arises with this statement:

```
motto4 = motto3 + motto2;
```

If you look at the output from this, you'll see that exactly the same problem arises when the move assignment operator for `CMessage` objects is called. The `text` member of the argument is copied when, really, it could be moved.

To fix these inefficiencies you need a way to force `aMess.text` to be an `rvalue` in the move assignment and move constructor functions in the `CMessage` class. The utility header in the C++ library thoughtfully provides you with the `std::move()` function that will do precisely what you want. This function returns whatever argument you pass to it as an `rvalue`. You can change the `CMessage` move constructor like this:

```
CMessage(CMessage&& aMess)
{
    cout << "CMessage move constructor called." << endl;
    text = std::move(aMess.text);
}
```

Now, the right-hand side of the assignment that sets up the `text` member of the new object is an `rvalue` so the move assignment operator function in the `CText` class will be called, not the copy assignment operator function.

You can modify the move assignment operator function in a similar way:

```
CMessage& operator=(CMessage&& aMess)
{
    cout << "CMessage move assignment operator function called." << endl;
    text = std::move(aMess.text);
    return *this;                                // Return a reference to 1st operand
}
```

The `std::move()` function is declared in the `utility` header, so you should add an `#include` directive for this to the example. If you recompile the program and execute it once more, the output will show that you now get the `CText` move assignment operator function called from the two functions you have modified. Implementing a constructor and an assignment operator function in a class so that they make use of the `std::move()` function is referred to as *move semantics*.

DEFAULT CLASS MEMBERS

It is useful to keep in mind everything that the compiler may supply by default for a class. Suppose you define a class like this:

```
class MyClass
{
    int data;
};
```

With just a single data member defined, you might imagine you can do very little with this class, but the compiler contributes some members. If you don't specify them, the compiler will supply definitions for:

- A default constructor:

```
MyClass() {}
```

- A copy constructor that does member-by-member copying:

```
MyClass(const MyClass& obj) /* Copy members */
```

- A destructor defined as:

```
~MyClass() {}
```

- A default assignment operator that does member-by-member copying:

```
MyClass& operator=(const MyClass& obj) /* Copy members */
```

WARNING Visual C++ does not implement automatically defined move constructors and move assignment operators which is not consistent with the C++ 11 language standard.

If you define any constructor, the default constructor will not be supplied. If you don't want the other default operations to be in effect, you must define them in your class and make them private so they cannot be accessed from outside of the class.

CLASS TEMPLATES

You saw in Chapter 6 that you could define a function template that would automatically generate functions varying in the type of arguments accepted, or in the type of values returned. C++ has a similar mechanism for classes. A *class template* is not, in itself, a class, but a sort of “recipe” for a class that will be used by the compiler to generate the code for a class. As Figure 8-5 shows, it's like a function template — you determine the class that you want generated by specifying your choice of type for the parameter (\mathbf{T} , in this case) that appears between the angled brackets in the template. This generates a particular class that is referred to as an *instance* of the template. Creating a class from a template is described as *instantiating* the template.




FIGURE 8-5

An appropriate class definition is generated when you instantiate an instance of a template class with a particular type parameter, so you can generate any number of different classes from one class template. You'll get a good idea of how this works in practice by looking at an example.

Defining a Class Template

I'll choose a simple example to illustrate how you define and use a class template, and I won't complicate things by worrying too much about possible errors that can arise if it's misused. Suppose you want to define classes that can store a number of data samples of some kind, and each class is to provide a `Max()` function to determine the maximum sample value of those stored. This function will be similar to the one you saw in the function template discussion in Chapter 6. You can define a class template to generate a `CSamples` class to store samples of any type:

```
template <class T>
class CSamples
{
public:
    // Constructor definition to accept an array of samples
    CSamples(const T values[], int count)
    {
        m_Free = count < maxSamples ? count : maxSamples; // Don't exceed the array
        for(int i = 0; i < m_Free; i++)
```

```

        m_Values[i] = values[i];           // Store count number of samples
    }

    // Constructor to accept a single sample
    CSamples(const T& value)
    {
        m_Values[0] = value;           // Store the sample
        m_Free = 1;                  // Next is free
    }

    // Default constructor
    CSamples() : m_Free(0) {}       // Nothing stored, so first is free

    // Function to add a sample
    bool Add(const T& value)
    {
        bool OK = m_Free < maxSamples; // Indicates there is a free place
        if(OK)
            m_Values[m_Free++] = value; // OK true, so store the value
        return OK;
    }

    // Function to obtain maximum sample
    T Max() const
    {
        // Set first sample as maximum
        T theMax = m_Values[0];

        for(int i = 1; i < m_Free; i++) // Check all the samples
            if(m_Values[i] > theMax)
                theMax = m_Values[i]; // Store any larger sample
        return theMax;
    }

private:
    static const size_t maxSamples = 100; // Maximum number of sample
    T m_Values[maxSamples];           // Array to store samples
    int m_Free;                      // Index of free location in m_Values
};

```

To indicate that you are defining a template, rather than a straightforward class, you insert the `template` keyword followed by the type parameter, `T`, between angled brackets, just before the `class` keyword and the class name. This is essentially the same syntax that you used to define a function template in Chapter 6. The parameter `T` is the type variable that will be replaced by a specific type when you declare a class object. Wherever the parameter `T` appears in the class definition, it will be replaced by the type that you specify in your object declaration; this creates a class definition corresponding to this type. You can specify any type (a basic data type or a class type), but it has to make sense in the context of the class template, of course. Any class type that you use to instantiate a class from a template must have all the operators defined that the member functions of the template will use with such objects. If your class hasn't implemented `operator>()`, for example, it will not work with the preceding `CSamples` class template. You can specify multiple parameters in a class template if you need them and I'll come back to this possibility later in the chapter.

Getting back to the example, the type of the array in which the samples will be stored is specified as `T`. The array will be an array of elements of whatever type you specify for `T` when you declare a `CSamples` object. As you can see, you also use the type `T` in two of the constructors as well as in the `Add()` and `Max()` functions. Each of these occurrences will also be replaced when you instantiate a class instance using the template.

The constructors support the creation of an empty object, an object with a single sample, and an object initialized with an array of samples. The `Add()` function allows samples to be added to an object one at a time. You could also overload this function to add an array of samples. The class template includes some elementary provision to prevent the capacity of the `m_Values` array being exceeded in the `Add()` function, and in the constructor that accepts an array of samples.

As I said earlier, in theory, you can create instances of `CSamples` classes that will handle any data type: type `int`, type `double`, type `CBox`, or any class type that you've defined. In practice, this doesn't mean it will necessarily compile and work as you expect. It all depends on what the template definition does, and usually, a template will only work for a particular range of types. For example, the `Max()` function implicitly assumes that the `>` operator is available for whatever type is being processed. If it isn't, your program will not compile. Clearly, you'll usually be in the position of defining a template that works for some types but not others, but there's no easy way you can restrict what type is applied to a template.

Template Member Functions

You may want to place the definition of a class template member function outside of the template definition. The syntax for this isn't particularly obvious, so let's look at how you do it. You put the function declaration in the class template definition in the normal way. For instance:

```
template <class T>
class CSamples
{
    // Rest of the template definition...
    T Max() const;           // Function to obtain maximum sample
    // Rest of the template definition...
}
```

This declares the `Max()` function as a member of the class template, but doesn't define it. You now need to create a separate function template for `Max()`. You must use the template class name plus the parameters in angled brackets to identify the class template to which the function template belongs:

```
template<class T>
T CSamples<T>::Max() const
{
    // Set first sample as maximum
    T theMax = m_Values[0];

    for(int i = 1; i < m_Free; i++)          // Check all the samples
        if(theMax < m_Values[i])
            theMax = m_Values[i];             // Store any larger sample
    return theMax;
}
```

You saw the syntax for a function template in Chapter 6. Since this function template is for a member of a class template with the parameter `T`, the function template definition here must have the same parameters as the class template definition. There's just one in this case — `T` — but in general there can be several. If the class template had two or more parameters, then so would each template defining a member function.

Note how you only put the parameter name, `T`, along with the class name before the scope resolution operator. This is necessary — the parameters are fundamental to the identification of the class to which a function, produced from the template, belongs. The type will be `CSamples<T>` with whatever type you assign to `T` when you create an instance of the class template. Your type is plugged into the class template to generate the class definition, and into the function template to generate the definition for the `Max()` function for the class. Each class that's produced from the class template needs to have its own definition for `Max()`.

Defining a constructor or a destructor outside of the class template definition is very similar. You could write the definition of the constructor that accepts an array of samples as:

```
template<class T>
CSamples<T>::CSamples(const T values[], int count)
{
    m_Free = count < maxSamples ? count : maxSamples; // Don't exceed the array

    for(int i = 0; i < m_Free; i++)
        m_Values[i] = values[i]; // Store count number of samples
}
```

You specify the class to which the constructor belongs in the template in the same way as for an ordinary member function. Note that the constructor name doesn't require the type parameter specification — it is just `CSamples`, but it must be qualified by the class template type `CSamples<T>`. You only use the parameter with the class template name *preceding* the scope resolution operator.

NOTE *If you have the implementation of member functions outside the class definition, they have to be in the header file that defines the class template; they cannot be in a .cpp file because the compiler needs to know the complete implementation of template functions at the point where you use them.*

Creating Objects from a Class Template

When you use a function defined by a function template, the compiler is able to deduce the template type arguments from the types of the function arguments. The type parameters for a function template are implicitly defined by the specific use of a particular function. Class templates are a little different. To create an object based on a class template, you must always specify the type parameters following the class name in the declaration.

For example, to declare a `CSamples<T>` object to handle samples of type `double`, you could write the declaration as:

```
CSamples<double> myData(10.0);
```

This defines an object of type `CSamples<double>` that can store samples of type `double`, and the object is created with one sample stored with the value 10.0.

TRY IT OUT Using a Class Template

You could create an object from a slightly extended version of the `CSamples<>` template to store `CBox` objects. This will work because the `CBox` class implements the `operator>()` function to overload the greater-than operator. You could exercise the class template with the `main()` function in the following code:

```
// Ex8_10.cpp
// Using a class template
#include <iostream>
#include <utility>                                // For operator overload templates
using std::cout;
using std::endl;
using namespace std::rel_ops;

// Put the CBox class definition from Ex8_06.cpp here...

// CSamples class template definition
template <class T> class CSamples
{
public:
    // Constructors
    CSamples(const T values[], int count);
    CSamples(const T& value);
    CSamples(T& value);
    CSamples() : m_Free(0) { }

    bool Add(const T& value);                      // Insert a value
    bool Add(T& value);                            // Insert a value with move semantics
    T Max() const;                                // Calculate maximum

private:
    static const size_t maxSamples = 100;           // Maximum number od sample
    T m_Values[maxSamples];                         // Array to store samples
    int m_Free;                                    // Index of free location in m_Values
};

// Constructor template definition to accept an array of samples
template<class T> CSamples<T>::CSamples(const T values[], int count)
{
    m_Free = count < 100 ? count : 100;           // Don't exceed the array
    for(int i = 0; i < m_Free; i++)
        m_Values[i] = values[i];                  // Store count number of samples
}

// Constructor to accept a single sample
template<class T> CSamples<T>::CSamples(T& value)
{
    m_Values[0] = value;                          // Store the sample
    m_Free = 1;                                  // Next is free
}

// Constructor to accept a temporary sample
template<class T> CSamples<T>::CSamples(T&& value)
```

```

{
    cout << "Move constructor." << endl;
    m_Values[0] = std::move(value);           // Store the sample
    m_Free = 1;                            // Next is free
}

// Function to add a sample
template<class T> bool CSamples<T>::Add(const T& value)
{
    cout << "Add." << endl;
    bool OK = m_Free < 100;                  // Indicates there is a free place
    if(OK)
        m_Values[m_Free++] = value;         // OK true, so store the value
    return OK;
}

template<class T> bool CSamples<T>::Add(T&& value)

{
    cout << "Add move." << endl;
    bool OK = m_Free < 100;                  // Indicates there is a free place
    if(OK)
        m_Values[m_Free++] = std::move(value); // OK true, so store the value
    return OK;
}

// Function to obtain maximum sample
template<class T> T CSamples<T>::Max() const
{
    T theMax = m_Values[0];                  // Set first sample as maximum
    for(int i = 1; i < m_Free; i++)          // Check all the samples
        if(theMax < m_Values[i])
            theMax = m_Values[i];             // Store any larger sample
    return theMax;
}

int main()
{
    CBox boxes[] = {                         // Create an array of boxes
                    CBox(8.0, 5.0, 2.0),      // Initialize the boxes...
                    CBox(5.0, 4.0, 6.0),
                    CBox(4.0, 3.0, 3.0)
                };

    // Create the CSamples object to hold CBox objects
    CSamples<CBox> myBoxes(boxes, _countof(boxes));

    CBox maxBox = myBoxes.Max();              // Get the biggest box
    cout << endl                             // and output its volume
    << "The biggest box has a volume of "
    << maxBox.Volume()
    << endl << endl;

    CSamples<CBox> moreBoxes(CBox(8.0, 5.0, 2.0));
    moreBoxes.Add(CBox(5.0, 4.0, 6.0));
    moreBoxes.Add(CBox(4.0, 3.0, 3.0));
}

```

```

cout << "The biggest box has a volume of "
    << moreBoxes.Max().Volume()
    << endl;
return 0;
}

```

You should replace the comment with the `CBox` class definition from `Ex8_06.cpp`. With the exception of the default constructor, all the member functions of the template are defined by separate function templates, just to show you a complete example of how it's done. The `CSamples` class template also includes a constructor and an `Add()` function with move semantics to show them in action.

In `main()`, you first create an array of three `CBox` objects and then use this array to initialize a `CSamples` object that can store `CBox` objects. The declaration of the `CSamples` object is basically the same as it would be for an ordinary class, but with the addition of the template type parameter in angled brackets following the template class name.

Next, you create the `moreBoxes` object but in a different way. This time the constructor and `Add()` function with move semantics are called because the arguments are rvalues.

The program will generate the following output:

```

The biggest box has a volume of 120
Move constructor.
Add move.
Add move.
The biggest box has a volume of 120

```

Note that when you create an instance of a class template, it does not follow that instances of the function templates for function members will also be created. The compiler will only create instances of templates for member functions that you actually call in your program. In fact, as with templates for ordinary functions, your function templates can even contain coding errors and, as long as you don't call the member function that the template generates, the compiler will not complain. You can test this out with the example. Try introducing a few errors into the template for the non-move `Add()` member. The program will still compile and run because it doesn't call that `Add()` function.

You could try modifying the example to see what happens when you instantiate classes by using the template with various other types.

NOTE You might be surprised at what happens if you add some output statements to the class constructors. The constructor for `CBox` is being called 103 times for the operations with `myBoxes` alone! Look at what is happening in `main()`. First, you create an array of three `CBox` objects, so that's three calls. You then create a `CSamples` object to hold them, but a `CSamples` object contains an array of 100 variables of type `CBox`, so you call the default constructor another 100 times, once for each array element. Of course, the `maxBox` object is created by the default copy constructor.

Class Templates with Multiple Parameters

Using multiple type parameters in a class template is a straightforward extension of the example using a single parameter. You can use each type parameter wherever you want in the template definition. For example, here's a class template with two type parameters:

```
template<class T1, class T2>
class CExampleClass
{
    // Class data members

    private:
        T1 m_Value1;
        T2 m_Value2;

    // Rest of the template definition...
};
```

The types of the two class data members shown will be determined by the types you supply for the parameters when you instantiate an instance of the class template. You can explicitly instantiate a template without defining any objects. For example, you can write the following statement after the definition of the CSamples template:

```
template class CSamples<Foo>;
```

This explicitly instantiates CSamples for type Foo, but it doesn't instantiate any objects yet. If Foo doesn't implement all the member functions required by the template, then the compiler will produce an error message with the above explicit instantiation, just as it would when you would define an object of this type.

The parameters in a class template aren't limited to types. You can also use parameters that require constants or constant expressions to be substituted in the class definition. In our CSamples template, we arbitrarily defined the m_Values array with 100 elements. You could, however, let the user of the template choose the size of the array when the object is instantiated, by defining the template as:

```
template <class T, size_t Size> class CSamples
{
    private:
        T m_Values[Size];           // Array to store samples
        int m_Free;                // Index of free location in m_Values

    public:
        // Constructor definition to accept an array of samples
        CSamples(const T values[], int count)
        {
            m_Free = count < Size ? count : Size; // Don't exceed the array

            for(int i = 0; i < m_Free; i++)
                m_Values[i] = values[i];          // Store count number of samples
        }
}
```

```

// Constructor to accept a single sample
CSamples(const T& value)
{
    m_Values[0] = value;                      // Store the sample
    m_Free = 1;                             // Next is free
}

CSamples() : m_Free(0) {}                  // Default constructor

// Function to add a sample
int Add(const T& value)
{
    int OK = m_Free < Size;                // Indicates there is a free place
    if(OK)
        m_Values[m_Free++] = value;        // OK true, so store the value
    return OK;
}

// Function to obtain maximum sample
T Max() const
{
    // Set first sample as maximum
    T theMax = m_Values[0];

    for(int i = 1; i < m_Free; i++)      // Check all the samples
        if(m_Values[i] > theMax)
            theMax = m_Values[i];          // Store any larger sample
    return theMax;
}
};

```

The value supplied for `Size` when you create an instance of the class template will replace the appearance of the parameter throughout the template definition. Now you can declare the `CSamples` object from the previous example as:

```
CSamples<CBox, 3> myBoxes(bboxes, _countof(bboxes));
```

Because you can supply *any* constant expression for the `Size` parameter, you could also have written this as:

```
CSamples<CBox, _countof(bboxes)> myBoxes(bboxes, _countof(bboxes));
```

The example is a poor use of a template, though — the original version was much more flexible. A consequence of making `Size` a template parameter is that instances of the template that store the same types of objects but have different size parameter values are totally different classes and cannot be mixed. For instance, an object of type `CSamples<double, 10>` cannot be used in an expression with an object of type `CSamples<double, 20>`.

You need to be careful with expressions that involve comparison operators when instantiating templates. Look at these statements:

```
CBox myBoxes[] = {CBox(1,2,3), CBox(2,3,4),CBox(4,5,6), CBox(5,7,8)};
CSamples<CBox, __countof(myBoxes) > 3 ? 3 : 2 > mySamples(myBoxes,4); // Wrong!
const int x = 2, y = 1;
CSamples<aType, x > y ? 10 : 20 > MyType();           // Wrong!
```

This will not compile correctly because the `>` following `__countof(myBoxes)` in the expression will be interpreted as a right-angled bracket. Instead, you should write this statement as:

```
CSamples<CBox, (__countof(myBoxes) > 3 ? 3 : 2) > mySamples(myBoxes,4);
```

The parentheses ensure that the expression for the second template argument is evaluated first and doesn't get mixed up with the angled brackets.

Templates for Function Objects

A class that defines function objects is typically defined by a template, for the obvious reason that it allows you to define function objects that will work with a variety of argument types. Here's a template for the `Area` class that you saw earlier:

```
template<class T> class Area
{
public:
    T operator()(const T length, const T width){ return length*width; }
};
```

This template will allow you to define function objects to calculate areas with dimensions of any numeric type. You can define the `printArea()` function that you saw earlier as a function template:

```
template<class T> void printArea(const T length, const T width, Area<T> area)
{ cout << "Area is " << area(length, width); }
```

Now, you can call the `printArea()` function like this:

```
printArea(1.5, 2.5, Area<double>());
printArea(100, 50, Area<int>());
```

Function objects are applied extensively with the Standard Template Library that you will learn about in Chapter 10, so you will see practical examples of their use in that context.

PERFECT FORWARDING

Perfect forwarding is an important concept because it can significantly improve performance with large objects that take significant time to copy or create. Perfect forwarding is only relevant in the context of a class or function template. At first sight it sounds a little complicated but once you grasp the idea, it is quite simple. So what is perfect forwarding?

Suppose you have a function, `fun1()`, that is parameterized by a class type, `T`. This could be defined by a function template or be within a class template. Suppose also that `fun1()` is defined with an

rvalue reference parameter of type `T&&`. You know from Chapter 6 that `fun1()` can be called with an argument that is an lvalue, an lvalue reference, or an rvalue. An lvalue or an lvalue reference argument results in the `fun1()` template instance having an lvalue reference parameter. Otherwise, it has an rvalue reference parameter.

Suppose further that `fun1()` calls another function, `fun2()`, that comes in two versions, one that has an lvalue reference parameter and another with an rvalue reference parameter. `fun1()` passes the argument it receives as the argument to `fun2()`. Ideally, when the argument received by `fun1()` is an rvalue reference, you want it to call the version of `fun2()` that has an rvalue reference parameter so there is no moving or copying of the original argument. When `fun1()` is instantiated and called with an lvalue or an lvalue reference argument, you want it to call the version of `fun2()` that has an lvalue reference parameter. You want *perfect forwarding* of the argument to `fun1()` in other words, so the code always maximizes efficiency.

What you need is a way to convert the parameter reference in `fun1()` from an lvalue to an rvalue when the argument is an rvalue so you can pass it to `fun2()` as an rvalue. Then there will be no copying or moving of the argument. When the argument to `fun1()` is an lvalue or an lvalue reference, you want it left as it is in the call to `fun2()`. This is precisely what the `std::forward()` function template that is declared in the `utility` header is designed to do. If you pass an rvalue reference argument to it, it returns it as an rvalue. If you pass an lvalue reference to it, it returns it as an lvalue reference. Let's see if it works.

TRY IT OUT Perfect Forwarding

This example uses the `string` class that I'll discuss in detail at the end of this chapter. In addition to showing perfect forwarding in action, the example demonstrates defining a template function as a member of a non-template class, and using a template with two type parameters. The example defines a `Person` class like this:

```
class Person
{
public:
    // Constructor template
    template<class T1, class T2>
    Person(T1&& first, T2&& second) :
        firstname(forward<T1>(first)), secondname(forward<T2>(second)) {}
    //    firstname(first), secondname(second) {}

    string getName() const
    {
        return firstname.getName() + " " + secondname.getName();
    }

private:
    Name firstname;
    Name secondname;
};
```

This is an ordinary class with the constructor defined by a template with two type parameters, `T1` and `T2`. This allows the constructor arguments to be of different types — type `string` and type `char*`, for

example. The data members that store the first and second name of a person are of type `Name`; I'll define the `Name` class in a moment. The `Person` constructor initializes the data members with the arguments after passing them to `std::forward()` from the `utility` header. This will ensure that an rvalue reference argument will remain as an rvalue reference when it is used to initialize a `Person` class data member. I'll come back to the commented-out line later. The `getName()` member returns a string representation of a `Person` object.

Here's the `Name` class definition:

```
class Name
{
public:
    Name(string& aName) : name(aName)
    {
        cout << "Lvalue Name constructor." << endl;
    }

    Name(string&& aName) : name(move(aName))
    {
        cout << "Rvalue Name constructor." << endl;
    }

    const string& getName() const { return name; }

private:
    string name;
};
```

This class encapsulates a single name as a `string` object. You can create a `string` object from a null-terminated string, or from another `string` object. The class has two constructors, one with an lvalue reference argument and the other with an rvalue reference argument. The latter will only be called when the argument is an rvalue reference. The reason for moving the rvalue reference argument is that the `string` class supports move semantics.

The program to use these classes is:

```
// Ex8_11.cpp
// Perfect forwarding
#include <iostream>
#include <utility>
#include <string>
using std::string;
using std::cout;
using std::endl;
using std::forward;
using std::move;

// Put the Name class definition here...

// Put the Person class definition here...

int main()
{
```

```

cout << "Creating Person(string(\"Ivor\"), string(\"Horton\")) - rvalue arguments:"
     << endl;
Person me(string("Ivor"), string("Horton"));
cout << "Person is " << me.getName() << endl << endl;

string first("Fred");
string second("Fernackerpan");
cout << "Creating Person(first, second) - lvalue arguments:" << endl;
Person other(first, second);
cout << "Person is " << other.getName() << endl << endl;

cout << "Creating Person(first, string(\"Bloggs\")) - lvalue, rvalue arguments:"
     << endl;
Person brother(first, string("Bloggs"));
cout << "Person is " << brother.getName() << endl << endl;

cout << "Creating Person(\"Richard\", \"Horton\") - rvalue const char* arguments:"
     << endl;
Person another("Richard", "Horton");
cout << "Person is " << another.getName() << endl << endl;

return 0;
}

```

The output from this example is:

```

Creating Person(string("Ivor"), string("Horton")) - rvalue arguments:
Rvalue Name constructor.
Rvalue Name constructor.
Person is Ivor Horton

Creating Person(first, second) - lvalue arguments:
Lvalue Name constructor.
Lvalue Name constructor.
Person is Fred Fernackerpan

Creating Person(first, string("Bloggs")) - lvalue, rvalue arguments:
Lvalue Name constructor.
Rvalue Name constructor.
Person is Fred Bloggs

Creating Person("Richard", "Horton") - rvalue const char* arguments:
Rvalue Name constructor.
Rvalue Name constructor.
Person is Richard Horton

```

How It Works

You can see from the output that the `Name` constructor with an lvalue reference parameter is called when the corresponding argument to the `Person` constructor is an lvalue reference, and the `Name` constructor that has an rvalue reference parameter is called when the `Person` constructor argument is an rvalue. Clearly the `std::forward()` function is working as advertised.

Now uncomment the commented-out line in the `Person` class and comment out the line above it. Now the constructor arguments are not being forwarded, and the output is:

```
Creating Person(string("Ivor") , string("Horton")) - rvalue arguments:  
Lvalue Name constructor.  
Lvalue Name constructor.  
Person is Ivor Horton  
  
Creating Person(first , second) - lvalue arguments:  
Lvalue Name constructor.  
Lvalue Name constructor.  
Person is Fred Fernackerpan  
  
Creating Person(first , string("Bloggs")) - lvalue, rvalue arguments:  
Lvalue Name constructor.  
Lvalue Name constructor.  
Person is Fred Bloggs  
  
Creating Person("Richard" , "Horton") - rvalue const char* arguments:  
Rvalue Name constructor.  
Rvalue Name constructor.  
Person is Richard Horton
```

Everything looks consistent with forwarding not being applied, except for the last `Person` object. How come the `Name` constructors with an `rvalue` reference parameter were called without forwarding? The answer is that a literal is always an `rvalue`. If presenting a literal argument as an `lvalue` was permitted, you would be able to modify it, which is somewhat contrary to the notion of what a literal is.

There is a significant aspect to the use of a template for the constructor in the `Person` class. It allows you to create a `Person` object from two arguments where each argument can be a temporary `string` object, an `lvalue` `string` object, a temporary null-terminated string, or an `lvalue` null-terminated string. To provide for this without using a template you would need to write sixteen `Person` class constructors. With the template, the source code is much shorter and will result in a smaller executable module if you use less than the sixteen possible combinations of constructor arguments.

USING CLASSES

I've touched on most of the basic aspects of defining a class, so maybe we should look at how a class might be used to solve a problem. The problem has to be simple in order to keep this book down to a reasonable number of pages, so I'll consider problems in which we can use an extended version of the `CBox` class.

The Idea of a Class Interface

The implementation of an extended `CBox` class should incorporate the notion of a *class interface*. You are going to provide a tool kit for anyone wanting to work with `CBox` objects, so you need to assemble a set of functions that represents the interface to the world of boxes. Because the interface

will represent the only way to deal with `CBox` objects, it needs to be defined to cover adequately the likely things one would want to do with a `CBox` object, and be implemented, as far as possible, in a manner that protects against misuse or accidental errors.

The first question that you need to consider in designing a class is the nature of the problem you intend to solve, and, from that, determine the kind of functionality you need to provide in the class interface.

Defining the Problem

The principal function of a box is to contain objects of one kind or another, so, in a word, the problem is *packaging*. We'll attempt to provide a class that eases packaging problems in general and then see how it might be used. We will assume that we'll always be working on packing `CBox` objects into other `CBox` objects since, if you want to pack candy in a box, you can always represent each of the pieces of candy as an idealized `CBox` object. The basic operations that you might want to provide in the `CBox` class include:

- Calculate the volume of a `CBox`. This is a fundamental characteristic of a `CBox` object, and you have an implementation of this already.
- Compare the volumes of two `CBox` objects to determine which is the larger. You probably should support a complete set of comparison operators for `CBox` objects.
- Compare the volume of a `CBox` object with a specified value, and vice versa.
- Add two `CBox` objects to produce a new `CBox` object that will contain both of the original objects. Thus, the result will be at least the sum of the volumes, but may be larger.
- Multiply a `CBox` object by an integer (and vice versa) to provide a new `CBox` object that will contain a specified number of the original objects. This is effectively designing a carton.
- Determine how many `CBox` objects of a given size can be packed in another `CBox` object of a given size. This is effectively division, so you could implement this by overloading the `/` operator.
- Determine the volume of space remaining in a `CBox` object after packing it with the maximum number of `CBox` objects of a given size.

I had better stop right there! There are undoubtedly other functions that would be useful but, in the interest of saving trees, we'll consider the set to be complete, apart from ancillaries such as accessing box dimensions.

Implementing the `CBox` Class

You really need to consider the degree of error protection that you want to build into the `CBox` class. The basic class that you defined to illustrate various aspects of classes is a starting point, but you should also consider some points a little more deeply. The constructor is a little weak in that it doesn't ensure that the dimensions for a `CBox` are valid, so, perhaps, the first thing you should do is to ensure that you always have valid objects. You could redefine the basic class as follows to do this:

```

class CBox                                // Class definition at global scope
{
public:
    // Constructor definition
    explicit CBox(double lv = 1.0, double wv = 1.0, double hv = 1.0): m_Height(hv)
    {
        if(lv < 0.0 || wv < 0.0 || hv < 0.0)
            throw "Negative dimension specified for CBox object.";

        m_Length = std::max(lv, wv);
        m_Width = std::min(lv, wv);

        // Length is now greater than or equal to width
        if(m_Height > m_Length)
        {
            m_Height = m_Length;
            m_Length = hv;

            // m_Height is still greater than m_Width so swap them
            double temp = m_Width;
            m_Width = m_Height;
            m_Height = temp;
        }
        else if( m_Height > m_Width)
        {
            m_Height = m_Width;
            m_Width = hv;
        }
    }

    // Function to calculate the volume of a box
    double Volume() const
    {
        return m_Length*m_Width*m_Height;
    }

    // Function providing the length of a box
    double GetLength() const { return m_Length; }

    // Function providing the width of a box
    double GetWidth() const { return m_Width; }

    // Function providing the height of a box
    double GetHeight() const { return m_Height; }

private:
    double m_Length;                         // Length of a box in inches
    double m_Width;                          // Width of a box in inches
    double m_Height;                        // Height of a box in inches
};

```

The constructor is now secure because any dimension that the user of the class tries to set to a value less than 0 will cause an exception to be thrown.

The default copy constructor and default assignment operator are satisfactory for the class, because you have no dynamic memory allocation for data members. The default destructor also works perfectly well in this case, so you do not need to define it. Perhaps now, you should consider what is required to support comparisons of objects of our class.

Comparing CBox Objects

You should support the operators `>`, `>=`, `==`, `!=`, `<`, and `<=` so that they all work with both operands as `CBox` objects, as well as between a `CBox` object and a value of type `double`. This totals eighteen operator functions. You can get four of these with both operands as `CBox` objects for free, courtesy of the templates in the utility header, once you have defined the `<` and `==` operator functions and you have seen how to do that in `Ex8_06`:

```
// Operator function for < comparing CBox objects
bool operator<(const CBox& aBox) const
{ return this->Volume() < aBox.Volume(); }

// Operator function for == comparing CBox objects
bool operator==(const CBox& aBox) const
{ return this->Volume() == aBox.Volume(); }
```

All the operator functions comparing a `CBox` left operand with a constant can be inside the class:

```
// Function for testing if a CBox object is > a value
bool operator>(const double& value) const
{ return Volume() > value; }

// Function for testing if a CBox object is < a value
bool operator<(const double& value) const
{ return Volume() < value; }

// Function for testing if a CBox object is >= a value
bool operator>=(const double& value) const
{ return Volume() >= value; }

// Function for testing if a CBox object is <= a value
bool operator<=(const double& value) const
{ return Volume() <= value; }

// Function for testing if a CBox object is == a value
bool operator==(const double& value) const
{ return Volume() == value; }

// Function for testing if a CBox object is != a value
bool operator!=(const double& value) const
{ return Volume() != value; }
```

Remember, these will be `inline` by default.

You must define those with a left operand of type `double` as ordinary functions outside the class:

```
// Function for testing if a value is > a CBox object
inline bool operator>(const double& value, const CBox& aBox)
{ return value > aBox.Volume(); }

// Function for testing if a value is < CBox object
inline bool operator<(const double& value, const CBox& aBox)
{ return value < aBox.Volume(); }

// Function for testing if a value is >= a CBox object
inline bool operator>=(const double& value, const CBox& aBox)
{ return value >= aBox.Volume(); }

// Function for testing if a value is <= CBox object
inline bool operator<=(const double& value, const CBox& aBox)
{ return value <= aBox.Volume(); }

// Function for testing if a value is == a CBox object
inline bool operator==(const double& value, const CBox& aBox)
{ return value == aBox.Volume(); }

// Function for testing if a value is != CBox object
inline bool operator!=(const double& value, const CBox& aBox)
{ return value != aBox.Volume(); }
```

You now have a complete set of comparison operators for `CBox` objects. Keep in mind that these will also work with expressions, as long as the expressions result in objects of the required type, so you will be able to combine them with the use of other overloaded operators.

Combining `CBox` Objects

Now, you come to the question of overloading the operators `+`, `*`, `/`, and `%`. I will take them in order. The add operation that you already have from `Ex8_06.cpp` has this prototype:

```
CBox operator+(const CBox& aBox) const; // Function adding two CBox objects
```

Although the original implementation of this isn't ideal, let's use it anyway to avoid overcomplicating the class. A better version would need to examine whether the operands had any faces with the same dimensions and, if so, join along those faces, but coding that could get a bit messy. Of course, if this were a practical application, a better add operation could be developed later and substituted for this version, and any programs written using the original would still run without change. The separation of the interface to a class from its implementation is crucial to good C++ programming.

Notice that I conveniently forgot the subtraction operator. This is a judicious oversight to avoid the complications inherent in implementing this when the result is to be a `CBox` object. If you're really enthusiastic about it, and you think it's a sensible idea, you can give it a try — but you need to decide what to do when the result has a negative volume. If you allow the concept, you need to resolve which box dimension or dimensions are to be negative, and how such a box is to be handled in subsequent operations. A simpler concept might be that subtracting `CBox` objects resulted in a volume.

The multiply operation is very easy. It represents the process of creating a box to contain n boxes, where n is the multiplier. The easiest solution would be to take the `m_Length` and `m_Width` of the object to be packed and multiply the height by n to get the new `CBox` object. You can make it a little cleverer by checking whether or not the multiplier is even and, if it is, stack the boxes side by side by doubling the `m_Width` value and only multiplying the `m_Height` value by half of n . This mechanism is illustrated in Figure 8-6 with examples of the `CBox` objects resulting from multiplying `aBox` by 3 and 6.




FIGURE 8-6

Of course, you don't need to check which is the larger of the length and width for the new object because the constructor sorts it out. You can write the `operator*()` function as a member function with the left operand as a `CBox` object like this:

```
// CBox multiply operator this*n
CBox operator*(int n) const
{
    if(n % 2)
        return CBox(m_Length, m_Width, n*m_Height);           // n odd
    else
        return CBox(m_Length, 2.0*m_Width, (n/2)*m_Height);   // n even
}
```

Here, you use the `%` operator to determine whether `n` is even or odd. If `n` is odd, the value of `n % 2` is 1 and the `if` statement is `true`. If it's even, `n % 2` is 0 and the statement is `false`.

You can now use the function you have just written in the implementation of the version with the left operand as an integer. You can write this as a non-member function:

```
// CBox multiply operator n*aBox
CBox operator*(int n, const CBox& aBox)
{
    return aBox*n;
}
```

This simply reverses the order of the operands so as to use the previous version of the function directly. That completes the set of arithmetic operators for `CBox` objects that we defined. You can now look at the two analytical operator functions, `operator/()` and `operator%()`.

Analyzing CBox Objects

The division operation will determine how many `CBox` objects identical to that specified by the right operand can be contained in the `CBox` object specified by the left operand. To keep it relatively simple, I'll assume that all the `CBox` objects are packed the right way up, that is, with the height dimensions vertical. I'll also assume that they are all packed the same way round, so that their length dimensions are aligned. Without these assumptions, it gets rather complicated.

The problem will amount to determining how many of the right-operand objects can be placed in a single layer inside the left-operand `CBox`, and then deciding how many layers you can get in it.

You can code this as a member function like this:

```
int operator/(const CBox& aBox) const
{
    // Number of boxes in horizontal plane this way
    int tc1 = static_cast<int>((m_Length / aBox.m_Length)) *
               static_cast<int>((m_Width / aBox.m_Width));

    // Number of boxes in horizontal plane that way
    int tc2 = static_cast<int>((m_Length / aBox.m_Width)) *
               static_cast<int>((m_Width / aBox.m_Length));

    //Return best fit
    return static_cast<int>((m_Height/aBox.m_Height)*(tc1 > tc2 ? tc1 : tc2));
}
```

You first determine how many of the right-operand `CBox` objects can fit in a layer with their lengths aligned with the length dimension of the left-operand `CBox`. This is stored in `tc1`. You then calculate how many can fit in a layer with the lengths of the right-operand `CBoxes` lying in the width direction of the left-operand `CBox`. Finally, you multiply the larger of `tc1` and `tc2` by the number of layers you can pack in, and return that value. This process is illustrated in Figure 8-7.




FIGURE 8-7

Consider two possibilities: fitting `bBox` into `aBox` with the length aligned with that of `aBox`, and then with the length of `bBox` aligned with the width of `aBox`. You can see from Figure 8-7 that the best packing results from rotating `bBox` so that the width divides into the length of `aBox`.

The other analytical operator function, `operator%()`, for obtaining the free volume in a packed `aBox` is easier, because you can use the operator you have just written to implement it. You can write it as an ordinary global function because you don't need access to the private members of the class.

```
// Operator to return the free volume in a packed box
inline double operator%(const CBox& aBox, const CBox& bBox)
{
    return aBox.Volume() - ((aBox/bBox)*bBox.Volume());
}
```

This computation falls out very easily using existing `CBox` class functions. The result is the volume of the big box, `aBox`, minus the volume of the `bBox` boxes that can be stored in it. The number of `bBox` objects packed into `aBox` is given by the expression `aBox/bBox`, which uses the previous overloaded operator. You multiply this by the volume of `bBox` objects to get the volume to be subtracted from the volume of the large box, `aBox`.

That completes the class interface. Clearly, there are many more functions that might be required for a production problem solver but, as an interesting working model demonstrating how you can produce a class for solving a particular kind of problem, it will suffice. Now you can go ahead and try it out on a real problem.

TRY IT OUT A Multifile Project Using the CBox Class

Before you can actually start writing the code to use the `CBox` class and its overloaded operators, you need to assemble the definition for the class into a coherent whole. You're going to take a rather different approach from what you've seen previously, in that you're going to create multiple files for the project. You're also going to start using the facilities that Visual C++ provides for creating and maintaining code for your classes. This will mean that you do rather less of the work, but it will also mean that the code will be slightly different in places.

Start by creating a new Win32 project for a console application called `Ex8_12` and checking the Empty project application option. If you select the Class View tab, you'll see the window shown in Figure 8-8. Don't forget to set the Character Set property for the project to Not Set.

Figure 8-8 shows a view of all the classes in a project but, of course, there are none here for the moment. Although there are no classes defined — or anything else, for that matter — Visual C++ has already made provision for including some. You can use Visual C++ to create a skeleton for the `CBox` class, and the files that relate to it, too. Right-click `Ex8_12` in Class View and select `Add Class...` from the pop-up menu that appears. You can then select `C++` from the class categories in the left pane of the Add Class dialog that is displayed and the `C++ Class` template in the right pane, and press Enter. (Ignore the Name and Location entry fields in this dialog. They are disabled and not used.) You will then be able to enter the name of the class that you want to create, `CBox`, in the dialog, as shown in Figure 8-9.




FIGURE 8-8




FIGURE 8-9

The name of the file that's indicated on the dialog, `Box.cpp`, will be used to contain the *class implementation*, which consists of the definitions for the function members of the class that do not appear in the class definition. This is the executable code for the class. You can change the name of this file, if you want, but `Box.cpp` looks like a good name for the file. The class definition will be stored in a file called `Box.h`. This is the standard way of structuring a program. Code that consists of class definitions is stored in files with the extension `.h`, and code that defines functions is stored in files with the extension `.cpp`. Usually, each class definition goes in its own `.h` file, and each class implementation goes in its own `.cpp` file.

When you click the Finish button in the dialog, two things happen:

1. A file `Box.h` is created, containing a skeleton definition for the class `CBox`. This includes a no-argument constructor and a destructor.
2. A file `Box.cpp` is created, containing a skeleton implementation for the functions in the class with definitions for the constructor and the destructor — both bodies are empty, of course.

The editor pane now displays the code for the class definition that is in `Box.h`. The second tab in the editor pane displays the contents of `Box.cpp`, which is the skeleton implementations for the constructor and destructor.

Let's start developing the `CBox` class based on what Visual C++ has provided automatically for us.

Defining the CBox Class

If you click the  to the left of `Ex8_12` in the `Class View`, the tree will be expanded and you will see that `CBox` is now defined for the project. All the classes in a project are displayed in this tree. You can view the source code supplied for the definition of a class by double-clicking the class name in the tree, or by clicking the tabs above the pane displaying the code.

The `CBox` class definition that was generated starts with a preprocessor directive:

```
#pragma once
```

The effect of this is to prevent the file from being opened and included in the source code more than once by the compiler in a build. Typically, a header file containing a given class definition may be included into several files in a project, including other header files, because each file that references the name of the class will need access to its definition. This can result in the contents of a header file potentially appearing more than once in a source file. Having more than one definition of a class in a build is not allowed and will be flagged as an error. Putting the `#pragma once` directive at the start of every header file will ensure this cannot happen.

`#pragma once` is a Microsoft-specific directive that may not be supported in other environments. If you are developing code that you anticipate may need to be compiled in other environments, you can use the following directives in a header file to achieve the same effect:

```
// Box.h header file
#ifndef BOX_H
#define BOX_H
// Code that must not be included more than once
// such as the CBox class definition
#endif
```

The important lines are bolded and correspond to directives that are supported by any C++ compiler. The lines following the `#ifndef` directive down to the `#endif` directive will be included in a build as long as the symbol `BOX_H` is not defined. The line following `#ifndef` defines the symbol `BOX_H`, thus ensuring that the code in this header file will not be included a second time. Thus, this has the same effect as placing the `#pragma once` directive at the beginning of a header file. Clearly, the `#pragma once` directive is simpler and less cluttered, so it's better to use that when you only expect to be using your code in the Visual C++ development environment. You will sometimes see the `#ifndef/#endif` combination written as:

```
#if !defined BOX_H
#define BOX_H
// Code that must not be included more than once
// such as the CBox class definition
#endif
```

The `Box.cpp` file that Class Wizard generated contains the following code:

```
#include "Box.h"

CBox::CBox(void)
{
```

```

}

CBox::~CBox(void)
{
}

```

The first line is an `#include` directive that inserts the contents of the `Box.h` file — the class definition — into this file, `Box.cpp`. This is necessary because the code in `Box.cpp` refers to the `CBox` class, and the class definition needs to be available to assign meaning to the name `CBox`.

Adding Data Members

First, you can add the `private` data members `m_Length`, `m_Width`, and `m_Height` as type `double`. Right-click `CBox` in Class View and select Add \Rightarrow Add Variable... from the pop-up menu. You can then specify the name, type, and access for the first data member that you want to add to the class in the Add Member Variable dialog.

The way you specify a new data member in this dialog is quite self-explanatory. The upper and lower limits for variables only applies when you are defining MFC variable attached to a control. You can add a comment in the lower input field, if you wish. When you click the Finish button, the variable will be added to the class definition, along with the comment if you have supplied one. You should repeat the process for the other two class data members, `m_Width` and `m_Height`. The class definition in `Box.h` will then be modified to look like this:

```

#pragma once

class CBox
{
public:
    CBox(void);
    ~CBox(void);
private:
    double m_Length;
    double m_Width;
    double m_Height;
};

```

Of course, you're quite free to enter the declarations for these members manually. You always have the choice of whether or not you use the automation provided by the IDE. You can also manually delete anything that was generated automatically, but don't forget that sometimes, both the `.h` and `.cpp` file will need to be changed. It's a good idea to save all the files whenever you make manual changes.

If you look in the `Box.cpp` file, you'll see that the Wizard has also added an initialization list to the constructor definition for the data members you have added, with each variable initialized to 0. You'll modify the constructor to do what you want next.

Defining the Constructor

You need to change the declaration of the no-arg constructor in the class definition so that it has arguments with default values, so modify it to:

```
explicit CBox(double lv = 1.0, double wv = 1.0, double hv = 1.0);
```

Now, you're ready to implement it. Open the `Box.cpp` file, if it isn't open already, and modify the constructor definition to:

```
CBox::CBox(double lv, double wv, double hv) : m_Height(hv)
{
    if(lv < 0.0 || wv < 0.0 || hv < 0.0)
        throw "Negative dimension specified for CBox object.";

    m_Length = std::max(lv, wv);
    m_Width = std::min(lv, wv);

    // Length is now greater than or equal to width
    if(m_Height > m_Length)
    {
        m_Height = m_Length;
        m_Length = hv;

        // m_Height is still greater than m_Width so swap them
        double temp = m_Width;
        m_Width = m_Height;
        m_Height = temp;
    }
    else if( m_Height > m_Width)
    {
        m_Height = m_Width;
        m_Width = hv;
    }
}
```

Remember that the initializers for the parameters to a member function should only appear in the member declaration in the class definition, not in the definition of the function. If you put them in the function definition, your code will not compile. You've seen this code already, so I won't discuss it again. You need to add an `#include` directive for the `algorithm` header to access the `max()` and `min()` functions. It would be a good idea to save the file at this point by clicking on the Save toolbar button. Get into the habit of saving the file you're editing before you switch to something else. If you need to edit the constructor again, you can get to it easily by either double-clicking its entry in the lower pane on the Class View tab, or selecting it from the right drop-down menu above the pane displaying the code.

Clicking a class name in Class View will cause the members of the class to be displayed in the lower pane. You can get to a member function's definition in a `.cpp` file or to its declaration in an `.h` file directly by right-clicking its name in the Class View pane and selecting the appropriate item from the context menu that appears.

Adding Function Members

You need to add all the functions you saw earlier to the `CBox` class. You defined several function members within the class definition, so that these functions were automatically inline. First, add the `#include` directive for the `utility` header to `Box.h` and a `using` directive for the `std::rel_ops` namespace to provide templates for some of the comparison operators, as you saw earlier. To add the `operator<()` function as inline, right-click `CBox` on the Class View tab and select `Add ➔ Add Function...` from the context menu. You then can enter the data defining the function in the dialog that is displayed, as Figure 8-10 shows.




FIGURE 8-10

The drop-down lists for the Return Type and Parameter Type contain a limited range of types. If the type you want does not appear in the list, you just type it in. Figure 8-10 shows the dialog after I entered the data to define the function but before the parameter has been added. You must click on the Add button to add the parameter. It will then appear in the parameter list to the right in the dialog. Clicking on Finish will create the skeleton for the function definition within the class definition. If you had not checked Inline, the prototype would appear in the class definition and a function skeleton would be added to the `Box.cpp` file. You must still edit the declaration in the `CBox` class definition to make the function `const` and to add the implementation to the function body. It should then look like this:

```
// Less-than operator for CBox objects
bool CBox::operator<(const CBox& aBox) const
{
    return Volume() < aBox.Volume();
}
```

You can add and implement the `operator==()` and `Volume()` members that you saw earlier to the class definition in the same way:

```
// Operator function for == comparing CBox objects
bool CBox::operator==(const CBox& aBox) const
{
    return Volume() == aBox.Volume();
}

// Calculate the box volume
```

```
double CBox::Volume(void) const
{
    return m_Length*m_Width*m_Height;
}
```

The templates in the utility header will take care of the operator functions for !=, >, <=, and >=. I will return to those comparing CBox objects with numerical values in a moment.

You can now add the GetHeight(), GetWidth(), and GetLength() functions that you saw earlier as inline class members. I'll leave it to you whether you use the Add \Rightarrow Add Function... menu option or enter them directly.

You could enter the operator functions for add, multiply, and divide operations as members using the Add Member Function Wizard to do it, because the practice will be useful. Right-click CBox in the Class View tab and select the Add \Rightarrow Add Function... menu item from the context menu, as before. You can then enter the details of the operator+() function in the dialog that appears, as Figure 8-11 shows.




FIGURE 8-11

Figure 8-11 shows the dialog after the Add button has been clicked to add the parameter to the list. When you click Finish, the declaration for the function will be added to the class definition in the Box.h file and a skeleton definition for the function will be added to the Box.cpp file. The function needs to be declared as `const`, so you must add this keyword to the declaration of the `operator+()` function within the class definition, and to the definition of the function in Box.cpp. You must also add the code in the body of the function, like this:

```
CBox CBox::operator+(const CBox& aBox) const
{
    // New object has larger length and width of the two,
    // and sum of the two heights
    return CBox(m_Length > aBox.m_Length ? m_Length : aBox.m_Length,
                m_Width > aBox.m_Width ? m_Width : aBox.m_Width,
                m_Height + aBox.m_Height);
}
```

When you have repeated this process for the `operator*()` and `operator/()` functions that you saw earlier, the class definition in `Box.h` will look something like this:

```
#pragma once
#include <utility>
using namespace std::rel_ops;

class CBox
{
public:
    explicit CBox(double lv = 1.0, double wv = 1.0, double hv = 1.0);
    ~CBox(void);

private:
    double m_Length;
    double m_Width;
    double m_Height;
public:
    bool operator<(const CBox& aBox) const;
    bool operator==(const CBox& aBox) const;
    double Volume(void) const;

    double GetLength() const { return m_Length; }
    double GetWidth() const { return m_Width; }
    double GetHeight() const { return m_Height; }

    CBox operator+(const CBox& aBox) const;           // Addition operator for CBox objects
    CBox operator*(int n) const;                      // Multiply operator for CBox objects
    int operator/(const CBox& aBox) const;            // Division operator for CBox objects
};
```

You can edit or rearrange the code in any way that you want — as long as it's still correct, of course.

If you look at Class View by clicking the tab, and then clicking the `CBox` class name, you'll see that all the members of the class are shown in the lower pane.

This completes the `CBox` class with its members, but you still need to define the global functions that implement operators that compare the volume of a `CBox` object with a numerical value. These are short and can be inline for efficiency.

Adding Global Functions

You might think that you put definitions for inline functions in a `.cpp` file like other function definitions, but this is not the case. Inline functions end up not being “real” functions in the compiled code because the compiler inserts the code from the body of an inline function at each position it is called. The

definitions for inline functions need to be available when a file containing calls to them is compiled. If they're not, you'll get linker errors and your program will not run. The .h files that you include into a .cpp file must contain everything the compiler needs to compile the code in the .cpp file. If you call an inline function in a .cpp file, the inline function definition *must* appear in an .h file that is included in the .cpp file. This also applies to inline member functions that you define outside the class definition.

The global functions that support operations on CBox objects will all be inline. You could put the global functions that support operations on CBox objects after the CBox class definition in Box.h, but to get the experience you will add another .h file to the project to house them. Click the Solution Explorer tab to display it (you currently will have the Class View tab displayed) and right-click the Header Files folder. Select Add → New Item... from the context menu to display the dialog. Choose the category as Code and the template as Header File (.h) in the right pane of the dialog, and enter the filename as **BoxOperators**.

You can now enter the following code in the editor pane:

```
// BoxOperators.h
// CBox object operations that don't need to access private members
#pragma once
#include "Box.h"

// Function for testing if a constant is > a CBox object
inline bool operator>(const double& value, const CBox& aBox)
{ return value > aBox.Volume(); }

// Function for testing if a constant is < CBox object
inline bool operator<(const double& value, const CBox& aBox)
{ return value < aBox.Volume(); }

// Function for testing if CBox object is > a constant
inline bool operator>(const CBox& aBox, const double& value)
{ return aBox.Volume() > value; }

// Function for testing if CBox object is < a constant
inline bool operator<( const CBox& aBox, const double& value)
{ return aBox.Volume() < value; }

// Function for testing if a constant is >= a CBox object
inline bool operator>=(const double& value, const CBox& aBox)
{ return value >= aBox.Volume(); }

// Function for testing if a constant is <= CBox object
inline bool operator<=(const double& value, const CBox& aBox)
{ return value <= aBox.Volume(); }

// Function for testing if CBox object is >= a constant
inline bool operator>=( const CBox& aBox, const double& value)
{ return aBox.Volume() >= value; }

// Function for testing if CBox object is <= a constant
inline bool operator<=( const CBox& aBox, const double& value)
```

```
{ return aBox.Volume() <= value; }

// Function for testing if a constant is == CBox object
inline bool operator==(const double& value, const CBox& aBox)
{ return value == aBox.Volume(); }

// Function for testing if CBox object is == a constant
inline bool operator==(const CBox& aBox, const double& value)
{ return aBox.Volume() == value; }

// CBox multiply operator n*aBox
inline CBox operator*(int n, const CBox& aBox)
{ return aBox * n; }

// Operator to return the free volume in a packed CBox
inline double operator%( const CBox& aBox, const CBox& bBox)
{ return aBox.Volume() - (aBox / bBox) * bBox.Volume(); }
```

The `#pragma once` directive ensures the contents of this cannot be included into another file more than once. You have an `#include` directive for `Box.h` because the functions refer to the `CBox` class. Save the file. When you have completed this, you can select the Class View tab. The Class View tab now includes a Global Functions and Variables folder that contains all the functions you have just added. You have seen definitions for all these earlier in the chapter, so I won't discuss them again.

When you define global functions in a project that are not inline, you put their definitions in a `.cpp` file. You also need to put the prototypes for the functions in an `.h` file with a `#pragma once` directive at the beginning. You can then include the `.h` file into any `.cpp` file that calls any of the functions so the compiler knows what they are.

You're now ready to start applying these global functions, along with the `CBox` class, to a specific problem in the world of boxes.

Using the CBox Class

Suppose that you are packaging candies. The candies are on the big side, real jawbreakers, occupying an envelope 1.5 inches long by 1 inch wide by 1 inch high. You have access to a standard candy box that is 4.5 inches by 7 inches by 2 inches, and you want to know how many candies will fit in the box so that you can set the price. You also have a standard carton that is 2 feet, 6 inches long by 18 inches wide and 18 inches deep, and you want to know how many boxes of candy it can hold and how much space you're wasting when it has been filled.

In case the standard candy box isn't a good solution, you would also like to know what custom candy box would be suitable. You know that you can get a good price on boxes with a length from 3 inches to 7.5 inches, a width from 3 inches to 5 inches, and a height from 1 inch to 2.5 inches, where each dimension can vary in steps of half an inch. You also know that you need to have at least 30 candies in a box, because this is the minimum quantity consumed by your largest customers at a sitting. Also, the candy box should not have empty space; complaints go up because customers think they are being cheated when the box is not full. Further, ideally, you want to pack the standard carton completely so the candies don't rattle around. You don't want to be too stringent about this; otherwise, packing could become difficult, so let's say you have no wasted space if the free space in the packed carton is less than the volume of a single candy box.

With the CBox class, the problem becomes almost trivial; the solution is generated by the following main() function. Add a new C++ source file, Ex8_12.cpp, to the project through the context menu you get when you right-click Source Files in the Solution Explorer pane, as you've done before. You can then type in the code shown here:

```
// Ex8_12.cpp
// A sample packaging problem
#include <iostream>
#include "Box.h"
#include "BoxOperators.h"
using std::cout;
using std::endl;

int main()
{
    CBox candy(1.5, 1.0, 1.0);           // Candy definition
    CBox candyBox(7.0, 4.5, 2.0);        // Candy box definition
    CBox carton(30.0, 18.0, 18.0);       // Carton definition

    // Calculate candies per candy box
    int numCandies = candyBox/candy;

    // Calculate candy boxes per carton
    int numCboxes = carton/candyBox;

    // Calculate wasted carton space
    double wasted = carton%candyBox;

    cout << endl << "There are " << numCandies << " candies per candy box" << endl
        << "For the standard boxes there are " << numCboxes
        << " candy boxes per carton " << endl << "with "
        << wasted << " cubic inches wasted.";

    cout << endl << endl << "CUSTOM CANDY BOX ANALYSIS (No Waste)";
    const int minCandiesPerBox = 30;

    // Try the whole range of custom candy boxes
    for(double length = 3.0 ; length <= 7.5 ; length += 0.5)
    {
        for(double width = 3.0 ; width <= 5.0 ; width += 0.5)
        {
            for(double height = 1.0 ; height <= 2.5 ; height += 0.5)
            {
                // Create new box each cycle
                CBox tryBox(length, width, height);

                if((carton%tryBox < tryBox.Volume()) && // Carton waste < a candy box
                   (tryBox % candy == 0.0) &&           // & no waste in candy box
                   (tryBox/candy >= minCandiesPerBox)) // & candy box holds minimum
                    cout << endl << endl
                        << "Trial Box L = " << tryBox.GetLength()
                        << " W = " << tryBox.GetWidth()
                        << " H = " << tryBox.GetHeight()
```

```

        << endl
        << "Trial Box contains " << tryBox / candy << " candies"
        << " and a carton contains " << carton / tryBox
        << " candy boxes.";
    }
}
cout << endl;
return 0;
}

```

Let's first look at how the program is structured. You have divided it into a number of files, which is typical in C++. You will be able to see them if you look at the Solution Explorer tab. `Ex8_12.cpp` contains `main()` and an `#include` directive for `BoxOperators.h` that contains the prototypes for the functions in `BoxOperators.cpp` (which aren't class members). It also has an `#include` directive for the `CBox` class definition in `Box.h`. A console program is usually divided into a number of files that fall into one of three basic categories:

- 1.** .h files containing library `#include` commands, global constants and variables, class definitions, and function prototypes — in other words, everything that is not executable code. They also contain inline function definitions. Where a program has several classes, the definitions are usually placed in separate .h files.
- 2.** .cpp files containing the executable code for the program, plus `#include` directives for .h files that provide the definitions required by the executable code.
- 3.** Another .cpp file containing the function `main()`.

The code in `main()` doesn't need a lot of explanation — it's almost a direct expression of the definition of the problem in words, because the operators in the class interface perform problem-oriented actions on `CBox` objects.

The solution to the question of the use of standard boxes is in the declaration statements, which also compute the answers we require as initializing values. You output these values with some explanatory comments.

The second part of the problem is solved by the three nested `for` loops iterating over the possible ranges of `m_Length`, `m_Width`, and `m_Height` so that you evaluate all possible combinations. You could output them all as well, but because this would involve 200 combinations, of which you might only be interested in a few, you have an `if` statement which identifies the options that you're actually interested in. The `if` expression is only `true` if there's no space wasted in the carton *and* the current trial candy box has no wasted space *and* it contains at least 30 candies.

How It Works

Here's the output from this program:

```

There are 42 candies per candy box
For the standard boxes there are 144 candy boxes per carton
with 648 cubic inches wasted.

```

CUSTOM CANDY BOX ANALYSIS (No Waste)

Trial Box L = 5 W = 4.5 H = 2

Trial Box contains 30 candies and a carton contains 216 candy boxes.

Trial Box L = 5 W = 4.5 H = 2

Trial Box contains 30 candies and a carton contains 216 candy boxes.

Trial Box L = 6 W = 3 H = 2.5

Trial Box contains 30 candies and a carton contains 216 candy boxes.

Trial Box L = 6 W = 4.5 H = 2

Trial Box contains 36 candies and a carton contains 180 candy boxes.

Trial Box L = 6 W = 4.5 H = 2.5

Trial Box contains 45 candies and a carton contains 144 candy boxes.

Trial Box L = 6 W = 5 H = 1.5

Trial Box contains 30 candies and a carton contains 216 candy boxes.

Trial Box L = 6 W = 5 H = 2

Trial Box contains 40 candies and a carton contains 162 candy boxes.

Trial Box L = 6 W = 5 H = 2.5

Trial Box contains 50 candies and a carton contains 129 candy boxes.

Trial Box L = 7.5 W = 3 H = 2


Trial Box contains 30 candies and a carton contains 216 candy boxes.

You have a duplicate solution due to the fact that you evaluate boxes in the nested loop that have a length of 5 and a width of 4.5, as well as boxes that have a length of 4.5 and a width of 5. Because the CBox class constructor ensures that the length is not less than the width, these two are identical. You could include some additional logic to avoid presenting duplicates, but it hardly seems worth the effort. You could treat it as an exercise if you like.

ORGANIZING YOUR PROGRAM CODE

In example Ex8_12, you distributed the code among several files for the first time. Not only is this common practice with C++ applications generally, but with Windows programming it is essential. The sheer volume of code involved in even the simplest program necessitates dividing it into workable chunks.

As I discussed in the previous section, there are basically two kinds of source code files in a C++ program, .h files and .cpp files. This is illustrated in Figure 8-12.

**FIGURE 8-12**

From time to time, you might want to use code from existing files in a new project. In this case, you only have to add the files to the project, which you can do by using the Project \Rightarrow Add Existing Item... menu option, or by right-clicking either Source Files or Header Files in the Solution Explorer tab and selecting Add \Rightarrow Existing Item... from the context menu to add the file to your project.

You don't need to add .h files to your project, although you can if you want them to be shown in the Solution Explorer pane immediately. The code from .h files will be added at the beginning of the .cpp files that require them as a result of the #include directives that you specify. You need #include directives for header files containing standard library functions and other standard definitions, as well as for your own header files. Visual C++ automatically keeps track of all these files, and enables you to view them in the Solution Explorer tab. As you saw in the previous example, you can also view class definitions and global constants and variables in the Class View tab.

In a Windows program, there are other kinds of definitions for the specification of such things as menus and toolbar buttons. These are stored in files with extensions like .rc and .ico. These are created and tracked automatically by Visual C++ when you need them.

Naming Program Files

As I have said, for classes of any complexity, it's usual to store the class definition in a .h file with a filename based on the class name, and to store the implementation of the function members of the class that are defined outside the class definition in a .cpp file with the same name. On this basis, the definition of our CBox class appeared in a file with the name Box.h. Similarly, the class implementation was stored in the file Box.cpp. We didn't follow this convention in the earlier examples in the chapter because the examples were very short, and it was easier to reference the examples with names derived from the chapter number and the sequence number of the example within the chapter. With programs of any size, though, it becomes essential to structure the code this way, so it would be a good idea to get into the habit of creating .h and .cpp files from now on.

Segmenting a C++ program into .h and .cpp files is a very convenient approach, as it makes it easy for you to find the definition or implementation of any class, particularly if you're working

in a development environment that doesn't have all the tools that Visual C++ provides. As long as you know the class name, you can go directly to the file you want. This isn't a rigid rule, though. It's sometimes useful to group the definitions of a set of closely related classes together in a single file and assemble their implementations similarly. However you choose to structure your files, the Class View still displays all the individual classes, as well as all the members of each class. Double-clicking any of the entries in the Class View tree will take you directly to the relevant source code.

LIBRARY CLASSES FOR STRINGS

As I said in Chapter 4, the `string` header defines the `string` and `wstring` classes that represent character strings. Both are defined as instances of the `basic_string<T>` class template. The `string` class is defined as `basic_string<char>`, and `wstring` is defined as `basic_string<wchar_t>`, so the `string` class represents strings of characters of type `char`, and `wstring` represents strings of characters of type `wchar_t`.

These string types are much easier to use than null-terminated strings and bring with them a whole range of powerful functions. Because `string` and `wstring` are both instances of the `basic_string<T>` template they provide the same functionality, so I'll only discuss the features and use in the context of the `string` type. The `wstring` type will work just the same, except that the strings contain Unicode character codes and you must use the `L` prefix for string literals in your code.

Creating String Objects

Creating `string` objects is very easy but you have a lot of choices as to how you do it. First, you can create and initialize a `string` object like this:

```
string sentence = "This sentence is false.;"
```

The `sentence` object is initialized with the string literal that appears to the right of the assignment operator. You can also use functional notation:

```
string sentence("This sentence is false.");
```

A `string` object has no terminating null character, so the string length is the number of characters in the string, 23 in this instance. You can discover the length of the string encapsulated by a `string` object at any time by calling its `length()` member function. For example:

```
cout << "The string is of length " << sentence.length() << endl;
```

Executing the statement produces the output:

```
The string is of length 23
```

Incidentally, you can output a `string` object to `cout` in the same way as any other variable:

```
cout << sentence << endl;
```

This displays the `sentence` string on a line by itself. You can also read a character string into a `string` object like this:

```
cin >> sentence;
```

Reading from `cin` in this way ignores leading whitespace until a non-whitespace character is found, and also terminates input when you enter a space following one or more non-whitespace characters. You will often want to read text into a `string` object that includes spaces and may span several lines. In this case, the `getline()` function template that is defined in the `string` header file is much more convenient. For example:

```
getline(cin, sentence, '*');
```

This template function is specifically for reading data from a stream into a `string` or `wstring` object. The first argument is the stream that is the source of input — it doesn't have to be `cin`, the second argument is the object that is to receive the input, and the third argument is the character that terminates input. Here, I specified the terminating character as `'*'`, so this statement will read text into `sentence` from `cin`, including spaces, until the end of input is indicated by an asterisk being read from the stream.

If you don't specify an initial string literal when you create a `string` object, the object will contain an empty string:

```
string astring; // Create an empty string
```

Calling `length()` for `astring` will return zero.

Another possibility is to initialize a `string` object with a single character repeated a number of times:

```
string bees(7, 'b'); // String is "bbbbbbb"
```

The first argument to the constructor is the number of repetitions of the character specified by the second argument.

Finally, you can initialize a `string` object with all or part of another `string` object. This uses another `string` object as an initializer:

```
string letters(bees);
```

The `letters` object will be initialized with the string from `bees`.

To select part of a `string` object as initializer, you call the `string` constructor with three arguments; the first is the `string` object that is the source of the initializing string, the second is the index position of the first character to be selected, and the third argument is the number of characters to be selected. Here's an example:

```
string sentence("This sentence is false.");
string part(sentence, 5, 11);
```

The `part` object will be initialized with 11 characters from `sentence` beginning with the sixth character (the first character is at index position 0). Thus, `part` will contain "sentence is".

Of course, you can create arrays of `string` objects and initialize them using the usual notation. For example:

```
string animals[] = { "dog", "cat", "horse", "donkey", "lion"};
```

This creates an array of five `string` objects initialized with the string literals between the braces.

Concatenating Strings

Perhaps the most common operation with strings is joining two strings to form a single string. You can use the `+` operator to join two `string` objects or a `string` object with a string literal. Here are some examples:

```
string sentence1("This sentence is false.");
string sentence2("Therefore the sentence above must be true!");
string combined;                                // Create an empty string
sentence1 = sentence1 + "\n";                    // Append string containing newline
combined = sentence1 + sentence2;                // Join two strings
cout << combined << endl;                      // Output the result
```

Executing these statements will result in the following output:

```
This sentence is false.
Therefore the sentence above must be true!
```

The first three statements create `string` objects. The next statement appends the string literal `"\n"` to `sentence1` and stores the result in `sentence1`. The next statement joins `sentence1` and `sentence2` and stores the result in `combined`. The last statement outputs `combined`.

String concatenation using the `+` operator is possible because the `string` class implements `operator+()`. This implies that one of the operands must be a `string` object, so you can't use the `+` operator to join two string literals. Keep in mind that each time you use the `+` operator, you are creating a new `string` object, which involves a certain amount of overhead. You'll see in the next section how you can modify and extend an existing `string` object, and this may be a more efficient alternative in many cases, because it avoids creating new objects.

You can also use the `+` operator to join a character to a `string` object, so you could have written the fourth statement in the previous code fragment as:

```
sentence1 = sentence1 + '\n';                  // Append newline character to string
```

The `string` class implements `operator+=()` such that the right operand can be a string literal, a `string` object, or a single character. You could write the previous statement as:

```
sentence1 += '\n';
```

or:

```
sentence1 += "\n";
```

There is a difference between using the `+=` operator and using the `+` operator. As I said, the `+` operator creates a new `string` object containing the combined string. The `+=` operator appends the string or character that is the right operand to the `string` object that is the left operand, so the `string` object is modified directly and no new object is created.

Let's exercise some of what I have described in an example.

TRY IT OUT Creating and Joining Strings

This is a simple example that reads names and ages from the keyboard and then lists what you entered. Here's the code:

```
// Ex8_13.cpp
// Creating and joining string objects
#include <iostream>
#include <string>
using std::cin;
using std::cout;
using std::endl;
using std::string;
using std::getline;

// List names and ages
void listnames(string names[], string ages[], size_t count)
{
    cout << endl << "The names you entered are: " << endl;
    for(size_t i = 0 ; i < count && !names[i].empty() ; ++i)
        cout << names[i] + " aged " + ages[i] + '.' << endl;
}

int main()
{
    const size_t count = 100;
    string names[count];
    string ages[count];
    string firstname;
    string secondname;

    for(size_t i = 0 ; i<count ; i++)
    {
        cout << endl << "Enter a first name or press Enter to end: ";
        getline(cin, firstname, '\n');
        if(firstname.empty())
        {
            listnames(names, ages, i);
            cout << "Done!!" << endl;
            return 0;
        }

        cout << "Enter a second name: ";
        getline(cin, secondname, '\n');

        names[i] = firstname + ' ' + secondname;
        cout << "Enter " + firstname + "'s age: ";
    }
}
```

```
    getline(cin, ages[i], '\n');
}
cout << "No space for more names." << endl;
listnames(names, ages, count);
return 0;
}
```

ages would usually be an array of integers but I made it an array of strings here to just use more strings. This example produces output similar to the following:

```
Enter a first name or press Enter to end: Marilyn
Enter a second name: Munroe
Enter Marilyn's age: 26
```

```
Enter a first name or press Enter to end: Tom
Enter a second name: Crews
Enter Tom's age: 45
```

```
Enter a first name or press Enter to end: Arnold
Enter a second name: Weisseneggar
Enter Arnold's age: 52
```

```
Enter a first name or press Enter to end:
```

```
The names you entered are:
Marilyn Munroe aged 26.
Tom Crews aged 45.
Arnold Weisseneggar aged 52.
Done!!
```

How It Works

The listnames function lists names and ages stored in arrays that are passed as the first two arguments. The third argument is a count of the number of elements in the arrays. Listing of the data occurs in a loop:

```
for(size_t i = 0 ; i < count && !names[i].empty() ; ++i)
    cout << names[i] + " aged " + ages[i] + '.' << endl;
```

The loop condition is a belt-and-braces control mechanism in that it not only checks that the index *i* is less than the value of *count* that is passed as the third argument, but it also calls the `empty()` function for the current element to verify that it is not an empty string. The single statement in the body of the loop concatenates the current string in `names[i]` with the literal "aged ", the `ages[i]` string, and the character '.' using the + operator, and writes the resultant string to `cout`. The expression concatenating the strings is equivalent to:

```
((names[i].operator+(" aged ")).operator+(ages[i])).operator+('.')
```

Each call of the `operator+()` function returns a new `string` object. Thus, the expression demonstrates combining a `string` object with a string literal, a `string` object with another `string` object, and a `string` object with a character literal.

Although the preceding code demonstrates the `string::operator+()` function, for performance reasons, you would use the following:

```
cout << names[i] << " aged " << ages[i] << '.' << endl;
```

This avoids the calls to the operator function and the creation of all the `string` objects that result from that.

In `main()`, you create two arrays of `string` objects of length `count` with the statements:

```
const size_t count = 100;
string names[count];
string ages[count];
```

The `names` and `ages` arrays store names and corresponding age values that are entered from the keyboard.

Within the `for` loop in `main()`, you read the first and second names separately using the `getline()` template function:

```
cout << endl << "Enter a first name or press Enter to end: ";
getline(cin, firstname, '\n');
if(firstname.empty())
{
    listnames(names, ages, i);
    cout << "Done!!" << endl;
    return 0;
}

cout << "Enter a second name: ";
getline(cin, secondname, '\n');
```

The `getline()` function allows an empty string to be read, something you cannot do using the `>>` operator with `cin`. The first argument to `getline()` is the stream that is the source of the input, the second argument is the destination for the input, and the third argument is the character that signals the end of the input operation. If you omit the third argument, the default is '`\n`', so you could have omitted it here. You use the ability to read an empty string here as you test for an empty string in `firstname` by calling its `empty()` function. An empty string signals the end of input, so you call `listnames()` to output the data and end program execution.

When `firstname` is not empty, you continue with reading the second name into `secondname`, again using the `getline()` template function. You concatenate `firstname` and `secondname` using the `+` operator and store the result in `names[i]`, the currently unused element in the `names` array.

Finally in the loop, you read a string for the age of the person and store the result in `ages[i]`. The `for` loop limits the number of entries to `count`, which corresponds to the number of elements in the arrays. If you fall through the end of the loop, the arrays are full, so after displaying a message, you output the data that was entered.

Accessing and Modifying Strings

You can access any character in a `string` object to read it or overwrite it by using the subscript operator, `[]`. Here's an example:

```
string sentence("Too many cooks spoil the broth.");
for(size_t i = 0; i < sentence.length(); i++)
{
    if(' ' == sentence[i])
        sentence[i] = '*';
}
```

This inspects each character in the `sentence` string in turn to see if it is a space, and if it is, replaces the character with an asterisk.

You can use the `at()` member function to achieve the same result:

```
string sentence("Too many cooks spoil the broth.");
for(size_t i = 0; i < sentence.length(); i++)
{
    if(' ' == sentence.at(i))
        sentence.at(i) = '*';
}
```

This does exactly the same as the previous fragment, so what's the difference between them? Well, subscripting is faster than using the `at()` function, but the downside is the validity of the index is not checked. If the index is out of range, the result of using the subscript operator is undefined. The `at()` function is a bit slower but it does check the index, and if it is not valid, the function will throw an `out_of_range` exception. You would use the `at()` function when there is the possibility of the index value being out of range, and in this situation you should put the code in a `try` block and handle the exception appropriately. If you are sure index out of range conditions cannot arise, then use the `[]` operator.

You can use the range-based `for` loop with a `string` object to iterate over all of the characters in the string:

```
string sentence("Too many cooks spoil the broth.");
for(auto& ch : sentence)
{
    if(' ' == ch)
        ch = '*';
}
```

This replaces spaces with asterisks like the loop you saw earlier. This is much simpler. Using a reference type for `ch` enables you to change the string.

You can extract part of an existing object as a new `string` object. For example:

```
string sentence("Too many cooks spoil the broth.");
string substring = sentence.substr(4, 10);           // Extracts "many cooks"
```

The first argument to the `substr()` function is the first character of the substring to be extracted, and the second argument is the count of the number of characters in the substring.

By using the `append()` function for a `string` object, you can add one or more characters to the end of the string. This function comes in several versions; there are versions that append one or more of a given character, a string literal, or a `string` object to the object for which the function is called. For example:

```
string phrase("The higher");
string word("fewer");
phrase.append(1, ' ');
// Append one space
phrase.append("the ");
// Append a string literal
phrase.append(word);
// Append a string object
phrase.append(2, '!');
// Append two exclamation marks
```

After executing this sequence, `phrase` will contain "The higher the fewer!!". With the version of `append()` with two arguments, the first argument is the count of the number of times the character specified by the second argument is to be appended. When you call `append()`, the function returns a reference to the object for which it was called, so you could write the preceding four `append()` calls in a single statement:

```
phrase.append(1, ' ').append("the ").append(word).append(2, '!');
```

You can also use `append()` to append part of a string literal or part of a `string` object to an existing string:

```
string phrase("The more the merrier.");
string query("Any");
query.append(phrase, 3, 5).append(1, '?');
```

After these statements `query` will contain "Any more?". In the last statement, the first call to the `append()` function has three arguments:

- The first argument, `phrase`, is the `string` object from which characters are to be extracted and appended to `query`.
- The second argument, 3, is the index position of the first character to be extracted.
- The third argument, 5, is the count of the total number of characters to be appended.

Thus, the substring " more" is appended to `query` by this call. The second call for the `append()` function appends a question mark to `query`.

To append a single character to a `string` object, you could use the `push_back()` function as an alternative to `append()` like this:

```
query.push_back('*');
```

This appends an asterisk to the end of the `query` string.

Sometimes, adding characters to the end of a string just isn't enough. There are occasions when you want to insert one or more characters into the interior of a string. Versions of the `insert()` function will do that for you:

```

string saying("A horse");
string word("blind");
string sentence("He is as good as gold.");
string phrase("a wink too far");
saying.insert(1, " ") // Insert a space character
saying.insert(2, word) // Insert a string object
saying.insert(2, "nodding", 3) // Insert 3 characters of a string literal
saying.insert(5, sentence, 2, 15) // Insert part of a string at position 5
saying.insert(20, phrase, 0, 9) // Insert part of a string at position 20
saying.insert(29, " ").insert(30, "a poor do", 0, 2);

```

I'm sure you'll be interested to know that after executing the preceding statements, `saying` will contain the string "A nod is as good as a wink to a blind horse". The parameters to the various versions of `insert()` are:

FUNCTION PROTOTYPE	DESCRIPTION
<code>string& insert(size_t index, const char* pstring)</code>	Inserts the null-terminated string <code>pstring</code> at position <code>index</code> .
<code>string& insert(size_t index, const string& astring)</code>	Inserts the <code>string</code> object <code>astring</code> at position <code>index</code> .
<code>string& insert(size_t index, const char* pstring, size_t count)</code>	Inserts the first <code>count</code> characters from the null-terminated string <code>pstring</code> at position <code>index</code> .
<code>string& insert(size_t index, size_t count, char ch)</code>	Inserts <code>count</code> copies of the character <code>ch</code> at position <code>index</code> .
<code>string& insert(size_t index, const string& astring, size_t start, size_t count)</code>	Inserts <code>count</code> characters from the <code>string</code> object <code>astring</code> , beginning with the character at position <code>start</code> ; the substring is inserted at position <code>index</code> .

These versions of `insert()` return a reference to the `string` object for which the function is called. This allows you to chain calls together, as in the last statement in the code fragment.

This is not the complete set of `insert()` functions, but you can do everything you need with those in the table. The other versions use *iterators* as arguments, and you'll learn about iterators in Chapter 10.

You can interchange the strings encapsulated by two `string` objects by calling the `swap()` member function. For example:

```
string phrase("The more the merrier.");
string query("Any");
query.swap(phrase);
```

This results in `query` containing the string "The more the merrier." and `phrase` containing the string "Any". Of course, executing `phrase.swap(query)` would have the same effect.

If you need to convert a `string` object to a null-terminated string, the `c_str()` function will do this. For example:

```
string phrase("The higher the fewer");
const char *pstring = phrase.c_str();
```

The `c_str()` function returns a pointer to a null-terminated string with the same contents as the `string` object.

You can obtain the contents of a `string` object as an array of type `char` by calling its `data()` function. Note that the array contains just the characters from the `string` object, without a terminating null.

You can replace part of a `string` object by calling its `replace()` function. This comes in several versions, as the table shows.

FUNCTION PROTOTYPE	DESCRIPTION
<code>string& replace(size_t index, size_t count, const char* pstring)</code>	Replaces <code>count</code> characters, starting at position <code>index</code> , with the first <code>count</code> characters from <code>pstring</code> .
<code>string& replace(size_t index, size_t count, const string& astring)</code>	Replaces <code>count</code> characters, starting at position <code>index</code> , with the first <code>count</code> characters from <code>astring</code> .
<code>string& replace(size_t index, size_t count1, const char* pstring, size_t count2)</code>	Replaces <code>count1</code> characters, starting at position <code>index</code> , with up to <code>count2</code> characters from <code>pstring</code> . This allows the replacement substring to be longer or shorter than the substring that is replaced.

continues

(continued)

FUNCTION PROTOTYPE	DESCRIPTION
<pre>string& replace(size_t index1, size_t count1, const string& astring, size_t index2, size_t count2)</pre>	Replaces count1 characters, starting at position index1, with count2 characters from astring, starting at position index2.
<pre>string& replace(size_t index, size_t count1, size_t count2, char ch)</pre>	Replaces count1 characters, starting at index, with count2 occurrences of the character ch.

In each case, a reference to the `string` object for which the function is called is returned.

Here's an example:

```
string proverb("A nod is as good as a wink to a blind horse");
string sentence("It's bath time!");
proverb.replace(38, 5, sentence, 5, 3);
```

This uses the fourth version of `replace()` from the preceding table to substitute "bat" in place of "horse" in the string `proverb`.

Comparing Strings

You have a full complement of operators for comparing `string` objects or comparing a `string` object with a literal. Operator overloading has been implemented in the `string` class for the following operators:

`==` `!=` `<` `<=` `>` `>=`

Here's an example of the use of these:

```
string dog1("St Bernard");
string dog2("Tibetan Mastiff");
if(dog1 < dog2)
    cout << "dog2 comes first!" << endl;
else if(dog1 > dog2)
    cout << "dog1 comes first!" << endl;
```

When you compare two strings, corresponding characters are compared until either a pair of characters is found that differ, or the end of one or both strings is reached. When two corresponding

characters differ, the values of the character codes determine which string is less than the other. If no character pairs are found to be different, the string with fewer characters is less than the other string. Two strings will be equal if they contain the same number of characters and corresponding characters are identical.

TRY IT OUT Comparing Strings

This example illustrates the use of the comparison operators by implementing an extremely inefficient sorting method. Here's the code:

```
// Ex8_14.cpp
// Comparing and sorting words
#include <iostream>
#include <iomanip>
#include <string>
using std::cin;
using std::cout;
using std::endl;
using std::ios;
using std::setiosflags;
using std::setw;
using std::string;

string* sort(string* strings, size_t count)
{
    bool swapped(false);
    while(true)
    {
        for(size_t i = 0 ; i < count-1 ; i++)
        {
            if(strings[i] > strings[i+1])
            {
                swapped = true;
                strings[i].swap(strings[i+1]);
            }
        }
        if(!swapped)
            break;
        swapped = false;
    }
    return strings;
}

int main()
{
    const size_t maxstrings(100);
    string strings[maxstrings];
    size_t nstrings(0);
    size_t maxwidth(0);

    // Read up to 100 words into the strings array
    while(nstrings < maxstrings)
```

```
{  
    cout << "Enter a word or press Enter to end: ";  
    getline(cin, strings[nstrings]);  
    if(maxwidth < strings[nstrings].length())  
        maxwidth = strings[nstrings].length();  
    if(strings[nstrings].empty())  
        break;  
    ++nstrings;  
}  
  
// Sort the input in ascending sequence  
sort(strings,nstrings);  
cout << endl  
    << "In ascending sequence, the words you entered are:"  
    << endl  
    << setiosflags(ios::left);           // Left-justify the output  
for(size_t i = 0 ; i < nstrings ; i++)  
{  
    if(i % 5 == 0)  
        cout << endl;  
    cout << setw(maxwidth+2) << strings[i];  
}  
cout << endl;  
return 0;  
}
```

Here's some typical output from this example:

```
Enter a word or press Enter to end: loquacious  
Enter a word or press Enter to end: transmogrify  
Enter a word or press Enter to end: abstemious  
Enter a word or press Enter to end: facetious  
Enter a word or press Enter to end: xylophone  
Enter a word or press Enter to end: megaphone  
Enter a word or press Enter to end: chauvinist  
Enter a word or press Enter to end:
```

```
In ascending sequence, the words you entered are:
```

```
abstemious    chauvinist    facetious    loquacious    megaphone  
transmogrify  xylophone
```

How It Works

The most interesting part is the `sort()` function that accepts two arguments, the address of a `string` array and the number of elements. The function implements the bubble sort, which works by scanning through the elements in sequences and comparing successive elements. All the work is done in the `while` loop:

```
bool swapped(false);  
while(true)  
{  
    for(size_t i = 0 ; i < count-1 ; i++)
```

```

{
    if(strings[i] > strings[i+1])
    {
        swapped = true;
        strings[i].swap(strings[i+1]);
    }
}
if(!swapped)
    break;
swapped = false;
}

```

Successive elements in the `strings` array are compared using the `>` operator. If the first element is greater than the second in a pair, the elements are swapped. In this case, the elements are interchanged by calling the `swap()` function for one `string` object with the second `string` object as argument. Comparing successive elements and swapping when necessary continues for the entire array. This process is repeated until there is a pass through all the elements where no elements are swapped. The elements are then in ascending sequence. The `bool` variable `swapped` acts as an indicator for whether swapping occurs on any given pass. It is only set to `true` when two elements are swapped.

The `main()` function reads up to 100 words into the `strings` array in a loop:

```

while(nstrings < maxstrings)
{
    cout << "Enter a word or press Enter to end: ";
    getline(cin, strings[nstrings]);
    if(maxwidth < strings[nstrings].length())
        maxwidth = strings[nstrings].length();
    if(strings[nstrings].empty())
        break;
    ++nstrings;
}

```

The `getline()` function reads characters from `cin` until '`\n`' is read. The input is stored in the `string` object specified by the second argument `strings[nstrings]`. Just pressing the Enter key will result in an `empty()` string, so the loop is terminated when the `empty()` function for the last `string` object read returns `true`. The `maxwidth` variable is used to record the length of the longest string entered. This will be used later in the output process after the input has been sorted.

Calling the `sort()` function sorts the contents of the `strings` array in ascending sequence. The result is output in a loop:

```

cout << endl
    << "In ascending sequence, the words you entered are:"
    << endl
    << setiosflags(ios::left);           // Left-justify the output
for(size_t i = 0 ; i < nstrings ; i++)
{
    if(i % 5 == 0)
        cout << endl;
    cout << setw(maxwidth+2) << strings[i];
}

```

This outputs each element in a field width of `maxwidth+2` characters. Each word is left-justified in the field because of the call to the `setiosflags()` manipulator with the argument `ios::left`. Unlike the `setw()` manipulator, the `setiosflags()` manipulator remains in effect until you reset it.

Searching Strings

You have four versions of the `find()` function that search a `string` object for a given character or substring, and they are described in the following table. All the `find()` functions are defined as `const`.

FUNCTION PROTOTYPE	DESCRIPTION
<code>size_t find(char ch, size_t offset=0)</code>	Searches a <code>string</code> object for the character <code>ch</code> starting at index position <code>offset</code> . You can omit the second argument, in which case, the default value is 0.
<code>size_t find(const char* pstr, size_t offset=0)</code>	Searches a <code>string</code> object for the null-terminated string <code>pstr</code> , starting at index position <code>offset</code> . You can omit the second argument, in which case, the default value is 0.
<code>size_t find(const char* pstr, size_t offset, size_t count)</code>	Searches a <code>string</code> object for the first <code>count</code> characters of the null-terminated string <code>pstr</code> , starting at index position <code>offset</code> .
<code>size_t find(const string& str, size_t offset=0)</code>	Searches a <code>string</code> object for the string object <code>str</code> , starting at index position <code>offset</code> . You can omit the second argument, in which case, the default value is 0.

In each case, the `find()` function returns the index position where the character or first character of the substring was found, and returns the value `string::npos` if the item was not found. This value is a constant defined in the `string` class that represents an illegal position in a `string` object; it is used generally to signal a search failure.

Here's a fragment showing some of the ways you might use `find()`:

```
string phrase("So near and yet so far");
string str("So near");
cout << phrase.find(str) << endl;           // Outputs 0
cout << phrase.find("so far") << endl;        // Outputs 16
cout << phrase.find("so near") << endl;       // Outputs string::npos = 4294967295
```

The value of `string::npos` can vary with different compiler implementations, so you should always use `string::npos` and not the explicit value to test for it.

Here's another example that scans a string repeatedly, searching for occurrences of a particular substring:

```
string str( "Smith, where Jones had had \"had had\"", \"had had\" had."
            " \"Had had\" had had the examiners' approval.");
string substr("had");

cout << "The string to be searched is:"
     << endl << str << endl;
size_t offset(0);
size_t count(0);
size_t increment(substr.length());

while(true)
{
    offset = str.find(substr, offset);
    if(string::npos == offset)
        break;
    offset += increment;
    ++count;
}
cout << endl << " The string \""
     << "\"" was found " << count << " times in the string above."
     << endl;
```

This searches the string `str` to see how many times "had" appears. The search is done in the `while` loop, where `offset` records the position found, and is also used as the start position for the search. The search starts at index position 0, the start of the string, and each time the substring is found, the new starting position for the next search is set to the found position plus the length of the substring. This ensures that the substring that was found is bypassed. Every time the substring is found, `count` is incremented. If `find()` returns `string::npos`, then the substring was not found and the search ends. Executing this fragment produces the output:

```
The string to be searched is:
Smith, where Jones had had "had had", "had had" had. "Had had" had had the
examiners' approval.
```

The string "had" was found 10 times in the string above.

"Had" is not a match for "had", so 10 is the correct result.

The `find_first_of()` and `find_last_of()` member functions search a `string` object for an occurrence of any character from a given set. You could search a string to find spaces or punctuation characters, for example, to break a string up into individual words. Both functions come in several flavors, as the following table shows. All functions in the table are defined as `const` and return a value of type `size_t`.

FUNCTION PROTOTYPE	DESCRIPTION
<code>find_first_of(char ch, size_t offset=0)</code>	Searches a <code>string</code> object for the first occurrence of the character, <code>ch</code> , starting at position <code>offset</code> , and returns the index position where the character is found as a value of type <code>size_t</code> . If you omit the second argument, the default value of <code>offset</code> is 0.
<code>find_first_of(const char* pstr, size_t offset=0)</code>	Searches a <code>string</code> object for the first occurrence of any character in the null-terminated string, <code>pstr</code> , starting at position <code>offset</code> , and returns the index position where the character is found as a value of type <code>size_t</code> . If you omit the second argument, the default value of <code>offset</code> is 0.
<code>find_first_of(const char* pstr, size_t offset, size_t count)</code>	Searches a <code>string</code> object for the first occurrence of any character in the first <code>count</code> characters of the null-terminated string, <code>pstr</code> , starting at position <code>offset</code> , and returns the index position where the character is found as a value of type <code>size_t</code> .
<code>find_first_of(const string& str, size_t offset=0)</code>	Searches a <code>string</code> object for the first occurrence of any character in the string, <code>str</code> , starting at position <code>offset</code> , and returns the index position where the character is found as a value of type <code>size_t</code> . If you omit the second argument, the default value of <code>offset</code> is 0.
<code>find_last_of(char ch, size_t offset=npos)</code>	Searches backwards through a <code>string</code> object for the last occurrence of the character, <code>ch</code> , starting at position <code>offset</code> , and returns the index position where the character is found as a value of type <code>size_t</code> . If you omit the second argument, the default value of <code>offset</code> is <code>npos</code> , which is the end of the string.
<code>find_last_of(const char* pstr, size_t offset=npos)</code>	Searches backwards through a <code>string</code> object for the last occurrence of any character in the null-terminated string, <code>pstr</code> , starting at position <code>offset</code> , and returns the index position where the character is found as a value of type <code>size_t</code> . If you omit the second argument, the default value of <code>offset</code> is <code>npos</code> , which is the end of the string.
<code>find_last_of(const char* pstr, size_t offset, size_t count)</code>	Searches backwards through a <code>string</code> object for the last occurrence of any of the first <code>count</code> characters in the null-terminated string, <code>pstr</code> , starting at position <code>offset</code> , and returns the index position where the character is found as a value of type <code>size_t</code> .
<code>find_last_of(const string& str, size_t offset=npos)</code>	Searches backwards through a <code>string</code> object for the last occurrence of any character in the string, <code>str</code> , starting at position <code>offset</code> , and returns the index position where the character is found as a value of type <code>size_t</code> . If you omit the second argument, the default value of <code>offset</code> is <code>npos</code> , which is the end of the string.

With all versions of `find_first_of()` and `find_last_of()`, `string::npos` will be returned if no matching character is found.

With the same string as the last fragment, you could see what the `find_last_of()` function does with the same search string, "had".

```
size_t count(0);
size_t offset(string::npos);
while(true)
{
    offset = str.find_last_of(substr, offset);
    if(string::npos == offset)
        break;
    --offset;
    ++count;
}
cout << endl << " Characters from the string \""
<< substr
<< "\" were found " << count << " times in the string above."
<< endl;
```

This time, you are searching backwards starting at index position `string::npos`, the end of the string, because this is the default starting position. The output from this fragment is:

```
The string to be searched is:
Smith, where Jones had had "had had", "had had" had. "Had had" had had
the examiners' approval.
```

```
Characters from the string "had" were found 38 times in the string above.
```

The result should not be a surprise. You are searching for occurrences of *any* of the characters in "had" in the string `str`. There are 32 in the "Had" and "had" words, and 6 in the remaining words. Because you are searching backwards, you decrement `offset` when you find a character.

The last set of search facilities are versions of the `find_first_not_of()` and `find_last_not_of()` functions. All of the functions in the following table are `const` and return a `size_t` value.

FUNCTION PROTOTYPE	DESCRIPTION
<code>find_first_not_of(char ch, size_t offset=0)</code>	Searches for the first occurrence of a character that is not the character, <code>ch</code> , starting at position <code>offset</code> . The function returns the index position where the character is found as a value of type <code>size_t</code> . If you omit the second argument, the default value of <code>offset</code> is 0.
<code>find_first_not_of(const char* pstr, size_t offset=0)</code>	Searches for the first occurrence of a character that is not in the null-terminated string, <code>pstr</code> , starting at position <code>offset</code> , and returns the index position where the character is found as a value of type <code>size_t</code> . If you omit the second argument, the default value of <code>offset</code> is 0.

continues

(continued)

FUNCTION PROTOTYPE	DESCRIPTION
<code>find_first_not_of(const char* pstr, size_t offset, size_t count)</code>	Searches for the first occurrence of a character that is not in the first <code>count</code> characters of the null-terminated string, <code>pstr</code> , starting at <code>offset</code> . The function returns the index position where the character is found as a value of type <code>size_t</code> .
<code>find_first_not_of(const string& str, size_t offset=0)</code>	Searches for the first occurrence of any character that is not in <code>str</code> , starting at <code>offset</code> . The function returns the index position where the character is found as a <code>size_t</code> value. If you omit the second argument, the default value of <code>offset</code> is 0.
<code>find_last_not_of(char ch, size_t offset=npos)</code>	Searches backwards for the last occurrence of a character that is not <code>ch</code> starting at <code>offset</code> . The index position where the character is found is returned as a <code>size_t</code> value. If you omit the second argument, the default value of <code>offset</code> is <code>npos</code> , which is the end of the string.
<code>find_last_not_of(const char* pstr, size_t offset=npos)</code>	Searches backwards for the last occurrence of any character that is not in the null-terminated string, <code>pstr</code> , starting at <code>offset</code> . The index position where the character is found is returned as a <code>size_t</code> value. If you omit the second argument, the default value of <code>offset</code> is <code>npos</code> .
<code>find_last_not_of(const char* pstr, size_t offset, size_t count)</code>	Searches backwards for the last occurrence of a character that is not among the first <code>count</code> characters in <code>pstr</code> starting at <code>offset</code> . The function returns the index position where the character is found as a <code>size_t</code> value.
<code>find_last_not_of(const string& str, size_t offset=npos)</code>	Searches backwards for the last occurrence of any character not in <code>str</code> starting at <code>offset</code> . The function returns the index position where the character is found as a <code>size_t</code> value. If you omit the second argument, the default value of <code>offset</code> is <code>npos</code> .

As with previous search functions, `string::npos` will be returned if the search does not find a character. These functions have many uses, typically finding tokens in a string that may be separated by characters of various kinds. For example, text consists of words separated by spaces and punctuation characters, so you could use these functions to find the words in a block of text. Let's see that working in an example.

TRY IT OUT Sorting Words from Text

This example reads a block of text, and then extracts the words and outputs them in ascending sequence. I'll use the somewhat inefficient bubble sort function that you saw in Ex8_14 here. In Chapter 10, you will use a library function for sorting that would be much better, but you need to learn about some other stuff before you can use that. The program will also figure out how many times each word occurs and output the count for each word. Such an analysis is called a *collocation*. Here's the code:

```
// Ex8_15.cpp
// Extracting words from text
#include <iostream>
#include <iomanip>
#include <string>
using std::cin;
using std::cout;
using std::endl;
using std::ios;
using std::setiosflags;
using std::resetiosflags;
using std::setw;
using std::string;

// Sort an array of string objects
string* sort(string* strings, size_t count)
{
    bool swapped(false);
    while(true)
    {
        for(size_t i = 0 ; i < count-1 ; i++)
        {
            if(strings[i] > strings[i+1])
            {
                swapped = true;
                strings[i].swap(strings[i+1]);
            }
        }
        if(!swapped)
            break;
        swapped = false;
    }
    return strings;
}

int main()
{
    const size_t maxwords(100);
    string words[maxwords];
    string text;
    string separators(" \",.:;!?\n");
    size_t nwords(0);
    size_t maxwidth(0);

    cout << "Enter some text on as many lines as you wish."
        << endl << "Terminate the input with an asterisk:" << endl;

    getline(cin, text, '*');

    size_t start(0), end(0), offset(0); // Record start & end of word & offset
    while(true)
    {
        // Find first character of a word
        start = text.find_first_not_of(separators, offset); // Find non-separator
        if(string::npos == start) // If we did not find it, we are done
            break;
        offset = start + 1; // Move past character found
        words[nwords] = string(text, start, end - start);
        nwords++;
        if(nwords == maxwords)
            break;
    }
}
```

```
// Find first separator past end of current word
end = text.find_first_of(separators, offset);           // Find separator
if(string::npos == end)                                // If it's the end of the string
{
    offset = end;                                      // current word is last in string
    end = text.length();                                // We use offset to end loop later
}
else
    offset = end + 1;                                  // Move past character found

words[nwords] = text.substr(start, end-start);          // Extract the word

// Keep track of longest word
if(maxwidth < words[nwords].length())
    maxwidth = words[nwords].length();

if(++nwords == maxwords)                               // Check for array full
{
    cout << endl << "Maximum number of words reached."
    << endl << "Processing what we have." << endl;
    break;
}

if(string::npos == offset)                            // If we reached the end of the string
    break;                                            // We are done

}

sort(words, nwords);

cout << endl
    << "In ascending sequence, the words in the text are:"
    << endl;

size_t count(0);                                     // Count of duplicate words
// Output words and number of occurrences
for(size_t i = 0 ; i<nwords ; i++)
{
    if(0 == count)
        count = 1;
    if(i < nwords-1 && words[i] == words[i+1])

    {
        ++count;
        continue;
    }
    cout << setiosflags(ios::left)                  // Output word left-justified
        << setw(maxwidth+2) << words[i];
    cout << resetiosflags(ios::right)                // and word count right-justified
        << setw(5) << count << endl;
    count = 0;
}
cout << endl;
return 0;
}
```

Here's an example of output from this program:

```
Enter some text on as many lines as you wish.  
Terminate the input with an asterisk:  
I sometimes think I'd rather crow  
And be a rooster than to roost  
And be a crow. But I dunno.
```

```
A rooster he can roost also,  
Which don't seem fair when crows can't crow  
Which may help some. Still I dunno.*
```

In ascending sequence, the words in the text are:

A	1
And	2
But	1
I	3
I'd	1
Still	1
Which	2
a	2
also	1
be	2
can	1
can't	1
crow	3
crows	1
don't	1
dunno	2
fair	1
he	1
help	1
may	1
rather	1
roost	2
rooster	2
seem	1
some	1
sometimes	1
than	1
think	1
to	1
when	1

How It Works

The input is read from `cin` using the `getline()` with the termination character specified as an asterisk. This allows an arbitrary number of lines of input to be entered. Individual words are extracted from the input in the string object `text` and stored in the `words` array. This is done in the `while` loop.

The first step in extracting a word from `text` is to find the index position of the first character of the word:

```
start = text.find_first_not_of(separators, offset); // Find non-separator
if(string::npos == start)                      // If we did not find it, we are done
    break;
offset = start + 1;                            // Move past character found
```

The `find_first_not_of()` function returns the index position of the first character from the position `offset` that is not one of the characters in `separators`. You could use the `find_first_of()` function here to search for any of A to Z, a to z, to achieve the same result. When the last word has been extracted, the search will reach the end of the string without finding a character, so you test for this by comparing the value returned with `string::npos`. If it is the end of the string, all words have been extracted, so you exit the loop. In any other instance, you set `offset` at one past the character that was found.

The next search is for any separator character:

```
end = text.find_first_of(separators, offset);           // Find separator
if(string::npos == end)                                // If it's the end of the string
{
    offset = end;                                     // current word is last in string
    end = text.length();                             // We use offset to end loop later
    offset = end + 1;                                // Set end as 1 past last character
}
else
    offset = end + 1;                                // Move past character found
```

The search is from index position `offset`, which is one past the first character of the word, so usually you will find the separator that is one past the last character of the word. When the word is the last in `text` and there is no separator following the last character of the word, the function returns `string::npos`, so you deal with this by setting `end` to one past the last character in the string and setting `offset` to `string::npos`. `offset` is tested later in the loop after the current word has been extracted to determine whether the loop should end.

Extracting a word is easy:

```
words[nwords] = text.substr(start, end-start);          // Extract the word
```

The `substr()` function extracts `end-start` characters from `text`, starting with the character at `start`. The length of the word is `end-start` because `start` is the first character and `end` is one past the last character.

The rest of the `while` loop keeps track of the maximum word length in the way you have seen before, checks for the end-of-string condition, and checks whether the `words` array is full.

The words are output in a `for` loop that iterates over all the elements in the `words` array. The `if` statements deal with counting duplicate words:

```
if(0 == count)
    count = 1;
if(i < nwords-1 && words[i] == words[i+1])
{
    ++count;
    continue;
}
```

The `count` variable records the number of duplicate words, so it is always a minimum of 1. At the end of the loop, `count` is set to 0 when a word and its count are written out. This acts as an indicator that a new word count is starting, so when `count` is 0, the first `if` statement sets it to 1; otherwise, it is left at its current value.

The second `if` statement checks if the next word is the same as the current word, and if it is, `count` is incremented and the rest of the current loop iteration is skipped. This mechanism accumulates the number of times a word is duplicated in `count`. The loop condition also checks that the index, `i`, is less than `nwords - 2`, because we don't want to check the next word when the current word is the last in the array. Thus, we only output a word and its count when the next word is different, or the current word is the last in the array.

The last step in the `for` loop is to output a word and its count:

```
cout << setiosflags(ios::left)           // Output word left-justified
    << setw(maxwidth+2) << words[i];
cout << resetiosflags(ios::right)         // and word count right-justified
    << setw(5) << count << endl;
count = 0;
```

A word is left-justified in a field width that is two greater than the longest word. The `count` is output right-justified in a field width of five.

SUMMARY

In this chapter, you have learned the basics of how you can define classes and how you create and use class objects. You have also learned about overloading operators to allow the operators to be applied to class objects.

EXERCISES

1. Define a class to represent an estimated integer, such as “about 40.” These are integers whose value may be regarded as exact or estimated, so the class needs to have as data members a value and an “estimation” flag. The state of the estimation flag affects arithmetic operations, so that “`2 * about 40`” is “about 80.” The state of variables should be switchable between “estimated” and “exact.”

Provide one or more constructors for such a class. Overload the `+` operator so that these integers can be used in arithmetic expressions. Do you want the `+` operator to be a global or a member function? Do you need an assignment operator? Provide a `Print()` member function so that they can be printed out, using a leading “E” to denote that the “estimation” flag is set. Write a program to test the operation of your class, checking especially that the operation of the estimation flag is correct.

2. Implement a simple string class that holds a `char*` and an integer length as `private` data members. Provide a constructor that takes an argument of type `const char*`, and implement the copy constructor, assignment operator, and destructor functions. Verify that your class works. You will find it easiest to use the string functions from the `cstring` header file.
3. What other constructors might you want to supply for your string class? Make a list, and code them up.
4. (Advanced) Does your class correctly deal with cases such as this?

```
string s1;  
...  
s1 = s1;
```

If not, how should it be modified?

5. (Advanced) Overload the `+` and `+=` operators of your class for concatenating strings.
6. Modify the stack example from Exercise 5 in the previous chapter so that the size of the stack is specified in the constructor and dynamically allocated. What else will you need to add? Test the operation of your new class.
7. Write a program that uses the `string` class that is declared in the `string` header to read a text string of arbitrary length from the keyboard. The program should then prompt for entry of one or more words that appear in the input text. All occurrences of the chosen words in the input text, regardless of case, should be replaced, with as many asterisks as there are letters in the word. Only whole words should be replaced, so if the string is "Our friend Wendy is at the end of the road." and the chosen word is "end", the result should be "Our friend Wendy is at the *** of the road.", not "Our fri*** W***y is at the *** of the road.".
8. Write a class called `CTrace` that you can use to show at run time when code blocks have been entered and exited, by producing output like this:

```
function 'f1' entry  
'if' block entry  
'if' block exit  
function 'f1' exit
```

9. Can you think of a way to automatically control the indentation in the last exercise so that the output looks like this?

```
function 'f1' entry  
'if' block entry  
'if' block exit  
function 'f1' exit
```

► WHAT YOU LEARNED IN THIS CHAPTER

TOPIC	CONCEPT
Destructors	Objects are destroyed using functions called <i>destructors</i> . It is essential to define a destructor in native C++ classes to destroy objects which contain members that are allocated on the heap, because the default constructor will not do this.
The default copy constructor	The compiler will supply a default copy constructor for a native C++ class if you do not define one. The default copy constructor will not deal correctly with objects of classes that have data members allocated on the free store.
Defining a copy constructor	When you define your own copy constructor in a native C++ class, you must use a reference parameter.
Operator overloading	Most basic operators can be overloaded to provide actions specific to objects of a class. You should only implement operator functions for your classes that are consistent with the normal interpretation of the basic operators.
The assignment operator in a class	If you do not define an assignment operator for a class, the compiler will supply a default version. As with the copy constructor, the default assignment operator will not work correctly with classes that have data members allocated on the free store.
Classes that allocate memory on the heap	It is essential that you provide a destructor, a copy constructor, and an assignment operator for classes that have members allocated by <code>new</code> .
Unions	A union is a mechanism that allows two or more variables to occupy the same location in memory.
The <code>string</code> class	The <code>string</code> class in the standard library provides a powerful and superior way to process strings in your programs.
Class templates	A class template is a pattern that you can use to create classes with the same structure, but which support different data types.
Class template parameters	You can define a class template that has multiple parameters, including parameters that can assume constant values rather than types.
Move semantics	You can use the <code>std::move()</code> function that is declared in the <code>utility</code> header to convert an <code>lvalue</code> or an <code>rvalue</code> to an <code>rvalue</code> without copying. This allows you to move rather than copy objects when it is appropriate to do so and avoid the unnecessary copying overhead.

continues

(continued)

TOPIC	CONCEPT
Perfect forwarding	Perfect forwarding is enabled by the <code>std::forward<T>()</code> template function that is declared in the <code>utility</code> header. This allows you to avoid unnecessary copying in a template function that has an rvalue reference argument when the argument is passed to another function.
Organizing your code	You should put definitions for your programs in <code>.h</code> files, and executable code — function definitions — in <code>.cpp</code> files. You can then incorporate <code>.h</code> files into your <code>.cpp</code> files by using <code>#include</code> directives.



Class Inheritance and Virtual Functions

WHAT YOU WILL LEARN IN THIS CHAPTER:

- How inheritance fits into object-oriented programming
- How you define a new class in terms of an existing class
- How you use the `protected` keyword
- How a class can be a friend to another class
- How to use virtual functions
- What pure virtual functions are
- What an abstract class is
- When you should use a virtual destructor

WROX.COM CODE DOWNLOADS FOR THIS CHAPTER

You can find the wrox.com code downloads for this chapter on the Download Code tab at www.wrox.com/remtitle.cgi?isbn=9781118368084. The code is in the Chapter 9 download and individually named according to the names throughout the chapter.

OBJECT-ORIENTED PROGRAMMING BASICS

As you have seen, a class is a data type that you define to suit your own application requirements. Classes in OOP also define the objects to which your program relates. You program the solution to a problem in terms of the objects that are specific to the problem, using operations that work directly with those objects. You can define a class to represent something abstract,

such as a complex number, which is a mathematical concept, or a truck, which is decidedly physical (especially if you run into one on the highway). So, as well as being a data type, a class can also be a definition of a set of real-world objects of a particular kind, at least to the degree necessary to solve a given problem.

You can think of a class as defining the characteristics of a particular group of things that are specified by a common set of parameters and share a common set of operations that may be performed on them. The operations that you can apply to objects of a given class type are defined by the class interface, which corresponds to the functions contained in the `public` section of the class definition. The `CBox` class that you used in the previous chapter is a good example — it defined a box in terms of its dimensions plus a set of public functions that you could apply to `CBox` objects to solve a problem.

Of course, there are many different kinds of boxes in the real world: there are cartons, coffins, candy boxes, and cereal boxes, to name but a few, and you will certainly be able to come up with many others. You can differentiate boxes by the kinds of things they hold, the materials from which they are made, and in a multitude of other ways, but even though there are many different kinds of boxes, they share some common characteristics — the essence of *boxiness*, perhaps. Therefore, you can still visualize all kinds of boxes as actually being related to one another, even though they have many differentiating features. You could define a particular kind of box as having the generic characteristics of all boxes — perhaps just a length, a width, and a height. You could then add some additional characteristics to the basic box type to differentiate a particular kind of box from the rest. You may also find that there are new things you can do with your specific kind of box that you can't do with other boxes.

It's also possible that some objects may be the result of combining a particular kind of box with some other type of object: a box of candy or a crate of beer, for example. To accommodate this, you could define one kind of box as a generic box with basic "boxiness" characteristics and then specify another sort of box as a further specialization of that. Figure 9-1 illustrates an example of the kinds of relationships you might define between different sorts of boxes.




FIGURE 9-1

The boxes become more specialized as you move down the diagram, and the arrows run from a given box type to the one on which it is based. Figure 9-1 defines three different kinds of boxes based on the generic type, CBox. It also defines beer crates as a further refinement of crates designed to hold bottles.

Thus, a good way to approximate the real world relatively well is to define classes that are inter-related. A candy box can be considered to be a box with all the characteristics of a basic box, plus a few characteristics of its own. This precisely illustrates the relationship between classes when one class is defined based on another. A more specialized class has all the characteristics of the class on which it is based, plus a few characteristics of its own that identify what makes it special. Let's look at how this works in practice.

INHERITANCE IN CLASSES

When you define one class based on an existing class, the new class is referred to as a *derived class*. A derived class automatically contains all the data members of the class that you used to define it and, with some restrictions, the function members as well. The class is said to *inherit* the data members and function members of the class on which it is based.

The only members of a base class that are not inherited by a derived class are the destructor, the constructors, and any member functions overloading the assignment operator. All other function members, together with all the data members of a base class, are inherited by a derived class. Of course, the reason for certain base members not being inherited is that a derived class always has its own constructors and destructor. If the base class has an assignment operator, the derived class provides its own version. When I say these functions are not inherited, I mean that they don't exist as members of a derived class object. However, they still exist for the base class part of an object, as you will see.

What Is a Base Class?

A *base class* is any class that you use as a basis for defining another class. For example, if you define a class, B, directly in terms of a class, A, A is said to be a *direct base class* of B. In Figure 9-1, the CCrate class is a direct base class of CBeerCrate. When a class such as CBeerCrate is defined in terms of another class, CCrate, CBeerCrate is said to be derived from CCrate. Because CCrate is itself defined in terms of the class CBox, CBox is said to be an *indirect base class* of CBeerCrate. You'll see how this is expressed in the class definition in a moment. Figure 9-2 illustrates the way in which base class members are inherited in a derived class.




FIGURE 9-2

Just because member functions are inherited doesn't mean that you won't want to replace them in the derived class with new versions, and, of course, you can do that when necessary.

Deriving Classes from a Base Class

Let's go back to the original `CBox` class with `public` data members that you saw at the beginning of the previous chapter:

```
// Header file Box.h in project Ex9_01
#pragma once

class CBox
{
public:
    double m_Length;
    double m_Width;
    double m_Height;

    explicit CBox(double lv = 1.0, double wv = 1.0, double hv = 1.0):
        m_Length(lv), m_Width(wv), m_Height(hv) {}
};


```

Create a new empty Win32 console project with the name `Ex9_01` and save this code in a new header file in the project with the name `Box.h`. The `#pragma once` directive ensures the definition of `CBox` appears only once in a build. There's a constructor in the class so that you can initialize objects when you declare them. Suppose you now need another class of objects, `CCandyBox`, that are the same as `CBox` objects but also have another data member — a pointer to a text string — that identifies the contents of the box. I am using a pointer here to demonstrate aspects of constructors and destructors in derived classes. In real-world code you should use `std::string` to store a string.

You can define `CCandyBox` as a derived class with the `CBox` class as the base class, as follows:

```
// Header file CandyBox.h in project Ex9_01
#pragma once
#include <cstring>                                // For strlen() and strcpy()
#include "Box.h"
class CCandyBox: CBox
{
public:
    char* m_Contents;

    explicit CCandyBox(const char* str = "Candy")           // Constructor
    {
        m_Contents = new char[ strlen(str) + 1 ];
        strcpy_s(m_Contents, strlen(str)+ 1, str);
    }

    ~CCandyBox()                                         // Destructor
    { delete[] m_Contents; };

};


```

Add this header file to the project Ex9_01. You need the `#include` directive for the `Box.h` header file because you refer to the `CBox` class in the code. If you were to leave this directive out, `CBox` would be unknown to the compiler, so the code would not compile. The base class name, `CBox`, appears after the name of the derived class, `CCandyBox`, and is separated from it by a colon. In all other respects, it looks like a normal class definition. You have added the new member, `m_Contents`, and, because it is a pointer to a string, you need a constructor to initialize it and a destructor to release the memory for the string. You have also put a default value for the string describing the contents of a `CCandyBox` object in the constructor. Objects of the `CCandyBox` class type contain all the members of the base class, `CBox`, plus the additional data member, `m_Contents`.

Note the use of the `strcpy_s()` function that you first saw in Chapter 6. Here, there are three arguments — the destination for the copy operation, the length of the destination buffer, and the source. If both arrays were static — that is, not allocated on the heap — you could omit the second argument and just supply the destination and source pointers. This is possible because the `strcpy_s()` function is also available as a template function that can infer the length of the destination string automatically. You can therefore call the function with just the destination and source strings as arguments when you are working with static strings.

TRY IT OUT Using a Derived Class

Now, you'll see how the derived class works in an example. Add the following code to the `Ex9_01` project as the source file `Ex9_01.cpp`:

```
// Ex9_01.cpp
// Using a derived class
#include <iostream>                                // For stream I/O
#include "CandyBox.h"                                // For CBox and CCandyBox
using std::cout;
using std::endl;

int main()
{
    CBox myBox(4.0, 3.0, 2.0);                      // Create CBox object
    CCandyBox myCandyBox;                            // Create CCandyBox object
    CCandyBox myMintBox("Wafer Thin Mints");         // Create CCandyBox object

    cout << endl
        << "myBox occupies " << sizeof myBox           // Show how much memory
        << " bytes" << endl                          // the objects require
        << "myCandyBox occupies " << sizeof myCandyBox
        << " bytes" << endl
        << "myMintBox occupies " << sizeof myMintBox
        << " bytes";

    cout << endl
        << "myBox length is " << myBox.m_Length;

    myBox.m_Length = 10.0;

    // myCandyBox.m_Length = 10.0;                  // uncomment this for an error
```

```
    cout << endl;
    return 0;
}
```

How It Works

You have an `#include` directive for the `CandyBox.h` header here, and because you know that contains an `#include` directive for `Box.h`, you don't need to add a directive to include `Box.h`. You could put an `#include` directive for `Box.h` in this file, in which case, the `#pragma once` directive in `Box.h` would prevent its inclusion more than once. This is important because each class can only be defined once in a program; two definitions for a class in the code would be an error.

After declaring a `CBox` object and two `CCandyBox` objects, you output the number of bytes that each object occupies. Let's look at the output:

```
myBox occupies 24 bytes
myCandyBox occupies 32 bytes
myMintBox occupies 32 bytes
myBox length is 4
```

The first line is what you would expect from the discussion in the previous chapter. A `CBox` object has three data members of type `double`, each of which is 8 bytes, making 24 bytes in all. Both the `CCandyBox` objects are the same size — 32 bytes. The length of the string doesn't affect the size of an object, as the memory to hold the string is allocated in the free store. The 32 bytes are made up of 24 bytes for the three `double` members inherited from the base class `CBox`, plus 4 bytes for the pointer member `m_Contents`, which makes 28 bytes. So, where did the other 4 bytes come from? This is due to the compiler aligning members at addresses that are multiples of 8 bytes. You should be able to demonstrate this by adding an extra member of type `int`, say, to the class `CCandyBox`. You will find that the size of a class object is still 32 bytes.

You also output the value of the `m_Length` member of the `CBox` object, `myBox`. Even though you have no difficulty accessing this member of the `CBox` object, if you uncomment the following statement in the function `main()`,

```
// myCandyBox.m_Length = 10.0;           // uncomment this for an error
```

the program no longer compiles. The compiler generates the following message:

```
error C2247: 'CBox::m_Length' not accessible because 'CCandyBox'
uses 'private' to inherit from 'CBox'
```

It says quite clearly that the `m_Length` member from the base class is not accessible because `m_Length` has become `private` in the derived class. This is because there is a default access specifier of `private` for a base class when you define a derived class — it's as if the first line of the derived class definition had been:

```
class CCandyBox: private CBox
```

There always has to be an access specification for a base class that determines the status of the inherited members in the derived class. If you omit the access specification for a base class, the compiler assumes that it's `private`. If you change the definition of the `CCandyBox` class in `CandyBox.h` to the following,

```

class CCandyBox: public CBox
{
    public:
        char* m_Contents;

        explicit CCandyBox(const char* str = "Candy") // Constructor

    {
        m_Contents = new char[ strlen(str) + 1 ];
        strcpy_s(m_Contents, strlen(str) + 1, str);
    }

    ~CCandyBox() // Destructor
    { delete[] m_Contents; }
};

```

the `m_Length` member is inherited in the derived class as `public`, and is accessible in the function `main()`. With the access specifier `public` for the base class, all the inherited members originally specified as `public` in the base class have the same access level in the derived class.

ACCESS CONTROL UNDER INHERITANCE

The access to inherited members in a derived class needs to be looked at more closely. Consider the status of the `private` members of a base class in a derived class.

There was a good reason to choose the version of the class `CBox` with `public` data members in the previous example, rather than the later, more secure version with `private` data members. Although `private` data members of a base class are also members of a derived class, they remain `private` to the base class in the derived class, so member functions defined in the derived class cannot access them. They are only accessible in the derived class through function members of the base class that are not `private`. You can demonstrate this very easily by changing all the `CBox` class data members to `private` and putting a `Volume()` function in the derived class `CCandyBox`, so that the class definition is as follows:

```

// Version of the classes that will not compile
#include <cstring> // For strlen() and strcpy()
class CBox
{
    public:
        explicit CBox(double lv = 1.0, double wv = 1.0, double hv = 1.0):
            m_Length(lv), m_Width(wv), m_Height(hv) {}

    private:
        double m_Length;
        double m_Width;
        double m_Height;
};

```

```

class CCandyBox: public CBox
{
public:
    char* m_Contents;

    // Function to calculate the volume of a CCandyBox object
    double Volume() const           // Error - members not accessible
    { return m_Length*m_Width*m_Height; }

    explicit CCandyBox(const char* str = "Candy")      // Constructor

    {
        m_Contents = new char[ strlen(str) + 1 ];
        strcpy_s(m_Contents, strlen(str) + 1, str);
    }

    ~CCandyBox()                      // Destructor
    { delete[] m_Contents; }
};

```

A program using these classes does not compile. The function `Volume()` in the class `CCandyBox` attempts to access the `private` members of the base class, which is not legal, so the compiler will flag each instance with error number C2248.

TRY IT OUT Accessing Private Members of the Base Class

However, it is legal to use the `Volume()` function in the base class, so if you move the definition of the function `Volume()` to the `public` section of the base class, `CBox`, not only will the program compile, but you can use the function to obtain the volume of a `CCandyBox` object. Create a new Win32 project, `Ex9_02`, with the `Box.h` contents as the following:

```

// Box.h in Ex9_02
#pragma once

class CBox
{
public:
    explicit CBox(double lv = 1.0, double wv = 1.0, double hv = 1.0):
        m_Length(lv), m_Width(wv), m_Height(hv) {}

    //Function to calculate the volume of a CBox object
    double Volume() const
    { return m_Length*m_Width*m_Height; }

private:
    double m_Length;
    double m_Width;
    double m_Height;
};

```

The CandyBox.h header in the project contains:

```
// Header file CandyBox.h in project Ex9_02
#pragma once
#include "Box.h"
#include <cstring> // For strlen() and strcpy()

class CCandyBox: public CBox
{
public:
    char* m_Contents;

    explicit CCandyBox(const char* str = "Candy") // Constructor
    {
        m_Contents = new char[ strlen(str) + 1 ];
        strcpy_s(m_Contents, strlen(str) + 1, str);
    }

    ~CCandyBox() // Destructor
    { delete[] m_Contents; };
};
```

The Ex9_02.cpp file in the project contains:

```
// Ex9_02.cpp
// Using a function inherited from a base class
#include <iostream> // For stream I/O
#include "CandyBox.h" // For CBox and CCandyBox
using std::cout;
using std::endl;

int main()
{
    CBox myBox(4.0,3.0,2.0); // Create CBox object
    CCandyBox myCandyBox;
    CCandyBox myMintBox("Wafer Thin Mints"); // Create CCandyBox object

    cout << endl
        << "myBox occupies " << sizeof myBox // Show how much memory
        << " bytes" << endl // the objects require
        << "myCandyBox occupies " << sizeof myCandyBox
        << " bytes" << endl
        << "myMintBox occupies " << sizeof myMintBox
        << " bytes";
    cout << endl
        << "myMintBox volume is " << myMintBox.Volume(); // Get volume of a
        // CCandyBox object
    cout << endl;
    return 0;
}
```

This example produces the following output:

```
myBox occupies 24 bytes
myCandyBox occupies 32 bytes
myMintBox occupies 32 bytes
myMintBox volume is 1
```

How It Works

The interesting additional output is the last line. This shows the value produced by the function `volume()`, which is now in the `public` section of the base class. Within the derived class, it operates on the members of the derived class that are inherited from the base. It is a full member of the derived class, so it can be used freely with objects of the derived class.

The value for the volume of the derived class object is 1 because, in creating the `CCandyBox` object, the `CBox()` default constructor was called first to create the base class part of the object, and this sets default `CBox` dimensions to 1.

Constructor Operation in a Derived Class

Although I said that base class constructors are not inherited in a derived class, they still exist in the base class and are used to create the base part of a derived class object. This is because creating the base class part of a derived class object is really the business of a base class constructor, not the derived class constructor. After all, you have seen that private members of a base class are inaccessible in a derived class object, even though they are inherited, so responsibility for these has to lie with the base class constructors.

The default base class constructor was called by default in the last example to create the base part of a derived class object, but this doesn't have to be the case. You can arrange to call a particular base class constructor from a derived class constructor. This enables you to initialize the base class data members with a constructor other than the default, or, indeed, to choose to call a particular base class constructor, depending on the data supplied to the derived class constructor.

TRY IT OUT Calling Constructors

You can see this in action through a modified version of the previous example. To make the class usable, you really need to provide a constructor for the derived class that allows you to specify the dimensions of the object. You can add an additional constructor in the derived class to do this, and call the base class constructor explicitly to set the values of the data members that are inherited from the base class.

In the `Ex9_03` project, `Box.h` contains:

```
// Box.h in Ex9_03
#pragma once
#include <iostream>

class CBox
```

```

{
public:
    // Base class constructor
    explicit CBox(double lv = 1.0, double wv = 1.0, double hv = 1.0):
        m_Length(lv), m_Width(wv), m_Height(hv)
    { std::cout << std::endl << "CBox constructor called"; }

    //Function to calculate the volume of a CBox object
    double Volume() const
    { return m_Length*m_Width*m_Height; }

private:
    double m_Length;
    double m_Width;
    double m_Height;
};

```

The CandyBox.h header file should contain:

```

// CandyBox.h in Ex9_03
#pragma once
#include <cstring>                                // For strlen() and strcpy()
#include <iostream>
#include "Box.h"

class CCandyBox: public CBox
{
public:
    char* m_Contents;

    // Constructor to set dimensions and contents
    // with explicit call of CBox constructor
    explicit CCandyBox(double lv, double wv, double hv, const char* str = "Candy")
        : CBox(lv, wv, hv)
    {
        std::cout << std::endl << "CCandyBox constructor2 called";
        m_Contents = new char[ strlen(str) + 1 ];
        strcpy_s(m_Contents, strlen(str) + 1, str);
    }

    // Constructor to set contents
    // calls default CBox constructor automatically
    explicit CCandyBox(const char* str = "Candy")
    {
        std::cout << std::endl << "CCandyBox constructor1 called";
        m_Contents = new char[ strlen(str) + 1 ];
        strcpy_s(m_Contents, strlen(str) + 1, str);
    }

    ~CCandyBox()                                     // Destructor
    { delete[] m_Contents; }
};

```

The `#include` directive for the `iostream` header and the two `using` declarations are not strictly necessary here because `Box.h` contains the same code, but it does no harm to put them in. On the contrary, putting these statements in here also means that if you were to remove this code from `Box.h` because it was no longer required there, `CandyBox.h` would still compile.

The contents of `Ex9_03.cpp` are:

```
// Ex9_03.cpp
// Calling a base constructor from a derived class constructor
#include <iostream> // For stream I/O
#include "CandyBox.h" // For CBox and CCandyBox
using std::cout;
using std::endl;

int main()
{
    CBox myBox(4.0, 3.0, 2.0);
    CCandyBox myCandyBox;
    CCandyBox myMintBox(1.0, 2.0, 3.0, "Wafer Thin Mints");

    cout << endl
        << "myBox occupies " << sizeof myBox // Show how much memory
        << " bytes" << endl // the objects require
        << "myCandyBox occupies " << sizeof myCandyBox
        << " bytes" << endl
        << "myMintBox occupies " << sizeof myMintBox
        << " bytes";
    cout << endl
        << "myMintBox volume is " // Get volume of a
        << myMintBox.Volume(); // CCandyBox object
    cout << endl;
    return 0;
}
```

How It Works

As well as adding a constructor to the derived class, you have added an output statement in each constructor so you know when either gets called. The explicit `CBox` constructor call appears after a colon in the function header of the derived class constructor. The notation is exactly the same as what you have been using for initializing members in a constructor:

```
// Calling the base class constructor
explicit CCandyBox(double lv, double wv, double hv, const char* str= "Candy") :
    CBox(lv, wv, hv)
{
    ...
}
```

This is perfectly consistent with what you are doing here, because you are essentially initializing the `CBox` sub-object of a derived class object. In the first case, you are explicitly calling the default constructor for the `double` members `m_Length`, `m_Width`, and `m_Height` in the initialization list. In the

second instance, you are calling the constructor for `CBox`. This causes the specific `CBox` constructor you have chosen to be called before the `CCandyBox` constructor code is executed.

If you build and run this example, it produces the following output:

```
CBox constructor called
CBox constructor called
CCandyBox constructor1 called
CBox constructor called
CCandyBox constructor2 called
myBox occupies 24 bytes
myCandyBox occupies 32 bytes
myMintBox occupies 32 bytes
myMintBox volume is 6
```

The constructor calls are explained in the following table:

SCREEN OUTPUT	OBJECT BEING CONSTRUCTED
<code>CBox constructor called</code>	<code>myBox</code>
<code>CBox constructor called</code>	<code>myCandyBox</code>
<code>CCandyBox constructor1 called</code>	<code>myCandyBox</code>
<code>CBox constructor called</code>	<code>myMintBox</code>
<code>CCandyBox constructor2 called</code>	<code>myMintBox</code>

The first line of output is due to the `CBox` class constructor call, originating from the declaration of the `CBox` object, `myBox`. The second line of output arises from the automatic call of the base class constructor caused by the declaration of the `CCandyBox` object, `myCandyBox`.

Notice how the base class constructor is always called before the derived class constructor. The base class is the foundation on which the derived class is built, so the base class must be created first.

The next line is due to your version of the default derived class constructor being called for the `myCandyBox` object. This constructor is invoked because the object is not initialized. The fourth line of output arises from the explicit identification of the `CBox` class constructor to be called in our new constructor for `CCandyBox` objects. The argument values specified for the dimensions of the `CCandyBox` object are passed to the base class constructor. Next comes the output from the new derived class constructor itself, so constructors are again called for the base class first, followed by the derived class.

It should be clear from what you have seen up to now that when a derived class constructor is executed, a base class constructor is always called to construct the base part of the derived class object. If you don't specify the base class constructor to be used, the compiler arranges for the default base class constructor to be called. The last line in the table shows that the initialization of the base part of the `myMintBox` object is working as it should be, with the `private` members having been initialized by the `CBox` class constructor.

Having the `private` members of a base class that are only accessible to function members of the base class isn't always convenient. There will be many instances where you want to have `private` members of a base class that *can* be accessed from within the derived class. As you surely have anticipated by now, C++ provides a way to do this.

Declaring Protected Class Members

In addition to the `public` and `private` access specifiers for members of a class, you can also declare members as `protected`. The `protected` keyword has the same effect as the `private` keyword within a class: members that are `protected` can only be accessed by member functions of the class, and by `friend` functions of the class (also by member functions of a `friend` class — you will learn about `friend` classes later in this chapter). Base class members that are `protected` can be accessed from any derived class function. Using the `protected` keyword, you could redefine the `CBox` class as follows:

```
// Box.h in Ex9_04
#pragma once
#include <iostream>
using std::cout;
using std::endl;

class CBox
{
public:
    // Base class constructor
    explicit CBox(double lv = 1.0, double wv = 1.0, double hv = 1.0):
        m_Length(lv), m_Width(wv), m_Height(hv)
    { cout << endl << "CBox constructor called"; }

    // CBox destructor - just to track calls
    ~CBox()
    { std::cout << "CBox destructor called" << std::endl; }

protected:
    double m_Length;
    double m_Width;
    double m_Height;
};
```

The data members are still effectively `private`, in that they can't be accessed by ordinary global functions, but they can still be accessed by member functions of a derived class.

TRY IT OUT Using Protected Members

You can demonstrate the use of `protected` data members by using this version of the class `CBox` to derive a new version of the `CCandyBox` class that accesses the members of the base class through its own member function, `Volume()`:

```

// CandyBox.h in Ex9_04
#pragma once
#include "Box.h"
#include <cstring>                                // For strlen() and strcpy()
#include <iostream>
using std::cout;
using std::endl;

class CCandyBox: public CBox
{
public:
    char* m_Contents;

    // Derived class function to calculate volume
    double Volume() const
    { return m_Length*m_Width*m_Height; }

    // Constructor to set dimensions and contents
    // with explicit call of CBox constructor
    explicit CCandyBox(double lv, double wv, double hv,
                        const char* str = "Candy") : CBox(lv, wv, hv)
                                         // Constructor
    {
        std::cout << std::endl << "CCandyBox constructor2 called";
        m_Contents = new char[ strlen(str) + 1 ];
        strcpy_s(m_Contents, strlen(str) + 1, str);
    }

    // Constructor to set contents
    // calls default CBox constructor automatically
    explicit CCandyBox(const char* str = "Candy")           // Constructor
    {
        std::cout << std::endl << "CCandyBox constructor1 called";
        m_Contents = new char[ strlen(str) + 1 ];
        strcpy_s(m_Contents, strlen(str) + 1, str);
    }

    ~CCandyBox()                                         // Destructor
    {
        std::cout << "CCandyBox destructor called" << std::endl;
        delete[] m_Contents;
    }
};

```

The code for `main()` in `Ex9_04.cpp` is:

```

// Ex9_04.cpp
// Using the protected access specifier
#include <iostream>                                // For stream I/O
#include "CandyBox.h"                                // For CBox and CCandyBox
using std::cout;
using std::endl;

int main()
{

```

```
CCandyBox myCandyBox;
CCandyBox myToffeeBox(2, 3, 4, "Stickjaw Toffee");

cout << endl
    << "myCandyBox volume is " << myCandyBox.Volume()
    << endl
    << "myToffeeBox volume is " << myToffeeBox.Volume();

// cout << endl << myToffeeBox.m_Length; // Uncomment this for an error

cout << endl;
return 0;
}
```

How It Works

In this example you calculate the volumes of the two `CCandyBox` objects by invoking the `Volume()` function that is a member of the derived class. This function accesses the inherited members `m_Length`, `m_Width`, and `m_Height` to produce the result. The members are declared as `protected` in the base class and remain `protected` in the derived class. The program produces the output shown as follows:

```
CBox constructor called
CCandyBox constructor1 called
CBox constructor called
CCandyBox constructor2 called
myCandyBox volume is 1
myToffeeBox volume is 24
CCandyBox destructor called
CBox destructor called
CCandyBox destructor called
CBox destructor called
```

The output shows that the volume is being calculated properly for both `CCandyBox` objects. The first object has the default dimensions produced by calling the default `CBox` constructor, so the volume is 1, and the second object has the dimensions defined as initial values in its declaration.

The output also shows the sequence of constructor and destructor calls, and you can see how each derived class object is destroyed in two steps.

Destructors for a derived class object are called in the reverse order of the constructors for the object. This is a general rule that always applies. Constructors are invoked starting with the base class constructor and then the derived class constructor, whereas the destructor for the derived class is called first when an object is destroyed, followed by the base class destructor.

You can demonstrate that the `protected` members of the base class remain `protected` in the derived class by uncommenting the statement preceding the `return` statement in the function `main()`. If you do this, you get the following error message from the compiler,

```
error C2248: 'CBox::m_Length': cannot access protected member declared in class 'CBox'
```

which indicates quite clearly that the member `m_Length` is inaccessible.

The Access Level of Inherited Class Members

You know that if you have no access specifier for the base class in the definition of a derived class, the default specification is `private`. This has the effect of causing the inherited `public` and `protected` members of the base class to become `private` in the derived class. The `private` members of the base class remain `private` to the base and, therefore, inaccessible to member functions of the derived class. In fact, they remain `private` to the base class regardless of how the base class is specified in the derived class definition.

You have also used `public` as the specifier for a base class. This leaves the members of the base class with the same access level in the derived class as they had in the base, so `public` members remain `public`, and `protected` members remain `protected`.

The last possibility is that you declare a base class as `protected`. This has the effect of making the inherited `public` members of the base `protected` in the derived class. The `protected` (and `private`) inherited members retain their original access level in the derived class. This is summarized in Figure 9-3, which shows classes `CABox`, `CBBox`, and `CCBox` derived from `CBox`.




FIGURE 9-3

This may look a little complicated, but you can reduce it to the following three points about the inherited members of a derived class:

- Members of a base class that are declared as `private` are never accessible in a derived class.
- Defining a base class as `public` doesn't change the access level of its members in the derived class.
- Defining a base class as `protected` changes its `public` members to `protected` in the derived class.

Being able to change the access level of inherited members in a derived class gives you a degree of flexibility, but don't forget that you cannot relax the level specified in the base class; you can only make the access level more stringent. This suggests that your base classes need to have `public` members if you want to be able to vary the access level in derived classes. This may seem to run contrary to the idea of encapsulating data in a class in order to protect it from unauthorized access, but, as you'll see, it is often the case that you define base classes in such a manner that their only purpose is to act as a base for other classes, and they aren't intended to be used for instantiating objects in their own right.

THE COPY CONSTRUCTOR IN A DERIVED CLASS

Remember that the copy constructor is called automatically when you declare an object that is initialized with an object of the same class. Look at these statements:

```
CBox myBox(2.0, 3.0, 4.0);           // Calls constructor
CBox copyBox(myBox);                // Calls copy constructor
```

The first statement calls the constructor that accepts three arguments of type `double`, and the second calls the copy constructor. If you don't supply your own copy constructor, the compiler supplies one that copies the initializing object, member by member, to the corresponding members of the new object. So that you can see what is going on during execution, you can add your own version of a copy constructor to the `CBox` class. You can then use this class as a base for defining the `CCandyBox` class:

```
// Box.h in Ex9_05
#pragma once
#include <iostream>
using std::cout;
using std::endl;

class CBox           // Base class definition
{
public:
    // Base class constructor
    explicit CBox(double lv = 1.0, double wv = 1.0, double hv = 1.0):
        m_Length(lv), m_Width(wv), m_Height(hv)
    { std::cout << std::endl << "CBox constructor called"; }
```

```

// Copy constructor
CBox(const CBox& initB)
{
    std::cout << std::endl << "CBox copy constructor called";
    m_Length = initB.m_Length;
    m_Width = initB.m_Width;
    m_Height = initB.m_Height;
}

// CBox destructor - just to track calls
~CBox()
{ std::cout << "CBox destructor called" << std::endl; }

protected:
    double m_Length;
    double m_Width;
    double m_Height;
};

```

Don't forget that a copy constructor must have its parameter specified as a reference. This avoids the infinite number of calls to itself that would otherwise result from the need to copy an argument that is transferred by value. When the copy constructor in our example is invoked, it outputs a message, so you can see from the output when this is happening. All you need now is to add a copy constructor to the CCandyBox class.

TRY IT OUT The Copy Constructor in a Derived Class

Add the following code for the copy constructor to the public section of the derived CCandyBox class in Ex9_04:

```

// Derived class copy constructor
CCandyBox(const CCandyBox& initCB)
{
    std::cout << std::endl << "CCandyBox copy constructor called";

    // Get new memory
    m_Contents = new char[ strlen(initCB.m_Contents) + 1 ];

    // Copy string
    strcpy_s(m_Contents, strlen(initCB.m_Contents) + 1, initCB.m_Contents);
}

```

You can now run this new version (Ex9_05) of the last example with the following `main()` function to see how the new copy constructor works:

```

int main()
{
    CCandyBox chocBox(2.0, 3.0, 4.0, "Chockies"); // Declare and initialize
    CCandyBox chocolateBox(chocBox); // Use copy constructor
}

```

```
    cout << endl
    << "Volume of chocBox is " << chocBox.Volume()
    << endl
    << "Volume of chocolateBox is " << chocolateBox.Volume()

    << endl;

    return 0;
}
```

How It Works

This example produces the following output:

```
CBox constructor called
CCandyBox constructor2 called
CBox constructor called
CCandyBox copy constructor called
Volume of chocBox is 24
Volume of chocolateBox is 1
CCandyBox destructor called
CBox destructor called
CCandyBox destructor called
CBox destructor called
```

Although this looks okay at first sight, there is something wrong. The third line of output shows that the default constructor for the `CBox` part of the object `chocolateBox` is called, rather than the copy constructor. As a consequence, the object has the default dimensions rather than the dimensions of the initializing object, so the volume is incorrect. The reason for this is that when you write a constructor for an object of a derived class, you are responsible for ensuring that the members of the derived class object are properly initialized. This includes the inherited members.

The fix for this is to call the copy constructor for the base part of the class in the initialization list for the copy constructor for the `CCandyBox` class. The copy constructor then becomes:

```
// Derived class copy constructor
CCandyBox(const CCandyBox& initCB): CBox(initCB)
{
    std::cout << std::endl << "CCandyBox copy constructor called";

    // Get new memory
    m_Contents = new char[ strlen(initCB.m_Contents) + 1 ];

    // Copy string
    strcpy_s(m_Contents, strlen(initCB.m_Contents) + 1, initCB.m_Contents);
}
```

The `CBox` class copy constructor is called with the `initCB` object. Only the base part of the object is passed to it, so everything works out. If you modify the example by adding the base copy constructor call, the output is:

```
CBox constructor called
CCandyBox constructor2 called
CBox copy constructor called
CCandyBox copy constructor called
Volume of chocBox is 24
Volume of chocolateBox is 24

CCandyBox destructor called
CBox destructor called
CCandyBox destructor called
CBox destructor called
```

This shows that all the constructors and destructors are called in the correct sequence, and the copy constructor for the CBox part of chocolateBox is called before the CCandyBox copy constructor. The volume of the object chocolateBox of the derived class is now the same as that of its initializing object, which is as it should be.

You have, therefore, another golden rule to remember:

NOTE If you write any kind of constructor for a derived class, you are responsible for the initialization of all members of the derived class object, including all its inherited members.

Of course, as you saw in the previous chapter, if you want to make a class that allocates memory on the heap as efficient as possible, you should overload the copy constructor with a version that uses an rvalue reference parameter. You could add the following to the CCandyBox class to take care of this:

```
// Move constructor
CCandyBox(CCandyBox&& initCB): CBox(std::move(initCB))
{
    std::cout << std::endl << "CCandyBox move constructor called";
    m_Contents = initCB.m_Contents;
    initCB.m_Contents = 0;
}
```

You still have to call the base class move constructor to get the base members initialized.

PREVENTING CLASS DERIVATION

Circumstances can arise where you want to be sure that your class cannot be used as a base class. You can do this by specifying your class as final. Here's how you could prevent derivation from the CBox class in Ex9_05:

```
class CBox final
{
    // Class details as before...
};
```

The `final` modifier following the class name in the definition tells the compiler that derivation from the `CBox` class is not to be allowed. If you modify the `CBox` class in `Ex9_05` in this way, the code will not compile.

Note that `final` is not a keyword; it just has a special meaning in context. You are not allowed to use a keyword as a name, whereas you could use `final` as the name for a variable, for example.

CLASS MEMBERS AS FRIENDS

You saw in Chapter 7 how a function can be declared as a `friend` of a class. This gives the `friend` function the privilege of free access to any of the class members. Of course, there is no reason why a `friend` function cannot be a member of another class.

Suppose you define a `CBottle` class to represent a bottle:

```
#pragma once

class CBottle
{
public:
    CBottle(double height, double diameter)
    {
        m_Height = height;
        m_Diameter = diameter;
    }

private:
    double m_Height;                      // Bottle height
    double m_Diameter;                     // Bottle diameter
};
```

You now need a class to represent the packaging for a dozen bottles that automatically has custom dimensions to accommodate a particular kind of bottle. You could define this as:

```
#pragma once
class CBottle;                                // Forward declaration

class CCarton
{
public:
    CCarton(const CBottle& aBottle)
    {
        m_Height = aBottle.m_Height;          // Bottle height
        m_Length = 4.0*aBottle.m_Diameter;    // Four rows of ...
        m_Width = 3.0*aBottle.m_Diameter;     // ...three bottles
    }

private:
    double m_Length;                      // Carton length
    double m_Width;                       // Carton width
    double m_Height;                      // Carton height
};
```

The constructor here sets the height to be the same as that of the bottle it is to accommodate, and the length and width are set based on the diameter of the bottle so that 12 ft in the box. The forward declaration for the `CBottle` class is necessary because the constructor refers to `CBottle`. As you know by now, this won't work. The data members of the `CBottle` class are `private`, so the `CCarton` constructor cannot access them. As you also know, a `friend` declaration in the `CBottle` class fixes it:

```
#pragma once;
class CCarton; // Forward declaration

class CBottle
{
public:
    CBottle(double height, double diameter)
    {
        m_Height = height;
        m_Diameter = diameter;
    }

private:
    double m_Height; // Bottle height
    double m_Diameter; // Bottle diameter

    // Let the carton constructor in
    friend CCarton::CCarton(const CBottle& aBottle);
};


```

The only difference between the `friend` declaration here and what you saw in Chapter 7 is that you must put the class name and the scope resolution operator with the `friend` function name to identify it. You have a forward declaration for the `CCarton` class because the `friend` function refers to it.

You might think that this will compile correctly, but there is a problem. The `CCarton` class definition refers to the `CBottle` class, and the `CBottle` class with the `friend` function added refers to the `CCarton` class, so you have a cyclic dependency here. You can put a forward declaration of the `CCarton` class in the `CBottle` class, and vice versa, but this still won't allow the classes to compile. The problem is with the `CCarton` class constructor. This appears within the `CCarton` class definition and the compiler cannot compile this function without having first compiled the `CBottle` class. On the other hand, it can't compile the `CBottle` class without having compiled the `CCarton` class. The only way to resolve this is to put the `CCarton` constructor definition in a `.cpp` file. The header file holding the `CCarton` class definition will be:

```
#pragma once
class CBottle; // Forward declaration

class CCarton
{
public:
    CCarton(const CBottle& aBottle);

private:
    double m_Length; // Carton length
    double m_Width; // Carton width
```

```
    double m_Height; // Carton height
};
```

The contents of the `carton.cpp` file will be:

```
#include "carton.h"
#include "bottle.h"

CCarton::CCarton(const CBottle& aBottle)
{
    m_Height = aBottle.m_Height; // Bottle height
    m_Length = 4.0*aBottle.m_Diameter; // Four rows of ...
    m_Width = 3.0*aBottle.m_Diameter; // ...three bottles
}
```

Now, the compiler is able to compile both class definitions and the `carton.cpp` file.

Friend Classes

You can also allow all the function members of one class to have access to all the data members of another by declaring it as a *friend class*. You could define the `CCarton` class as a friend of the `CBottle` class by adding a `friend` declaration within the `CBottle` class definition:

```
friend CCarton;
```

With this declaration in the `CBottle` class, all function members of the `CCarton` class now have free access to all the data members of the `CBottle` class.

Limitations on Class Friendship

Class friendship is not reciprocated. Making the `CCarton` class a `friend` of the `CBottle` class does not mean that the `CBottle` class is a `friend` of the `CCarton` class. If you want this to be so, you must add a `friend` declaration for the `CBottle` class to the `CCarton` class.

Class friendship is also not inherited. If you define another class with `CBottle` as a base, members of the `CCarton` class will not have access to its data members, not even those inherited from `CBottle`.

VIRTUAL FUNCTIONS

Let's look more closely at the behavior of inherited member functions and their relationship with derived class member functions. You could add a function to the `CBox` class to output the volume of a `CBox` object. The simplified class then becomes:

```
// Box.h in Ex9_06
#pragma once
#include <iostream>
```

```

class CBox                                // Base class
{
public:

    // Function to show the volume of an object
    void ShowVolume() const
    {
        std::cout << std::endl
                    << "CBox usable volume is " << Volume();
    }

    // Function to calculate the volume of a CBox object
    double Volume() const
    { return m_Length*m_Width*m_Height; }

    // Constructor
    explicit CBox(double lv = 1.0, double wv = 1.0, double hv = 1.0)
        :m_Length(lv), m_Width(wv), m_Height(hv) {}

protected:
    double m_Length;
    double m_Width;
    double m_Height;
};

```

Now, you can output the usable volume of a `CBox` object just by calling the `ShowVolume()` function for any object for which you require it. The constructor sets the data member values in the initialization list, so no statements are necessary in the body of the function. The data members are as before and are specified as `protected`, so they are accessible to the member functions of any derived class.

Suppose you want to derive a class for a different kind of box called `CGlassBox`, to hold glassware. The contents are fragile, and because packing material is added to protect them, the capacity of the box is less than the capacity of a basic `CBox` object. You therefore need a different `Volume()` function to account for this, so you add it to the derived class:

```

// GlassBox.h in Ex9_06
#pragma once
#include "Box.h"

class CGlassBox: public CBox           // Derived class
{
public:
    // Function to calculate volume of a CGlassBox
    // allowing 15% for packing
    double Volume() const
    { return 0.85*m_Length*m_Width*m_Height; }

    // Constructor
    CGlassBox(double lv, double wv, double hv): CBox(lv, wv, hv){}
};

```

There could conceivably be other additional members of the derived class, but we'll keep it simple and concentrate on how the inherited functions work for the moment. The constructor for the derived class objects just calls the base class constructor in its initialization list to set the data member values. No statements are necessary in its body. You have included a new version of the `Volume()` function to replace the version from the base class, the idea being that you can get the inherited function `ShowVolume()` to call the derived class version of the member function `Volume()` when you call it for an object of the class `CGlassBox`.

TRY IT OUT Using an Inherited Function

You can see how the derived class works in practice very simply by creating objects of the base class and the derived class with the same dimensions and then verifying that the correct volumes are being calculated. The `main()` function to do this is as follows:

```
// Ex9_06.cpp
// Behavior of inherited functions in a derived class
#include <iostream>
#include "GlassBox.h" // For CBox and CGlassBox
using std::cout;
using std::endl;

int main()
{
    CBox myBox(2.0, 3.0, 4.0); // Declare a base box
    CGlassBox myGlassBox(2.0, 3.0, 4.0); // Declare derived box - same size

    myBox.ShowVolume(); // Display volume of base box

    myGlassBox.ShowVolume(); // Display volume of derived box

    cout << endl;
    return 0;
}
```

How It Works

If you run this example, it produces the following output:

```
CBox usable volume is 24
CBox usable volume is 24
```

This isn't only dull and repetitive, but it's also disastrous. It isn't working the way you want at all, and the only interesting thing about it is why. Evidently, the fact that the second call is for an object of the derived class `CGlassBox` is not being taken into account. You can see this from the incorrect result for the volume in the output. The volume of a `CGlassBox` object should definitely be less than that of a basic `CBox` with the same dimensions.

The incorrect output is because the `Volume()` function call in the `ShowVolume()` function is being set, once and for all, by the compiler as the version defined in the base class. `ShowVolume()` is a base class function, and when `CBox` is compiled, the call to `Volume()` is resolved at that time to the base class `Volume()` function; the compiler has no knowledge of any other `Volume()` function. This is called

static resolution of the function call since the function call is fixed before the program is executed. This is also called *early binding* because the particular `Volume()` function chosen is bound to the call from the function `ShowVolume()` during the compilation of the program rather than its execution.

What we were hoping for in this example was that the question of which `Volume()` function call to use in any given instance would be resolved when the program was executed. This sort of operation is referred to as *dynamic linkage*, or *late binding*. We want the actual version of the function `Volume()` called by `ShowVolume()` to be determined by the kind of object being processed, and not arbitrarily fixed by the compiler before the program is executed.

No doubt, you'll be less than astonished that C++ does, in fact, provide you with a way to do this, because this whole discussion would have been futile otherwise! You need to use something called a *virtual function*.

What Is a Virtual Function?

A virtual function is a function in a base class that is declared using the keyword `virtual`. If you specify a function in a base class as `virtual` and there is another definition of the function in a derived class, it signals to the compiler that you don't want static linkage for this function. What you *do* want is the selection of the function to be called at any given point in the program to be based on the kind of object for which it is called.

TRY IT OUT Fixing the CGlassBox

To make this example work as originally hoped, you just need to add the keyword `virtual` to the definitions of the `Volume()` function in the two classes. You can try this in a new project, `Ex9_07`. Here's how the definition of `CBox` should be:

```
// Box.h in Ex9_07
#pragma once
#include <iostream>

class CBox                                // Base class
{
public:
    // Function to show the volume of an object
    void ShowVolume() const
    {
        std::cout << std::endl
            << "CBox usable volume is " << Volume();
    }

    // Function to calculate the volume of a CBox object
    virtual double Volume() const
    { return m_Length*m_Width*m_Height; }

    // Constructor
    explicit CBox(double lv = 1.0, double wv = 1.0, double hv = 1.0)
        :m_Length(lv), m_Width(wv), m_Height(hv) {}
}
```

```
protected:  
    double m_Length;  
    double m_Width;  
    double m_Height;  
};
```

The GlassBox.h header file contents should be:

```
// GlassBox.h in Ex9_07  
#pragma once  
#include "Box.h"  
  
class CGlassBox: public CBox           // Derived class  
{  
public:  
    // Function to calculate volume of a CGlassBox  
    // allowing 15% for packing  
    virtual double Volume() const  
    { return 0.85*m_Length*m_Width*m_Height; }  
  
    // Constructor  
    CGlassBox(double lv, double wv, double hv): CBox(lv, wv, hv){}  
};
```

The Ex9_07.cpp file version of main() is the same as for the previous example.

How It Works

If you run this version of the program with just the little word `virtual` added to the definitions of `Volume()`, it produces this output:

```
CBox usable volume is 24  
CBox usable volume is 20.4
```

This is now clearly doing what you wanted in the first place. The first call to the function `ShowVolume()` with the `CBox` object `myBox` calls the `CBox` class version of `Volume()`. The second call with the `CGlassBox` object `myGlassBox` calls the version defined in the derived class.

Note that although you have put the keyword `virtual` in the derived class definition of the function `Volume()`, it's not essential to do so. The definition of the base version of the function as `virtual` is sufficient. However, I recommend that you do specify the keyword for virtual functions in derived classes because it makes it clear to anyone reading the derived class definition that they are virtual functions and that they are selected dynamically.

For a function to behave as virtual, it must have the same name, parameter list, and return type in any derived class as the function has in the base class, and if the base class function is `const`, the derived class function must be, too. If you try to use different parameters or return types, or declare one as `const` and the other not, the virtual function mechanism won't work and the functions operate with static linkage that is fixed at compile time.

The operation of virtual functions is an extraordinarily powerful mechanism. You may have heard the term *polymorphism* in relation to object-oriented programming, and this refers to the virtual function

capability. Something that is polymorphic can appear in different guises, like a werewolf, or Dr. Jekyll, or a politician before and after an election, for example. Calling a virtual function produces different effects depending on the kind of object for which it is being called.

Note that the `Volume()` function in the derived `CGlassBox` class hides the base class version from the view of derived class functions. If you wanted to call the base version of `Volume()` from a derived class function, you would need to use the scope resolution operator to refer to the function as `CBox::Volume()`.

Ensuring Correct Virtual Function Operation

As I said in the previous section, for a function to behave as virtual, it must have the same name, parameter list, and return type in any derived class as a function in the base class. It's not difficult to make a mistake though. If you forget to specify the `Volume()` function as `const` in the `CGlassBox` class in `Ex9_07`, the program will still compile — it just won't work correctly. When the function in the derived class has a different signature from the function in the base class it is supposed to be overriding, you are not overriding the base class function at all and you will get static linkage for function calls. You can tell the compiler that a virtual function in a derived class is overriding a virtual function in a base class by using the `override` modifier. You could do this for the `Volume()` function in `CGlassBox` in `Ex9_07` like this:

```
class CGlassBox: public CBox           // Derived class
{
public:
    // Function to calculate volume of a CGlassBox
    // allowing 15% for packing
    virtual double Volume() const override
    { return 0.85*m_Length*m_Width*m_Height; }

    // Constructor
    CGlassBox(double lv, double wv, double hv): CBox(lv, wv, hv){}
};
```

Now the compiler will check that there is a base class `Volume()` function with the same signature. If there isn't, you will get an error message. You can demonstrate this by changing the definition of `Volume()` in `CGlassBox` by adding the `override` modifier and also omitting the `const` keyword.

If you always use the `override` modifier with virtual functions in derived classes that are intended to override a base class function, you are guaranteed that any mistakes in specifying the overrides will be reported by the compiler. Note that like the `final` modifier, `override` is not a keyword. It just has special meaning in context.

Preventing Function Overriding

You may want to prevent the possibility of a function member of a class being overridden. This could be because you want to preserve a particular aspect of behavior. In this case you can specify a member function as `final`. For example, you could specify that the `Volume()` member of the `CBox` class in `Ex9_07` is not to be overridden like this:

```

class CBox           // Base class
{
public:
    // Class definition as before....

    // Function to calculate the volume of a CBox object
virtual double Volume() const final
    { return m_Length*m_Width*m_Height; }

    // Rest of the class as before...
};

```

The **final** modifier tells the compiler that the **Volume()** function must not be overridden. With this amendment the compiler will flag the **Volume()** function in the derived class as an error.

Using Pointers to Class Objects

Using pointers with objects of a base class and of a derived class is an important technique. You can use a pointer to a base class type to store the address of a derived class object as well as that of a base class object. You can thus use a pointer of the type “pointer to base” to obtain different behavior with virtual functions, depending on what kind of object the pointer is pointing to. You’ll see more clearly how this works by looking at an example.

TRY IT OUT Pointers to Base and Derived Classes

You’ll use essentially the same classes as in the previous example, but make a small modification to the **main()** function so that it uses a pointer to a base class object. Create the **Ex9_08** project with **Box.h** and **GlassBox.h** header files as in the previous example. You can copy the **Box.h** and **Glassbox.h** files from the **Ex9_07** project to this project folder. In the code download, adding an existing file to a project is quite easy; you right-click **Ex9_08** in the Solution Explorer tab, select **Add** → **Existing Item...** from the pop-up menu, and then select a file to add it to the project. You can select multiple files to add, if you want. When you have added the headers, modify **Ex9_08.cpp** to the following:

```

// Ex9_08.cpp
// Using a base class pointer to call a virtual function
#include <iostream>
#include "GlassBox.h"           // For CBox and CGlassBox
using std::cout;
using std::endl;

int main()
{
    CBox myBox(2.0, 3.0, 4.0);           // Declare a base box
    CGlassBox myGlassBox(2.0, 3.0, 4.0); // Declare derived box of same size
    CBox* pBox(nullptr);               // Declare a pointer to base class objects

    pBox = &myBox;                    // Set pointer to address of base object
    pBox->ShowVolume();             // Display volume of base box
    pBox = &myGlassBox;              // Set pointer to derived class object
    pBox->ShowVolume();             // Display volume of derived box
}

```

```

    cout << endl;
    return 0;
}

```

In the code download for this example, you will find that I also added the `override` modifier to the `Volume()` function in the `CGlassBox` class.

How It Works

The classes are the same as in example `Ex9_07.cpp`, but `main()` has been altered to use a pointer to call `ShowVolume()`. Because you are using a pointer, you use the indirect member selection operator, `->`, to call the function. The `ShowVolume()` function is called twice, and both calls use the same pointer to base class objects, `pBox`. On the first occasion, the pointer contains the address of the base object, `myBox`, and on the occasion of the second call, it contains the address of the derived class object, `myGlassBox`.

The output produced is as follows:

```
CBox usable volume is 24
CBox usable volume is 20.4
```

This is exactly the same as that from the previous example, where you used explicit objects in the function call.

You can conclude from this example that the virtual function mechanism works just as well through a pointer to a base class, and the specific function to be called is selected based on the type of object being pointed to. This is illustrated in Figure 9-4.




FIGURE 9-4

This is an important result. Even when you don't know the precise type of the object pointed to by a base class pointer (when a pointer is passed to a function as an argument, for example), the virtual function mechanism ensures that the correct function is called. This is an extraordinarily powerful capability, so make sure you understand it. Polymorphism is a fundamental mechanism in C++ that you will find yourself using again and again.

Using References with Virtual Functions

If you define a function with a parameter that is a reference to a base class type, you can pass an object of a derived class type to it. When the function executes, the appropriate virtual function for the object passed is selected automatically. You can see this happening by modifying the `main()` function, in the previous example, to call a function that has a reference as a parameter.

TRY IT OUT

Using References with Virtual Functions

Let's move the call to `ShowVolume()` in `main()` into a separate function and call that separate function from `main()`:

```
// Ex9_09.cpp
// Using a reference to call a virtual function
#include <iostream>
#include "GlassBox.h" // For CBox and CGlassBox
using std::cout;
using std::endl;

void Output(const CBox& aBox); // Prototype of function

int main()
{
    CBox myBox(2.0, 3.0, 4.0); // Declare a base box
    CGlassBox myGlassBox(2.0, 3.0, 4.0); // Declare derived box of same size

    Output(myBox); // Output volume of base class object
    Output(myGlassBox); // Output volume of derived class object
    cout << endl;
    return 0;
}

void Output(const CBox& aBox)
{
    aBox.ShowVolume();
}
```

`Box.h` and `GlassBox.h` for this example are the same as in the previous example.

How It Works

The `main()` function now basically consists of two calls of the function `Output()`, the first with an object of the base class as an argument and the second with an object of the derived class. Because the

parameter is a reference to the base class, the `Output()` function accepts objects of either class as an argument, and the appropriate version of the virtual function `Volume()` is called, depending on the object that is initializing the reference.

The program produces exactly the same output as the previous example, demonstrating that the virtual function mechanism does indeed work through a reference parameter.

Incomplete Class Declaration

At the beginning of the previous example, you have the prototype declaration for the `Output()` function. To process this, the compiler needs to have access to the definition of the `CBox` class because the parameter is of type `CBox&`. In this case, the `CBox` class definition is available at this point because you have an `#include` directive for `GlassBox.h` that has its own `#include` directive for `Box.h`.

However, there may be situations where you have such a declaration and the class definition cannot be included in this way, in which case, you would need some other way to at least identify that the name `CBox` refers to a class type. In this situation, you could provide an *incomplete class declaration* for `CBox` preceding the prototype of the `Output` function. The statement that provides an incomplete declaration of the `CBox` class is:

```
class CBox;
```

The statement identifies that `CBox` refers to a class that is not defined at this point, but this is sufficient for the compiler to know that `CBox` is the name of a class, and this allows it to process the prototype of the `Output()` function. Without some indication that `CBox` is a class, the prototype causes an error message to be generated.

Pure Virtual Functions

It's possible that you'd want to include a virtual function in a base class so that it may be redefined in a derived class but there is no meaningful definition for the function in the base class.

For example, you could conceivably have a `CContainer` class, which could be used as a base for defining the `CBox` class, or a `CBottle` class, or even a `CTeapot` class. The `CContainer` class wouldn't have data members, but you might want to provide `Volume()` as a virtual member function to allow it to be called polymorphically for derived class objects. Because `CContainer` has no data members and therefore no container dimensions, there is no sensible definition for the `Volume()` function. However, you can still define the class including `Volume()` like this:

```
// Container.h for Ex9_10
#pragma once
#include <iostream>

class CContainer           // Generic base class for specific containers
{
public:
```

```

// Function for calculating a volume - no content
// This is defined as a 'pure' virtual function, signified by ' = 0 '
virtual double Volume() const = 0;

// Function to display a volume
virtual void ShowVolume() const
{
    std::cout << std::endl << "Volume is " << Volume();
}
};

```

The statement for the virtual function `Volume()` defines it as having no content by placing the equals sign and zero in the function header. This is called a *pure virtual function*. Any class derived from this class must either define the `Volume()` function or redefine it as a pure virtual function. Because you have declared `Volume()` as `const`, its implementation in any derived class must also be `const`. Remember that `const` and non-`const` varieties of a function with the same name and parameter list are different functions. In other words, a `const` version overloads a non-`const` version.

The class also contains the function `ShowVolume()`, which displays the volume of derived class objects. Because this function is `virtual`, it can be replaced in a derived class, but if it isn't, the base class version is called.

Abstract Classes

A class that contains a pure virtual function is called an *abstract class*. It's called abstract because you can't define objects of a class that contains a pure virtual function. It exists only for the purpose of deriving classes from it. If a class that is derived from an abstract class still defines a pure virtual function of the base as `pure`, it, too, is an abstract class.

You should not conclude from the previous example of the `CContainer` class that an abstract class can't have data members. An abstract class can have both data members and function members.

The presence of a pure virtual function is the only condition that makes a class abstract. In the same vein, an abstract class can have more than one pure virtual function. In this case, a derived class must define every pure virtual function in its base; otherwise, it too will be an abstract class. If you forget to make the derived class version of the `Volume()` function `const`, the derived class will still be abstract because it contains the pure virtual `Volume()` function that is `const`, as well as the non-`const` version.

TRY IT OUT An Abstract Class

You could implement a `CCan` class, representing beer or cola cans, perhaps, together with the original `CBox` class, and derive both from the `CContainer` class that you defined in the previous section. The definition of the `CBox` class as a subclass of `CContainer` is as follows:

```

// Box.h for Ex9_10
#pragma once
#include "Container.h" // For CContainer definition
#include <iostream>

```

```

class CBox: public CContainer           // Derived class
{
public:

    // Function to show the volume of an object
    virtual void ShowVolume() const override
    {
        std::cout << std::endl << "CBox usable volume is " << Volume();
    }

    // Function to calculate the volume of a CBox object
    virtual double Volume() const override
    { return m_Length*m_Width*m_Height; }

    // Constructor
    explicit CBox(double lv = 1.0, double wv = 1.0, double hv = 1.0)
        :m_Length(lv), m_Width(wv), m_Height(hv) {}

protected:
    double m_Length;
    double m_Width;
    double m_Height;
};

```

The `CBox` class is essentially as you had it in the previous example, except that this time you have specified that it is derived from the `CContainer` class. The `Volume()` function is fully defined within `CBox` (as it must be if this class is to be used to define objects). The only other option would be to specify it as a pure virtual function because it is pure in the base class but then you could not create `CBox` objects.

You can define the `CCan` class in the `Can.h` header file like this:

```

// Can.h for Ex9_10
#pragma once
#define _USE_MATH_DEFINES           // For constants in math.h
#include <math.h>
#include "Container.h"           // For CContainer definition

class CCan: public CContainer
{
public:
    // Function to calculate the volume of a can
    virtual double Volume() const override
    { return 0.25*M_PI*m_Diameter*m_Diameter*m_Height; }

    // Constructor
    explicit CCan(double hv = 4.0, double dv = 2.0): m_Height(hv), m_Diameter(dv) {}

protected:
    double m_Height;
    double m_Diameter;
};

```

The `CCan` class also defines a `volume()` function based on the formula $h\pi r^2$ where h is the height of a can and r is the radius of the cross-section. The constant, `M_PI`, is defined in `math.h` and becomes available when `_USE_MATH_DEFINES` is defined. The `math.h` header defines a wealth of other mathematical constants that you can see if you place the cursor in `math.h` in the code and press `Ctrl+Shift+G`. The volume is calculated as the height multiplied by the area of the base. The expression in the function definition assumes a global constant `PI` is defined, so you have the `extern` statement indicating that `PI` is a global variable of type `const double` that is defined elsewhere — in this program it is defined in the `Ex9_10.cpp` file. Also notice that you redefine the `ShowVolume()` function in the `CBox` class, but not in the `CCan` class. You will see the effect of this in the program output.

You can exercise these classes with the following source file:

```
// Ex9_10.cpp
// Using an abstract class
#include "Box.h"                                // For CBox and CContainer
#include "Can.h"                                 // For CCan (and CContainer)
#include <iostream>                            // For stream I/O
using std::cout;
using std::endl;

int main(void)
{
    // Pointer to abstract base class
    // initialized with address of CBox object
    CContainer* pC1 = new CBox(2.0, 3.0, 4.0);

    // Pointer to abstract base class
    // initialized with address of CCan object
    CContainer* pC2 = new CCan(6.5, 3.0);

    pC1->ShowVolume();                         // Output the volumes of the two
    pC2->ShowVolume();                         // objects pointed to
    cout << endl;

    delete pC1;                                // Now clean up ...
    delete pC2;                                // ... the free store

    return 0;
}
```

How It Works

You declare two pointers to the base class, `CContainer`. Although you can't define `CContainer` objects (because `CContainer` is an abstract class), you can still define pointers of type `CContainer*`, which you can then use to store the address of a derived class object; in fact, you can use it to store the address of any object whose type is a direct or indirect subclass of `CContainer`. The pointer `pC1` is assigned the address of a `CBox` object created in the free store by the operator `new`. The second pointer is assigned the address of a `CCan` object in a similar manner.

Of course, because you created the derived class objects dynamically, you must use the `delete` operator to clean up the free store when you have finished with them. You learned about `delete` back in Chapter 4.

The output produced by this example is as follows:

```
CBox usable volume is 24
Volume is 45.9458
```

Because you defined `ShowVolume()` in the `CBox` class, the derived class version of the function is called for the `CBox` object. You did not define this function in the `CCan` class, so the base class version that the `CCan` class inherits is called for the `CCan` object. Because `Volume()` is a virtual function that is implemented in both derived classes (necessarily, because it is a pure virtual function in the base class), the call to it is resolved when the program executes by selecting the version from the class of the object being pointed to. Thus, for the pointer `pC1`, the `CBox` version is called and for `pC2` the `CCan` version is called. Therefore you obtain the correct result in each case.

You could equally well have used one pointer and assigned the address of the `CCan` object to it after calling the `Volume()` function for the `CBox` object. A base class pointer can contain the address of any derived class object, even when several different classes are derived from the same base class, and so you can have automatic selection of the appropriate virtual function across a whole range of derived classes. Impressive stuff, isn't it?

Indirect Base Classes

At the beginning of this chapter, I said that a base class for a given class could, in turn, be derived from another, “more” base class. A small extension of the last example will illustrate this, as well as demonstrating the use of a virtual function across a second level of inheritance.

TRY IT OUT More Than One Level of Inheritance

All you need to do is to add the `CGlassBox` class to the classes you have from the previous example. The relationship between the classes you will then have is illustrated in Figure 9-5.




FIGURE 9-5

The CGlassBox class is derived from CBox exactly as before, but you omit the derived class version of ShowVolume() to show that the base class version still propagates through the derived classes. With the class hierarchy shown in Figure 9-5, the CContainer class is an indirect base of CGlassBox, and a direct base of the CBox and CCan classes.

The GlassBox.h header file for the example contains:

```
// GlassBox.h for Ex9_11
#pragma once
#include "Box.h"                                // For CBox

class CGlassBox: public CBox                  // Derived class
{
public:

    // Function to calculate volume of a CGlassBox
    // allowing 15% for packing
    virtual double Volume() const override
    { return 0.85*m_Length*m_Width*m_Height; }

    // Constructor
    CGlassBox(double lv, double wv, double hv): CBox(lv, wv, hv){}
};


```

The Container.h, Can.h, and Box.h header files contain the same code as those in the previous example, Ex9_10.

The main source file for the new example is as follows:

```
// Ex9_11.cpp
// Using an abstract class with multiple levels of inheritance
#include "Box.h"                                // For CBox and CContainer
#include "Can.h"                                 // For CCan (and CContainer)
#include "GlassBox.h"                            // For CGlassBox (and CBox and CContainer)
#include <iostream>                             // For stream I/O
using std::cout;
using std::endl;

int main()
{
    // Pointer to abstract base class initialized with CBox object address
    CContainer* pC1 = new CBox(2.0, 3.0, 4.0);

    CCan myCan(6.5, 3.0);                      // Define CCan object
    CGlassBox myGlassBox(2.0, 3.0, 4.0); // Define CGlassBox object

    pC1->ShowVolume();                         // Output the volume of CBox
    delete pC1;                                 // Now clean up the free store

    // initialized with address of CCan object
    pC1 = &myCan;                               // Put myCan address in pointer
    pC1->ShowVolume();                         // Output the volume of CCan
```

```

pC1 = &myGlassBox;
pC1->ShowVolume();                                // Put myGlassBox address in pointer
                                                    // Output the volume of CGlassBox

cout << endl;
return 0;
}

```

How It Works

You have the three-level class hierarchy shown in Figure 9-5 with `CContainer` as an abstract base class because it contains the pure virtual function, `volume()`. The `main()` function now calls the `ShowVolume()` function three times using the same pointer to the base class, but with the pointer containing the address of an object of a different class type each time. Because `ShowVolume()` is not defined in either `CCan` or `CGlassBox`, the inherited version is called in each instance. A separate branch from the base `CContainer` defines the derived class `CCan` so `CCan` inherits `ShowVolume()` from `CContainer` and `CGlassBox` inherits the function from `CBox`.

The example produces this output:

```

CBox usable volume is 24
Volume is 45.9458
CBox usable volume is 20.4

```

The output shows that one of the three different versions of the function `volume()` is selected for execution according to the type of object involved.

Note that you must delete the `CBox` object from the free store before you assign another address value to the pointer. If you don't do this, you won't be able to clean up the free store, because you would have no record of the address of the original object. This is an easy mistake to make when reassigning pointers and using the free store. You'll be able to avoid the possibility of this mistake by using smart pointers that you'll learn about in Chapter 10.

Virtual Destructors

A problem that arises when dealing with objects of derived classes using a pointer to the base class is that the correct destructor may not be called. You can see this happening by modifying the last example.

TRY IT OUT Calling the Wrong Destructor

You need to add a public destructor that outputs a message to each of the classes in the example so that you can track which destructor is called when the objects are destroyed. The destructor for the `CContainer` class in the `Container.h` file for this example is:

```

~CContainer()
{ std::cout << "CContainer destructor called" << std::endl; }

```

The destructor for the CCan class in Can.h in the example is:

```
~CCan()
{ std::cout << "CCan destructor called" << std::endl; }
```

The CBox class destructor in Box.h should be:

```
~CBox()
{ std::cout << "CBox destructor called" << std::endl; }
```

The CGlassBox destructor in the GlassBox.h header file should be:

```
~CGlassBox()
{ std::cout << "CGlassBox destructor called" << std::endl; }
```

Finally, the source file Ex9_12.cpp for the program should be:

```
// Ex9_12.cpp
// Destructor calls with derived classes
// using objects via a base class pointer
#include "Box.h"                                // For CBox and CContainer
#include "Can.h"                                   // For CCan (and CContainer)
#include "GlassBox.h"                             // For CGlassBox (and CBox and CContainer)
#include <iostream>                               // For stream I/O
using std::cout;
using std::endl;

int main()
{
    // Pointer to abstract base class initialized with CBox object address
    CContainer* pC1 = new CBox(2.0, 3.0, 4.0);

    CCan myCan(6.5, 3.0);                         // Define CCan object
    CGlassBox myGlassBox(2.0, 3.0, 4.0);           // Define CGlassBox object

    pC1->ShowVolume();                            // Output the volume of CBox
    cout << endl << "Delete CBox" << endl;
    delete pC1;                                    // Now clean up the free store

    pC1 = new CGlassBox(4.0, 5.0, 6.0);           // Create CGlassBox dynamically
    pC1->ShowVolume();                            // ...output its volume...
    cout << endl << "Delete CGlassBox" << endl;
    delete pC1;                                    // ...and delete it

    pC1 = &myCan;                                 // Get myCan address in pointer
    pC1->ShowVolume();                           // Output the volume of CCan

    pC1 = &myGlassBox;                            // Get myGlassBox address in pointer
    pC1->ShowVolume();                           // Output the volume of CGlassBox

    cout << endl;
    return 0;
}
```

How It Works

Apart from adding a destructor to each class that outputs a message to the effect that it was called, the only other change is a couple of additions to `main()`. There are additional statements that create a `CGlassBox` object dynamically, output its volume, and then delete it. There is also a message displayed to indicate when the dynamically created `CBox` object is deleted. The output generated by this example is:

```
CBox usable volume is 24
Delete CBox
CContainer destructor called

CBox usable volume is 102
Delete CGlassBox
CContainer destructor called

Volume is 45.9458
CBox usable volume is 20.4
CGlassBox destructor called
CBox destructor called
CContainer destructor called
CCan destructor called
CContainer destructor called
```

You can see from this that when you delete the `CBox` object pointed to by `pc1`, the destructor for the base class `CContainer` is called, but there is no call of the `CBox` destructor. Similarly, when the `CGlassBox` object that you added is deleted, the destructor for the base class `CContainer` is called but not the `CGlassBox` or `CBox` destructors. For the other objects, the correct destructor calls occur with the derived class destructor being called first, followed by the base class destructor. For the first `CGlassBox` object, three destructors are called: first, the destructor for the derived class, followed by the direct base destructor, and finally the indirect base destructor.

All the problems are with objects created in the free store. In both cases, the wrong destructor is called. The reason for this is that the linkage to the destructors is resolved statically, at compile time. For the automatic objects, there is no problem — the compiler knows what they are and arranges for the correct destructors to be called. With objects created dynamically and accessed through a pointer, things are different. The only information that the compiler has when the `delete` operation is compiled is that the pointer type is a pointer to the base class. The type of object the pointer is pointing to is unknown to the compiler because this is determined when the program executes. The compiler, therefore, simply ensures that the `delete` operation is set up to call the base class destructor. In a real application, this can cause a lot of problems, with bits of objects left strewn around the free store and possibly more serious problems, depending on the nature of the objects.

The solution is simple. You need the calls to be resolved dynamically — as the program is executed. You can organize this by using *virtual destructors*. As I said when I first discussed virtual functions, it's sufficient to declare a base class function as virtual to ensure that all functions in any derived classes with the same name, parameter list, and return type are virtual as well. This applies to destructors just as it does to ordinary member functions. You need to add the keyword `virtual` to the definition of the destructor in the class `CContainer` in `Container.h`:

```
class CContainer           // Generic base class for containers
{
public:

    // Destructor
    virtual ~CContainer()
    { cout << "CContainer destructor called" << endl; }

    // Rest of the class as before
};


```

Now, the destructors in all the derived classes are automatically virtual, even though you don't explicitly specify them as such. Of course, you're free to specify them as virtual if you want the code to be absolutely clear.

If you rerun the example with this change, it produces the following output:

```
CBox usable volume is 24
Delete CBox
CBox destructor called
CContainer destructor called

CBox usable volume is 102
Delete CGlassBox
CGlassBox destructor called
CBox destructor called
CContainer destructor called

Volume is 45.9458
CBox usable volume is 20.4
CGlassBox destructor called
CBox destructor called
CContainer destructor called
CCan destructor called
CContainer destructor called
```

As you can see, all the objects are now destroyed with a proper sequence of destructor calls. Destroying the dynamic objects produces the same sequence of destructor calls as the automatic objects of the same type.

The question may arise in your mind at this point, can constructors be declared as virtual? The answer is no — only destructors and other member functions.

NOTE It's a good idea to declare your base class destructor as virtual as a matter of course when using inheritance. There is a small overhead in the execution of the destructors but you won't notice it in the majority of circumstances. Using virtual destructors ensures that your objects will be properly destroyed and avoids potential program crashes that might otherwise occur.

CASTING BETWEEN CLASS TYPES

You have seen how you can store the address of a derived class object in a variable that is a pointer to a base class type, so a variable of type `CContainer*` can store the address of a `CBox` object for example. So if you have an address stored in a pointer of type `CContainer*`, can you cast it to type `CBox*`? Indeed, you can, and the `dynamic_cast` operator is specifically intended for this kind of operation. Here's how it works:

```
CContainer* pContainer = new CGlassBox(2.0, 3.0, 4.0);
CBox* pBox = dynamic_cast<CBox*>( pContainer );
CGlassBox* pGlassBox = dynamic_cast<CGlassBox*>( pContainer );
```

The first statement stores the address of the `CGlassBox` object created on the heap in a base class pointer of type `CContainer*`. The second statement casts `pContainer` up the class hierarchy to type `CBox*`. The third statement casts the address in `pContainer` to its actual type, `CGlassBox*`.

You can apply the `dynamic_cast` operator to references as well as pointers. The difference between `dynamic_cast` and `static_cast` is that `dynamic_cast` checks the validity of a cast at run time, whereas the `static_cast` operator does not. If a `dynamic_cast` operation is not valid, the result is null. The compiler relies on the programmer for the validity of a `static_cast` operation, so you should always use `dynamic_cast` for casting up and down a class hierarchy and check for a `nullptr` result if you want to avoid abrupt termination of your program.

NESTED CLASSES

You can put the definition of one class inside the definition of another, in which case, you have defined a *nested class*. A nested class has the appearance of being a static member of the class that encloses it and is subject to the member access specifiers, just like any other member of the class. If you place a nested class definition in the private section of a class, the class can only be referenced from within the scope of the enclosing class. If you specify a nested class as `public`, the class is accessible from outside the enclosing class, but the nested class name must be qualified by the outer class name in such circumstances.

A nested class has free access to all the static members of the enclosing class. All the instance members can be accessed through an object of the enclosing class type, or a pointer or reference to an object. The enclosing class can only access the public members of the nested class, but in a nested class that is private in the enclosing class, the members are frequently declared as `public` to provide free access to the entire nested class from functions in the enclosing class.

A nested class is particularly useful when you want to define a type that is only to be used within another type, whereupon the nested class can be declared as `private`. Here's an example of that:

```
// A push-down stack to store CBox objects
#pragma once
class CBox;                                // Forward class declaration
class CStack
{
private:
```

```

// Defines items to store in the stack
struct CItem
{
    CBox* pBox;                                // Pointer to the object in this node
    CItem* pNext;                             // Pointer to next item in the stack or null

    // Constructor
    CItem(CBox* pB, CItem* pN): pBox(pB), pNext(pN) {}

};

CItem* pTop;                                // Pointer to item that is at the top

public:
    // Constructor
    CStack():pTop(nullptr){}

    // Push a Box object onto the stack
    void Push(CBox* pBox)
    {
        pTop = new CItem(pBox, pTop);      // Create new item and make it the top
    }

    // Pop an object off the stack
    CBox* Pop()
    {
        if(!pTop)                         // If the stack is empty
            return nullptr;                // return null

        CBox* pBox = pTop->pBox;          // Get box from item
        CItem* pTemp = pTop;              // Save address of the top item
        pTop = pTop->pNext;             // Make next item the top
        delete pTemp;                   // Delete old top item from the heap
        return pBox;
    }

    // Destructor
    virtual ~CStack()

    {
        CItem* pTemp(nullptr);
        while(pTop)                      // While pTop not null
        {
            pTemp = pTop;
            pTop = pTop->pNext;
            delete pTemp;
        }
    }
};

```

The `CStack` class defines a push-down stack for storing `CBox` objects. To be absolutely precise, it stores pointers to `CBox` objects so the objects pointed to are still the responsibility of the code, making use of the `CStack` class. The nested `struct`, `CItem`, defines the items that are held in the stack. I chose to define `CItem` as a nested `struct` rather than a nested class because members of a `struct` are public by default. You could define `CItem` as a class and then specify the members as public so

they can be accessed from the functions in the `CStack` class. The stack is implemented as a set of `CIItem` objects, where each `CIItem` object stores a pointer to a `CBox` object plus the address of the next `CIItem` object down in the stack. The `Push()` function in the `CStack` class pushes a `CBox` object onto the top of the stack, and the `Pop()` function pops an object off the top of the stack.

Pushing an object onto the stack involves creating a new `CIItem` object that holds the address of the object to be stored plus the address of the previous item that was on the top of the stack — this is `nullptr` the first time you push an object onto the stack. Popping an object off the stack returns the address of the object in the item, `pTop`. The top item is deleted and the next item becomes the item at the top of the stack.

Because a `CStack` object creates `CIItem` objects on the heap, we need a destructor to make sure any remaining `CIItem` objects are deleted when a `CStack` object is destroyed. The process is to work down through the stack, deleting the top item after the address of the next item has been saved in `pTop`. Let's see if it works.

TRY IT OUT Using a Nested Class

This example uses `CCContainer`, `CBox`, and `CGlassBox` classes from `Ex9_12`, so create an empty Win32 console project, `Ex9_13`, and add the header files containing those class definitions to it. Then add `Stack.h` to the project containing the definition of the `CStack` class from the previous section, and add `Ex9_13.cpp` to the project with the following contents:

```
// Ex9_13.cpp
// Using a nested class to define a stack
#include "Box.h"                                // For CBox and CCContainer
#include "GlassBox.h"                            // For CGlassBox (and CBox and CCContainer)
#include "Stack.h"                               // For the stack class with nested struct CIItem

#include <iostream>                           // For stream I/O
using std::cout;
using std::endl;

int main()
{
    CBox* pBoxes[] = { new CBox(2.0, 3.0, 4.0),
                        new CGlassBox(2.0, 3.0, 4.0),
                        new CBox(4.0, 5.0, 6.0),
                        new CGlassBox(4.0, 5.0, 6.0)
    };

    cout << "The array of boxes have the following volumes:";
    for (CBox* pBox : pBoxes)
        pBox->ShowVolume();                      // Output the volume of a box

    cout << endl << endl << "Now pushing the boxes on the stack..." << endl;
    CStack stack;                                // Create the stack
    for (CBox* pBox : pBoxes)                    // Store box pointers in the stack
        stack.Push(pBox);

    cout << "Popping the boxes off the stack presents them in reverse order:";
```

```
CBox* pTemp(nullptr);
while(pTemp = stack.Pop())
    pTemp->ShowVolume();

cout << endl;

for (CBox* pBox : pBoxes)           // Delete the boxes
    delete pBox;

return 0;
}
```

The output from this example is:

```
The array of boxes have the following volumes:
CBox usable volume is 24
CBox usable volume is 20.4
CBox usable volume is 120
CBox usable volume is 102

Now pushing the boxes on the stack...
Popping the boxes off the stack presents them in reverse order:
CBox usable volume is 102
CBox usable volume is 120
CBox usable volume is 20.4
CBox usable volume is 24
```

How It Works

You create an array of pointers to `CBox` objects so each element in the array can store the address of a `CBox` object or an address of any type that is derived from `CBox`. The array is initialized with the addresses of four objects created on the heap:

```
CBox* pBoxes[] = { new CBox(2.0, 3.0, 4.0),
                    new CGlassBox(2.0, 3.0, 4.0),
                    new CBox(4.0, 5.0, 6.0),
                    new CGlassBox(4.0, 5.0, 6.0)
                };
```

The objects are two `CBox` objects and two `CGlassBox` objects with the same dimensions as the `CBox` objects.

After listing the volumes of the objects pointed to by the elements in the `pBoxes` array in a range-based `for` loop, you create a `Stack` object and push the pointers to the objects onto the stack in another range-based `for` loop:

```
Stack* stack;                                // Create the stack
for (CBox* pBox : pBoxes)                     // Store box pointers in the stack
    stack.Push(pBox);
```

Each element in the `pBoxes` array is pushed onto the stack by passing the array element as the argument to the `Push()` function for the `stack` object. This results in the first element from the array being at the bottom of the stack, and the last element at the top.

You pop the objects off the stack in a while loop:

```
CBox* pTemp(nullptr);
while(pTemp = stack.Pop())
    pTemp->ShowVolume();
```

The `Pop()` function returns the address of the element at the top of the stack, and you use this to call the `ShowVolume()` function for the object. The loop ends when the `Pop()` function returns null. Because the last element was at the top of the stack, the loop lists the volumes of the objects in reverse order. From the output, you can see that the `CStack` class does, indeed, implement a stack using a nested `struct` to define the items to be stored in the stack.

SUMMARY

This chapter covered the principal ideas involved in using inheritance.

You have now gone through all of the important language features of C++. It's important that you feel comfortable with the mechanisms for defining and deriving classes and the process of inheritance. Windows programming with Visual C++ involves extensive use of all these concepts.

EXERCISES

- What's wrong with the following code?

```
class CBadClass
{
private:
    int len;
    char* p;
public:
    CBadClass(const char* str): p(str), len(strlen(p)) {}
    CBadClass(){}
};
```

- Suppose you have a class `CBird`, as follows, that you want to use as a base class for deriving a hierarchy of bird classes:

```
class CBird
{
protected:
    int wingSpan;
    int eggSize;
    int airSpeed;
    int altitude;
public:
    virtual void fly() { altitude = 100; }
};
```

Is it reasonable to create a `CHawk` by deriving from `CBird`? How about a `COstrich`? Justify your answers. Derive an avian hierarchy that can cope with both of these birds.

- 3.** Given the following class,

```
class CBase
{
protected:
    int m_anInt;
public:
    CBase(int n): m_anInt(n) { std::cout << "Base constructor\n"; }
    virtual void Print() const = 0;
};
```

what sort of class is `CBase` and why? Derive a class from `CBase` that sets its inherited integer value, `m_anInt`, when constructed, and prints it on request. Write a test program to verify that your class is correct.

- 4.** A binary tree is a structure made up of nodes, where each node contains a pointer to a “left” node and a pointer to a “right” node plus a data item, as shown in Figure 9-6.




FIGURE 9-6

The tree starts with a root node, and this is the starting point for accessing the nodes in the tree. Either or both pointers in a node can be null. Figure 9-6 shows an ordered binary tree, which is a tree organized so that the value of each node is always greater than or equal to the left node and less than or equal to the right node.

Define a class that defines an ordered binary tree that stores integer values. You also need to define a `Node` class, but that can be an inner class to the `BinaryTree` class. Write a program to test the operation of your `BinaryTree` class by storing an arbitrary sequence of integers in it and retrieving and outputting them in ascending sequence.

Hint: Don't be afraid to use recursion.

► WHAT YOU LEARNED IN THIS CHAPTER

TOPIC	CONCEPT
Inherited members of a class	A derived class inherits all the members of a base class except for constructors, the destructor, and the overloaded assignment operator.
Accessibility of inherited members of a class	Members of a base class declared as <code>private</code> in the base class are not accessible in any derived class. To obtain the effect of the keyword <code>private</code> but allow access in a derived class, you should use the keyword <code>protected</code> in place of <code>private</code> .
Access specifiers for a base class	A base class can be specified for a derived class with the keyword <code>public</code> , <code>private</code> , or <code>protected</code> . If none is specified, the default is <code>private</code> . Depending on the keyword specified for a base, the access level of the inherited members may be modified.
Constructors in derived classes	If you write a derived class constructor, you must arrange for data members of the base class to be initialized properly, as well as those of the derived class.
Virtual functions	A function in a base class may be declared as <code>virtual</code> . This allows other definitions of the function appearing in derived classes to be selected at execution time, depending on the type of object for which the function call is made.
Using <code>override</code>	When you define a virtual function in a derived class with the <code>override</code> modifier specified, the compiler will verify that a direct or indirect base class contains a virtual function with the same signature, and will issue an error message if this is not the case.
Final function members of a class	If a function member of a class is specified using the <code>final</code> modifier, a derived class cannot override the function. Any attempt to override the function will result in an error message from the compiler.
Final classes	If a class is defined using the <code>final</code> modifier, it cannot be used as a base for another class. Attempting to use a final class as a base class will result in an error message from the compiler.
Virtual destructors	You should declare the destructor in a class as <code>virtual</code> . This ensures correct selection of a destructor for dynamically-created derived class objects.
friend classes	A class may be designated as a <code>friend</code> of another class. In this case, all the function members of the <code>friend</code> class may access all the members of the other class. If class A is a <code>friend</code> of B, class B is not a <code>friend</code> of A unless it has been declared as such.
Pure virtual functions	A virtual function in a base class can be specified as pure by placing = 0 at the end of the function declaration. The class then is an abstract class for which no objects can be created. In any derived class, all the pure virtual functions must be defined; if not, it, too, becomes an abstract class.

10

The Standard Template Library

WHAT YOU WILL LEARN IN THIS CHAPTER:

- The capabilities offered by the Standard Template Library (STL)
- How to use smart pointers
- How to create and use containers
- How to use iterators with containers
- The types of algorithms that are available with the STL, and how you can apply the more common ones
- How to use function objects with the STL
- How to define lambda expressions and use them with the STL
- How to use polymorphic function wrappers with lambda expressions

WROX.COM CODE DOWNLOADS FOR THIS CHAPTER

You can find the wrox.com code downloads for this chapter on the Download Code tab at www.wrox.com/remtitle.cgi?isbn=9781118368084. The code is in the Chapter 10 download and individually named according to the names throughout the chapter.

WHAT IS THE STANDARD TEMPLATE LIBRARY?

As its name implies, the Standard Template Library is a library of standard class and function templates. You can use these templates to create a wide range of powerful general-purpose classes for organizing your data, as well as functions for processing that data in various ways. The STL is defined by the standard for C++ and is therefore always available with a conforming compiler. Because of its broad applicability, the STL can greatly simplify programming in many of your applications.

I'll first explain, in general terms, the kinds of resources the STL provides and how they interact with one another, before diving into the details of working examples. The STL contains six kinds of components: containers, container adapters, iterators, algorithms, function objects, and function adapters. Because they are part of the standard library, the names of the STL components are all defined within the `std` namespace.

The STL is a very large library, some of which is highly specialized, and to cover the contents fully would require a book in its own right. In this chapter, I'll introduce the fundamentals of how you use the STL and describe the more commonly used capabilities. Let's start with containers.

Containers

Containers are objects that you use to store and organize other objects. A class that implements a linked list is an example of a container. You create a container class from an STL template by supplying the type of the object that you intend to store. For example, `vector<T>` is a template for a container that is a linear array that automatically increases in size when necessary. `T` is the type parameter that specifies the type of objects to be stored. Here are a couple of statements that create `vector<T>` containers:

```
vector<string> strings;      // Stores objects of type string
vector<double> data;        // Stores values of type double
```

The first statement creates the `strings` container class that stores objects of type `string`, while the second statement creates the `data` container that stores values of type `double`.

You can store items of a fundamental type, or of any class type, in a container. If your type argument for an STL container template is a class type, the container can potentially store objects of that type, or of any derived class type; however, this can cause *object slicing*. Object slicing results in the derived part of an object being sliced off and occurs when you pass a derived class object by value as a base class type. You can avoid object slicing by storing pointers to base class objects in the container. You can create objects of a derived class dynamically on the heap using `new` and store the pointers in a container that stores base class pointers.

The templates for the STL container classes are defined in the standard headers shown in the following table:

HEADER FILE	CONTENTS
<code>vector</code>	A <code>vector<T></code> container represents an array that stores elements of type <code>T</code> that automatically increases its capacity when required. You can only add new elements efficiently to the end of a <code>vector</code> container.
<code>array</code>	An <code>array<T, N></code> container represents an array with a fixed number of elements, <code>N</code> , of type <code>T</code> . One advantage of this container over a normal array is that it knows its size, so when you pass an <code>array<></code> container to a function it retains knowledge of the number of elements. An <code>array<></code> container has an advantage over a <code>vector<></code> in that it can be allocated entirely on the stack, whereas a <code>vector<></code> always needs heap access.

HEADER FILE	CONTENTS
deque	A deque<T> container implements a double-ended queue of elements of type T. This is equivalent to a vector with the capability for adding elements to the beginning efficiently.
list	A list<T> container is a doubly-linked list of elements of type T.
forward_list	A forward_list<T> container is a singly linked list of elements of type T. Inserting and deleting elements in a forward_list<T> will be faster than in a list<T> as long as you are processing the list elements in a forward direction. Random access will be slower for forward_list<T> than for a list<T>.
map	A map<K, T> is an associative container that stores each object (of type T) with an associated key (of type K). Key/object pairs are stored in the map as objects of type pair<K, T>, which is another STL template type. The key determines where the key/object pair is located and is used to retrieve an object. Each key must be unique. This header also defines the multimap<K, T> container where the keys in the key/object pairs need not be unique.
unordered_map	An unordered_map<K, T> container is similar to a map<K, T>, except that the key/object pairs are in no particular order in the container. The unordered_multimap<K, T> container is also in this header. This differs from an unordered_map<K, T> container in that the keys do not have to be unique.
hash_map	The hash_map<K, T> container stores key/object pairs that have unique keys. Pairs are grouped into buckets based on hash values produced from the keys. hash_map<K, T> is Visual C++ specific and not part of the C++ 11 standard. This header also contains the hash_multimap<K, T> container, which is similar to hash_map<K, T> except that the keys do not have to be unique.
set	A set<T> container is a map where each element serves as its own key. All elements in a set must be unique. A consequence of using an object as its own key is that you cannot change an object in a set; to change an object you must delete it and then insert the modified version. The elements in the container are ordered in ascending sequence. This header also defines the multiset<T> container, which is a set container where the elements need not be unique.
unordered_set	An unordered_set<T> container is similar to a set<T> except that the elements are not ordered in any particular way. The unordered_multiset<T> container that is also in this header is similar to unordered_set<T>, except that it stores elements in buckets based on a hash value produced from the element. Ordering of elements within a bucket is determined by comparing the elements.
bitset	Defines the bitset<T> class template that represents a fixed number of bits. This is typically used to store flags that represent a set of states or conditions.

All the template names are defined within the `std` namespace. `T` is the template type parameter for the type of elements stored in a container; where keys are used, `K` is the type of key.

Allocators

Most of the STL containers grow their capacity automatically to accommodate however many elements you store. Additional memory for these containers is made available by an object called an *allocator* that typically allocates space on the heap when required. You can optionally supply your own allocator object type through an additional type parameter. For example, the `vector<T>` template for creating a vector is really a `vector<T, A<T>>` template, where the second type parameter, `A<T>`, is the allocator type. The second type parameter has the default value `allocator<T>` so this is the allocator type that is used when you don't specify your own.

Your allocator must be defined as a class template with a type parameter so that an instance of the allocator type can match the type of element stored in the container. For example, suppose you have defined your own class template, `MyAllocator<T>`, to provide memory to a container on request. You could then create a vector container that will use your allocator with the statement:

```
auto data = vector<CBox, MyAllocator<CBox>>();
```

This container stores elements of type `CBox` with additional memory being allocated to the container by an object of type `MyAllocator<CBox>`.

So why would you want to define your own allocator when you can always use the default? The primary reason is efficiency in particular circumstances. For example, your application may lend itself to allocating a large chunk of memory on the heap that your allocator can issue piecemeal to the container without further dynamic memory operations. You can then release the memory in one go when the container is no longer required. I won't be delving deeper into how you can define your own allocators. It's not that it's difficult — but I have to stop somewhere.

Comparators

Some containers use a comparator object that is used to determine the order of elements within the container. For example, the `map<K, T>` container template is really:

```
map<K, T, C<K>, A<pair<K,T>> >
```

`A<pair<K,T>>` is an allocator type for key/object pairs and `C<K>` is a function object type that acts as a comparator for keys of type `K` that determines the order in which the key/object pairs are stored. The last two type parameters have default values so you don't have to supply them. The default allocator type is `allocator<pair<K,T>>`. The default comparator type is `less<K>`, which is a function object template defined in the STL that implements a “less than” comparison between objects of type `K`. I will discuss function objects a little later in this chapter.

It is quite likely that you will want to specify your own comparator for a map. You might want ordering based on “greater than” comparisons for the keys you are using. Supplying your own allocator type is much less likely. For this reason the allocator type parameter for the template comes last.

NOTE I won't be discussing allocators or comparators further. I will therefore ignore the optional template type parameters for these in all subsequent discussions of containers.

Container Adapters

The STL defines *container adapters*. A container adapter is a template class that wraps an existing STL container class to provide a different, and typically more restricted, capability. The container adapters are defined in the headers in the following table.

HEADER FILE	CONTENTS
queue	A <code>queue<T></code> container is defined by an adapter from a <code>deque<T></code> container by default, but you could define it using a <code>list<T></code> container. You can only access the first and last elements in a queue, and you can only add elements at the back and remove them from the front. Thus, a <code>queue<T></code> container works more or less like the queue in your local coffee shop. This header also defines a <code>priority_queue<T></code> container, which is a queue that orders the elements it contains so that the largest element is always at the front. Only the element at the front can be accessed or removed. A priority queue is defined by an adapter from a <code>vector<T></code> by default, but you could use a <code>deque<T></code> as the base container.
stack	A <code>stack<T></code> container is defined by an adapter from a <code>deque<T></code> container by default, but you could define it using a <code>vector<T></code> or a <code>list<T></code> container. A stack is a last-in first-out container, so adding or removing elements always occurs at the top, and you can only access the top element.

Iterators

Iterators are objects that behave like pointers and are very important for accessing the contents of all STL containers, except for those defined by a container adapter; container adapters do not support iterators. You can obtain an iterator from a container, which you can use to access the objects you have stored previously. You can also create iterators that will allow input and output of objects, or data items of a given type, from, or to, a C++ stream. Although basically all iterators behave like pointers, not all iterators provide the same functionality. However, they do share a base level of capability. Given two iterators, `iter1` and `iter2`, accessing the same set of objects, the comparison operations `iter1 == iter2`, `iter1 != iter2`, and the assignment `iter1 = iter2` are always possible, regardless of the types of `iter1` and `iter2`.

Iterator Categories

There are four different categories of iterators; each category supports a different range of operations, as shown in the following table. The operations described for each category are in addition to the three operations that I mentioned in the previous paragraph.

ITERATOR CATEGORY	DESCRIPTION
Input and output iterators	<p>These iterators read or write a sequence of objects and may only be used once. To read or write a second time, you must obtain a new iterator. You can perform the following operations on these iterators:</p> <pre data-bbox="529 387 733 451">++iter or iter++ *iter</pre> <p>For the dereferencing operation, only read access is allowed in the case of an input iterator, and only write access for an output iterator.</p>
Forward iterators	<p>Forward iterators incorporate the capabilities of both input and output iterators, so you can apply the operations shown for the previous category to them, and you can use them for access and store operations. Forward iterators can also be reused to traverse a set of objects in a forward direction as many times as you want.</p>
Bidirectional iterators	<p>Bidirectional iterators provide the same capabilities as forward iterators and additionally allow the operations <code>--iter</code> and <code>iter--</code>. This means you can traverse backward as well as forward through a sequence of objects.</p>
Random access iterators	<p>Random access iterators have the same capabilities as bidirectional iterators but also allow the following operations:</p> <pre data-bbox="529 1019 954 1239">iter+n or iter-n iter += n or iter -= n iter1 - iter2 iter1 < iter2 or iter1 > iter2 iter1 <= iter2 or iter1 >= iter2 iter[n]</pre> <p>Being able to increment or decrement an iterator by an arbitrary value <code>n</code> allows random access to the set of objects. The last operation using the <code>[]</code> operator is equivalent to <code>* (iter + n)</code>.</p>

Thus, iterators in the four successive categories provide a progressively greater range of functionality. Where an algorithm requires an iterator with a given level of functionality, you can use any iterator that provides the required level of capability. For example, if a forward iterator is required, you must use at least a forward iterator; an input or an output iterator will not do. On the other hand, you could also use a bidirectional iterator or a random access iterator because they both have the capability provided by a forward iterator.

Note that when you obtain an iterator to access the contents of a container, the kind of iterator you get will depend on the sort of container you are using. The types of some iterators can be complex, but as you'll see, in many instances the `auto` keyword can deduce the type for you if you initialize the iterator variable when you create it.

SCARY Iterators

Visual C++ supports SCARY iterators, which in spite of the name, are nothing to be frightened of. SCARY is a strange acronym that is less than obvious, standing for “Seemingly erroneous (appearing Constrained by conflicting generic parameters), but Actually work with the Right implementation (unconstrained bY the conflicts due to minimized dependencies).” SCARY iterators are simply iterators that have a type that depends only on the type of element stored in a container, and not on other parameters used to instantiate a container from its template, such as the allocator and comparator types. In previous implementations of the STL, different containers created to store elements of a given type, but with different comparator or allocator types, would have iterators of different types. There is no necessity for an iterator type to be dependent on the type of comparator or allocator used by a container. With the current implementation of the STL, the iterators will have the same type, just being determined by the element type. SCARY iterators can make the code faster and more compact.

`std::begin()` and `std::end()` Functions

The `std::begin()` and `std::end()` functions return an iterator that points to the first element and one past the last element respectively of the container, string object or array that you pass as the argument. These functions are included in the `iterator` header, the `string` header, and the headers for the majority of containers. You'll see these functions in action later in this chapter.

SMART POINTERS

Smart pointers are objects of a template type that behave like pointers but are different — well, they are smart. If you use a smart pointer when you allocate heap memory, the smart pointer will take care of deleting it for. Using smart pointers means never having to use `delete`. You can also store smart pointers in an STL container, as you'll see.

Smart pointers come in three flavors. The `memory` header defines the following types in the `std` namespace that represent smart pointers:

- `unique_ptr<T>` is a type that defines an object that stores a pointer of which there can be only one. Assigning or copying a `unique_ptr<T>` object is not possible. The pointer stored by one `unique_ptr<T>` object can be moved to another using `std::move()`. After such an operation the original object will be invalid.
- `shared_ptr<T>` is a type that stores a pointer to an object, but several `shared_ptr` objects can point to the same object and the number of `shared_ptr` objects that reference the object is recorded. All `shared_ptr` objects for a given `T` that reference the same pointer must be destroyed before the object that they all point to can be deleted. When the last of

the `shared_ptr` objects pointing to a given object dies, the object to which it points will be destroyed and the memory released.

- `weak_ptr<T>` is a type that also stores a pointer that is reference counted, but the existence of `weak_ptr` objects that point to a given object does not prevent the object from being destroyed and its memory released.

The reference count for a `shared_ptr` referencing a given object, `obj`, is incremented each time a new `shared_ptr` is created that points to `obj` and is decremented each time one of the `shared_ptr` objects is destroyed. When the last `shared_ptr` object pointing to `obj` is destroyed, `obj` will also be destroyed.

With `shared_ptr` objects, it is possible that you can inadvertently create *reference cycles*.

Conceptually a reference cycle is where a `shared_ptr` object, `pA`, points to another `shared_ptr` object `pB`, and object `pB` points to the object `pA`. With this situation, neither can be destroyed. In practice, the way in which this occurs is a lot more complicated. `weak_ptr` objects are designed to avoid the problem of reference cycles. By using `weak_ptr` objects to point to an object that a single `shared_ptr` object points to, you avoid reference cycles. It only requires the `shared_ptr` object to be destroyed for the object pointed to to be destroyed. The `weak_ptr` objects then become invalid.

Using `unique_ptr` Objects

A `unique_ptr` object stores a pointer uniquely. No other `unique_ptr` object can contain the same pointer so the object pointed to is effectively owned by the `unique_ptr` object. When the `unique_ptr` object is destroyed, the object to which it points is destroyed too.

You can create and initialize a smart pointer like this:

```
unique_ptr<Box> pBox(new CBox(2,2,2));
```

`pBox` will act just like an ordinary pointer and you can use it in the same way to call public member functions for the `CBox` object. The big difference is that you no longer have to worry about deleting the `CBox` object from the heap.

Here's a version of code that you saw back in Chapter 5, but modified to use a `unique_ptr`:

```
#include <iostream>
#include <memory>

using std::cout;
using std::endl;
using std::unique_ptr;

unique_ptr<double> treble(double);

int main(void)
{
    double num(5.0);
```

```

        unique_ptr<double> ptr(nullptr);
        ptr = treble(num);
        cout << endl << "Three times num = " << 3.0*num;
        cout << endl << "Result = " << *ptr;
        cout << endl;
        return 0;
    }

    unique_ptr<double> treble(double data)
    {
        unique_ptr<double> result(new double(0.0));
        *result = 3.0*data;
        return result;
    }
}

```

You cannot copy a `unique_ptr` object or pass it by value to a function. The `treble()` function creates a local `unique_ptr<double>` object, modifies the value that it points to, and then returns it. How does the `treble()` function return a `unique_ptr<double>` object when it cannot be copied? When you return a `unique_ptr` object from a function, the `std::move()` function is used automatically to move the pointer from the local `unique_ptr` object to the object that is received by the calling function. Moving the pointer from one `unique_ptr` to another transfers ownership of the object pointed to, so the source `unique_ptr` object will contain `nullptr`. This has implications when you store `unique_ptr` objects in a container. I'll show you how you can store smart pointers in an STL container later in this chapter.

Using `shared_ptr` Objects

You can define a `shared_ptr` object in the same way as a `unique_ptr` object, but it is better to use the `make_shared<T>()` function that creates an object of type `T`, then returns a `shared_ptr<T>` object that points to it. The arguments that you pass to `make_shared<T>()` are the arguments to the `T` class constructor. This means that memory is allocated on the heap for the `T` object and the `shared_ptr` is created in a single operation, so it is more efficient than constructing a `T` object using `new`. For example:

```
auto pBox = make_shared<CBox>(1.0, 2.0, 3.0); // Points to a CBox object
```

This creates a `CBox` object on the heap with length, width, and height values as 1.0, 2.0, and 3.0 and stores the `shared_ptr<CBox>` object that points to it in `pBox`.

In contrast to `unique_ptr`, you can have multiple `shared_ptr` objects pointing to the same object. The object pointed to will survive until the last `shared_ptr` object that points to it is destroyed, then it too will be destroyed.

You can initialize a `shared_ptr` with another `shared_ptr`:

```
std::shared_ptr<CBox> pBox2(pBox);
```

`pBox2` points to the same object as `pBox`.

Using a smart pointer works in the same way as an ordinary pointer:

```
cout << "Box volume = " << pBox->Volume() << endl;
```

A smart pointer that you define with a base class type, can store a pointer to a derived class type. For example, given the `CBox` and `CCandyBox` classes that you saw in Chapter 9, you could define a `shared_ptr` like this:

```
shared_ptr<CBox> pBox(new CCandyBox(2, 2, 2));
```

`pBox` points to a `CCandyBox` object so smart pointers work in the same way as ordinary pointers in this respect too.

If you use a local smart pointer to point to objects on the heap in a function, the memory will be automatically released when the function returns — assuming that you are not returning the smart pointer from the function. Smart pointers are also extremely useful when you are defining a class. You can use smart pointers as members of a class. If you are defining a class that uses smart pointers to keep track of heap objects, you won't need to implement a destructor in order to be sure that the memory for the objects is released when the class object is destroyed.

Accessing the Raw Pointer in a Smart Pointer

You will sometimes need access to the pointer that a smart pointer contains; this is called a *raw pointer*. You will see later in the book that there are circumstances with the MFC where you need a raw pointer because MFC member functions do not accept smart pointers as arguments. Calling the `get()` member of a smart pointer object returns the raw pointer, which you can then pass to a function that requires a raw pointer.

Calling the `reset()` member of a smart pointer resets the raw pointer to `nullptr`. This will cause the object that is pointed to be destroyed when there are no other smart pointers that contain the same address.

Casting SmartPointers

You cannot use the standard C++ cast operators such as `static_cast`, `dynamic_cast`, and `const_cast` with smart pointers. When you need to cast a smart pointer, you must use `static_pointer_cast`, `dynamic_pointer_cast` and `const_pointer_cast` instead of the standard operators. When you use `dynamic_pointer_cast` to cast a `shared_ptr<T>` object to a `shared_ptr<Base>` object, the result will be a `shared_ptr` containing `nullptr` if `Base` is not a base class for `T`. The cast operations for smart pointers are defined as function templates in the `memory` header.

ALGORITHMS

Algorithms are STL function templates that operate on a set of objects provided to them by an iterator. Because the objects are supplied by an iterator, an algorithm needs no knowledge of the source of the objects to be processed. The objects could be retrieved by the iterator from a container

or even from a stream. Because iterators work like pointers, all STL template functions that accept an iterator as an argument will work equally well with a regular pointer.

As you'll see, you will frequently use containers, iterators, and algorithms in concert, in the manner illustrated in Figure 10-1.




FIGURE 10-1

When you apply an algorithm to the contents of a container, you supply iterators that point to objects within the container. The algorithm uses these iterators to access objects within the container and to write them back when appropriate. For example, when you apply the `sort()` algorithm to a vector, you pass two iterators to the `sort()` function. One points to the first element, and the other to one past the last element. The `sort()` function uses these iterators to access objects for comparison, and to write the objects back to the container to establish the ordering. You see this working in an example later in this chapter.

Algorithms are defined in two standard header files, the `algorithm` header and the `numeric` header.

FUNCTION OBJECTS IN THE STL

Function objects are objects of a class type that overloads the `()` operator (the function call operator), which means that the class implements the `operator()()` function. The implementation of the `operator()()` function in a function object can return a value of any type. Function objects are also called *functors*.

The STL defines a set of standard function object types as templates in the `functional` header; you can use these to create a function object, where the overloaded `()` operator function will work with objects of your type. For example, the STL defines the `less<T>` template that I mentioned in the context of the map container. If you instantiate the template as `less<MyClass>`, you have a type for function objects that implement `operator()()` to provide the less-than comparison for objects of type `MyClass`. For this to work, `MyClass` must implement the `operator<()` function.

Many algorithms make use of function objects to specify binary operations to be carried out, or to specify *predicates* that determine how or whether a particular operation is to be carried out. A predicate is a function that returns a value of type `bool`, and because a function object can be an object of a type that implements the `operator()()` member function to return a value of type `bool`, a function object can also be a predicate. For example, suppose you have defined a class type `Comp` that implements the `operator()()` function to compare its two arguments and return a `bool` value.

If you create an object `f` of type `Comp`, the expression `f(a, b)` returns a `bool` value that results from comparing `a` and `b`, and thus acts as a predicate.

Predicates come in two flavors, *binary predicates* that involve two operands, and *unary predicates* that require one operand. For example, comparisons such as less-than and equal-to, and logical operations such as AND and OR, are implemented as binary predicates that are members of function objects; logical negation, NOT, is implemented as a unary predicate member of a function object.

You can also define your own function objects when necessary. You'll see function objects in action with algorithms and some container class functions later in this chapter. You can also define *lambda expressions*, which I'll explain later in this chapter. Lambda expressions are often easier to use than function objects.

FUNCTION ADAPTERS

Function adapters are function templates that allow function objects to be combined to produce a more complex function object. A simple example is the `not1` function adapter. This takes an existing function object that provides a unary predicate and inverts it. Thus, if the function object `function` returns `true`, the function that results from applying `not1` to it will be `false`. Function adapters are yet another topic I won't be discussing in depth, not because they are terribly difficult to understand — they aren't — but because there's a limit to how much I can cram into a single chapter.


THE RANGE OF STL CONTAINERS

The STL provides templates for a variety of container classes that you can use in a wide range of application contexts. *Sequence containers* are containers in which you store objects of a given type in a linear fashion, either as a dynamic array or as a list. Elements are retrieved based on their position in the container. *Associative containers* store objects based on a key that you supply with each object to be stored; the key is used to locate the object within the container. In a typical application, you might be storing phone numbers in an associative container, using names as the keys. This would enable you to retrieve a particular number from the container just by supplying the appropriate name. *Sets* are containers that hold elements that are stored and retrieved based on the elements themselves. They can be unordered, rather like objects rattling around in a bag, or they can be ordered. There are also sets that allow you to specify a comparator that will establish a particular order within the set. I won't be discussing sets in detail. I'll first introduce you to sequence containers, and then I'll delve into associative containers and what you can do with them.

SEQUENCE CONTAINERS

The class templates for the five basic sequence containers are `vector<T>`, `array<T, N>`, `list<T>`, `forward_list<T>` and `deque<T>`.

Which template you choose to use in any particular instance will depend on the application. These containers are differentiated by the operations they can perform efficiently, as Figure 10-2 shows.



Efficient Sequence Container Operations

FIGURE 10-2

If you need random access to the contents of the container with a variable capacity, and you are happy to always add or delete objects at the end of a sequence, then `vector<T>` is the container template to choose. It is possible to add or delete objects randomly within a vector, but the process will be somewhat slower than adding objects to the end because all the objects past the insertion

or deletion point have to be moved. If you can manage with storing a fixed number of elements, the `array<T, N>` container will be faster than a `vector<T>` in store and retrieve operations because you don't have the overhead of providing for increasing the capacity of the container. An `array<T, N>` container can be allocated on the stack and will also be more flexible than a normal array.

A `deque<T>` container is very similar to a `vector<T>` and supports the same operations, but it has the additional capability to add and delete elements at the beginning of the sequence. A `list<T>` container is a doubly-linked list, so adding and deleting at any position is efficient. The downside of a list is that there is no random access to the contents; the only way to access an object that is internal to the list is to traverse the contents from the beginning, or to run backward through the contents from the end.

Let's look at sequence containers in more detail and try some examples. I'll be introducing the use of iterators, algorithms, and function objects along the way.

Creating Vector Containers

The simplest way to create a vector container is like this:

```
vector<int> mydata;
```

This creates a container that will store values of type `int`. The initial capacity is zero, so you will be allocating more memory right from the outset when you insert the first value.

The `push_back()` function adds a new element to the end of a vector, so to store a value in this vector you would write:

```
mydata.push_back(99);
```

The argument to the `push_back()` function is the item to be stored. This statement stores the value 99 in the vector, so after executing this statement the vector contains one element. The `push_back()` function is overloaded with an rvalue reference parameter version so the preceding statement will move the value 99 into the vector rather than copy it.

Here's another way to create a vector to store integers:

```
vector<int> mydata(100);
```

This creates a vector that contains 100 elements that are all initialized to zero. If you add new elements to this vector, the memory allocated for storage in the vector will be increased automatically, so obviously it's a good idea to choose a reasonably accurate value for the number of integers you are likely to want to store. This vector already contains 100 elements and can be used just like an array. For example, to store a value in the third element, you can write:

```
mydata[2] = 999;
```

Of course, you can only use an index value to access elements within a vector that are within the range of elements that exist. You can't add new elements in this way, though. To add a new element, you can use the `push_back()` function.

You can initialize the elements in a vector to a different value, when you create it by using this statement:

```
vector<int> mydata(100, -1);
```

The second argument to the constructor is the initial value to be used, so all 100 elements in the vector will be set to -1.

If you don't want to create elements when you create a vector container, you can increase the capacity after you create it by calling its `reserve()` function:

```
vector<int> mydata;
mydata.reserve(100);
```

The argument to the `reserve()` function is the minimum number of elements to be accommodated. If the argument is less than the current capacity of the vector, then calling `reserve()` will have no effect. In this code fragment, calling `reserve()` causes the vector container to allocate sufficient memory for a total of 100 elements although the elements are not yet created.

You can also create a vector with initial values for elements from an external array. For example:

```
double data[] = {1.5, 2.5, 3.5, 4.5, 5.5, 6.5, 7.5, 8.5, 9.5, 10.5};
vector<double> mydata(data, data+8);
```

Here, the `data` array is created with 10 elements of type `double`, with the initial values shown. The second statement creates a vector storing elements of type `double`, with eight elements initially having the values corresponding to `data[0]` through `data[7]`. The arguments to the `vector<double>` constructor are pointers (and can also be iterators), where the first pointer points to the first initializing element in the array, and the second points to one past the last initializing element. Thus, the `mydata` vector will contain eight elements with initial values 1.5, 2.5, 3.5, 4.5, 5.5, 6.5, 7.5, and 8.5.

Because the constructor in the previous fragment can accept either pointer or iterator arguments, you can initialize a vector when you create it with values from another vector that contains elements of the same type. You just supply the constructor with an iterator pointing to the first element you want to use as an initializer, plus a second iterator pointing to one past the last element you want to use. Here's an example:

```
vector<double> values(begin(mydata), end(mydata));
```

After executing this statement, the `values` vector will have elements that are duplicates of the `mydata` vector. As Figure 10-3 illustrates, the `begin()` function returns a random access iterator that points to the first element in the vector for which it is called, and the `end()` function returns a random access iterator pointing to one past the last element. A sequence of elements is typically specified in the STL by two iterators, one pointing to the first element in the sequence and the other pointing to one past the last element in the sequence, so you'll see this time and time again.

NOTE If you check the documentation, you'll see that the vector container and other sequence containers have `begin()` and `end()` member functions that you could call for a container object:

```
vector<double> values(mydata.begin(), mydata.end());
```

This does the same as the preceding statement but it is recommended that you use the non-member `begin()` and `end()` functions because they are more flexible. They work with arrays, strings and other containers.

Because the `begin()` and `end()` functions return random access iterators, you can modify what they point to when you use them. For a `vector<T>`, the type of the iterators that the `begin()` and `end()` functions return is `vector<T>::iterator`, where `T` is the type of object stored in the vector. Most of the time you can use the `auto` keyword to specify the iterator type.

Here's a statement that creates a vector that is initialized with the third through the seventh elements from the `mydata` vector:

```
vector<double> values(begin(mydata)+2, end(mydata)-1);
```

Adding 2 to the first iterator makes it point to the third element in `mydata`. Subtracting 1 from the second iterator makes it point to the last element in `mydata`; remember that the second argument to the constructor is an iterator that points to a position that is *one past* the element to be used as the last initializer, so the object that the second iterator points to is not included in the set.

As I said earlier, it is pretty much standard practice in the STL to indicate a sequence of elements in a container by a begin iterator that points to the first element and an end iterator that points to one past the last element. This allows you to iterate over all the elements in a sequence by incrementing the begin iterator until it equals the end iterator. This means that the iterators only need to support the equality operator to allow you to walk through the sequence.

Occasionally, you may want to access the contents of a vector in reverse order. Calling the `rbegin()` function for a vector returns an iterator that points to the last element, while `rend()` points to one before the first element (that is, the position preceding the first element), as Figure 10-4 illustrates.




FIGURE 10-3




FIGURE 10-4

The iterators returned by `rbegin()` and `rend()` are called *reverse iterators* because they present the elements in reverse sequence. For a `vector<T>` container, reverse iterators are of type `vector<T>::reverse_iterator`. Figure 10-4 shows how adding a positive integer to the `rbegin()` iterator moves back through the sequence, and subtracting an integer from `rend()` moves forward through the sequence.

Here's how you could create a vector containing the contents of another vector in reverse order:

```
double data[] = {1.5, 2.5, 3.5, 4.5, 5.5, 6.5, 7.5, 8.5, 9.5, 10.5};
vector<double> mydata(data, data+8);
vector<double> values(mydata.rbegin(), mydata.rend());
```

Because you are using reverse iterators as arguments to the constructor in the last statement, the `values` vector will contain the elements from `mydata` in reverse order.

When you want to use iterators to access the elements in a vector but do not want to modify the elements you can use the `cbegin()` and `cend()` member functions that return `const` iterators. For example:

```
int n[] = {1,2,3,4,5};
std::vector<int> mydata(std::begin(n), std::end(n));
for(auto iter = mydata.cbegin() ; iter != mydata.cend() ; ++iter)
    cout << (*iter) << " squared is " << (*iter)*(*iter) << endl;
```

Using `cbegin()` and `cend()`, there is no possibility of modifying the elements in `mydata` accidentally within the loop. You also have the members `crbegin()` and `crend()` available to provide `const` reverse iterators.

The Capacity and Size of a Vector Container

It's about time I explained the difference between the capacity and the size of a vector container. The *capacity* is the maximum number of objects a container can currently accommodate without allocating more memory. The *size* is the number of objects actually stored in the container. So, the size cannot be greater than the capacity.

You can obtain both the size and capacity of the container `data` at any time by calling the `size()` and `capacity()` member functions. For example:

```
cout << endl << "The current capacity of the container is: " << data.capacity()
<< endl << "The current size of the container is: " << data.size() << endl;
```

Calling the `capacity()` function for a vector returns the current capacity, and calling its `size()` function returns the current size, both values being returned as type `vector<T>::size_type`. This is an implementation-defined integer type that is defined within the `vector<T>` class template by a `typedef`. To create a variable to store the value returned from the `size()` or `capacity()` function, you can specify it as type `vector<T>::size_type`, where you replace `T` with the type of object stored in the container. The following fragment illustrates this:

```
vector<double> values;
vector<double>::size_type cap = values.capacity();
```

Of course, the `auto` keyword makes it much easier:

```
auto cap = values.capacity();
```

NOTE *The Visual C++ implementation of STL defines the `vector<T>::size_type` type as `size_t`, which is an unsigned integer type that is also the type for the result of the `sizeof` operator.*

If the value returned by the `size()` function is zero, then clearly the vector contains no elements; thus, you can use it as a test for an empty vector. You can also call the `empty()` function for a vector to test for this:

```
if(values.empty())
    cout << "No more elements in the vector.";
```

The `empty()` function returns a value of type `bool` that is `true` when the vector is empty and `false` otherwise.

You are unlikely to need it very often, but you can discover the maximum possible number of elements in a vector by calling its `max_size()` function. For example:

```
vector<string> strings;
cout << "Maximum length of strings vector: " << strings.max_size();
```

Executing this fragment produces the output:

```
Maximum length of strings vector: 153391689
```

The maximum length is returned by the `max_size()` function as a value, in this case of type `vector<string>::size_type`. Note that the maximum length of a vector will depend on the type of element stored in the vector. If you try this out with a vector storing values of type `int`, you will get 1073741823 as the maximum length, and for a vector storing values of type `double` it is 536870911.

You can change the size of a vector by calling its `resize()` function, which can either increase or decrease the size of the vector. If you specify a new size that is less than the current size, sufficient elements will be deleted from the end of the vector to reduce it to its new size. If the new size is greater than the old, new elements will be added to the end of the vector to increase its length to the new size. Here's code illustrating this:

```
vector<int> values(5, 66);      // Contains 66 66 66 66 66
values.resize(7, 88);           // Contains 66 66 66 66 66 88 88
values.resize(10);              // Contains 66 66 66 66 88 88 0 0 0
values.resize(4);               // Contains 66 66 66 66
```

The first argument to `resize()` is the new size for the vector. The second argument, when it is present, is the value to be used for new elements that need to be added to make up the new size. If you are increasing the size and you don't specify a value to be used for new elements, the default

value will be used. In the case of a vector storing objects of a class type, the default value will be the object produced by the no-arg constructor for the class.

You can explore the size and capacity of a vector through the following example.

TRY IT OUT**Exploring the Size and Capacity of a Vector**

In this example, you will try out some of the ways you have seen for creating a vector, and you'll also see how the capacity changes as you add elements:

```
// Ex10_01.cpp
// Exploring the size and capacity of a vector

#include <iostream>
#include <vector>
using std::cout;
using std::endl;
using std::vector;

// Template function to display the size and capacity of any vector
template<class T>
void listInfo(const vector<T>& v)

{
    cout << "Container capacity: " << v.capacity()
        << " size: " << v.size() << endl;
}

int main()
{
    // Basic vector creation
    vector<double> data;
    listInfo(data);

    cout << endl << "After calling reserve(100):" << endl;
    data.reserve(100);
    listInfo(data);

    // Create a vector with 10 elements and initialize it
    vector<int> numbers(10, -1);

    // You can use the range-based for loop with a vector
    cout << endl << "The initial values are:";
    for(auto n : numbers)
        cout << " " << n;

    // See how adding elements affects capacity increments
    auto oldC = numbers.capacity();      // Old capacity
    auto newC = oldC;                    // New capacity after adding element
    cout << endl << endl;
    listInfo(numbers);
    for(int i = 0; i<1000 ; i++)
    {
        numbers.push_back(2*i);
    }
}
```

```
newC = numbers.capacity();
if(oldC < newC) // Only output when capacity increases
{
    oldC = newC;
    listInfo(numbers);
}
return 0;
}
```

This example produces the following output:

```
Container capacity: 0 size: 0

After calling reserve(100):
Container capacity: 100 size: 0

The initial values are: -1 -1 -1 -1 -1 -1 -1 -1 -1 -1 -1 -1

Container capacity: 10 size: 10
Container capacity: 15 size: 11
Container capacity: 22 size: 16
Container capacity: 33 size: 23
Container capacity: 49 size: 34
Container capacity: 73 size: 50
Container capacity: 109 size: 74
Container capacity: 163 size: 110
Container capacity: 244 size: 164
Container capacity: 366 size: 245
Container capacity: 549 size: 367
Container capacity: 823 size: 550
Container capacity: 1234 size: 824
```

How It Works

The `#include` directive for the `vector` header adds the definition for the `vector<T>` template to the source file.

Following the `using` declarations you have a definition of the `listInfo()` function template:

```
template<class T>
void listInfo(const vector<T>& v)
{
    cout << "Container capacity: " << v.capacity()
        << " size: " << v.size() << endl;
}
```

This function template outputs the current capacity and size of any vector container. You will often find it convenient to write function templates when working with the STL. The example shows how easy it is. The `T` parameter determines the type of argument the function expects. You can call this function with a `vector` container as the argument. Specifying the parameter as the reference type, `const vector<T>&`, enables the code in the function body to access directly the container you pass as the argument to the function. If you specified the parameter as type `const vector<T>`, then the argument

would be copied each time the function is called, which could be a time-consuming process for a large vector container.

The first action in `main()` is to create a vector and output its size and capacity:

```
vector<double> data;
listInfo(data);
```

You can see from the output that the size and the capacity are both zero for this container. Adding an element requires more space to be allocated.

Next, you call the `reserve()` function for the container:

```
data.reserve(100);
```

You can see from the output that the capacity is now 100 and the size is zero. To put it another way, the container contains no elements but has memory allocated to accommodate up to 100 elements. Only when you add the 101st element will the capacity be increased automatically.

Next, you create another container with this statement:

```
vector<int> numbers(10, -1);
```

This creates a container that contains 10 elements at the outset, each initialized with -1. To demonstrate that this is indeed the case, you output the elements in the container with the following loop:

```
for(auto n : numbers)
    cout << " " << n;
```

This demonstrates that the range-based `for` loop works with a vector.

Alternatively, you could write the loop using the regular `for` loop:

```
for(vector<int>::size_type i = 0; i<numbers.size(); ++i)
    cout << " " << numbers[i];
```

You could also use an iterator to access the elements in the loop:

```
for(auto iter = begin(numbers); iter != end(numbers); ++iter)
    cout << " " << *iter;
```

The loop variable is an iterator, `iter`, of type `vector<int>::iterator`, that you initialize to the iterator returned by the `begin()` function. This is incremented on each loop iteration, and the loop ends when it reaches `end(numbers)`, which points to one past the last element. Note how you dereference the iterator just like a pointer to get at the value of the element.

The remaining statements in `main()` demonstrate how the capacity of a vector increases as you add elements. The first two statements set up variables to store the current capacity and the new capacity after adding an element:

```
auto oldC = numbers.capacity(); // Old capacity
auto newC = oldC; // New capacity after adding element
```

After displaying the initial size and capacity, you execute the following loop:

```
for(int i = 0; i<1000 ; i++)
{
    numbers.push_back(2*i);
    newC = numbers.capacity();
    if(oldC < newC)
    {
        oldC = newC;
        listInfo(numbers);
    }
}
```

This loop calls the `push_back()` function for the `numbers` vector, to add 1000 elements. We are only interested in seeing output when the capacity increases, so the `if` condition ensures that we only display the capacity and size when the capacity increases.

The output shows an interesting pattern in the way additional space is allocated in the container. As you would expect with the initial size and capacity at 10, the first capacity increase occurs when you add the 11th element. The increase in this case is half the capacity, so the capacity increases to 15. The next capacity increase is when the size reaches 15, and the increase is to 22, so the increment is again half the capacity. This process continues with each capacity increase being half the current capacity. Thus, you automatically get larger chunks of memory space allocated when required, the more elements the vector contains. On the one hand, this mechanism ensures that once the initial memory allocation in a container is occupied, you don't cause more memory to be allocated every time you add a new element. On the other hand, this implies that you should take care when reserving space for a large number of elements in a vector. If you set up a container that provides initially for 100,000 elements for example, exceeding this by one element will cause space for another 50,000 to be allocated. In this sort of situation you could check for reaching the capacity, and use `reserve()` to increase the available memory by a less extravagant amount.

Accessing the Elements in a Vector

You have already seen that you can access the elements in a vector by using the subscript operator, just as you would for an array. You can also use the `at()` function where the argument is the index position of the element you want to access. Here's how you could list the contents of the `numbers` vector of integer elements in the previous example using `at()`:

```
for(vector<int>::size_type i = 0; i<numbers.size() ; i++)
    cout << " " << numbers.at(i);
```

So how does the `at()` function differ from using the subscript operator, `[]`? Well, if you use a subscript with the subscript operator that is outside the valid range, the result is undefined. If you do the same with the `at()` function, an exception of type `out_of_range` will be thrown. If there's the potential for subscript values outside the legal range to arise in a program, it's generally better to use the `at()` function and catch the exception than to allow the possibility for undefined results.

Of course, when you want to access all the elements in a vector, the range-based `for` loop always provides a simpler mechanism:

```
for(auto& number : numbers)
    cout << " " << number;
```

To access the first or last element in a vector you can call the `front()` or `back()` function, respectively:

```
cout << "The value of the first element is: " << numbers.front() << endl;
cout << "The value of the last element is: " << numbers.back() << endl;
```

Both functions come in two versions; one returns a reference to the object stored, and the other returns a `const` reference to the object stored. The latter option enables you to explicitly prevent modification of the object:

```
const int& firstvalue = numbers.front();      // firstvalue cannot be changed
int& lastvalue = numbers.back();              // lastvalue can be changed
```

Storing the reference that is returned in a `const` variable automatically selects the version of the function that returns a `const` reference.

Inserting and Deleting Elements in a Vector

In addition to the `push_back()` function you have seen, a vector container supports the `pop_back()` operation that deletes the last element. Both operations execute in *constant time*, that is, the time to execute will be the same, regardless of the number of elements in the vector. The `pop_back()` function is very simple to use:

```
vec.pop_back();
```

This statement removes the last element from the vector `vec` and reduces the size by 1. If the vector contains no elements, then calling `pop_back()` has no effect.

You could remove all the elements in a vector by calling the `pop_back()` function repeatedly, but the `clear()` function does this much more simply:

```
vec.clear();
```

This statement removes all the elements from `vec`, so the size will be zero. Of course, the capacity will be left unchanged.

Insert Operations

You can call the `insert()` function to insert one or more new elements anywhere in a vector. This operation will execute in *linear time*, which means that the time will increase in proportion to the number of elements in the container. This is because inserting new elements involves moving the existing elements. The simplest version of the `insert()` function inserts a single new element

at a specific position in the vector, where the first argument is an iterator specifying the insertion position and the second argument is the element to be inserted. For example:

```
vector<int> vec(5, 99);
vec.insert(vec.begin() + 1, 88);
```

The first statement creates a vector with five integer elements, all initialized to 99. The second statement inserts 88 after the first element; so, after executing this, the vector will contain:

```
99 88 99 99 99
```

The `insert()` function call will invoke the version with an rvalue reference parameter so 88 will be moved into the vector, not copied. If the second argument to `insert()` is an lvalue, the version with a normal reference parameter will be called.

You can insert several identical elements, starting from a given position:

```
vec.insert(vec.begin() + 2, 3, 77);
```

The first argument is an iterator specifying the insertion position for the first element, the second argument is the number of elements to be inserted, and the third argument is the element to be inserted. After executing this statement, `vec` will contain:

```
99 88 77 77 77 99 99 99
```

You have yet another version of the `insert()` function that inserts a sequence of elements at a given position. The first argument is an iterator pointing to the insertion position for the first element. The second and third arguments are input iterators specifying the range of elements to be inserted from some source. Here's an example:

```
vector<int> newvec(5, 22);
newvec.insert(newvec.begin() + 1, vec.begin() + 1, vec.begin() + 5);
```

The first statement creates a vector with five integer elements initialized to 22. The second statement inserts four elements from `vec`, starting with the second. After executing these statements, `newvec` will contain:

```
22 88 77 77 77 22 22 22
```

Don't forget that the second iterator in the interval specifies the position that is *one past* the last element, so the element it points to is not included.

Emplace Operations

The `emplace()` and `emplace_back()` functions are used to insert an object in a vector by creating it in place, rather than moving or copying it. This is useful when the object is constructed using two or more constructor arguments. The `emplace()` function inserts an object at a specified position. The first parameter is an iterator specifying the insertion position. This is followed by one or more rvalue reference parameters that will be used in a constructor call for type `T` to create the object in place.

The `emplace_back()` function has one or more rvalue reference parameters that specify the object to be added at the end of the vector. For example, suppose you have defined a vector like this:

```
auto boxes = vector<CBox>();
```

`CBox` is the class you used in the previous chapter. You could add `CBox` objects to the vector like this:

```
boxes.push_back(CBox(1, 2, 3));
boxes.push_back(CBox(2, 4, 6));
boxes.push_back(CBox(3, 6, 9));
```

If you execute this fragment, tracing the `CBox` destructor calls with some output as in `Ex9_13`, you will see that there are two destructor calls for each object placed in the vector, so six in total.

A much better way would be to insert the objects like this:

```
boxes.emplace_back(1, 2, 3);
boxes.emplace_back(2, 4, 6);
boxes.emplace_back(3, 6, 9);
```

This results in just three destructor calls, which is a significant improvement in performance.

Erase Operations

The `erase()` function deletes one or more elements from any position within a vector, but this also is a linear time function and will typically be slow. Here's how you erase a single element at a given position:

```
newvec.erase(end(newvec) - 2);
```

The argument is an iterator that points to the element to be erased, so this statement removes the second to last element from `newvec`.

To delete several elements, you supply two iterator arguments specifying the interval. For example:

```
newvec.erase(begin(newvec) + 1, begin(newvec) + 4);
```

This will delete the second, third, and fourth elements from `newvec`. The element that the second iterator argument points to is not included in the operation.

As I said, both the `erase()` and `insert()` operations are slow, so you should use them sparingly.

Swap and Assign Operations

The `swap()` function enables you to swap the contents of two vectors, provided, of course, the elements in the two vectors are of the same type. Here's a code fragment showing an example of how this works:

```
vector<int> first(5, 77);           // Contains 77 77 77 77 77
vector<int> second(8, -1);          // Contains -1 -1 -1 -1 -1 -1 -1 -1
first.swap(second);
```

After executing the last statement, the contents of the vectors `first` and `second` will have interchanged. Note that the capacities of the vectors are swapped as well as the contents, and, of course, the size.

The `assign()` function enables you to replace the entire contents of a vector with another sequence, or to replace the contents with a given number of instances of an object. Here's how you could replace the contents of one vector with a sequence from another:

```
vector<double> values;
for(int i = 1 ; i <= 50 ; ++i)
    values.emplace_back(2.5*i);
vector<double> newdata(5, 3.5);
newdata.assign(begin(values)+1,end(values)-1);
```

This code fragment creates the `values` vector and stores 50 elements that have the values 2.5, 5.0, 7.5, ... 125.0. The `newdata` vector is created with five elements, each having the value 3.5. The last statement calls the `assign()` function for `newdata`, which deletes all elements from `newdata`, and then inserts copies of all the elements from `values`, except for the first and the last. You specify the new sequence to be inserted by two iterators, the first pointing to the first element to be inserted and the second pointing to one past the last element to be inserted. Because you specify the new elements to be inserted by two iterators, the source of the data can be from any sequence, not just a vector. The `assign()` function will also work with regular pointers, so you could also insert elements from an array of `double` elements.

Here's how you use the `assign()` function to replace the contents of a vector with a sequence of instances of the same element:

```
newdata.assign(30, 99.5);
```

The first argument is the count of elements in the replacement sequence, and the second argument is the element to be used. This statement will cause the contents of `newdata` to be deleted and replaced by 30 elements, each having the value 99.5.

Storing Class Objects in a Vector

You can store objects of any class type in a vector, but the class must meet certain minimum criteria. Here's a minimum specification for a given class `T` to be compatible with a vector, or, in fact, any sequence container:

```
class T
{
public:
    T();                                // Default constructor
    T(const T& t);                      // Copy constructor
    ~T();                                // Destructor
    T& operator=(const T& t);           // Assignment operator
};
```

The compiler will supply default versions of these class members if you don't define them, so it's not difficult for a class to meet these requirements. The important thing to note is that they are required

and are likely to be used, so when the default implementation that the compiler supplies will not suffice, you must provide your own implementation.

If you store objects of your own class types in a vector, it's highly recommended that you implement a move constructor and a move assignment operator for your class type because the vector container fully supports move semantics. For example, if the vector needs to resize itself to allow more elements to be added, without move semantics the following sequence of events will occur:

1. A new vector with the new size is allocated.
2. All objects from the old vector are *copied* to the new vector.
3. All objects in the old vector are destroyed.
4. The old vector is deallocated.

With move semantics support in your class, this is what happens:

1. A new vector with the new size is allocated.
2. All objects from the old vector are *moved* to the new vector.
3. All objects in the old vector are destroyed.
4. The old vector is deallocated.

This will be significantly faster because no copying is necessary.

Let's try an example.

TRY IT OUT Storing Objects in a Vector

In this example you create `Person` objects that represent individuals by their name. Just to make it more interesting, I'm going to pretend that you have never heard of the `string` class, so you are stuck with using null-terminated strings to store names. This means you have to take care how you implement the class if you want to store objects in a `vector<Person>` container. In general, such a class might have lots of different data members relating to a person, but I'll keep it simple with just their first and second names.

Here's the definition of the `Person` class:

```
// Person.h
// A class defining people by their names
#pragma once
#include <cstring>
#include <iostream>
using std::cout;
using std::endl;

class Person
{
public:
    // Constructor, includes no-arg constructor
    Person(const char* first = "John", const char* second = "Doe")
```

```
{  
    initName(first, second);  
}  
  
// Copy constructor  
Person(const Person& p)  
{  
    initName(p.firstname, p.secondname);  
}  
  
// Move constructor  
Person(Person&& p)  
{  
    firstname = p.firstname;  
    secondname = p.secondname;  
  
    // Reset rvalue object pointers to prevent deletion  
    p.firstname = nullptr;  
    p.secondname = nullptr;  
}  
  
// Destructor  
~Person()  
{  
    delete[] firstname;  
    delete[] secondname;  
}  
  
// Assignment operator  
Person& operator=(const Person& p)  
{  
    // Deal with p = p assignment situation  
    if(&p != this)  
    {  
        delete[] firstname;  
        delete[] secondname;  
        initName(p.firstname, p.secondname);  
    }  
    return *this;  
}  
  
// Move assignment operator  
Person& operator=(Person&& p)  
{  
    // Deal with p = p assignment situation  
    if(&p != this)  
    {  
        // Release current memory  
        delete[] firstname;  
        delete[] secondname;  
        firstname = p.firstname;  
        secondname = p.secondname;  
        p.firstname = nullptr;  
    }  
}
```

```

        p.secondname = nullptr;
    }
    return *this;
}

// Less-than operator
bool operator<(const Person& p)
{
    int result(strcmp(secondname, p.secondname));
    return (result < 0 || result == 0 && strcmp(firstname, p.firstname) < 0);
}

// Output a person
void showPerson() const
{
    cout << firstname << " " << secondname << endl;
}

private:
char* firstname;
char* secondname;

// Private helper function to avoid code duplication
void initName(const char* first, const char* second)
{
    size_t length(strlen(first)+1);
    firstname = new char[length];
    strcpy_s(firstname, length, first);
    length = strlen(second)+1;
    secondname = new char[length];
    strcpy_s(secondname, length, second);
}
};

The #pragma once directive is there to ensure that the header does not get included in a program more than once.
```

The `private initName()` function is there because the constructors and the assignment operator function need to carry out the same operations to initialize the class data members. Using this helper function avoids having repeated occurrences of the same code.

Because the `Person` class allocates memory dynamically to store the first and second names of a person, you must implement the destructor to release the memory when an object is destroyed. You must also implement the assignment operator because this involves more memory allocation. Note the code at the beginning for dealing with the `a = a` assignment situation. Assigning an object to itself can arise in ways that are less than obvious, and can cause problems if you don't implement the `operator=()` function to take account of this.

The `showPerson()` function is a convenience function for outputting an entire name. It is declared as `const` to allow it to work with `const` and non-`const` `Person` objects. The `operator<()` function is there for use later.

The program to store Person objects in a vector looks like this:

```
// Ex10_02.cpp
// Storing objects in a vector

#include <iostream>
#include <vector>
#include "Person.h"

using std::cin;
using std::cout;
using std::endl;
using std::vector;

int main()
{
    vector<Person> people;                      // Vector of Person objects
    const size_t maxlen(50);
    char firstname[maxlen];
    char secondname[maxlen];

    // Input all the people
    while(true)
    {
        cout << "Enter a first name or press Enter to end: ";
        cin.getline(firstname, maxlen, '\n');
        if(strlen(firstname) == 0)
            break;
        cout << "Enter the second name: ";
        cin.getline(secondname, maxlen, '\n');
        people.push_back(Person(firstname, secondname));
    }

    // Output the contents of the vector using an iterator
    cout << endl;
    auto iter(people.cbegin());
    while(iter != people.cend())
        iter++>showPerson();

    return 0;
}
```

Here's an example of some output from this program:

```
Enter a first name or press Enter to end: Jane
Enter the second name: Fonda
Enter a first name or press Enter to end: Bill
Enter the second name: Cosby
Enter a first name or press Enter to end: Sally
Enter the second name: Field
Enter a first name or press Enter to end: Mae
Enter the second name: West
Enter a first name or press Enter to end: Oliver
Enter the second name: Hardy
```

Enter a first name or press Enter to end:

```
Jane Fonda
Bill Cosby
Sally Field
Mae West
Oliver Hardy
```

How It Works

You create a vector to store Person objects like this:

```
vector<Person> people; // Vector of Person objects
```

You then create two arrays of type `char[]` that you'll use as working storage when reading names from the standard input stream:

```
const size_t maxlen(50);
char fname[maxlen];
char sname[maxlen];
```

Each array accommodates a name up to `maxlen` characters long, including the terminating null.

You read names from the standard input stream in an indefinite loop:

```
while(true)
{
    cout << "Enter a first name or press Enter to end: ";
    cin.getline(fname, maxlen, '\n');
    if(strlen(fname) == 0)
        break;
    cout << "Enter the second name: ";
    cin.getline(sname, maxlen, '\n');
    people.push_back(Person(fname, sname));
}
```

You read each name using the `getline()` member function for `cin`. This reads characters until a newline character is read, or until `maxlen-1` characters have been read. This ensures that you don't overrun the capacity of the input array because both arrays have `maxlen` elements, allowing for strings up to `maxlen-1` characters plus the terminating null. When an empty string is entered for the first name, the loop ends.

You create the `Person` object in the expression that is the argument to the `push_back()` function. This adds the objects to the end of the vector.

The last step is to output the contents of the vector:

```
cout << endl;
auto iter(people.cbegin());
while(iter != people.cend())
    iter++>showPerson();
```

Here, you use an iterator of type `const vector<Person>::const_iterator` to output the elements of the vector with the type deduced automatically from the initial value. Within the body of the while

loop, you output the element that the iterator points to, and then you increment the iterator using the postfix increment operator. The loop continues as long as `iter` is not equal to the iterator returned by `cend()`.

A range-based `for` loop would greatly simplify the output. You don't need to use an iterator explicitly at all. Just write the loop as:

```
for(auto& p : people)
    p.showPerson();
```

The loop variable, `p`, will be of type `Person&`, which is a reference to the type of element stored in the vector.

Sorting Vector Elements

The `sort<T>()` function template that is defined in the `algorithm` header will sort a sequence of objects of any type as long as the required object comparisons are possible. You identify the sequence to be sorted by two random access iterators that point to the first and one-past-the-last objects in the sequence. Note that random access iterators are essential; iterators with lesser capability will not suffice. The type parameter, `T`, specifies the type of random access iterator that the function will use. The `sort<T>()` function template uses the `<` operator to order the elements. Thus, you can use the `sort()` template to sort the contents of any container that provides random access iterators, as long as the objects it contains can be compared using the less-than operator.

In the previous example, you implemented `operator<()` in the `Person` class, so you can sort a sequence of `Person` objects. Here's how you could sort the contents of the `vector<Person>` container:

```
sort(begin(people), end(people));
```

This sorts the contents of the vector in ascending sequence. You can add an `#include` directive for `algorithm`, and put the statement in `main()` before the output loop, to see the sort in action. You'll also need a `using` declaration for `std::sort`.

Note that you can use the `sort<T>()` template function to sort arrays. The only requirement is that the `<` operator should work with the type of elements stored in the array. Here's a code fragment showing how you could use it to sort an array of integers:

```
const size_t max(100);
int data[max];
cout << "Enter up to " << max << " non-zero integers. Enter 0 to end." << endl;
int value(0);
size_t count(0);
for(size_t i = 0 ; i<max ; i++)           // Read up to max integers
{
    cin >> value;                      // Read a value
    if(value == 0)                      // If it is zero,
        break;                          // We are done
    data[count++] = value;
}
sort(data, data+count);                  // Sort the integers
```

Note how the pointer marking the end of the sequence of elements that are to be sorted must still be one past the last element.

When you need to sort a sequence in descending order, you can use the version of the `sort<T>()` algorithm that accepts a third argument that is a function object that defines a binary predicate. The functional header defines a complete set of function object types for comparison predicates:

```
less<T>    less_equal<T>    equal<T>    greater_equal<T>    greater<T>
```

Each of these templates creates a class type for function objects that you can use with `sort()` and other algorithms for sorting objects of type `T`. The `sort()` function used in the previous fragment uses a `less<int>` function object by default. To specify a different function object to be used as the sort criterion, you add it as a third argument, like this:

```
sort(data, data+count, greater<int>());      // Sort the integers
```

The third argument to the function is an expression that calls the constructor for the `greater<int>` type, so you are passing an object of this type to the `sort()` function. This statement will sort the contents of the `data` array in descending sequence. If you are trying these fragments out, don't forget that you need the `functional` header to be included for the function object, and a using declaration for the `greater` name that is defined in the `std` namespace.

Storing Pointers in a Vector

A vector container, like other containers, makes a copy of the objects you add to it. This has tremendous advantages in most circumstances, but it could be very inconvenient in some situations. For example, if your objects are large, there could be considerable overhead in copying each object as you add it to the container. This is an occasion where you might be better off storing smart pointers to the objects in the container rather than the objects themselves, and managing the objects externally. You could create a new version of the `Ex10_02.cpp` example to store pointers to `Person` objects in a container.

TRY IT OUT Storing Pointers in a Vector

The `Person` class definition is exactly the same as before. Here's a revised version of the source file that defines `main()`:

```
// Ex10_03.cpp
// Storing pointers to objects in a vector

#include <iostream>
#include <vector>
#include <memory>
#include "Person.h"

using std::cin;
using std::cout;
using std::endl;
```

```
using std::vector;
using std::shared_ptr;
using std::make_shared;

int main()
{
    vector<shared_ptr<Person>> people;           // Vector of Person object pointers
    const size_t maxlen(50);
    char firstname[maxlen];
    char secondname[maxlen];
    while(true)
    {
        cout << "Enter a first name or press Enter to end: ";
        cin.getline(firstname, maxlen, '\n');
        if(strlen(firstname) == 0)
            break;
        cout << "Enter the second name: ";
        cin.getline(secondname, maxlen, '\n');
        people.push_back(make_shared<Person>(firstname, secondname));
    }

    // Output the contents of the vector
    cout << endl;
    for(auto& p : people)
        p->showPerson();

    people.clear();                                // Clear the vector
    return 0;
}
```

The output is essentially the same as before.

How It Works

There is an `#include` directive for the `memory` header and additional `using` declarations for the `shared_ptr` smart pointer type name and the `make_shared` function name. The first change in `main()` from Ex10_02 is in the definition of the container:

```
vector<shared_ptr<Person>> people;           // Vector of Person object pointers
```

The `vector<T>` template type parameter is now `shared_ptr<Person>`, which is a smart pointer to a `Person` object.

Within the input loop, each `Person` object is now created on the heap, and the address wrapped inside a `shared_ptr` is passed to the `push_back()` function for the vector:

```
people.push_back(make_shared<Person>(firstname, secondname));
```

The arguments to `make_shared<Person>()` are the arguments that it will use for the `Person` class constructor that will be pointed to by the `shared_ptr<Person>` object it will return. This is stored in the vector by the `push_back()` function.

You output the Person objects using the range-based for loop:

```
for(auto& p : people)
    p->showPerson();
```

This time p is of type `shared_ptr<Person>&`, so you use the indirect member selection operator to call `showPerson()` for each Person object.

Finally, you empty the vector by calling its `clear()` function. This simply deletes everything stored in the container. There is no need to delete Person objects. This will be taken care of when the smart pointers are destroyed.

You could also store `unique_ptr<Person>` objects in the vector:

```
vector<unique_ptr<Person>> people;           // Vector of Person object pointers
```

The statement to store the pointers in the vector would be:

```
people.push_back(unique_ptr<Person>(new Person(firstname, secondname)));
```

The loop to output the Person objects would be just the same. However, there's a difference between using `unique_ptr` and `shared_ptr`. This rather less efficient loop would work with `shared_ptr` objects:

```
for(auto p : people)
    p->showPerson();
```

However, this will not compile with `unique_ptr` objects in the vector because they cannot be copied. You must use a reference to access the elements in this case.

These statements also would not compile:

```
auto pPerson = unique_ptr<Person>(new Person(firstname, secondname));
people.push_back(pPerson);
```

This involves copying the `unique_ptr` object so it's not allowed.

You could do this though:

```
people.push_back(std::move(pPerson));
```

This moves the pointer in pPerson to a `unique_ptr` in the vector. But now pPerson is not valid, so this statement would throw an exception:

```
pPerson->showPerson();
```

If you plan to retain a smart pointer for use after you have stored it in a container, use a `shared_ptr` and not a `unique_ptr`.

Array Containers

The `array<T, N>` template that is defined in the `array` header defines a container that is similar to an ordinary array in that it is of fixed length, `N`, and you can use the subscript operator to access the elements. You can also initialize an array container with an initializer list. For example:

```
array<double, 5> values = {1.5, 2.5, 3.5, 4.5, 5.5};
```

If you supply fewer initializers than there are elements, the remaining elements will be initialized with the equivalent of zero. This means `nullptr` if the elements are pointers and objects created by the default constructor if the elements are objects of a class type. If you supply too many initializers, the code won't compile.

You can define an array container without initializing it:

```
array<int, 4> data;
```

The size is fixed and the four elements of type `int` will be created and contain junk values. Array elements of a primitive type will not be initialized by default, but elements of a class type will be initialized by calling the no-arg constructor. You could construct an array of `Person` objects where the `Person` class is as in `Ex10_03`:

```
array<Person, 10> people;
```

This container has 10 elements of type `Person`, all with the name "John Doe". You could demonstrate this by outputting the contents of the `people` array:

```
for(auto& person : people)
    person.showPerson();
```

An array container knows its size, so you can use the range-based `for` loop when it is passed as an argument to a function. For example, here's a function template that will list any array container of `Person` objects:

```
template<size_t N>
void listPeople(const array<Person, N>& folks)
{
    for(auto& p : folks)
        p.showPerson();
}
```

Defining the function by a template with a parameter, `N`, allows it to be used to list an array of any number of `Person` objects. If your application classes use a standard function to display an object, you could add a template type parameter for the type of element stored and get a function that will list any of your arrays of any length or type.

Because the elements of an array container are always created when you define it, you can reference an element using the subscript operator and use it as an lvalue. For example:

```
people[1] = Person("Joe", "Bloggs");
```

This stores a `Person` object in the second element in the array.

Here's a summary of some of the most useful members of an array container type:

- `void fill(T& arg)` sets all the array elements to `arg`:

```
people.fill(Person("Ned", "Kelly")); // Fill array with Ned Kellys
```

- `size()` returns the size of the array as an integer.

- `back()` returns a reference to the last array element:

```
people.back().showPerson(); // Output the last person
```

- `begin()` returns an iterator pointing to the first array element.

- `end()` returns an iterator pointing to one past the last array element.

- `rbegin()` returns a reverse iterator pointing to the last array element.

- `rend()` returns a reverse iterator pointing to before the first array element.

- `swap(array& right)` swaps the current array with `right`. The current array and `right` must store the same type of elements and have the same size.

```
array<int, 3> left = {1, 2, 3};
array<int, 3> right = {10, 20, 30};
left.swap(right); // Swap contents of left and right
```

You can use any of the comparison operators, `<`, `<=`, `==`, `>=`, `>`, and `!=`, to compare two array containers as long as they store the same number of elements of the same type. Corresponding elements are compared in sequence to determine the result. For example, `array1<array2` will result in `true` if `array1` has the first occurring element that is less than the corresponding element in `array2`. Two arrays are equal if all corresponding elements are equal and unequal if any pair of corresponding elements differ.

Let's see an example of an array in use.

TRY IT OUT Using an Array

This example creates an interesting series of values in array containers:

```
// Ex10_04
// Using array containers
#include <iostream>
#include <iomanip>
#include <array>
#include <numeric>

using std::cin;
using std::cout;
using std::endl;
using std::setw;
using std::array;
```

```
using std::accumulate;

template<class T, size_t N>
void listValues(const array<T, N>& data)
{
    const int values_per_line(6);
    int count(0);
    for(auto& value : data)
    {
        cout << setw(14) << value;
        if(++count % values_per_line == 0)
            cout << endl;
    }
    cout << endl;
}

int main()
{
    // Create the famous Fibonacci series
    const size_t N(20);
    array<long, N> fibonacci = {1L, 1L};
    for(size_t i = 2 ; i<fibonacci.size() ; ++i)
        fibonacci[i] = fibonacci[i-1] + fibonacci[i-2];
    cout << "Fibonacci series is:" << endl;
    listValues(fibonacci);

    array<long, N> numbers;
    numbers.fill(99L);
    fibonacci.swap(numbers);
    cout << endl << "After swap fibonacci contains:" << endl;
    listValues(fibonacci);

    // Create the series for pi/4
    array<double, 120> series;
    double factor(-1.0);
    for(size_t x = 0 ; x<series.size() ; ++x)
    {
        factor *= -1.0;
        series[x] = factor/(2*x+1);
    }
    cout << endl << "Series for pi is:" << endl;
    listValues(series);
    double result(accumulate(begin(series), end(series), 0.0));
    cout << "The series sum converges slowly to pi/4. The sum x 4 is: "
        << 4.0*result << endl;

    return 0;
}
```

I won't include the output here because there's quite a lot of it.

How It Works

You create the first array container with 20 elements of type `long` with the first two initialized to `1L`. In the Fibonacci series, each element is the sum of the two preceding elements and the `for` loop sets

the values for the array from the third element onwards. You then output the contents of the array using the `listValues()` template function. This will list values of an array container of any size that contains elements of any type that can be written to the standard output stream.

Next, you create the `numbers` container storing the same number of `long` elements as `fibonacci`. The elements are all set to `99L` using the `fill()` function. You use the `swap()` function to swap the contents of `numbers` and `fibonacci`, and the output shows that `fibonacci` now contains elements that are all `99`.

The third container, `series`, contains 120 elements of type `double`. The values are set in the `for` loop to those of the Leibnitz series that total $\pi/4$ if you sum an infinite number of them.

You sum the 120 elements using the `accumulate()` template function that is defined in the `numeric` header. The first argument is an iterator specifying the first element in a container, the second argument is an iterator specifying one past the last element, and the third argument is a value to which the elements specified by the first two arguments are to be added. This function works with any sequence container that contains elements that support the `+` operator. There is another version of `accumulate()` that accepts a fourth argument that specifies the operation to be applied between elements if you don't want to add them. You specify the operation by a function object or lambda expression that defines a binary predicate.

You'll see from the output that the sum of the first 120 elements in the Leibnitz series is fairly close to $\pi/4$.

Double-Ended Queue Containers

The double-ended queue container template, `deque<T>`, is defined in the `deque` header. A double-ended queue container is very similar to a vector in that it can do everything a vector container can, and includes the same function members, but you can also add and delete elements efficiently at the beginning of the sequence as well as at the end. You could replace the vector used in `Ex10_02.cpp` with a double-ended queue, and it would work just as well:

```
deque<Person> people; // Double-ended queue of Person objects
```

Of course, you would need to change the `#include` directive to include the `deque` header instead of the `vector` header and the `using` declaration to refer to `std::deque`.

The function to add an element to the front of the container is `push_front()`, and you can delete the first element by calling the `pop_front()` function. Thus, if you were using a `deque<Person>` container in `Ex10_02.cpp`, you could add elements at the front instead of the back:

```
people.push_front(Person(firstname, secondname));
```

Using this statement to add elements to the container, the order of elements in the double-ended queue would be the reverse of those in the vector.

The range of constructors available for a `deque<T>` container is the same as for `vector<T>`. Here are examples of each of them:

```
deque<string> strings; // Create an empty container
deque<int> items(50); // A container of 50 elements initialized to
                      // default value
```

```
deque<double> values(5, 0.5);      // A container with 5 elements 0.5
deque<int> data(items.begin(), items.end()); // Initialized with a sequence
```

Although a double-ended queue is very similar to a vector and does everything a vector can do, as well as allowing you to add to the front of the sequence efficiently, it does have one disadvantage. Because of the additional capability it offers, the memory management for a double-ended queue is more complicated than for a vector, so it will be slightly slower. Unless you need to add elements to the front of the container, a vector is a better choice.

Let's see a double-ended queue in action.

TRY IT OUT Using a Double-Ended Queue

This example stores an arbitrary number of integers in a double-ended queue and then operates on them:

```
// Ex10_05.cpp
// Using a double-ended queue

#include <iostream>
#include <deque>
#include <algorithm>           // For sort<T }()
#include <numeric>             // For accumulate<T }()
#include <functional>          // For function objects

using std::cin;
using std::cout;
using std::endl;
using std::deque;
using std::sort;

int main()
{
    deque<int> data;

    // Read the data
    cout << "Enter a series of non-zero integers separated by spaces."
        << " Enter 0 to end." << endl;
    int value(0);
    while(cin >> value, value != 0)
        data.push_front(value);

    // Output the data
    cout << endl << "The values you entered are:" << endl;
    for(auto& n : data)
        cout << n << " ";
    cout << endl;

    // Output the data using a reverse iterator
    cout << endl << "In reverse order the values you entered are:" << endl;
    for(auto riter = data.rbegin() ; riter != data.rend() ; riter++)
        cout << *riter << " ";

    // Sort the data in descending sequence
```

```

cout << endl;
cout << endl << "In descending sequence the values you entered are:" << endl;
sort(data.begin(), data.end(), std::greater<int>()); // Sort the elements
for(auto& n : data)
    cout << n << " ";
cout << endl;

// Calculate the sum of the elements
cout << endl << "The sum of the elements in the queue is: "
    << std::accumulate(data.begin(), data.end(), 0) << endl;

return 0;
}

```

Here is some sample output from this program:

```

Enter a series of non-zero integers separated by spaces. Enter 0 to end.
405 302 1 23 67 34 56 111 56 99 77 82 3 23 34 111 89 0

The values you entered are:
89 111 34 23 3 82 77 99 56 111 56 34 67 23 1 302 405

In reverse order the values you entered are:
405 302 1 23 67 34 56 111 56 99 77 82 3 23 34 111 89

In descending sequence the values you entered are:
405 302 111 111 99 89 82 77 67 56 56 34 34 23 23 3 1

The sum of the elements in the queue is: 1573

```

How It Works

You create the double-ended queue container at the beginning of `main()`:

```
deque<int> data;
```

The data container is empty to start with and the input is read in a `while` loop:

```

int value(0);
while(cin >> value, value != 0)
    data.push_front(value);

```

The `while` loop condition makes use of the comma operator to separate two expressions, one that reads an integer from `cin` into `value` and another that tests whether the value read is non-zero. You saw in Chapter 2 that the value of a series of expressions separated by commas is the value of the rightmost expression, so the `while` loop continues as long as the expression `value != 0` is `true`, and the value read is non-zero. Within the loop you store the value in the queue using the `push_front()` function.

The next loop lists the values that you stored in the queue:

```

cout << endl << "The values you entered are:" << endl;
for(auto& n : data)
    cout << n << " ";
cout << endl;

```

This uses a range-based `for` loop to output the values. You could also write this as a `while` loop using an iterator:

```
auto iter = data.begin();
while(iter != data.end())
    cout << *iter++ << " ";
cout << endl;
```

Here, you increment the iterator, `iter`, after the value it points to is written to `cout`. It's just for illustration — not a good alternative to the range-based `for`!

The next loop outputs the values in reverse order:

```
for(auto riter = data.rbegin() ; riter != data.rend() ; riter++)
    cout << *riter << " ";
```

This uses a reverse iterator, so the loop starts with the last element and ends when `riter` is incremented to be equal to the iterator returned by `rend()`. The `rbegin()` function returns an iterator pointing to the last element and the `rend()` function returns an iterator pointing to one before the first element. For vector and double-ended queue containers, you get random access iterators. The `auto` keyword selects the type automatically. The iterator type will be `deque<int>::reverse_iterator`.

Next, you sort the elements in descending sequence and output them:

```
sort(data.begin(), data.end(), std::greater<int>()); // Sort the elements
for(auto& n : data)
    cout << n << " ";
cout << endl;
```

By default, the `sort<T>()` function sorts in ascending sequence using a `less<T>()` function object as the comparator. When you supply the `greater<int>()` function object as the optional third argument, the integer elements will be sorted into descending sequence.

You could also sort the queue elements in descending sequence like this:

```
sort(data.rbegin(), data.rend()); // Sort the elements
```

The default operation of the `sort()` algorithm is to sort the sequence passed to it by the two random access iterator arguments in ascending sequence. Here, you pass reverse iterators to the function, so it sees the elements in reverse order and sorts the reversed sequence in ascending order. The result is that the elements end up in descending sequence when seen in the normal forward order.

The last operation in `main()` is to output the sum of the elements:

```
cout << endl << "The sum of the elements in the queue is: "
    << accumulate(data.begin(), data.end(), 0) << endl;
```

You could use a conventional loop to do this, but here you make use of the `accumulate()` algorithm from the numeric header that you saw in the previous example. The default addition operation applies here.

Using List Containers

The `list<T>` container template from the `list` header implements a doubly-linked list. The big advantage this has over a vector or a double-ended queue is that you can insert or delete elements anywhere in the sequence in constant time. The main drawback is that a list cannot directly access an element by its position. It's necessary to traverse the elements in a list from a known position when you want to do this, usually the first or the last. The range of constructors for a list container is similar to that for a vector or double-ended queue. This statement creates an empty list:

```
list<string> names;
```

You can also create a list with a given number of default elements:

```
list<string> sayings(20); // A list of 20 empty strings
```

Here's how you create a list containing a given number of elements that are identical:

```
list<double> values(50, 2.71828);
```

This creates a list of 50 values of type `double`.

Of course, you can also construct a list initialized with values from a sequence specified by two iterators:

```
list<double> samples(++begin(values), --end(values));
```

This creates a list from the contents of the `values` list, omitting the first and last elements in `values`. Note that the iterators returned by the `begin()` and `end()` functions for a list are bidirectional iterators, so you do not have the same flexibility as with a `vector` or a `deque` container that support random access iterators. You can only change the value of a bidirectional iterator using the increment or decrement operators.

Just like the other sequence containers, you can discover the number of elements in a list by calling its `size()` member. You can also change the number of elements in a list by calling its `resize()` function. If the argument to `resize()` is less than the number of elements, elements will be deleted from the end; if the argument is greater, elements will be added using the default constructor for the type of elements stored.

Adding Elements to a List

You add an element to the beginning or end of a list by calling `push_front()` or `push_back()`, just as you would for a double-ended queue. To add elements to the interior of a list, you use the `insert()` function, which comes in three versions. Using the first version, you can insert a new element at a position specified by an iterator:

```
list<int> data(20, 1); // List of 20 elements value 1
data.insert(++begin(data), 77); // Insert 77 as the second element
```

The first argument to `insert()` is an iterator specified in the insertion position, and the second argument is the element to be inserted. The increment operator applied to the bidirectional iterator returned by `begin()` makes it point to the second element in the list. After executing this, the list contents will be:

```
1 77 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
```

You can see that the list now contains 21 elements, and that the elements from the insertion point on are simply displaced to the right.

You can also insert a number of copies of the same element at a given position:

```
auto iter = begin(data);
for(int i = 0 ; i<9 ; i++)
    ++iter;
data.insert(iter, 3, 88); // Insert 3 copies of 88 starting at the 10th
```

`iter` will be of type `list<int>::iterator`. The first argument to the `insert()` function is an iterator specifying the position, the second argument is the number of elements to be inserted, and the third argument is the element to be inserted repeatedly. To get to the tenth element you increment the iterator nine times in the `for` loop. Thus, this fragment inserts three copies of 88 into the list, starting at the tenth element. Now the contents of the list will be:

```
1 77 1 1 1 1 1 1 88 88 88 1 1 1 1 1 1 1 1 1 1 1 1
```

Now the list contains 24 elements.

Here's how you can insert a sequence of elements into a list:

```
vector<int> numbers(10, 5); // Vector of 10 elements with value 5
data.insert(--(--end(data)), begin(numbers), end(numbers));
```

The first argument to `insert()` is an iterator pointing to the second-to-last element position. The sequence to be inserted is specified by the second and third arguments to the `insert()` function, so this will insert all the elements from the vector into the list, starting at the second-to-last element position. After executing this, the contents of the list will be:

```
1 77 1 1 1 1 1 1 88 88 88 1 1 1 1 1 1 1 1 1 1 1 1 5 5 5 5 5 5 5 5 5 5 5 1 1
```

Inserting the 10 elements from `numbers` in the second-to-last element position displaces the last two elements in the list to the right. The list now contains 34 elements.

There are three functions that will construct an element in place in the list: `emplace()`, which constructs an element at a position specified by an iterator; `emplace_front()`, which constructs an element at the beginning; and `emplace_back()`, which constructs an element at the end. Here are some examples of their use:

```
std::list<string> strings;
strings.emplace_back("first");
```

```

string s("second");
strings.emplace_back(std::move(s));
strings.emplace_front("third");
strings.emplace(++begin(strings), "fourth");

```

The fourth line of code uses the `std::move()` function to pass an rvalue reference to `s` to the `emplace_back()` function. After executing this operation, `s` will be empty because the contents will have been moved to the list. After executing these statements, `strings` will contain the elements:

```
third fourth first second
```

Accessing Elements in a List

You can obtain a reference to the first or last element in a list by calling the `front()` or `back()` function for the list. To access elements interior to the list you must use an iterator and increment or decrement it to get to the element you want. As you have seen, the `begin()` and `end()` functions return a bidirectional iterator pointing at the first element, or one past the last element, respectively. The `rbegin()` and `rend()` functions return bidirectional iterators and enable you to iterate through the elements in reverse sequence. You can use the range-based `for` loop with a list so you don't have to use iterators when you want to process all the elements:

```

std::list<string> strings;
strings.emplace_back("first");
string s("second");
strings.emplace_back(std::move(s));
strings.emplace_front("third");
strings.emplace(++begin(strings), "fourth");

for(auto& s : strings)
    cout << s << endl;

```

The loop variable, `s`, is a reference that will contain a reference to each list element in turn.

Sorting List Elements

Because a `list<T>` container does not provide random access iterators, you cannot use the `sort()` function that is defined in the `algorithm` header. This is why the `list<T>` template defines its own `sort()` function member that comes in two versions. To sort a list of elements in ascending sequence you call the `sort()` member function with no arguments. Alternatively, you can specify a function object or a lambda expression that defines a different predicate for comparing members. For example:

```
strings.sort(std::greater<string>()); // Descending sequence
```

Let's try out some of what we have seen in an example.

TRY IT OUT Working with a List

In this example you read sentences from the keyboard and store them in a list:

```
// Ex10_06.cpp
// Working with a list

#include <iostream>
#include <list>
#include <string>

using std::cin;
using std::cout;
using std::endl;
using std::list;
using std::string;

int main()
{
    list<string> text;

    // Read the data
    cout << "Enter a few lines of text. Just press Enter to end:"
        << endl;
    string sentence;
    while(getline(cin, sentence, '\n'), !sentence.empty())
        text.push_front(sentence);

    // Output the data using an iterator
    cout << endl << "In reverse order, here is the text you entered:" << endl;
    for(auto& s : text)
        cout << s << endl;

    // Sort the data in ascending sequence
    cout << endl << "In ascending sequence the sentences you entered are:" << endl;
    text.sort();
    for(auto& s : text)
        cout << s << endl;

    return 0;
}
```

Here is an example of some output from this program:

```
Enter a few lines of text. Just press Enter to end:
This sentance contains three erors.
This sentence is false.
People who live in glass houses might as well answer the door.
If all else fails, read the instructions.
Home is where the mortgage is.
```

```
In reverse order, here is the text you entered:
Home is where the mortgage is.
If all else fails, read the instructions.
People who live in glass houses might as well answer the door.
```

```

This sentence is false.
This sentance contains three erors.

In ascending sequence the sentences you entered are:
Home is where the mortgage is.
If all else fails, read the instructions.
People who live in glass houses might as well answer the door.
This sentance contains three erors.
This sentence is false.

```

How It Works

You first create a list container to hold strings:

```
list<string> text;
```

You then read an arbitrary number of text inputs from the standard input stream, `cin`:

```

string sentence;
while(getline(cin, sentence, '\n'), !sentence.empty())
    text.push_front(sentence);

```

This uses the same idiom for input as the previous example. The second expression in the `while` loop condition determines when the loop ends, which will be when calling `empty()` for `sentence` returns `true`. You add each input to the list using the `push_front()` function, but you could equally well use `push_back()`. The only difference would be that the order of elements in the list would be reversed.

A better way to code this would be to use an `emplace` function:

```

while(getline(cin, sentence, '\n'), !sentence.empty())
    text.emplace_front(std::move(sentence));

```

This would move the string from `sentence` to the front of the list. This would avoid any copying and therefore would be faster to execute. The `sentence` object would be empty after each `emplace` operation.

You output the contents of the list in a loop:

```

for(auto& s : text)
    cout << s << endl;

```

Lastly, you sort the contents of the list and output it:

```

text.sort();
for(auto& s : text)
    cout << s << endl;

```

This uses the `sort()` member of the `list<string>` object to sort the contents in ascending sequence. If you want to try descending sequence, change the first statement to:

```
text.sort(std::greater<string>());
```

Don't forget to include the functional header.

Other Operations on Lists

The `clear()` function deletes all the elements from a list. The `erase()` function allows you to delete either a single element specified by a single iterator, or a sequence of elements specified by a pair of iterators in the usual fashion — the first in the sequence and one past the last.

```
int data[] = {10, 22, 4, 56, 89, 77, 13, 9};  
list<int> numbers(begin(data), end(data));  
  
numbers.erase(++begin(numbers)); // Remove the second element  
  
// Remove all except the first and the last two  
numbers.erase(++begin(numbers), --(--end(numbers))');
```

Initially, the list will contain all the values from the `data` array. The first `erase()` operation deletes the second element, so the list will contain:

```
10 4 56 89 77 13 9
```

For the second `erase()` operation, the first argument is the iterator returned by `begin()`, incremented by 1, so that it points to the second element. The second argument is the iterator returned by `end()`, decremented twice, so that it points to the second-to-last element. Of course, this is one past the end of the sequence, so the element that this iterator points to is not included in the set to be deleted, and the list contents after this operation will be:

```
10 13 9
```

The `remove()` function removes the elements from a list that match a particular value. With the `numbers` list defined as in the previous fragment, you could remove all elements equal to 22 with the following statement:

```
numbers.remove(22);
```

The `assign()` function removes all the elements from a list and copies either a single object into the list a given number of times, or copies a sequence of objects specified by two iterators. Here's an example:

```
int data[] = {10, 22, 4, 56, 89, 77, 13, 9};  
list<int> numbers(begin(data), end(data));  
numbers.assign(10, 99); // Replace contents by 10 copies of 99  
numbers.assign(data+1, data+4); // Replace contents by 22 4 56
```

The `assign()` function comes in the two overloaded versions illustrated here. The arguments to the first are the count of the number of replacement elements, and the replacement element value. The arguments to the second version are either two iterators or two pointers, specifying a sequence in the way you have already seen.

The `unique()` function will eliminate adjacent duplicate elements from a list, so if you sort the contents first, applying the function ensures that all elements are unique. Here's an example:

```

int data[] = {10, 22, 4, 10, 89, 22, 89, 10};
list<int> numbers(begin(data), end(data));      // 10 22 4 10 89 22 89 10

numbers.sort();                                // 4 10 10 10 22 22 89 89
numbers.unique();                             // 4 10 22 89

```

The result of each operation is shown in the comments.

The `splice()` function allows you to remove all or part of one list and insert it in another. Obviously, both lists must store elements of the same type. Here's the simplest way you could use the `splice()` function:

```

int data[] = {1, 2, 3, 4, 5, 6, 7, 8};
list<int> numbers(data, data+3);                // 1 2 3
list<int> values(data+4, data+8);              // 5 6 7 8
numbers.splice(++begin(numbers), values);        // 1 5 6 7 8 2 3

```

The first argument to the `splice()` function is an iterator specifying where the elements should be inserted, and the second argument is the list that is the source of the elements to be inserted. This operation removes all the elements from the `values` list and inserts them immediately preceding the second element in the `numbers` list.

Here's another version of the `splice()` function that removes elements from a given position in a source list and inserts them at a given position in the destination list:

```

int data[] = {1, 2, 3, 4, 5, 6, 7, 8};
list<int> numbers(data, data+3);                // 1 2 3
list<int> values(data+4, data+8);              // 5 6 7 8
numbers.splice(begin(numbers), values, --end(values)); // 8 1 2 3

```

In this version, the first two arguments to the `splice()` function are the same as the previous version of the function. The third argument is an iterator specifying the position of the first element to be selected from the source list; all elements, from this position to the end, are removed from the source and inserted in the destination list. After executing this code fragment, `values` will contain 5 6 7.

The third version of `splice()` requires four arguments and selects a range of elements from the source list:

```

int data[] = {1, 2, 3, 4, 5, 6, 7, 8};
list<int> numbers(data, data+3);                // 1 2 3
list<int> values(data+4, data+8);              // 5 6 7 8
numbers.splice(++begin(numbers), values, ++begin(values), --end(values));
// 1 6 7 2 3

```

The first three arguments to the version of `splice()` are the same as the previous version, and the last argument is one past the last element to be removed from the source, `values`. After executing this, `values` will contain

5 8

The `merge()` function removes elements from the list that you supply as an argument and inserts them in the list for which the function is called. The function then sorts the contents of the extended

list into ascending order by default, or into some other order determined by a function object or lambda expression that you supply as a second argument to the function. Both lists must be ordered appropriately before you call `merge()`; in other words, the lists must be ordered in the way that you want the final combined list to be ordered. Here's a fragment showing how you might use it:

```
int data[] = {1, 2, 3, 4, 5, 6, 7, 8};  
list<int> numbers(data, data+3);           // 1 2 3  
list<int> values(data+1, data+8);          // 2 3 4 5 6 7 8  
numbers.merge(values);                      // 1 2 2 3 3 4 5 6 7 8
```

This merges the contents of `values` into `numbers`, so `values` will be empty after this operation. The `merge()` function that accepts a single argument orders the result in ascending sequence by default, and because the values in both lists are already ordered, you don't need to sort them. To merge the same lists in descending sequence, the code would be as follows:

```
numbers.sort(greater<int>());           // 3 2 1  
values.sort(greater<int>());             // 8 7 6 5 4 3 2  
numbers.merge(values, greater<int>());    // 8 7 6 5 4 3 3 2 2 1
```

A `greater<int>()` function object specifies that the lists should be sorted in descending sequence and then merged into the same sequence.

The `remove_if()` function removes elements based on the result of applying a unary predicate; I'm sure you'll recall that a unary predicate is a function object that applies to a single argument and returns a `bool` value, `true` or `false`. If the result of applying the predicate to an element is `true`, then the element will be deleted from the list. Typically, you would define your own predicate to do this. This involves defining your own class template for the function object or lambda expression that you want, while the STL defines the `unary_function<T, R>` base template for use when you want to define your own class template. This template just defines types that will be inherited by the derived class that specifies your function object type. The base class template is defined as follows:

```
template<class _Arg, class _Result>  
struct unary_function  
{ // base class for unary functions  
    typedef _Arg argument_type;  
    typedef _Result result_type;  
};
```

This defines `argument_type` and `result_type` as standardized types for use in your definition of the `operator()()` function. You must use this base template if you want to use your predicates with function adapters. You'll see later in this chapter that lambda expressions provide a much easier way to define a predicate.

The way in which you can use the `remove_if()` function is best explained with a specific application, so let's try this in a working example.

TRY IT OUT**Defining a Predicate for Filtering a List**

Here's how you could define a template for a function object based on the helper template from the STL, which you could then use to remove negative values from a list:

```

// function_object.h
// Unary predicate to identify negative values
#pragma once
#include <functional>

template <class T> class is_negative: public std::unary_function<T, bool>
{
public:
    result_type operator()(argument_type& value)
    {
        return value < 0;
    }
};

```

This predicate works with any numeric type. The base template is very useful in that it standardizes the representation of the argument and return types for the predicate, and this is required if you want your function object to be usable with function adapters. Function adapters allow function objects to be used in combination to provide more complex functions. You should be able to see how you could define unary predicates for filtering a list in other ways — selecting even or odd numbers for example, or multiples of a given number, or numbers falling within a given range.

If you are not concerned about the use of your predicate with function adapters, you could define the template very easily without the base class template:

```

// Unary predicate to identify negative values
#pragma once

template <class T> class is_negative
{
public:
    bool operator()(T& value)
    {
        return value < 0;
    }
};

```

You don't need the `#include functional` here because you are not using the base template. This definition is simple, and perhaps easier to understand, but I included the original version just to show how you use the base template. You will want to do this if you intend to use your predicate in a more general context, in particular if you want to use it with function adapters. I'll create the example with the first version, but you can use either version, or perhaps try both.

To make the example more interesting, I'll include function templates for inputting data to a list and for writing out the contents of a list. Here's the program to make use of your predicate:

```

// Ex10_07.cpp
// Using the remove_if() function for a list

#include <iostream>
#include <list>
#include "function_object.h"

using std::cin;

```

```
using std::cout;
using std::endl;
using std::list;

// Template function to list the contents of a list
template <class T>
void listlist(const list<T>& data) {
    for(auto& t : data)
        cout << t << " ";
    cout << endl;
}

// Template function to read data from cin and store it in a list
template<class T>
void loadlist(list<T>& data)
{
    T value = T();
    while(cin >> value , value != T()) //Read non-zero values
        data.emplace_back(std::move(value));
}

int main()
{
    // Process integers
    list<int> numbers;
    cout << "Enter non-zero integers separated by spaces. Enter 0 to end."
        << endl;
    loadlist(numbers);
    cout << "The list contains:" << endl;
    listlist(numbers);
    numbers.remove_if(is_negative<int>());

    cout << "After applying the remove_if() function the list contains:"
        << endl;
    listlist(numbers);

    // Process floating-point values
    list<double> values;
    cout << endl
        << "Enter non-zero float values separated by spaces(some negative!)."
        << "Enter 0 to end." << endl;
    loadlist(values);
    cout << "The list contains:" << endl;
    listlist(values);
    values.remove_if(is_negative<double>());
    cout << "After applying the remove_if() function the list contains:" << endl;
    listlist(values);

    return 0;
}
```

Here's some sample output from this program:

```
Enter non-zero integers separated by spaces. Enter 0 to end.
23 -4 -5 66 67 89 -1 22 34 -34 78 62 -9 99 -19 0
The list contains:
23 -4 -5 66 67 89 -1 22 34 -34 78 62 -9 99 -19
After applying the remove_if() function the list contains:
23 66 67 89 22 34 78 62 99

Enter non-zero values separated by spaces. Enter 0 to end.
2.5 -3.1 5.5 100 -99 -.075 1.075 13 -12.1 13.2 0
The list contains:
2.5 -3.1 5.5 100 -99 -.075 1.075 13 -12.1 13.2
After applying the remove_if() function the list contains:
2.5 5.5 100 1.075 13 13.2
```

How It Works

The output shows that the predicate works for values of types `int` and `double`. The `remove_if()` function applies the predicate to each element in a list in turn, and deletes the elements for which the predicate returns `true`.

The body of the `loadlist<T>()` template function that reads the input is:

```
T value = T();
while(cin >> value, value != T()) //Read non-zero values
    data.emplace_back(std::move(value));
```

The local variable `value` is defined as type `T`, the type parameter for the template, so this will be of whatever type you use to instantiate the function. Because `value` is a template type, you initialize it using the no-arg constructor. The input is read in the `while` loop, and values continue to be read until you enter zero, in which case the last expression in the `while` loop condition will be `false`, thus ending the loop. Using `emplace_back()` with an rvalue reference to `value` moves `value` to the list, rather than copying it.

The body of the `listlist<T>()` function template is also very straightforward:

```
for(auto& t : data)
    cout << t << " ";
cout << endl;
```

Note how you can use `auto`, even in a template. This deduces the type for the `for` loop control variable, `t`, which maps to the type required for the elements in the list container that is passed as the argument. If you wanted to try out the `merge()` function within this example, you could add the following code before the `return` statement in `main()`:

```
// Another list to use in merge
list<double> morevalues;
cout << endl
    << "Enter non-zero float values separated by spaces. Enter 0 to end."
    << endl;
```

```
loadlist(morevalues);
cout << "The list contains:" << endl;
listlist(morevalues);
morevalues.remove_if(is_negative<double>());
cout << "After applying the remove_if() function the list contains:" << endl;
listlist(morevalues);

// Merge the last two lists
values.sort(std::greater<double>());
morevalues.sort(std::greater<double>());
values.merge(morevalues, std::greater<double>());
cout << endl;
listlist(values);
```

Using `forward_list` Containers

The `forward_list` header defines the `forward_list` container template. A `forward_list<T>` container implements a singly linked list of elements of type `T`, where each element contains a pointer to the next element. This means that, unlike a list container, you can only traverse the elements forwards. Like the `list<T>` container, you cannot access an element by its position. The only way to access an element is to traverse the list from the beginning. Because the operations for a `forward_list<T>` container are similar to those for a `list<T>`, I'll just highlight a few of them.

The `front()` member function returns a `const` reference to the first element in the list as long as the list is not empty. You can test whether or not the list is empty using the `empty()` member function, which returns `false` as long as there is at least one element in the list. The `remove()` function removes the element that matches the object you supply as the argument. There's also the `remove_if()` member for which you supply a predicate as an argument, which can be a function object or a lambda expression. All elements for which the predicate is true are removed.

Because it is a singly linked list, a `forward_list<T>` container only has forward iterators. You can use the global `begin()` and `end()` functions with a `forward_list`, and it also has member functions `cbegin()` and `cend()` that return `const` iterators.

You can add an element to a `forward_list` using either `push_front()` or `emplace_front()`. The `emplace_front()` function creates an object from the arguments that you supply and inserts it at the front of the list. The `push_front()` function inserts the object you supply as the argument at the front of the list.

For example:

```
std::forward_list<std::string> words;
string s1("first");
words.push_front(s1);
words.emplace_front("second");
string s2("third");
words.emplace_front(std::move(s2));
words.emplace_front("fourth");
```

After executing this fragment, `words` will contain:

```
fourth third second first
```

You can insert one or more objects after a given position in the list using the `insert_after()` function. There are several versions of this. Here are some examples:

```
int data[] = {1, 2, 4, 5};
std::forward_list<int> datalist;
// std::forward_list<int>::iterator iter;

// Returns an iterator pointing to the inserted element, 11
auto iter = datalist.insert_after(datalist.before_begin(), 11); // 11

// Inserts 3 copies of the 3rd argument after iter and increments iter
iter = datalist.insert_after(iter, 3, 15); // 11 15 15 15

// Insert a range following iter, and increments iter to point to 5
iter = datalist.insert_after(iter, begin(data), end(data)); // 11 15 15 15 1 2 4 5

iter will be of type forward_list<int>::iterator.
```

You can also insert an element after a given position in the list using the `emplace_after()` function. The first argument to `emplace_after()` is an iterator specifying the element after which the new element should be inserted. The second and subsequent arguments are passed to the constructor for the class type of the object to be inserted. For example:

```
words.emplace_after(begin(words), "fifth");
```

After executing this statement with `words` as it was left by the previous fragment adding elements, the list will contain:

```
fourth fifth third second first
```

The function created a `string("fifth")` object and stored it following the position pointed to by the first argument.

A `forward_list<T>` container also has a `before_begin()` function that returns an iterator pointing to the position before the first element. This is for use with the `insert_after()` and `emplace_after()` member functions. For example:

```
words.emplace_after(words.before_begin(), "sixth");
```

After executing this statement, the list will contain:

```
sixth fourth fifth third second first
```

The `string` object that was created was inserted as the first element in the list.

The `forward_list<T>` container provides much better performance than a `list<T>` container. Having only one link to maintain makes it faster in operation and there is no size member keeping

track of the number of elements. If you need to know the number of elements, you can obtain it using the `distance()` function from the `algorithm` header:

```
cout << "Size = " << std::distance(begin(words), end(words)) << endl;
```

The arguments are iterators specifying the first element and one past the last element you want counted.

Using Other Sequence Containers

The remaining sequence containers are implemented through container adapters that I introduced at the beginning of this chapter. I'll discuss each of them briefly and illustrate their operation with examples.

Queue Containers

A `queue<T>` container implements a first-in first-out storage mechanism through an adapter. You can only add to the end of the queue or remove from the front. Here's one way you can create a queue:

```
queue<string> names;
```

This creates a queue storing elements of type `string`. By default, the `queue<T>` adapter class uses a `deque<T>` container as the base, but you can specify a different sequence container as a base, as long as it supports the operations `front()`, `back()`, `push_back()`, and `pop_front()`. These four functions are used to operate the queue. Thus, a queue can be based on a list or a vector container. You specify the alternate container as a second template parameter. Here's how you would create a queue based on a list:

```
queue<string, list<string>> names;
```

The second type parameter to the adapter template specifies the underlying sequence container that is to be used. The queue adapter class acts as a wrapper for the underlying container class and essentially restricts the range of operations you can carry out to those described in the following table.

FUNCTION	DESCRIPTION
<code>back()</code>	Returns a reference to the element at the back of the queue. There are two versions of the function, one returning a <code>const</code> reference and the other returning a non- <code>const</code> reference. If the queue is empty, then the value returned is undefined.
<code>front()</code>	Returns a reference to the element at the front of the queue. There are two versions of the function, one returning a <code>const</code> reference and the other returning a non- <code>const</code> reference. If the queue is empty, then the value returned is undefined.
<code>push()</code>	Adds the element specified by the argument to the back of the queue.

FUNCTION	DESCRIPTION
<code>pop()</code>	Removes the element at the front of the queue.
<code>size()</code>	Returns the number of elements in the queue.
<code>empty()</code>	Returns <code>true</code> if the queue is empty and <code>false</code> otherwise.

Note that there are no functions in the table that make iterators available for a queue container. The only way to access the contents of a queue is via the `back()` or `front()` functions.

TRY IT OUT Using a Queue Container

In this example you read a succession of one or more sayings, store them in a queue, and then retrieve the sayings and output them:

```
// Ex10_08.cpp
// Exercising a queue container

#include <iostream>
#include <queue>
#include <string>

using std::cin;
using std::cout;
using std::endl;
using std::queue;
using std::string;

int main()
{
    queue<string> sayings;
    string saying;
    cout << "Enter one or more sayings. Press Enter to end." << endl;
    while(true)
    {
        getline(cin, saying);
        if(saying.empty())
            break;
        sayings.push(saying);
    }

    cout << "There are " << sayings.size()
        << " sayings in the queue."
        << endl << endl;
    cout << "The sayings that you entered are:" << endl;
    while(!sayings.empty())
    {
        cout << sayings.front() << endl;
        sayings.pop();
    }
}
```

```
    }  
  
    return 0;  
}
```

Here's an example of some output from this program:

```
Enter one or more sayings. Press Enter to end.  
If at first you don't succeed, give up.  
A preposition is something you should never end a sentence with.  
The bigger they are, the harder they hit.  
A rich man is just a poor man with money.  
Wherever you go, there you are.  
Common sense is not so common.
```

There are 6 sayings in the queue.

```
The sayings that you entered are:  
If at first you don't succeed, give up.  
A preposition is something you should never end a sentence with.  
The bigger they are, the harder they hit.  
A rich man is just a poor man with money.  
Wherever you go, there you are.  
Common sense is not so common.
```

How It Works

You first create a queue container that stores string objects:

```
queue<string> sayings;
```

You read sayings from the standard input stream and store them in the queue container in a while loop:

```
while(true)  
{  
    getline(cin, saying);  
    if(saying.empty())  
        break;  
    sayings.push(saying);  
}
```

This version of the `getline()` function reads text from `cin` into the `string` object, `saying`, until a newline character is recognized. Newline is the default input termination character, and when you want to override this, you specify the termination character as the third argument to `getline()`. The loop continues until the `empty()` function for `saying` in the `if` statement returns `true`, which indicates an empty line was entered. When the input in `saying` is not empty, you store it in the `sayings` queue container by calling its `push()` function.

When input is complete, you output the count of the number of sayings that were stored in the queue:

```
cout << "There are " << sayings.size()  
<< " sayings in the queue."  
<< endl << endl;
```

The `size()` function returns the number of elements in the queue.

You list the contents of the queue in another `while` loop:

```
while(!sayings.empty())
{
    cout << sayings.front() << endl;
    sayings.pop();
}
```

The `front()` function returns a reference to the object at the front of the queue, but the object remains in its place. Because you want to access each of the elements in the queue in turn, you have to call the `pop()` function, after listing each element, to remove it from the queue.

The process of listing the elements in the queue also deletes them, so after the loop ends, the queue will be empty. What if you wanted to retain the elements in the queue? Well, one possibility is that you could put each saying back in the queue after you have listed it. Here's how you could do that:

```
for(queue<string>::size_type i = 0 ; i < sayings.size() ; i++)
{
    saying = sayings.front();
    cout << saying << endl;
    sayings.pop();
    sayings.push(saying);
}
```

Here, you make use of the value returned by `size()` to iterate over the number of sayings in the queue. After writing each saying to `cout`, you remove it from the queue by calling `pop()`, and then you return it to the back of the queue by calling `push()`. When the loop ends, the queue will be left in its original state. Of course, if you don't want to remove the elements when you access them, you could always use a different kind of container.

Priority Queue Containers

A `priority_queue<T>` container is a queue that always has the largest or highest priority element at the top. Think of a queue of people arranged from the tallest to the shortest. Here's one way to define a priority queue container:

```
priority_queue<int> numbers;
```

The default criterion for determining the relative priority of elements as you add them to the queue is a standard `less<T>()` function object. You add an element to the priority queue using the `push()` function:

```
numbers.push(99); // Add 99 to the queue
```

When you add an element to the queue, if the queue is not empty the function will use the `less<T>()` predicate to decide where to insert the new object. This will result in elements being ordered in ascending sequence from the back of the queue to the front. You cannot modify elements while they are in a priority queue, as this could invalidate the ordering that has been established.

The complete set of operations for a priority queue is shown in the following table.

FUNCTION	DESCRIPTION
<code>top()</code>	Returns a <code>const</code> reference to the element at the front of the priority queue, which will be the largest or highest priority element in the container. If the priority queue is empty, then the value returned is undefined.
<code>push()</code>	Adds the element specified by the argument to the priority queue at a position determined by the predicate for the container, which by default is <code>less<T></code> .
<code>pop()</code>	Removes the element at the front of the priority queue, which will be the largest or highest priority element in the container.
<code>size()</code>	Returns the number of elements in the priority queue.
<code>empty()</code>	Returns <code>true</code> if the priority queue is empty and <code>false</code> otherwise.

Note that there is a significant difference between the functions available for the priority queue and for the queue container. With a priority queue, you have no access to the element at the back of the queue; only the element at the front is accessible.

By default, the base container for the priority queue adapter class is `vector<T>`. You can specify a different sequence container from the base, and an alternative function object for determining the priority of the elements. Here's how you could do that:

```
priority_queue<int, deque<int>, greater<int>> numbers;
```

This statement defines a priority queue based on a `deque<int>` container, with elements being inserted using a function object of type `greater<int>`. The elements in this priority queue will be in descending sequence, with the smallest element at the top. The three template parameters are the element type, the type of the container to be used as a base, and the type for the predicate to be used for ordering the elements.

You could omit the third template parameter if you want the default predicate to apply, which will be `less<int>` in this case. If you want a different predicate but want to retain the default base container, you must explicitly specify it, like this:

```
priority_queue<int, vector<int>, greater<int>> numbers;
```

This specifies the default base container `vector<int>` and a new predicate type, `greater<int>`, to be used to determine the ordering of elements.

TRY IT OUT Using a Priority Queue Container

In this example you store `Person` objects in the container, with the `Person` class defined this time to hold the names as type `string`:

```
// Person.h
// A class defining a person
#pragma once
#include <iostream>
#include <string>
using std::cout;
using std::endl;
using std::string;

class Person
{
public:
    Person(const string& first, const string& second)

    {
        firstname = first;
        secondname = second;
    }

    // No-arg constructor
    Person() {}

    // Copy constructor
    Person(const Person& p)
    {
        firstname = p.firstname;
        secondname = p.secondname;
    }

    // Less-than operator
    bool operator<(const Person& p) const
    {
        if(secondname < p.secondname ||
           ((secondname == p.secondname) && (firstname < p.firstname)))
            return true;

        return false;
    }

    // Greater-than operator
    bool operator>(const Person& p) const
    {
        return p < *this;
    }

    // Output a person
    void showPerson() const
    {
        cout << firstname << " " << secondname << endl;
    }

private:
    string firstname;
    string secondname;
};
```

Note that the `>` operator is overloaded here. This will make it possible to put objects in a priority queue that is ordered in either ascending or descending sequence.

Here's the program that stores `Person` objects in a priority queue:

```
// Ex10_09.cpp
// Exercising a priority queue container

#include <iostream>
#include <vector>
#include <queue>
#include <functional>
#include "Person.h"

using std::cin;
using std::cout;
using std::endl;
using std::vector;
using std::priority_queue;

int main()
{
    priority_queue<Person, vector<Person>, std::greater<Person>> people;
    string first, second;
    while(true)
    {
        cout << "Enter a first name or press Enter to end: " ;
        getline(cin, first);
        if(first.empty())
            break;

        cout << "Enter a second name: " ;
        getline(cin, second);
        people.push(Person(first, second));
    }

    cout << endl << "There are " << people.size()
        << " people in the queue."
        << endl << endl;

    cout << "The names that you entered are:" << endl;
    while(!people.empty())
    {
        people.top().showPerson();
        people.pop();
    }

    return 0;
}
```

Typical output from this example looks like this:

```
Enter a first name or press Enter to end: Oliver
Enter a second name: Hardy
Enter a first name or press Enter to end: Stan
```

```

Enter a second name: Laurel
Enter a first name or press Enter to end: Harold
Enter a second name: Lloyd
Enter a first name or press Enter to end: Mel
Enter a second name: Gibson
Enter a first name or press Enter to end: Brad
Enter a second name: Pitt
Enter a first name or press Enter to end:

```

There are 5 people in the queue.

The names that you entered are:

```

Mel Gibson
Oliver Hardy
Stan Laurel
Harold Lloyd
Brad Pitt

```

How It Works

The Person class is simpler than in the earlier version because the names are stored as `string` objects, and no dynamic memory allocation is necessary. You no longer need to define the assignment operator, as the default will be fine. Defining the `<` operator function is sufficient to allow `Person` objects to be stored in a default priority queue, and the overloaded `>` operator will permit `Person` objects to be ordered using the `greater<Person>` predicate type.

You define the priority queue in `main()` like this:

```
priority_queue<Person, vector<Person>, std::greater<Person>> people;
```

Because you want to specify the third template type parameter, you must supply all three, even though the base container type is the default. Incidentally, don't confuse the *type argument* you are using in the template instantiation here, `greater<Person>`, with the *object*, `greater<Person>()`, that you might supply as an argument to the `sort()` algorithm.

Of course, the third parameter to the priority queue template that defines the predicate for ordering the objects does not have to be a template type. You could use your own function object type as long as it has a suitable implementation of `operator()()` in the class. For example:

```

// function_object.h
#pragma once
#include <functional>
#include "Person.h"
using std::binary_function;

class PersonComp: binary_function<Person, Person, bool>
{
public:
    result_type operator()(const first_argument_type& p1,
                           const second_argument_type& p2) const
    {
        return p1 > p2;
    }
};

```

For function objects that work with the STL, a binary predicate must implement `operator()()` with two parameters, and if you want the predicate to work with function adapters, your function object type must have an instance of the `binary_function<Arg1Type, Arg2Type, ResultType>` template as a base. Although you will typically make both arguments to a binary predicate of the same type, the base class does not require it, so when it is meaningful, your predicates can apply to arguments of different types.

If you don't want to use your function objects with function adapters, you could define the type as:

```
// function_object.h
#pragma once
#include "Person.h"

class PersonComp
{
public:
    bool operator()(const Person& p1, const Person& p2) const
    {
        return p1 > p2;
    }
};
```

With this function object type, you could define the priority queue object as:

```
priority_queue< Person, vector<Person>, PersonComp> people;
```

You read names from the standard input stream in an indefinite `while` loop:

```
while(true)
{
    cout << "Enter a first name or press Enter to end: " ;
    getline(cin, first);
    if(first.empty())
        break;

    cout << "Enter a second name: " ;
    getline(cin, second);
    people.push(Person(std::move(first), std::move(second)));
}
```

An empty first name will terminate the loop. After reading a second name, you create the `Person` object in the argument expression to the `push()` function that adds the object to the priority queue. It will be inserted at a position determined by a `greater<Person>()` predicate. This will result in the objects being ordered in the priority queue with the smallest at the top. You can see from the output that the names are in ascending sequence based on the second name.

After outputting the number of objects in the queue using the `size()` function, you output the contents of the queue in a `while` loop:

```

while(!people.empty())
{
    people.top().showPerson();
    people.pop();
}

```

The `top()` function returns a reference to the object at the front of the queue, and you use this reference to call the `showPerson()` function to output the name. You then call `pop()` to remove the element at the front of the queue; unless you do this, you can't access the next element.

When the loop ends, the priority queue will be empty. There's no way to access all the elements and retain them in the queue. If you want to keep them, you would have to put them somewhere else — perhaps in another priority queue.

Stack Containers

The `stack<T>` adapter template is defined in the `stack` header and implements a pushdown stack based on a `deque<T>` container by default. A pushdown stack is a last-in first-out storage mechanism where only the object that was added most recently to the stack is accessible.

Here's how you can define a stack:

```
stack<Person> people;
```

This defines a stack to store `Person` objects.

The base container can be any sequence container that supports the operations `back()`, `push_back()`, and `pop_back()`. You could define a stack based on a list like this:

```
stack<string, list<string>> names;
```

The first template type argument is the element type, as before, and the second is the container type to be used as a base for the stack.

There are only five operations available with a `stack<T>` container, and they are shown in the following table.

FUNCTION	DESCRIPTION
<code>top()</code>	Returns a reference to the element at the top of the stack. If the stack is empty, then the value returned is undefined. You can assign the reference returned to a <code>const</code> or non- <code>const</code> reference and if it is assigned to the latter, you can modify the object in the stack.
<code>push()</code>	Adds the element specified by the argument to the top of the stack.
<code>pop()</code>	Removes the element at the top of the stack.
<code>size()</code>	Returns the number of elements in the stack.
<code>empty()</code>	Returns <code>true</code> if the stack is empty and <code>false</code> otherwise.

As with the other containers provided through container adapters, you cannot use iterators to access the contents of a stack.

Let's see a stack working in another example.

TRY IT OUT Using a Stack Container

This example stores `Person` objects in a stack. The `Person` class is the same as in the previous example, so I won't repeat the code here.

```
// Ex10_10.cpp
// Exercising a stack container

#include <iostream>
#include <stack>
#include <list>
#include "Person.h"

using std::cin;
using std::cout;
using std::endl;
using std::stack;
using std::list;

int main()
{
    stack<Person, list<Person>> people;

    string first, second;
    while(true)
    {
        cout << "Enter a first name or press Enter to end: " ;
        getline(cin, first);
        if(first.empty())
            break;

        cout << "Enter a second name: " ;
        getline(cin, second);
        people.push(Person(first, second));
    }

    cout << endl << "There are " << people.size()
        << " people in the stack."
        << endl << endl;
    cout << "The names that you entered are:" << endl;
    while(!people.empty())
    {
        people.top().showPerson();
        people.pop();
    }

    return 0;
}
```

Here is an example of the output:

```
Enter a first name or press Enter to end: Gordon
Enter a second name: Brown
Enter a first name or press Enter to end: Harold
Enter a second name: Wilson
Enter a first name or press Enter to end: Margaret
Enter a second name: Thatcher
Enter a first name or press Enter to end: Winston
Enter a second name: Churchill
Enter a first name or press Enter to end: David
Enter a second name: Lloyd-George
Enter a first name or press Enter to end:
```

There are 5 people in the stack.

The names that you entered are:

```
David Lloyd-George
Winston Churchill
Margaret Thatcher
Harold Wilson
Gordon Brown
```

How It Works

The code in `main()` is more or less the same as in the previous example. Only the container definition is significantly different:

```
stack<Person, list<Person>> people;
```

The `stack` container stores `Person` objects and is based on a `list<T>` container in this instance. You could also use a `vector<T>` container, and if you omit the second type parameter, the `stack` will use a `deque<T>` container as a base.

The output demonstrates that a `stack` is indeed a last-in first-out container, as the order of names in the output is the reverse of the input.

The tuple Class Template

The `tuple<>` class template that is defined in the `tuple` header is a useful adjunct to the `array<>` container, and to other sequence containers such as the `vector<>`. As its name suggests, a `tuple<>` object encapsulates a number of different items of different types. If you were working with fixed records from a file, or possibly from an SQL database, you could use a `vector<>` or an `array<>` container to store `tuple<>` objects that encapsulate the fields in a record. Let's look at a specific example.

Suppose you are working with personnel records that contain an integer employee number, a first name, a second name, and the age of the individual in years. You could define a `tuple<>` instance to encapsulate an employee record like this:

```
typedef std::tuple<int, std::string, std::string, int> Record;
```

A `typedef` is very useful for reducing the verbosity of the type specification in this case. This `typedef` defines the `Record` type as being a `tuple<>` that stores values of type `int`, `string`, `string`, and `int`, corresponding to a person's ID, first name, second name, and age. You could now define an `array<>` container to store `Record` objects:

```
std::array<Record, 5> personnel = { Record(1001, "Joan", "Jetson", 35),
                                     Record(1002, "Jim", "Jones", 26),
                                     Record(1003, "June", "Jello", 31),
                                     Record(1004, "Jack", "Jester", 39)};
```

This defines the `personnel` object, which is an array that can store five `Record` objects. If you wanted flexibility in the number of tuples you were dealing with, you could use a `vector<>` or a `list<>`. Here, you initialize four of the five elements in `personnel` from the initializer list. Here's how you might add a fifth element:

```
personnel[4] = Record(1005, "Jean", "Jorell", 29);
```

This uses the index operator to access the fifth element in the array. You also have the option of creating a `tuple<>` object using the `make_tuple()` function template:

```
personnel[4] = std::make_tuple(1005, "Jean", "Jorell", 29);
```

The `make_tuple()` function creates a `tuple<>` instance that is equivalent to our `Record` type because the deduced type parameters are the same.

To access the fields in a tuple, you use the `get()` template function. The template parameter is the index position of the field you want, indexed from zero. The argument to the function is the tuple that you are accessing. Here's how you could list the records in the `personnel` container:

```
cout << std::setiosflags(std::ios::left);           // Left align output
for (auto& r : personnel)
{
    cout << std::setw(10) << get<0>(r) << std::setw(10) << get<1>(r)
        << std::setw(10) << get<2>(r) << std::setw(10) << get<3>(r)
        << endl;
}
```

This outputs the fields in each tuple in `personnel` on a single line, with the fields left-justified in a field width of 10 characters, so it looks tidy. Note that the type parameter to the `get()` function template must be a compile-time constant. This implies that you cannot use a loop index variable as the type parameter, so you can't iterate over the fields in a loop. It is helpful to define some integer constants that you can use to identify the fields in a tuple in a more readable way. For example, you could define the following constants:

```
const size_t ID(0), firstname(1), secondname(2), age(3);
```

Now you can use these variables as type parameters in `get()` function instantiations making it much clearer which field you are retrieving.

Let's put some of the fragments together into something you can compile and run.

TRY IT OUT **Storing Tuples in an Array**

Here's the code for the example:

```
// Ex10_11.cpp Using an array storing tuple objects
#include <array>
#include <tuple>
#include <string>
#include <iostream>
#include <iomanip>

using std::get;
using std::cout;
using std::endl;
using std::setw;
using std::string;

const size_t maxRecords(100);
typedef std::tuple<int, string, string, int> Record;
typedef std::array<Record, maxRecords> Records;

// Lists the contents of a Records array
void listRecords(const Records& people)
{
    const size_t ID(0), firstname(1), secondname(2), age(3);
    cout << std::setiosflags(std::ios::left);
    Record empty;  for(auto& record : people)  {
        if(record == empty) break;          // In case array is not full
        cout << "ID: " << setw(6) << get<ID>(record)
            << "Name: " << setw(25)
                << (get<firstname>(record) + " " + get<secondname>(record))
            << "Age: " << setw(5) << get<age>(record)
            << endl;
    }
}

int main()
{
    Records personnel = {Record(1001, "Arthur", "Dent", 35),
                        Record(1002, "Mary", "Poppins", 55),
                        Record(1003, "David", "Copperfield", 34),
                        Record(1004, "James", "Bond", 44)};
    personnel[4] = std::make_tuple(1005, "Harry", "Potter", 15);
    personnel.at(5) = Record(1006, "Bertie", "Wooster", 28);

    listRecords(personnel);
    return 0;
}
```

This program produces the following output:

ID: 1001	Name: Arthur Dent	Age: 35
ID: 1002	Name: Mary Poppins	Age: 55
ID: 1003	Name: David Copperfield	Age: 34

ID: 1004	Name: James Bond	Age: 44
ID: 1005	Name: Harry Potter	Age: 15
ID: 1006	Name: Bertie Wooster	Age: 28

How It Works

To make the code easier to read, there are two `typedef` statements:

```
typedef std::tuple<int, string, string, int> Record;
typedef std::array<Record, maxRecords> Records;
```

The first `typedef` statement defines `Record` as equivalent to the `tuple<>` type that stores four fields of type `int`, `string`, `string`, and `int`. The second `typedef` defines `Records` as an `array<>` type, storing `maxRecords` elements of type `Record`. `maxRecords` is defined as a `const` value of type `size_t`. `typedef` statements are a great help in simplifying code that uses the STL.

The `listRecords()` function outputs the elements in a `Records` array:

```
void listRecords(const Records& people)
{
    const size_t ID(0), firstname(1), secondname(2), age(3);
    cout << std::setiosflags(std::ios::left);
    Record empty;  for(auto& record : people)
    {
        if(record == empty) break;           // In case array is not full

        cout << "ID: "   << setw(6)   << get<ID>(record)
            << "Name: " << setw(25)
                << (get<firstname>(record) + " " + get<secondname>(record))
            << "Age: "  << setw(5)   << get<age>(record)
            << endl;
    }
}
```

The first statement in the function body defines constants for accessing the fields in a `Record` tuple. This enables meaningful names to be used, rather than numeric index values whose meaning would not be obvious. The next statement ensures that subsequent output to the output stream will be left-aligned. The range-based `for` loop runs through the elements in the `Records` array that has been passed to the function until an element that is the equivalent of zero is found. Elements that were not explicitly initialized will have been initialized using the no-arg constructor for the element type, `Record`. Fields in the tuple that each array element contains are accessed with the `get<>()` function using the constants that were defined for that purpose. The `setw()` manipulators set the width of the output field for the next item that is written to `cout`.

In `main()` you create the `personnel` array as type `Records` and initialize the first four elements with `Record` objects:

```
Records personnel = {Record(1001, "Arthur", "Dent", 35),
                     Record(1002, "Mary", "Poppins", 55),
                     Record(1003, "David", "Copperfield", 34),
                     Record(1004, "James", "Bond", 44)};
```

This is clearly a much more readable statement because of the `typedef` statements for `Records` and `Record`.

The next statement adds another `Record` to the array:

```
personnel[4] = std::make_tuple(1005, "Harry", "Potter", 15);
```

This uses the `operator[]()` function overload for the `personnel` array to access the element, and uses the `make_tuple()` function to create a tuple that is similar to the tuple of type `Record` to be stored in the array.

Curiously, the next statement uses a different technique to set the value for an array element:

```
personnel.at(5) = Record(1006, "Bertie", "Wooster", 28);
```

This uses the `at()` function for the array, and the argument value of 5 selects the sixth element in the array. Here, the tuple is created using the `Record` type name.

Finally, you call the `listRecords()` function to list the contents of `personnel`. The output shows that everything works as it should.

ASSOCIATIVE CONTAINERS

I'll just discuss some of those available to give you an idea of how they work. The most significant feature of an associative container such as `map<K, T>` is that you can retrieve a particular object without searching. The location of an object of type `T` within an associative container is determined from a key of type `K` that you supply along with the object, so you can retrieve any object rapidly just by supplying the appropriate key. The key is used as a sort key that determines the order of the entries in the map.

For `set<T>` and `multiset<T>` containers, objects act as their own keys. You might be wondering what the use of a container is if, before you can retrieve an object, you have to have the object available. After all, if you already have the object, why would you need to retrieve it? The point of `set` and `multiset` containers is not so much to store objects for later retrieval, but to create an aggregation of objects that you can test to see whether or not a given object is already a member.

I'll concentrate on map containers. The `set` and `multiset` containers are used somewhat less frequently, and their operations are very similar to the `map` and `multimap` containers, so you should have little difficulty using these once you have learned how to apply the map containers.

Using Map Containers

When you create a `map<K, T>` container, `K` is the type of key you will use to store an associated object of type `T`. Key/object pairs are stored as objects of the type `pair<K, T>` that is defined in the `utility` header. The `utility` header is included into the `map` header so the type definition is automatically available. Here's an example of creating a map:

```
map<Person, string> phonebook;
```

This defines an empty map container that stores entries that are key/object pairs, with keys of type `Person` and objects of type `string`.

NOTE Although you use class objects here for both keys and objects to be stored in the map, the keys and associated objects can also be of a fundamental type, such as `int`, or `double`, or `char`.

You can also create a map container that is initialized with a sequence of `pair<K, T>` objects from another container:

```
map<Person, string> phonebook(iterator1, iterator2);
```

`iterator1` and `iterator2` are a pair of iterators defining a series of key/object pairs from another container in the usual way, with `iterator2` specifying a position one past the last pair to be included in the sequence. These iterators can be input iterators although the iterators you obtain from a map are bidirectional. You obtain iterators to access the contents of a map using the `begin()` and `end()` functions, just as you would for a sequence container.

The entries in a map are ordered based on a function object of type `less<Key>` by default, so they will be stored in ascending key sequence. You can change the type function object used for ordering entries in a map by supplying a third template type parameter. For example:

```
map<Person, string, greater<Person>> phonebook;
```

This map stores entries that are `Person/string` pairs, where `Person` is the key with an associated string object. The ordering of entries will be determined by a function object of type `greater<Person>`, so the entries will be in descending key sequence.

Storing Objects

You can define a `pair` object like this:

```
auto entry = pair<Person, string>(Person("Mel", "Gibson"), "213 345 5678");
```

This creates the variable `entry` of type `pair<Person, string>` and initializes it to an object created from a `Person` object and a `string` object. I'm representing a phone number in a very simplistic way, just as a string, but of course it could be a more complicated class identifying the components of the number, such as country code and area code. The `Person` class is the class you used in the previous example.

An instance of the `pair<K, T>` class template defines two constructors, a default constructor that creates an object from the default constructors for type `K` and `T`, and a constructor that defines an object from a key and its associated object. There are also constructor templates for copy constructors and constructors creating an object from rvalue references.

You can access the elements in a `pair` through the members `first` and `second`; thus, in the example, `entry.first` references the `Person` object and `entry.second` references the `string` object.

There is a helper template function, `make_pair()`, defined in the utility header that creates a pair object:

```
auto entry = make_pair(Person("Nell", "Gwynne"), "213 345 5678");
```

The `make_pair()` function automatically deduces the type for the pair, from the argument types you supply.

All of the comparison operators are overloaded for pair objects, so you can compare them with any of the operators `<`, `<=`, `==`, `!=`, `>=`, and `>`.

It's often convenient to use a `typedef` to abbreviate the `pair<K, T>` type you are using in a particular instance. For example:

```
map<Person, string> phonebook;
typedef pair<Person, string> Entry;
```

The first statement defines a map container that will store `string` objects using `Person` objects as keys. The second statement defines `Entry` as the type for the key/object pair. Having defined the `Entry` type, you can create objects of this type. For example:

```
Entry entry1 = Entry(Person("Jack", "Jones"), "213 567 1234");
```

This statement defines a pair of type `pair<Person, string>`, using `Person("Jack", "Jones")` as the `Person` argument and `"213 567 1234"` as the `string` argument.

You can insert one or more pairs in a map using the `insert()` function. For example, here's how you insert a single object:

```
phonebook.insert(entry1);
```

This statement inserts the `entry1` pair into the `phonebook` container, as long as there is no other entry in the map that uses the same key. This version of the `insert()` function returns a value that is also a pair, where the first object in the pair is an iterator and the second is a `bool` value. The `bool` value will be `true` if the insertion was made, and `false` otherwise. The iterator will point to the element if it was stored in the map, or the element that is already in the map for the `entry1` key if the `insert` failed. Therefore, you can check if the object was stored, like this:

```
auto checkpair = phonebook.insert(entry1);
if(checkpair.second)
    cout << "Insertion succeeded." << endl;
else
    cout << "Insertion failed." << endl;
```

The pair that the `insert()` function returns is stored in `checkpair`. The type for `checkpair` is `pair<map<Person, string>::iterator, bool>`, so `auto` is very helpful here. The type corresponds to a pair encapsulating an iterator of type `map<Person, string>::iterator` that you can access as `checkpair.first`; and a value of type `bool` that you access as `checkpair.second`. Dereferencing the iterator in the pair will give you access to the pair that is stored in the map; you can use the

first and second members of that pair to access the key and object, respectively. This can be a little tricky, so let's see what it looks like for `checkpair` in the preceding code:

```
cout << "The key for the entry is:" << endl;
checkpair.first->first.showPerson();
```

The expression `checkpair.first` references the first member of the `checkpair` pair, which is an iterator, so you are accessing a pointer to the entry in the map with this expression. The entry in the map is another pair, so the expression `checkpair.first->first` accesses the first member of that pair, the key, which is the `Person` object. You use this to call the `showPerson()` member to output the name. You could access the pair member that represents the phone number in a similar way, with the expression `checkpair.first->second`.

Another version of the `insert()` function inserts a series of pairs in a map. The pairs are defined by two iterators and the series would typically be from a map, although it could be from another type of container.

A map defines the `operator[]()` function, so you can also use the subscript operator to insert an object. Here's how you could insert the `entry1` object in the `phonebook` map:

```
phonebook[Person("Jack", "Jones")] = "213 567 1234";
```

The subscript value is the key to be used to store the object that appears to the right of the assignment operator. This is perhaps a somewhat more intuitive way to store objects in a map. The disadvantage compared to `insert()` is that you lose the ability to discover whether the key was already in the map.

You can insert a pair that is constructed in place in a map using the `emplace()` function template:

```
Entry him(Person("Jack", "Spratt"), "213 456 7899");
auto checkpair = phonebook.emplace(std::move(him));
```

This creates the pair, `him`, and calls `emplace()` with an rvalue reference to `him` as the argument. The pair that is returned contains an iterator and a `bool` value, with the same significance as the pair returned by the `insert()` function.

Of course, using the `Entry` type definition, you can also write:

```
auto checkpair = phonebook.emplace(Person("Jack", "Spratt"), "213 456 7899");
```

Accessing Objects

You can use the subscript operator to retrieve the object from a map that corresponds to a given key. For example:

```
string number = phonebook[Person("Jack", "Jones")];
```

This stores the object for the key `Person("Jack", "Jones")` in `number`. If the key is not in the map, then a pair entry will be inserted into the map for this key, with the object as the default for

the object type; here, the no-arg `string` constructor will be called to create the object for this key if the entry is not there.

Of course, you may not want a default object inserted when you attempt to retrieve an object corresponding to a given key. In this case, you can use the `find()` function to check whether there's an entry for a given key, and then retrieve it if it's there:

```
string number;
Person key("Jack", "Jones");

auto iter = phonebook.find(key);

if(iter != phonebook.end())
{
    number = iter->second;
    cout << "The number is " << number << endl;
}
else
{
    cout << "No number for the key ";
    key.showPerson();
}
```

The `find()` function returns an iterator of type `map<Person, string>::iterator` that points to the object corresponding to the key if the key is present in the map, or to one past the last entry, which corresponds to the iterator returned by the `end()` function. Thus, if `iter` is not equal to the iterator returned by `end()`, the entry is present so you can access the object through the second member of the pair. If you want to prevent the object in the map from being modified, you could define the iterator type explicitly as `map<Person, string>::const_iterator`.

Calling the `count()` function for a map with a key as the argument will return a count of the number of entries found corresponding to the key. For a map, the value returned can only be 0 or 1, because each key in a map must be unique. A multimap container allows multiple entries for a given key, so in this case other values are possible for the return value from `count()`.

Other Map Operations

The `erase()` function enables you to remove a single entry, or a range of entries, from a map. You have two versions of `erase()` that will remove a single entry. One version requires an iterator as the argument pointing to the entry to be erased, and the other requires a key corresponding to the entry to be erased. For example:

```
Person key("Jack", "Jones");
auto count = phonebook.erase(key);
if(count == 0)
    cout << "Entry was not found." << endl;
```

When you supply a key to `erase()`, it returns a count of the number of entries that were erased. The value returned can only be 0 or 1 for a map. A multimap container can have several entries with the same key, in which case the `erase()` function may return a value greater than 1.

You can also supply an iterator as an argument to `erase()`:

```
Person key("Jack", "Jones");

auto iter = phonebook.find(key);
if(iter != phonebook.end())
    iter = phonebook.erase(iter);
if(iter == phonebook.end())
    cout << "End of the map reached." << endl;
```

In this case, the `erase()` function returns an iterator that points to the entry that remains in the map beyond the entry that was erased, or a pointer to one beyond the end of the map if no such element is present.

The following table shows other operations available with a map:

FUNCTION	DESCRIPTION
<code>begin()</code>	Returns a bidirectional iterator pointing to the first entry in the map.
<code>end()</code>	Returns a bidirectional iterator pointing to one past the last entry in the map.
<code>cbegin()</code>	Returns a const bidirectional iterator pointing to the first entry in the map.
<code>cend()</code>	Returns a const bidirectional iterator pointing to one past the last entry in the map.
<code>rbegin()</code>	Returns a reverse iterator pointing to the last entry in the map.
<code>rend()</code>	Returns a reverse iterator pointing to one before the first entry in the map.
<code>crbegin()</code>	Returns a const reverse iterator pointing to the last entry in the map.
<code>crend()</code>	Returns a const reverse iterator pointing to one before the first entry in the map.
<code>at()</code>	Returns a reference to the data value corresponding to the key you supply as the argument.
<code>lower_bound()</code>	Accepts a key as an argument and returns an iterator pointing to the first entry with a key that is greater than or equal to (the lower bound of) the specified key. If the key is not present, the iterator pointing to one past the last entry will be returned.
<code>upper_bound()</code>	Accepts a key as an argument and returns an iterator pointing to the first entry with a key that is greater than (the upper bound of) the specified key. If the key is not present, the iterator pointing to one past the last entry will be returned.
<code>equal_range()</code>	Accepts a key as an argument and returns a pair containing two iterators. The first pair member points to the lower bound of the specified key, and the second points to the upper bound of the specified key. If the key is not present, both iterators in the pair will point to one past the last entry in the map.

FUNCTION	DESCRIPTION
swap()	Interchanges the entries in the map you pass as the argument, with the entries in the map for which the function is called.
clear()	Erases all entries in the map.
size()	Returns the number of entries in the map.
max_size()	Return the maximum capacity of the map.
empty()	Returns true if the map is empty and false otherwise.

The `lower_bound()`, `upper_bound()`, and `equal_range()` functions are not very useful with a map container. However, they come into their own with a multimap when you want to find all elements with a given key.

Let's see a map in action.

TRY IT OUT Using a Map Container

In this example you use a map to store phone numbers, and provide a mechanism for finding a phone number for a person. You use a variation on the `Person` class:

```
// Person.h
// A class defining a person
#pragma once
#include <string>
using std::string;

class Person
{
public:
    Person(const string& first = "", const string& second = "") :
        firstname(first), secondname(second) {}

    // Move constructor
    Person(string&& first, string&& second) :
        firstname(std::move(first)), secondname(std::move(second)) {}

    // Less-than operator
    bool operator<(const Person& p) const
    {
        return (secondname < p.secondname ||
                ((secondname == p.secondname) && (firstname < p.firstname)));
    }

    // Get the name
    string getName() const
    {
```

```
    return firstname + " " + secondname;
}

private:
    string firstname;
    string secondname;
};
```

The no-arg constructor is defined by providing default values for the constructor arguments. There is a move constructor for rvalue arguments. The new function `getName()` returns the complete name as a string.

The source file containing `main()` and some helper functions looks like this:

```
// Ex10_12.cpp
// Using a map container

#include <iostream>
#include <cstdio>
#include <iomanip>
#include <string>
#include <map>
#include "Person.h"

using std::cin;
using std::cout;
using std::endl;
using std::setw;
using std::ios;
using std::string;

typedef std::map<Person, string> PhoneBook;
typedef std::pair<Person, string> Entry;

// Read a person from cin
Person getPerson()
{
    string first;
    string second;
    cout << "Enter a first name: " ;
    getline(cin, first);
    cout << "Enter a second name: " ;
    getline(cin, second);
    return Person(first, second);
}

// Read a phone book entry from standard input
Entry inputEntry()
{
    Person person = getPerson();

    string number;
    cout << "Enter the phone number for " << person.getName() << ":" ;
    getline(cin, number);
    return std::make_pair(std::move(person), std::move(number));
}
```

```

}

// Add a new entry to a phone book
void addEntry(PhoneBook& book)
{
    Entry entry = inputEntry();
    auto pr = book.insert(std::move(entry));

    if(pr.second)
        cout << "Entry successful." << endl;
    else
    {
        cout << "Entry exists for " << pr.first->first.getName()
            << ". The number is " << pr.first->second << endl;
    }
}

// List the contents of a phone book
void listEntries(const PhoneBook& book)
{
    if(book.empty())
    {
        cout << "The phone book is empty." << endl;
        return;
    }
    cout << setiosflags(ios::left);           // Left justify output
    for(auto& entry : book)
    {
        cout << setw(30) << entry.first.getName()
            << setw(12) << entry.second << endl;
    }
    cout << resetiosflags(ios::right);        // Right justify output
}

// Retrieve an entry from a phone book
void getEntry(const PhoneBook& book)

{
    Person person = getPerson();
    auto iter = book.find(person);
    if(iter == book.end())
        cout << "No entry found for " << person.getName() << endl;
    else
        cout << "The number for " << person.getName()
            << " is " << iter->second << endl;
}

// Delete an entry from a phone book
void deleteEntry(PhoneBook& book)
{
    Person person = getPerson();
    auto iter = book.find(person);
    if(iter == book.end())
        cout << "No entry found for " << person.getName() << endl;
    else
}

```

```
{  
    book.erase(iter);  
    cout << person.getName() << " erased." << endl;  
}  
}  
  
int main()  
{  
    PhoneBook phonebook;  
    char answer = 0;  
  
    while(true)  
    {  
        cout << "Do you want to enter a phone book entry(Y or N): " ;  
        cin >> answer;  
        cin.ignore(); // Ignore newline in buffer  
        if(toupper(answer) == 'N')  
            break;  
        if(toupper(answer) != 'Y')  
        {  
            cout << "Invalid response. Try again." << endl;  
            continue;  
        }  
        addEntry(phonebook);  
    }  
  
    // Query the phonebook  
    while(true)  
    {  
        cout << endl << "Choose from the following options:" << endl  
            << "A Add an entry D Delete an entry G Get an entry" << endl  
            << "L List entries Q Quit" << endl;  
        cin >> answer;  
        cin.ignore(); // Ignore newline in buffer  
  
        switch(toupper(answer))  
        {  
            case 'A':  
                addEntry(phonebook);  
                break;  
            case 'G':  
                getEntry(phonebook);  
                break;  
            case 'D':  
                deleteEntry(phonebook);  
                break;  
            case 'L':  
                listEntries(phonebook);  
                break;  
            case 'Q':  
                return 0;  
            default:  
                cout << "Invalid selection. Try again." << endl;  
                break;  
        }  
    }  
}
```

```
        }
    }
    return 0;
}
```

Here is some output from this program:

```
Do you want to enter a phone book entry(Y or N): y
Enter a first name: Jack
Enter a second name: Bateman
Enter the phone number for Jack Bateman: 312 455 6576
Entry successful.
Do you want to enter a phone book entry(Y or N): y
Enter a first name: Mary
Enter a second name: Jones
Enter the phone number for Mary Jones: 213 443 5671
Entry successful.
Do you want to enter a phone book entry(Y or N): y
Enter a first name: Jane
Enter a second name: Junket
Enter the phone number for Jane Junket: 413 222 8134
Entry successful.
Do you want to enter a phone book entry(Y or N): n

Choose from the following options:
A Add an entry   D Delete an entry   G Get an entry
L List entries   Q Quit
a
Enter a first name: Bill
Enter a second name: Smith
Enter the phone number for Bill Smith: 213 466 7688
Entry successful.

Choose from the following options:
A Add an entry   D Delete an entry   G Get an entry
L List entries   Q Quit
g
Enter a first name: Mary
Enter a second name: Miller
No entry found for Mary Miller

Choose from the following options:
A Add an entry   D Delete an entry   G Get an entry
L List entries   Q Quit
g
Enter a first name: Mary
Enter a second name: Jones
The number for Mary Jones is 213 443 5671

Choose from the following options:
A Add an entry   D Delete an entry   G Get an entry
L List entries   Q Quit
d
Enter a first name: Mary
```

```
Enter a second name: Jones
Mary Jones erased.

Choose from the following options:
A Add an entry  D Delete an entry  G Get an entry
L List entries  Q Quit
L
Jack Bateman      312 455 6576
Jane Junket       413 222 8134
Bill Smith        213 466 7688

Choose from the following options:
A Add an entry  D Delete an entry  G Get an entry
L List entries  Q Quit
q
```

How It Works

You define types for a `PhoneBook` container and its entries like this:

```
typedef std::map<Person, string> PhoneBook;
typedef std::pair<Person, string> Entry;
```

The object in an entry is a `string` containing a phone number, and the key is a `Person` object. These types will make the code easier to read.

You load up the map initially in a `while` loop:

```
while(true)
{
    cout << "Do you want to enter a phone book entry(Y or N): " ;
    cin >> answer;
    cin.ignore();                                // Ignore newline in buffer
    if(toupper(answer) == 'N')
        break;
    if(toupper(answer) != 'Y')
    {
        cout << "Invalid response. Try again." << endl;
        continue;
    }
    addEntry(phonebook);
}
```

You check whether an entry is to be read by reading a character from the input stream. Reading a character from `cin` leaves a newline character in the buffer, and this can cause problems for subsequent input. Calling `ignore()` for `cin` ignores the next character so that subsequent input will work properly. If '`n`' or '`N`' is entered, the loop is terminated. When '`y`' or '`Y`' is entered, an entry is created by calling the helper function `addEntry()` that is coded like this:

```
void addEntry(PhoneBook& book)
{
    Entry entry = inputEntry();
```

```

auto pr = book.insert(std::move(entry));

if(pr.second)
    cout << "Entry successful." << endl;
else
{
    cout << "Entry exists for " << pr.first->first.getName()
        << ". The number is " << pr.first->second << endl;
}
}
}

```

The parameter for `addEntry()` is a reference. The function modifies the container that is passed as the argument, so the function must have access to the original object. In any event, even if read-only access to the container argument was needed, it is important not to allow potentially very large objects, such as a map container, to be passed by value, because copying them can seriously degrade performance.

An entry is created by calling the `inputEntry()` helper function, which makes use of the `getPerson()` function that creates a `Person` object from keyboard input in the way you saw in the previous section. You then call `insert()` for the `phonebook` object, and store the object returned in `pr`. The `pr` object enables you to check that the entry was successfully inserted into the map, by testing its `bool` member. The `pr` variable is of type `pair<map<Person, string>::iterator, bool>`, but the `auto` keyword works that out for you. The first member of `pr` provides access to the entry, whether it's an existing entry or the new entry, and the second is the `bool` value. You use these to output a message when insertion fails.

After initial input is complete, a `while` loop provides the mechanism for querying and modifying the phone book. The `switch` statement decides the action to be taken, based on the character that is entered and stored in `answer`. Querying the phone book is managed by the `getEntry()` function:

```

void getEntry(const PhoneBook& book)
{
    Person person = getPerson();
    auto iter = book.find(person);
    if(iter == book.end())
        cout << "No entry found for " << person.getName() << endl;
    else
        cout << "The number for " << person.getName()
            << " is " << iter->second << endl;
}

```

A `Person` object is created from a name that is read from the keyboard by calling the `getPerson()` function. The `Person` object is then used as the argument to the `find()` function for the map object. This returns an iterator of type `map<Person, string>::const_iterator` that either points to the required entry, or points to one past the last entry in the map. If an entry is found, accessing the `second` member of the pair pointed to by the iterator provides the number corresponding to the `Person` object key.

The `deleteEntry()` function deletes an entry from the map. The process is similar to that used in the `getEntry()` function, the difference being that when an entry is found by the `find()` function, the `erase()` function is called to remove it. You could use another version of `erase()` to do this, in which case the code would be like this:

```

void deleteEntry(PhoneBook& book)
{
    Person person = getPerson();

```

```
if(book.erase(person))
    cout << person.getName() << " erased." << endl;
else
    cout << "No entry found for " << person.getName() << endl;
}
```

The code turns out to be much simpler if you pass the key to the `erase()` function.

The `listEntries()` function lists the contents of a phone book. After an initial check for an empty map, the entries are listed in a range-based `for` loop. The output is left-justified by the `setiosflags` manipulator to produce tidy output. This remains in effect until the `resetiosflags` manipulator is used to restore right-justification.

Using a Multimap Container

A multimap container works very much like the map container, in that it supports the same range of functions — except for the subscript operator, which you cannot use with a multimap. The principle difference between a map and a multimap is that you can have multiple entries with the same key in a multimap, and this affects the way some of the functions behave. Obviously, with the possibility of several keys having the same value, overloading the `operator[]()` function would not make much sense.

The `insert()` function flavors for a multimap are a little different from those for a map. The simplest version accepts a `pair<K,T>` object as an argument and returns an iterator pointing to the entry that was inserted. The equivalent function for a map returns a pair object, because this provides an indication of when the key already exists in the map and the insertion is not possible; of course, this cannot arise with a multimap. A multimap also has a version of `insert()` with two arguments: the second being the pair to be inserted, and the first being an iterator pointing to the position in the multimap from which to start searching for an insertion point. This gives you some control over where a pair will be inserted when the same key already exists. This version of `insert()` also returns an iterator pointing to the element that was inserted. A third version of `insert()` accepts two iterator arguments that specify a range of elements to be inserted from another source.

When you pass a key to the `erase()` function for a multimap, it erases all entries with the same key, and the value returned indicates how many entries were deleted. The significance of having a version of `erase()` available that accepts an iterator as an argument should now be apparent — it allows you to delete a single element. You also have a version of `erase()` that accepts two iterators to delete a range of entries.

The `find()` function can only find the first element with a given key in a multimap. You really need a way to find several elements with the same key and the `lower_bound()`, `upper_bound()`, and `equal_range()` functions provide you with a way to do this. For example, given a `phonebook` object that is of type `multimap<Person, string>`, you could list the phone numbers corresponding to a given key like this:

```
Person person("Jack", "Jones");

auto iter = phonebook.lower_bound(person);
```

```

if(iter == phonebook.end())
    cout << "There are no entries for " << person.getName() << endl;
else
{
    cout << "The following numbers are listed for " << person.getName() << ":" 
    << endl;
    for( ; iter != phonebook.upper_bound(person) ; iter++)
        cout << iter->second << endl;
}

```

It's important to check the iterator returned by `lower_bound()`. If you don't, you could end up referencing an entry one beyond the last entry.

MORE ON ITERATORS

The `iterator` header defines several templates for iterators that transfer data from a source to a destination. *Stream iterators* act as pointers to a stream for input or output, and they enable you to transfer data between a stream and any source or destination that works with iterators, such as an algorithm. *Inserter iterators* can transfer data into a basic sequence container. The `iterator` header defines two stream iterator templates, `istream_iterator<T>` for input streams and `ostream_iterator<T>` for output streams, where `T` is the type of object to be extracted from, or written to, the stream. The header also defines three inserter templates, `inserter<T>`, `back_inserter<T>`, and `front_inserter<T>`, where `T` is the type of sequence container in which data is to be inserted.

Let's explore some of these iterators in a little more depth.

Using Input Stream Iterators

Here's an example of how you create an input stream iterator:

```
istream_iterator<int> numbersInput(cin);
```

This creates the iterator `numbersInput` of type `istream_iterator<int>` that can point to objects of type `int` in a stream. The argument to the constructor specifies the stream to which the iterator relates, so this is an iterator that can read integers from `cin`, the standard input stream.

The default `istream_iterator<T>` constructor creates an end-of-stream iterator, which will be equivalent to the `end` iterator for a container that you have been obtaining by calling the `end()` function. Here's how you could create an end-of-stream iterator, complementing the `numbersInput` iterator:

```
istream_iterator<int> numbersEnd;
```

Now you have a pair of iterators that defines a sequence of values of type `int` from `cin`. You could use these to load values from `cin` into a `vector<int>` container:

```

vector<int> numbers;
cout << "Enter integers separated by spaces then a letter to end:" << endl;
istream_iterator<int> numbersInput(cin), numbersEnd;
while(numbersInput != numbersEnd)
    numbers.push_back(*numbersInput++);

```

After defining the vector container to hold values of type `int`, you create two input stream iterators: `numbersInput` is an input stream iterator reading values of type `int` from `cin`, and `numbersEnd` is an end-of-stream iterator. The `while` loop continues as long as `numbersInput` is not equal to the end-of-stream iterator, `numbersEnd`. When you execute this fragment, input continues until end-of-stream is recognized for `cin`. But what produces that condition? The end-of-stream condition will arise if you enter `Ctrl+Z` to close the input stream, or if you enter an invalid character such as a letter.

Of course, you are not limited to using input stream iterators as loop control variables. You can use them to pass data to an algorithm, such as `accumulate()`, which is defined in the `numeric` header:

```
cout << "Enter integers separated by spaces then a letter to end:" << endl;
istream_iterator<int> numbersInput(cin), numbersEnd;
cout << "The sum of the input values that you entered is "
    << accumulate(numbersInput, numbersEnd, 0) << endl;
```

This fragment outputs the sum of however many integers you enter. You will recall that the arguments to `accumulate()` are an iterator pointing to the first value in the sequence, an iterator pointing to one past the last value, and the initial value for the sum. Here, you are transferring data directly from `cin` to the algorithm.

The `sstream` header defines the `basic_istringstream<T>` template that defines an object type that can access data from a stream buffer such as a `string` object. The header also defines the `istringstream` type as `basic_istringstream<char>`, which will be a stream of characters of type `char`. You can construct an `istringstream` object from a `string` object, which means you can read data from the `string` object, just as you read from `cin`. Because an `istringstream` object is a stream, you can pass it to an input iterator constructor and use the iterator to access the data in the underlying stream buffer. Here's an example:

```
string data("2.4 2.5 3.6 2.1 6.7 6.8 94 95 1.1 1.4 32");
istringstream input(data);
istream_iterator<double> begin(input), end;
cout << "The sum of the values from the data string is "
    << accumulate(begin, end, 0.0) << endl;
```

You create the `istringstream` object, `input`, from the `string` object, `data`, so you can read from `data` as a stream. You create two stream iterators that can access `double` values in the `input` stream, and you use these to pass the contents of the `data` stream to the `accumulate()` algorithm. Note that the type of the third argument to the `accumulate()` function determines the type of the result, so you must specify this as a value of type `double` to get the sum produced correctly. Let's try an example.

TRY IT OUT Using an Input Stream Iterator

This example uses a stream iterator to read text from the standard input stream and transfer it to a map container to produce a word count for the text. Here's the code:

```
// Ex10_13.cpp
// A simple word collocation
#include <iostream>
```

```

#include <iomanip>
#include <string>
#include <map>
#include <iterator>
using std::cout;
using std::cin;
using std::endl;
using std::string;

int main()
{
    std::map<string, int> words;           // Map to store words and word counts
    cout << "Enter some text and press Enter followed by Ctrl+Z then Enter to end:"
        << endl << endl;

    std::istream_iterator<string> begin(cin); // Stream iterator
    std::istream_iterator<string> end;         // End stream iterator

    while(begin != end)                      // Iterate over words in the stream
        words[*begin++]++;                  // Increment and store a word count

    // Output the words and their counts
    cout << endl << "Here are the word counts for the text you entered:" << endl;
    const int wordsPerLine(4);
    int wordCount(0);
    cout << std::setiosflags(std::ios::left); // Ouput left-justified
    for (auto& word : words)

    {
        cout << std::setw(15) << word.first << " " << std::setw(5) << word.second;
        if(++wordCount % wordsPerLine == 0) cout << endl;
    }
    cout << endl;

    return 0;
}

```

Here's an example of some output from this program:

Enter some text and press Enter followed by Ctrl+Z then Enter to end:

Peter Piper picked a peck of pickled pepper
A peck of pickled pepper Peter Piper picked
If Peter Piper picked a peck of pickled pepper
Where's the peck of pickled pepper Peter Piper picked
^Z

Here are the word counts for the text you entered:

A	1	If	1	Peter	4	Piper	4
Where's	1	a	2	of	4	peck	4
pepper	4	picked	4	pickled	4	the	1

How It Works

You first define a map container to store the words and their counts:

```
std::map<string, int> words;           // Map to store words and word counts
```

This container stores each word count of type `int`, using the word of type `string` as the key. This will make it easy to accumulate the count for each word when you read from the input stream using stream iterators:

```
std::istream_iterator<string> begin(cin); // Stream iterator
std::istream_iterator<string> end;         // End stream iterator
```

The `begin` iterator is a stream iterator for the standard input stream, and `end` is an end-of-stream iterator.

You read the words and accumulate the counts in a loop:

```
while(begin != end)           // Iterate over words in the stream
    words[*begin++]++;        // Increment and store a word count
```

This simple `while` loop does a great deal of work. The loop control expression will iterate over the words entered via the standard input stream until the end-of-stream state is reached. The stream iterator reads words from `cin` delimited by whitespace, just like the overloaded `>>` operator for `cin`. You use the subscript operator for the map to store a count with the word as the key; remember, the argument to the subscript operator for a map is the key. The expression `*begin` accesses a word, and the expression `*begin++` increments the iterator after accessing the word.

The first time a word is read, it will not be in the map, so the expression `words[*begin++]` will store a new entry with the count having the default value 0, and increment the `begin` iterator to the next word, ready for the next loop iteration. The whole expression `words[*begin++]++` will increment the count for the entry, regardless of whether it is a new entry or not. Thus, an existing entry will just get its count incremented, whereas a new entry will be created and then its count incremented from 0 to 1.

Finally, you output the count for each word in a `for` loop:

```
for (auto& word : words)
{
    cout << std::setw(15) << word.first << " " << std::setw(5) << word.second;
    if(++wordCount % wordsPerLine == 0) cout << endl;
}
```

Using Inserter Iterators

An inserter iterator can add new elements to the sequence containers `vector<T>`, `deque<T>`, and `list<T>`. There are three templates that create inserter iterators defined in the `iterator` header:

- `back_insert_iterator<T>` — Inserts elements at the end of a container of type `T`. The container must provide the `push_back()` function for this to work.
- `front_insert_iterator<T>` — Inserts elements at the beginning of a container of type `T`. This depends on `push_front()` being available for the container.
- `insert_iterator<T>` — Inserts elements starting at a specified position within a container of type `T`. The container must have an `insert()` function that accepts an iterator as the first argument, and an item to be inserted as the second argument.

The constructors for the first two inserter iterator types expect a single argument specifying the container. For example:

```
list<int> numbers;
front_insert_iterator<list<int>> iter(numbers);
```

Here, you create an iterator that can insert data at the beginning of the `list<int>` container `numbers`.

Inserting a value into the container is very simple:

```
*iter = 99;                                // Insert 99 at the front of the numbers container
```

You could also use `front_inserter()` with the `numbers` container, like this:

```
front_inserter(numbers) = 99;
```

This creates a front inserter for the `numbers` list and uses it to insert 99 at the beginning of the list. The argument to the `front_inserter()` function is the container to which the iterator is to be applied.

The constructor for an `insert_iterator<T>` iterator requires two arguments:

```
vector<int> values;
insert_iterator<vector<int>> iter_anywhere(values, begin(values));
```

The second argument is an iterator specifying where data is to be inserted — the start of the sequence in this instance. You can use this iterator in exactly the same way as the previous one. Here's how you could insert a series of values into the vector using this iterator:

```
for(int i = 0 ; i<100 ; i++)
    *iter_anywhere = i + 1;
```

This loop inserts the values from 1 to 100 in the `values` container at the beginning. After executing this, the first 100 elements will be 1, 2, and so on, through to 100.

You could also use the `inserter()` function to insert the elements in reverse order:

```
for(int i = 0 ; i<100 ; i++)
    inserter(values, begin(values)) = i + 1;
```

The first argument to `inserter()` is the container, and the second is an iterator identifying the position where data is to be inserted. The values will be in reverse order from 100 down to 1.

The inserter iterators can be used in conjunction with the `copy()` algorithm in a particularly useful way. Here's how you could read values from `cin` and transfer them to a `list<T>` container:

```
list<double> values;
cout << "Enter a series of values separated by spaces"
     << " followed by Ctrl+Z or a letter to end:" << endl;
istream_iterator<double> input(cin), input_end;
copy(input, input_end, back_inserter<list<double>>(values));
```

You first create a list container that stores double values. After a prompt for input, you create two input stream iterators for `double` values. The first iterator points to `cin`, and the second is an end-of-stream iterator created by the default constructor. You specify the input to the `copy()` function with the two iterators; the destination for the copy operation is a back inserter iterator that you create in the third argument to the `copy()` function. The back inserter iterator adds the data transferred by the `copy` operation to the list container, `values`. This is quite powerful stuff. If you ignore the prompt, in two statements you read an arbitrary number of values from the standard input stream and transfer them to a list container.

Using Output Stream Iterators

Complementing the input stream iterator template, the `ostream_iterator<T>` template provides output stream iterators for writing objects of type `T` to an output stream. There are two constructors for output stream iterators. One creates an iterator that transfers data to the destination stream:

```
std::ostream_iterator<int> out(cout);
```

The template type argument, `int`, specifies the type of data to be handled, while the constructor argument, `cout`, specifies the stream that will be the destination for data, so the `out` iterator can write values of type `int` to the standard output stream. Here's how you might use this iterator:

```
int data[] = {1, 2, 3, 4, 5, 6, 7, 8, 9};
std::copy(begin(data), end(data), out);
// Contents 1 2 3 4 5 6 7 8 9
copy(begin(numbers), end(numbers), out);
```

The `copy()` algorithm that is defined in the `algorithm` header copies the sequence of objects specified by the first two iterator arguments to the output iterator specified by the third argument. Here, the function copies the elements from the `data` array to the `out` iterator, which will write the elements to `cout`. The result of executing this fragment will be:

```
123456789
```

As you can see, the values are written to the output stream with no spaces in between. The second constructor can improve on this:

```
std::ostream_iterator<int> out(cout, " ", ");
```

The second argument is a string to be used as a delimiter for output values. If you use this iterator as the third argument to the `copy()` function in the previous fragment, the output will be:

```
1, 2, 3, 4, 5, 6, 7, 8, 9,
```

The delimiter string that you specify as a second constructor argument is written to the stream following each value.

Let's see how an output stream iterator works in practice.

TRY IT OUT Using an Output Stream Iterator

Suppose you want to read a series of integer values from `cin` and store them in a vector. You then want to output the values and their sum. Here's how you could do this with the STL:

```
// Ex10_14.cpp
// Using stream and inserter iterators
#include <iostream>
#include <numeric>
#include <vector>
#include <iterator>
using std::cout;
using std::cin;
using std::endl;
using std::vector;

int main()
{
    vector<int> numbers;
    cout << "Enter a series of integers separated by spaces"
        << " followed by Ctrl+Z or a letter:" << endl;

    std::istream_iterator<int> input(cin), input_end;
    std::ostream_iterator<int> out(cout, " ");

    copy(input, input_end, std::back_inserter<vector<int>>(numbers));

    cout << "You entered the following values:" << endl;
    copy(begin(numbers), end(numbers), out);

    cout << endl << "The sum of these values is "
        << std::accumulate(begin(numbers), end(numbers), 0) << endl;
    return 0;
}
```

Here's an example of some output:

```
Enter a series of integers separated by spaces followed by Ctrl+Z or a letter:
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 ^Z
You entered the following values:
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15
The sum of these values is 120
```

How It Works

After creating the `numbers` vector to store integers and issuing a prompt for input, you create three stream iterators:

```
std::istream_iterator<int> input(cin), input_end;
std::ostream_iterator<int> out(cout, " ");
```

The first statement creates two input stream iterators for reading values of type `int` from the standard input stream, `input` and `input_end`, the latter being an end-of-stream iterator. The second statement creates an output stream iterator for transferring values of type `int` to the standard output stream, with the delimiter of a single space following each output value.

Data is read from `cin` and transferred to the vector container using the `copy()` algorithm:

```
copy(input, input_end, std::back_inserter<vector<int>>(numbers));
```

You specify the source of data by the two input stream iterators, `input` and `input_end`, and the destination for the copy is a back inserter iterator for the `numbers` container. Thus, the `copy` operation will transfer data values from `cin` to the `numbers` container via the back inserter.

You output the values that have been stored in the container using another `copy` operation:

```
copy(begin(numbers), end(numbers), out);
```

Here the source for the `copy` is specified by the `begin` and `end` iterators for the container, and the destination is the output stream iterator, `out`. This operation will therefore write the data from `numbers` to `cout`, with the values separated by a space.

Finally, you calculate the sum of the values in the `numbers` container in the output statement using the `accumulate()` algorithm:

```
cout << endl << "The sum of these values is "
    << std::accumulate(begin(numbers), end(numbers), 0) << endl;
```

You specify the range of values to be summed by the `begin` and `end` iterators for the container, and the initial value for the sum is zero. If you wanted the average rather than the sum, this is easy too, using the statement:

```
cout << "The average is "
    << std::accumulate(begin(numbers), end(numbers), 0)/numbers.size() << endl;
```

MORE ON FUNCTION OBJECTS

The `functional` header defines an extensive set of templates for creating function objects that you can use with algorithms and containers. I won't discuss them in detail, but I'll summarize the most useful ones. The function objects for comparisons are shown in the following table:

FUNCTION OBJECT TEMPLATE	DESCRIPTION
<code>less<T></code>	Creates a binary predicate representing the <code><</code> operation between objects of type <code>T</code> . For example, <code>less<string>()</code> defines a function object for comparing objects of type <code>string</code> .
<code>less_equal<T></code>	Creates a binary predicate representing the <code><=</code> operation between objects of type <code>T</code> . For example, <code>less_equal<double>()</code> defines a function object for comparing objects of type <code>double</code> .
<code>equal_to<T></code>	Creates a binary predicate representing the <code>==</code> operation between objects of type <code>T</code> .
<code>not_equal_to<T></code>	Creates a binary predicate representing the <code>!=</code> operation between objects of type <code>T</code> .
<code>greater_equal<T></code>	Creates a binary predicate representing the <code>>=</code> operation between objects of type <code>T</code> .
<code>greater<T></code>	Creates a binary predicate representing the <code>></code> operation between objects of type <code>T</code> .
<code>not2</code>	Creates a binary predicate that is the negation of a binary predicate of type <code>B</code> . For example, <code>not2(less<int>)</code> creates a binary predicate for comparing objects of type <code>int</code> that returns <code>true</code> if the left operand is not less than the right operand. The template type parameter value <code>B</code> is deduced from the type of the constructor argument.

Here's how you could use the `not2` template to define a binary predicate for use with the `sort()` algorithm:

```
sort(begin(v), end(v), not2(greater<string>()));
```

The argument to the `not2` constructor is `greater<string>()`, which is a call to the constructor for the `greater<string>` class type, so the `sort()` function will sort using “not greater than” as the comparison between objects in the container, `v`.

The functional header also defines function objects for performing arithmetic operations on elements. You would typically use these to apply operations to sequences of numerical values using the `transform()` algorithm that is defined in the `algorithm` header. These function objects are described in the following table.

FUNCTION OBJECT TEMPLATE	DESCRIPTION
<code>plus<T></code>	Calculates the sum of two elements of type T.
<code>minus<T></code>	Calculates the difference between two elements of type T by subtracting the second operand from the first.
<code>multiplies<T></code>	Calculates the product of two elements of type T.
<code>divides<T></code>	Divides the first operand of type T by the second.
<code>modulus<T></code>	Calculates the remainder after dividing the first operand of type T by the second.
<code>negate<T></code>	Returns the negative of the operand of type T.

To make use of these, you need to apply the `transform()` function. I'll explain how this works in the next section.

MORE ON ALGORITHMS

The `algorithm` and `numeric` headers define a large number of algorithms. The algorithms in the `numeric` header are primarily devoted to processing arrays of numerical values, whereas those in the `algorithm` header are more general purpose and provide such things as the ability to search, sort, copy, and merge sequences of objects specified by iterators. There are far too many to discuss in detail in this introductory chapter, so I'll just introduce a few of the most useful algorithms from the `algorithm` header to give you a basic idea of how they can be used.

You have already seen the `sort()` and `copy()` algorithms from the `algorithm` header in action. Let's take a brief look at a few other of the more interesting functions in the `algorithm` header:

The `fill()` algorithm

The `fill()` algorithm is of this form:

```
fill(ForwardIterator begin, ForwardIterator end, const Type& value)
```

This fills the elements specified by the iterators `begin` and `end` with `value`. For example, given a vector `v`, storing values of type `string` containing more than 10 elements, you could write:

```
fill(v.begin(), v.begin() + 10, "invalid");
```

This would set the first 10 elements in `v` to "invalid", the value specified by the last argument to `fill()`.

The `replace()` algorithm

The `replace()` algorithm is of the form:

```
replace(ForwardIterator begin, ForwardIterator end,
       const Type& oldValue, const Type& newValue)
```

This function examines each element in the range specified by `begin` and `end`, and replaces each occurrence of `oldValue` by `newValue`. Given a vector `v` that stores `string` objects, you could replace occurrences of "yes" by "no" with the following statement:

```
replace(v.begin(), v.end(), string("yes"), string("no"));
```

Like all the algorithms that receive an interval defined by a couple of iterators, the `replace()` function will also work with pointers. For example:

```
char str[] = "A nod is as good as a wink to a blind horse.";
replace(str, str+strlen(str), 'o', '*');
cout << str << endl;
```

This will replace every occurrence of 'o' in the null-terminated string `str` by '*', so the result of executing this fragment will be the output:

```
A n*d is as g**d as a wink t* a blind h*rse.
```

The `find()` algorithm

The `find()` algorithm is of the form:

```
find(InputIterator begin, InputIterator end, const Type& value)
```

This searches the sequence specified by the first two arguments for the first occurrence of `value`. For example, given a vector `v` containing values of type `int`, you could write:

```
auto iter = find(begin(v), end(v), 21);
```

By using `iter` as the starting point for a new search, you could use the `find()` algorithm repeatedly to find all occurrences of a given value:

```
auto iter = begin(v);
int value = 21, count = 0;
while((iter = find(iter, end(v), value)) != end(v))
{
    iter++;
    count++;
}
cout << "The vector contains " << count << " occurrences of " << value << endl;
```

This searches the vector `v` for all occurrences of `value`. On the first iteration, the search starts at `begin(v)`. On subsequent iterations, the search starts at one past the previous position that was found. The loop will accumulate the total number of occurrences of `value` in `v`. You could also code it as a `for` loop:

```
for((iter = find(begin(v), end(v), value)); iter != end(v) ;
    (iter = find(iter, end(v), value))+, count++);
```

Now the find operation is in the third loop control expression, and you increment `iter` after the result from `find()` is stored. In my view, the `while` loop is a better solution because it's easier to understand.

The `transform()` algorithm

`transform()` comes in two versions. The first applies an operation specified by a unary function object to a set of elements specified by a pair of iterators, and is of the form:

```
transform(InputIterator begin, InputIterator end,
          OutputIterator result, UnaryFunction f)
```

This applies the unary function `f` to all elements in the range specified by the iterators `begin` and `end`, and stores the results, beginning at the position specified by the `result` iterator. The `result` iterator can be the same as `begin`, in which case the results will replace the original elements. The function returns an iterator that is one past the last result stored. Here's an example:

```
double values[] = { 2.5, -3.5, 4.5, -5.5, 6.5, -7.5};
vector<double> data(values, values + _countof(values));
transform(begin(data), end(data), begin(data), negate<double>());
```

The `transform()` call applies a `negate<double>` function object to all the elements in the vector `data`. The results are stored back in `data` and overwrite the original values so after this operation the vector will contain:

```
-2.5, 3.5, -4.5, 5.5, -6.5, 7.5
```

Because the operation writes the results back to the `data` vector, the `transform()` function will return the iterator `data.end()`.

The second version of `transform()` applies a binary function, with the operands coming from two ranges specified by iterators. The function is of the form:

```
transform(InputIterator1 begin1, InputIterator1 end1, InputIterator2 begin2,
          OutputIterator result, BinaryFunction f)
```

The range specified by `begin1` and `end1` defines the set of left operands for the binary function `f` that is specified by the last argument. The range defining the right operands starts at the position specified by the `begin2` iterator; an `end` iterator does not need to be supplied for this range because there must be the same number of elements as in the range specified by `begin1` and `end1`. The results will be stored in the range, starting at the `result` iterator position. The `result` iterator can be the same as `begin1` if you want the results stored back in that range, but it must not be any other position between `begin1` and `end1`. Here's an example:

```
double values[] = { 2.5, -3.5, 4.5, -5.5, 6.5, -7.5};
vector<double> squares(_countof(values));
transform(begin(values), end(values), begin(values),
          squares.begin(), multiplies<double>());
```

```
ostream_iterator<double> out(cout, " ");
copy(squares.begin(), squares.end(), out);
```

You create `squares` with the same number of elements as `values` to store the results of the `transform()` operation. The `transform()` function uses the `multiplies<double>()` function object to multiply each element of `values` by itself. The results are stored in `squares`. The last two statements use an output stream iterator to list the contents of `squares`, which will be:

```
6.25 12.25 20.25 30.25 42.25 56.25
```

TYPE TRAITS AND STATIC ASSERTIONS

A *static assertion* enables you to detect usage errors at compile time. A static assertion is of the form:

```
static_assert(constant_expression, string_literal);
```

The `constant_expression` should result in a value that is convertible to type `bool`. If the result is `true`, the statement does nothing; if it is `false`, the string literal will be displayed by the compiler. A static assertion has no effect on the compiled code. Note that `static_assert` is a keyword.

The `type_traits` header defines a range of templates that enable you to create compile-time constants that you can use in conjunction with static assertions to cause the compiler to issue customized error messages. I don't have the space to describe the contents of `type_traits` in detail so I'll just give you one example and use type traits in the next section.

The `type_traits` header includes several templates for testing types that are particularly useful when you are defining your own templates. Suppose you define the following template:

```
template<class T>
T average(const std::vector<T>& data)
{
    T sum(0);
    for(auto& value : data)
        sum += value;
    return sum/data.size();
}
```

This template is intended to be used with a vector of values that are of an arithmetic type. It would be useful to be able to prevent the template from being used with non-arithmetic types — `Person` objects, for example. If this can be caught at compile time, it will prevent a runtime crash from occurring. A `static_assert` in conjunction with the `is_arithmetic<T>` template from `type_traits` will do the trick:

```
template<class T>
T average(const std::vector<T>& data)
{
    static_assert(std::is_arithmetic<T>::value,
                 "Type parameter for average() must be arithmetic.");
```

```
T sum(0);
for(auto& value : data)
    sum += value;
return sum/data.size();
}
```

The `value` member of the `is_arithmetic<T>` template will be `true` if `T` is an arithmetic type and `false` otherwise. If it is `false` during compilation; that is, when the compiler processes the `average<T>()` template used with a non-arithmetic type, the error message will be displayed. An arithmetic type is a floating-point type or an integral type.

Other type testing templates include `is_integral<T>`, `is_signed<T>`, `is_unsigned<T>`, `is_floating_point<T>`, and `is_enum<T>`. There are many other useful templates in the `type_traits` header so it is well worth exploring the contents further.

LAMBDA EXPRESSIONS

A *lambda expression* provides you with an alternative programming mechanism to function objects. Lambda expressions are a C++ language feature and not specific to STL but they can be applied extensively in this context, which is why I chose to discuss them here. A lambda expression defines a function object without a name, and without the need for an explicit class definition. You would typically use a lambda expression as the means of passing a function as an argument to another function. A lambda expression is much easier to use and understand, and requires less code than defining and creating a function object. Of course, it is not a replacement for function objects in general.

Let's consider an example. Suppose you want to calculate the cubes (x^3) of the elements in a vector containing numerical values. You could use the `transform()` operation for this, except that there is no function object to calculate cubes. You can easily create a lambda expression to do it, though:

```
double values[] = { 2.5, -3.5, 4.5, -5.5, 6.5, -7.5};
vector<double> cubes(_countof(values));
transform(begin(values), end(values), begin(cubes),
    [] (double x){ return x*x*x; } );
```

The last statement uses `transform()` to calculate the cubes of the elements in the array, `values`, and store the result in the vector `cubes`. The lambda expression is the last argument to the `transform()` function:

```
    [] (double x){ return x*x*x; }
```

The opening square brackets are called the *lambda introducer*, because they mark the beginning of the lambda expression. There's a bit more to this, so I'll come back to it a little later in this chapter.

The lambda introducer is followed by the *lambda parameter list* between parentheses, just like a normal function. In this case, there's just a single parameter, `x`. There are restrictions on the lambda parameter list, compared to a regular function: You cannot specify default values for the parameters and the parameter list cannot be of a variable length.

Finally, you have the body of the lambda expression between braces, again just like a normal function. In this case the body is just a single `return` statement, but in general, it can consist of as many statements as you like, just like a normal function. I'm sure you have noticed that there is no return type specification. When the body of the lambda expression is a single return statement that returns a value in the body, the return type defaults to that of the value returned. Otherwise, the default return type is `void`. Of course, you can specify the return type. To specify the return type you would write the lambda expression like this:

```
[ ](double x)->double { return x*x*x; }
```

The type `double` following the arrow specifies the return type.

If you wanted to output the values calculated, you could do so in the lambda expression:

```
[ ](double x)->double {
    double result(x*x*x);
    std::cout << result << " ";
    return result;
}
```

This extends the body of the lambda to provide for writing the value that is calculated to the standard output stream. In this case, the return type must be specified because the default return type would be `void`.

The Capture Clause

The lambda introducer can contain a *capture clause* that determines how the body of the lambda can access variables in the enclosing scope. In the previous section, the lambda expression had nothing between the square brackets, indicating that no variables in the enclosing scope can be accessed within the body of the lambda. A lambda that does not access anything from the enclosing scope is called a *stateless lambda*.

The first possibility is to specify a *default capture clause* that applies to all variables in the enclosing scope. You have two options for this. If you place `=` between the square brackets, the body has access to all automatic variables in the enclosing scope by value — that is, the values of the variables are made available within the lambda expression, but the original variables cannot be changed. On the other hand, if you put `&` between the square brackets, all the variables in the enclosing scope are accessible by reference, and therefore can be changed by the code in the body of the lambda. Look at this code fragment:

```
double factor = 5.0;
double values[] = { 2.5, -3.5, 4.5, -5.5, 6.5, -7.5 };
vector<double> cubes(_countof(values));
transform(begin(values), end(values), begin(cubes),
         [=](double x){ return factor*x*x*x; } );
```

In this fragment, the `=` capture clause allows all the variables in scope to be accessible by value from within the body of the lambda. Note that this is not quite the same as passing arguments by value.

The value of the variable `factor` is available within the lambda, but you cannot update the copy of `factor` because it is effectively `const`. The following statement will not compile, for example:

```
transform(begin(values), end(values), cubes.begin(),
         [=](double x)-> double{ factor += 10.0;           // Not allowed!
                                         return factor*x*x*x; } );
```

If you want to modify the temporary copy of a variable in scope from within the lambda, adding the `mutable` keyword will enable this:

```
transform(begin(values), end(values), cubes.begin(),
         [=](double x)mutable -> double{ factor += 10.0;           // OK
                                         return factor*x*x*x; } );
```

Now you can modify the copy of any variable within the enclosing scope without changing the original variable. After executing this statement, the value of `factor` will still be `5.0`. The lambda remembers the local value of `factor` from one call to the next, so for the first element `factor` will be $5 + 10 = 15$, for the second element it will be $15 + 10 = 25$, and so on.

If you do want to change the original value of `factor` from within the lambda, just use `&` as the capture clause:

```
transform(begin(values), end(values), cubes.begin(),
         [&](double x)->double{ factor += 10.0;           // Changes original variable
                                         return factor*x*x*x; } );
cout << "factor = " << factor << endl;
```

You don't need the `mutable` keyword here. All variables within the enclosing scope are available by reference, so you can use and alter their values. The result of executing this will be that `factor` has the value `65`. If you thought it was going to be `15.0`, remember that the lambda expression executes once for each element in `data`, and the cubes of the elements will be multiplied by successive values of `factor` from `15.0` to `65.0`.

Capturing Specific Variables

There may be circumstances where you want to be more selective about how a lambda expression accesses variables in the enclosing scope. In this case, you can explicitly identify the variables to be accessed. You could rewrite the previous `transform()` statement as:

```
transform(begin(values), end(values), cubes.begin(),
         [&factor](double x)->double{ factor += 10.0;           // Changes original variable
                                         return factor*x*x*x; } );
```

Now, `factor` is the only variable from the enclosing scope that is accessible, and it is available by reference. If you omit the `&`, `factor` would be available by value and not updatable. If you want to identify several variables in the capture clause, just separate them with commas. You could include `=` in the capture clause list, as well as explicit variable names. For example, with the capture clause `[=, &factor]` the lambda would have access to `factor` by reference and all other variables in the enclosing scope by value. Conversely, putting `[&, factor]` as the capture clause would capture

factor by value and all other variables by reference. Note that in a function member of a class, you can include the `this` pointer in the capture clause for a lambda expression, which allows access to the other functions and data members that belong to the class.

A lambda expression can also include a `throw()` exception specification that indicates that the lambda does not throw exceptions. Here's an example:

```
transform(begin(values), end(values), cubes.begin(),
    [&factor](double x)throw() ->double{ factor += 10.0;
        return factor*x*x*x; } );
```

If you want to include the `mutable` specification, as well as the `throw()` specification, the `mutable` keyword must precede `throw()` and must be separated from it by one or more spaces.

Templates and Lambda Expressions

You can use a lambda expression inside a template. Here's an example of a function template that uses a lambda expression:

```
template <class T>
T average(const vector<T>& vec)
{
    static_assert(std::is_arithmetic<T>::value,
                 "Type parameter for average() must be arithmetic.");
    T sum(0);
    std::for_each(vec.begin(), vec.end(),
                  [&sum](const T& value){ sum += value; });
    return sum/vec.size();
}
```

This template generates functions for calculating the average of a set of numerical values stored in a vector. The `algorithm` header defines `for_each()`. The lambda expression uses the template type parameter in the lambda parameter specification, and accumulates the sum of all the elements in a vector. The `sum` variable is accessed from the lambda by reference, so it is able to accumulate the sum there. The last line of the function returns the average, which is calculated by dividing `sum` by the number of elements in the vector. Let's try an example.

TRY IT OUT Using Lambda Expressions

This example shows the use of a variety of lambda expressions:

```
// Ex10_15.cpp Using lambda expressions
#include <algorithm>
#include <iostream>
#include <iomanip>
#include <vector>
#include <ctime>
#include <cstdlib>
using namespace std; // Just to avoid a lot of using directives in the example...

// Template function to return the average of the elements in a vector
```

```
template <class T> T average(const vector<T>& vec)
{
    static_assert(std::is_arithmetic<T>::value,
                 "Type parameter for average() must be arithmetic.");
    T sum(0);
    for_each(vec.begin(), vec.end(),
             [&sum](const T& value){ sum += value; });
    return sum/vec.size();
}

// Template function to set a vector to values beginning with start
// and incremented by increment
template <class T> void setValues(vector<T>& vec, T start, T increment)
{
    static_assert(std::is_arithmetic<T>::value,
                 "Type parameter for setValues() must be arithmetic.");
    T current(start);
    generate(begin(vec), end(vec),
             [increment, &current]()>T{ T result(current);
                                         current += increment;
                                         return result; });
}

// Template function to set a vector to random values between min and max
template<class T> void randomValues(vector<T>& vec, T min, T max)
{
    static_assert(std::is_arithmetic<T>::value,
                 "Type parameter for randomValues() must be arithmetic.");
    srand(static_cast<unsigned int>(time(0))); // Initialize random
                                                // number generator
    generate(begin(vec), end(vec),
             [=](){ return static_cast<T>(static_cast<double>(rand())/
                                         RAND_MAX*(max-min)+ min); });
}

// Template function to list the values in a vector
template<class T> void listVector(const vector<T>& vec)
{
    int count = 0; // Used to control outputs per line
    const int valuesPerLine(5);
    for_each(begin(vec), end(vec),
             [&count, valuesPerLine](const T& n)>void{
                                         cout << setw(10) << n << " ";
                                         if(++count % valuesPerLine == 0)
                                             cout << endl; });
}

int main()
{
    vector<int> integerData(50);
    randomValues(integerData, 1, 10); // Set random integer values
    cout << "Vector contains:" << endl;
    listVector(integerData);
```

```

cout << "Average value is " << average(integerData) << endl;

vector<double> realData(20);
setValues(realData, 5.0, 2.5); // Set real values starting at 5.0
cout << "Vector contains:" << endl;
listVector(realData);
cout << "Average value is " << average(realData) << endl;

return 0;
}

```

This example produces output similar to the following:

```

Vector contains:
    1      7      7      6      6
    6      1      5      7      1
    2      9      5      5      1
    6      7      3      2      1
    1      8      7      7      9
    3      9      9      6      3
    9      4      2      3      5
    5      1      2      5      5
    3      2      7      3      7
    6      3      5      2      3
Average value is 4
Vector contains:
    5      7.5     10     12.5     15
   17.5     20     22.5     25     27.5
    30     32.5     35     37.5     40
   42.5     45     47.5     50     52.5
Average value is 28.75

```

Where the example uses random number generation, the values are likely to be different.

How It Works

There are four function templates that use lambda expressions in the implementation of the functions that operate on vectors. The first template function, `average()`, calculates the average value of the elements in a vector by passing the following lambda expression as the last argument to the `for_each()` function:

```
[&sum] (const T& value){ sum += value; }
```

The `sum` variable that is declared in the `average()` function is accessed by reference in the lambda to accumulate the sum of all the elements. The parameter to the lambda is `value`, which is of type reference to `T`, so the lambda automatically deals with whatever element type is in the vector. The static assertion ensures that the template type argument is arithmetic.

The next function template is `setValues()`. This sets the elements of a vector in sequence with the first element set to `start`, the next to `start+increment`, the next to `start+2*increment`, and so on. Thus, the function will set the vector elements to any set of equispaced values. The function calls the `generate()` function that is defined in the `algorithm` header. This function sets a sequence of

elements, defined by the first two iterator arguments, to the value returned by the function object you specify as the third argument. In this case, the third argument is the lambda expression:

```
[increment, &current] ()->T{  
    T result(current);  
    current += increment;  
    return result;}
```

The lambda accepts no arguments, but it accesses `increment` by value and `current` by reference, the latter being used to store the next value to be set. This lambda has the side effect that `current` will be updated when `generate` is finished. The following lambda expression is similar, but without the side effect:

```
[=] ()mutable->T{  
    T result(current);  
    current += increment;  
    return result;}
```

The third function template is `randomValues()`, which stores random values of the appropriate type in the elements of a vector. The values will be in the range from `min` to `max`, the second and third arguments to the function.

The second statement in the function is:

```
rand(static_cast<unsigned int>(time(0))); // Initialize random number generator
```

This calls the `rand()` function that is defined in the `cstdlib` header. This initializes the sequence of random numbers generated by the `rand()` function, also defined in `cstdlib`. The argument to `rand()` is an unsigned integer value that is the seed for the random number generator. The same seed will always produce the same sequence of random numbers, so here the argument is the current time that is returned by the `time()` function (defined in the `ctime` header). This will always return a different integer each time it is called, so the sequence of random numbers will be different each time the `randomValues()` function is called.

The `randomValues()` function calls the `generate()` function to store values produced by the following lambda expression in the vector:

```
[=] () { return static_cast<T>(static_cast<double>(rand()) /  
    RAND_MAX * (max-min) + min); }
```

All variables within scope are accessible by value, and this includes the `randomValues()` function parameters, `min` and `max`. The `RAND_MAX` constant represents the maximum integer that the `rand()` function can return, so the expression for the value to be returned evaluates to a value in the range `min` to `max`.

The last template function is `listVector()`, which outputs the values of the elements in a vector with the number of values per line specified by `valuesPerLine`. It uses the following lambda expression as the argument to the `for_each()` function to do this:

```
[&count, valuesPerLine](const T& n)->void{  
    cout << setw(10) << n << " ";  
    if(++count % valuesPerLine == 0)  
        cout << endl;}
```

The capture clause captures the `count` variable that is defined in the `listVector()` function by reference, and this is used to record the number of values processed. `valuesPerLine` is captured by value. The parameter is of type `const` reference to `T`, so any element type can be processed. The body of the lambda outputs the value of the current element, `n`, and the `if` statement ensures that after every fifth value, a newline is written to `cout`. The `setw()` manipulator ensures values are presented in the output in a field that is 10 characters wide, so we get nice neat columns of output.

In `main()`, you create a vector storing 50 integers and call `randomValues()` to set the elements to random values between 1 and 10:

```
vector<int> integerData(50);
randomValues(integerData, 1, 10);      // Set random integer values
cout << "Vector contains:" << endl;
listVector(integerData);
cout << "Average value is " << average(integerData) << endl;
```

The call to `listVector()` outputs the values, five to a line, as you see in the output that was produced. The last statement calls the `average()` template function to calculate the average of the values in the vector. In all three template functions, the type is deduced from the `vector<int>` argument that is passed, and this also determines the type in the lambda expression that each function uses.

The next block of code in `main()` is:

```
vector<double> realData(20);
setValues(realData, 5.0, 2.5);    // Set real values starting at 5.0
cout << "Vector contains:" << endl;
listVector(realData);
cout << "Average value is " << average(realData) << endl;
```

This vector stores values of type `double`, and its elements are set using `setValues()`. The output shows that everything works as expected.

Naming a Lambda Expression

You can assign a *stateless lambda* — one that does not reference anything in an external scope — to a variable that is a function pointer, thus giving the lambda a name. You can then use the function pointer to call the lambda as many times as you like. For example:

```
auto sum = [](int a,int b){return a+b; };
```

The function pointer, `sum`, points to the lambda expression, so you can use it as many times as you like:

```
cout << "5 + 10 equals " << sum(5,10) << endl;
cout << "15 + 16 equals " << sum(15,16) << endl;
```

This is quite useful, but there's a much more powerful capability. An extension to the STL functional header defines the `function<>` class template that you can use to define a wrapper for a function object; this includes a lambda expression. The `function<>` template is referred to as a

polymorphic function wrapper because an instance of the template can wrap a variety of function objects with a given parameter list and return type. I won't discuss all the details of the `function<>` class template, but I'll just show how you can use it to wrap a lambda expression. Using the `function<>` template to wrap a lambda expression effectively gives a name to the lambda expression, which not only provides the possibility of recursion within a lambda expression, it also allows you to use the lambda expression in multiple statements or pass it to several different functions. The same function wrapper could also wrap different lambda expressions at different times.

To create a wrapper object from the `function<>` template you need to supply information about the return type, and the types of any parameters, to a lambda expression. Here's how you could create an object of type `function` that can wrap a function object that has one parameter of type `double` and returns a value of type `int`:

```
function<int(double)> f = [](double x) -> int { return static_cast<int>(x*x); };
```

The type specification for the function template is the return type for the function object to be wrapped, followed by its parameter types between parentheses, and separated by commas. Let's try a working example that uses the basic capability that is built into the C++ language as well as the `function<T>` template.

TRY IT OUT Recursion in a Lambda Expression

This example will find the *highest common factor* (HCF) for a pair of integer values. The HCF is the largest number that will divide exactly into both integers. The HCF is also called the greatest common divisor (GCD). Here's the code:

```
// Ex10_16.cpp Wrapping a lambda expression
#include <iostream>
#include <functional>
using std::function;
using std::cout;
using std::endl;

// Global wrapper for lambda expression computing HCF
function<long long(long long, long long)> hcf =
    [&](long long m, long long n) mutable ->long long{
        if(m < n) return hcf(n,m);
        long long remainder(m%n);
        if(0 == remainder) return n;
        return hcf(n, remainder);};

int main()
{
    // A lambda expression assigned to a function pointer
    // that outputs the highest common factor of the arguments
    auto showHCF = [] (long long a, long long b) {
        cout << "For numbers " << a << " and " << b
            << " the highest common factor is " << hcf(a, b) << endl;
    };
}
```

```

    };

    long long a(17719LL), b(18879LL);
    showHCF(a,b);
    showHCF(103LL*53*17*97, 3LL*29*103);
    showHCF(53LL*941*557*43*29*229, 83LL*89*941*11*17*863*431);

    return 0;
}

```

This produces the output:

```

For numbers 17719 and 18879 the highest common factor is 29
For numbers 9001891 and 8961 the highest common factor is 103
For numbers 7932729108943 and 483489887381237 the highest common factor is 941

```

How It Works

You define a wrapper with the name `hcf` for a lambda expression that calculates the HCF at global scope:

```

function<long long(long long, long long)> hcf =
    [&](long long m, long long n) mutable ->long long{
        if(m < n) return hcf(n,m);
        long long remainder(m%n);
        if(0 == remainder) return n;
        return hcf(n, remainder);};

```

The lambda needs to refer to `hcf` in order to work, and because this is defined outside the scope of the lambda, you cannot use a regular function pointer for `hcf`.

The lambda expression has two parameters of type `long long` and returns a value of type `long long`, so `hcf` is of type:

```
function<long long(long long, long long)>
```

The lambda expression uses Euclid's method for finding the highest common factor for two integer values. This involves dividing the larger number by the smaller number, and if the remainder is zero, the HCF is the smaller number. If the remainder is non-zero, the process continues by dividing the previous smaller number by the remainder, and this is repeated until the remainder is zero.

The code for the lambda expression assumes `m` is the larger of the two numbers that are passed as arguments, so if it isn't, it calls `hcf()` with the arguments reversed. If the first argument is the larger number, the remainder after dividing `m` by `n` is calculated. If the remainder is zero, then `n` is the highest common factor and is returned. If the remainder is not zero, `hcf()` is called with `n` and the remainder.

The first statement in `main()` assigns a stateless lambda to the `showHCF` pointer:

```

auto showHCF = [](long long a, long long b) {
    cout << "For numbers " << a << " and " << b
        << " the highest common factor is " << hcf(a, b) << endl;
};

```

This lambda outputs the values for which the HCF is requested together with the HCF produced using the `hcf` object. The rest of `main()` calls this lambda through the `showHCF` function pointer three times to produce the results that you see. The results show that the lambda pointed to by `hcf` does indeed produce the highest common factor for its arguments.

You can use the `function<>` class template to specify the type for a function parameter. This enables you to define a function with a parameter for which you can supply an argument that can be a function object, a lambda expression, or a normal function pointer.

SUMMARY

This chapter introduced the capabilities of the STL. My objective in this chapter was to introduce enough of the details of the STL to enable you to explore the rest on your own. Even though this is a substantial chapter, I have barely scratched the surface of the STL's capabilities so I would encourage you to explore it further.

EXERCISES

1. Write a program that will read some text from the standard input stream, possibly involving several lines of input, and store the letters from the text in a `list<T>` container. Sort the letters in ascending sequence and output them.
 2. Use a `priority_queue<T>` container to achieve the same result as in Exercise 1.
 3. Modify `Ex10_12.cpp` so that it allows multiple phone numbers to be stored for a given name. The functionality in the program should reflect this: The `getEntry()` function should display all numbers for a given name, and the `deleteEntry()` function should delete a particular person/number combination.
 4. Write a program to implement a phone book capability that will allow a name to be entered to retrieve one or more numbers, or a number to be entered to retrieve a name.
 5. As you know, the Fibonacci series consists of the sequence of integers 0, 1, 1, 2, 3, 5, 8, 13, 21, ... where each integer after the first two is the sum of the two preceding integers (note the series sometimes omits the initial zero). Write a program that uses a lambda expression to initialize a vector of integers with values from the Fibonacci series.
-

► WHAT YOU LEARNED IN THIS CHAPTER

TOPIC	CONCEPT
Standard Template Libraries	The STL includes templates for containers, iterators, algorithms, and function objects.
Containers	A container is a class object for storing and organizing other objects. Sequence containers store objects in a sequence, like an array. Associative containers store elements that are key/object pairs, where the key determines where the pair is stored in the container.
Iterators	Iterators are objects that behave like pointers. Iterators are used in pairs to define a set of objects by a semi-open interval, where the first iterator points to the first object in the series, and the second iterator points to a position one past the last object in the series.
Stream iterators	Stream iterators are iterators that allow you to access or modify the contents of a stream.
Iterator categories	There are four categories of iterators: input and output iterators, forward iterators, bidirectional iterators, and random access iterators. Each successive category of iterator provides more functionality than the previous one; thus, input and output iterators provide the least functionality, and random access iterators provide the most.
Smart pointers	Smart pointers are objects of template class types that encapsulate raw pointers. By using smart pointers instead of raw pointers you can often avoid the need to worry about deleting objects that you have allocated on the heap and thus avoid the risk of memory leaks.
Algorithms	Algorithms are template functions that operate on a sequence of objects specified by a pair of iterators.
Function objects	Function objects are objects of a type that overloads the () operator (by implementing the function <code>operator()</code> in the class). The STL defines a wide range of standard function objects for use with containers and algorithms; you can also write your own classes to define function objects.
Lambda expressions	A lambda expression defines an anonymous function object without the need to explicitly define a class type. You can use a lambda expression as an argument to STL algorithms that expect a function object as an argument.
Stateless lambda expressions	A stateless lambda expression does not refer to any variables in an enclosing scope. You can store a pointer to a stateless lambda expression in a function pointer.
Polymorphic function wrappers	A polymorphic function wrapper is an instance of the <code>function<></code> template that you can use to wrap a function object. You can also use a polymorphic function wrapper to wrap a lambda expression.

11

Windows Programming Concepts

WHAT YOU WILL LEARN IN THIS CHAPTER:

- The basic structure of a window
- The Windows API and how it is used
- Windows messages and how you deal with them
- The notation that is commonly used in Windows programs
- The basic structure of a Windows program
- How you create an elementary program using the Windows API and how it works
- Microsoft Foundation Classes
- The basic elements of an MFC-based program

WROX.COM CODE DOWNLOADS FOR THIS CHAPTER

You can find the wrox.com code downloads for this chapter on the Download Code tab at www.wrox.com/remtitle.cgi?isbn=9781118368084. The code is in the Chapter 11 download and individually named according to the names throughout the chapter.

This chapter will take you on a tour of the basic ideas that are involved in every Windows program in C++. You'll first develop a simple example that uses the Windows operating system API directly. This will enable you to understand how a Windows application works behind the scenes, which will be useful when you are developing applications using the more sophisticated facilities provided by Visual C++. Next you will see what you get when you create a Windows program using the Microsoft Foundation Classes (MFC) that encapsulates Win32 capabilities.

WINDOWS PROGRAMMING BASICS

The Windows API is referred to as *WinAPI* or *Win32*, the latter being a slightly dated term since the availability of 64-bit versions of Windows. When you are developing an application with the Windows API, you are writing code at a relatively low level throughout — all the elements that make up the GUI for your application must be created programmatically by calling operating system functions. With MFC applications you are using a set of standard classes that insulate you from the Windows API and make coding much easier. There's also some help with GUI creation in that you can assemble controls on a dialog form graphically and just program the interactions with the user; however, you are still involved in a lot of coding.

Using the Windows API directly is the most laborious method for developing an application so I won't go into this in detail. However, you will put together a basic Windows API application so you'll have an opportunity to understand the mechanism that all Windows applications use under the covers to work with the operating system. Of course, it also is possible to develop applications in C++ that do not require the Windows operating system, and games sometimes take this approach. Many games use DirectX, which is a Windows specific graphics library. Although this is an interesting topic, it would require a whole book to do it justice, so I won't pursue it further.

Before getting to the examples I'll review the terminology that is used to describe an application window. You have already created a Windows program in Chapter 1 without writing a single line of code yourself, and I'll use the window generated by this example to illustrate the elements that go to make up a window.

Elements of a Window

You will inevitably be familiar with most, if not all, of the principal elements of the user interface to a Windows program. However, I will go through them anyway just to be sure we have a common understanding of what the terms mean. The best way to understand what the elements of a window can be is to look at one. An annotated version of the window displayed by the example that you saw in Chapter 1 is shown in Figure 11-1.




FIGURE 11-1

The example generated two windows. The larger window with the menu and the toolbars is the main application window, or *parent window*, and the smaller window is a *child window* of the parent. The child window can be closed without closing the parent window by double-clicking the title bar icon that is in the upper-left corner of the child window or by clicking the Close button in the upper-right corner of the child window. Closing the parent window automatically closes the child window. This is because the child window is owned by and dependent upon the parent window. In general, a parent window may have a number of child windows, as you'll see.

The most fundamental parts of a typical window are its *border*, the *title bar* that shows the name that you give to the window, the *title bar icon* that appears at the left end of the title bar, and the *client area*, which is the area in the center of the window not used by the title bar or borders. You can get all of these created for free in a Windows program. As you will see, all you have to do is provide some text for the title bar.

The border defines the boundary of a window and may be fixed or resizable. If the border is resizable, you can drag it to alter the size of the window. The window also may possess a size grip, which you can use to alter the size of a window. When you define a window, you can modify how the border behaves and appears if you want. Most windows will also have the maximize, minimize, and close buttons in the upper-right corner of the window. These allow the window to be increased to full screen size, reduced to an icon, or closed.

When you click the title bar icon with the left mouse button, it provides a standard menu for altering or closing the window called the *system menu* or *control menu*. The system menu also appears

when you right-click the title bar of a window. Although it's optional, it is always a good idea to include the title bar icon in any main windows that your program generates. Including the title bar icon provides you with a very convenient way of closing the program when things don't work during debugging, which is the process by which you find and eliminate errors in your code.

The client area is the part of the window where you usually want your program to write text or graphics. You can address the client area for this purpose in exactly the same way as the yard that you saw in Figure 7-1, in Chapter 7. The upper-left corner of the client area has the coordinates (0, 0), with x increasing from left to right, and y increasing from top to bottom.

The menu bar is optional in a window but is probably the most common way to control an application. Each menu in the menu bar displays a drop-down list of menu items when you click it. The contents of a menu and the physical appearance of many objects that are displayed in a window, such as the icons on the toolbar that appear in Figure 11-1, the cursor, and many others, are defined by a *resource file*. You will see many more resource files when we get to write some more sophisticated Windows programs.

A ribbon is an alternative to the menu bar. The latest editions of Microsoft Word and Microsoft Excel provide a ribbon as the primary mechanism for navigating around application functions. The MFC provides an extensive set of classes for creating a ribbon but I don't have the space to go into these.

The toolbar provides a set of icons that usually act as alternatives to the menu options that you use most often. Because they give a pictorial clue to the function provided, they can often make a program easier and faster to use.

I'll mention a caveat about terminology that you need to be conscious of before I move on. Users tend to think of a window as the thing that appears on the screen with a border around it, and, of course, it is, but it is only one kind of window. In Windows a window is a generic term covering a whole range of entities. Many entities that are displayed are windows — for example, a dialog is a window and each toolbar and dockable menu bar are also windows. I will generally use terminology to refer to objects that describe what they are, buttons, dialogs, and so on, but you need to have tucked in the back of your mind that many of them are windows too, because you can do things to them that you can do with a regular window — you can draw on a button, for instance.

Windows Programs and the Operating System

When you write a Windows program, your program is subservient to the operating system and Windows is in control. Your program cannot deal directly with the hardware, and all communications with the outside world must pass through Windows. When you use a Windows program, you are interacting primarily with Windows, which then communicates with the application program on your behalf. Your Windows program is the tail, Windows is the dog, and your program wags only when Windows tells it to.

There are a number of reasons why this is so. First and foremost, because your program is potentially always sharing the computer with other programs that may be executing at the same time, Windows has to have primary control to manage the sharing of machine resources. If one application were allowed to have primary control in a Windows environment, this would inevitably make programming more complicated because of the need to provide for the possibility of other

programs, and information intended for other applications could be lost. A second reason is that Windows embodies a standard user interface and needs to be in charge to enforce that standard. You can only display information on the screen using the tools that Windows provides, and then only when authorized.

Event-Driven Programs

You have already seen in Chapter 1 that a Windows program is *event-driven*, so a Windows program essentially waits around for something to happen. A significant part of the code for a Windows application is dedicated to processing events that are caused by external actions of the user, but activities that are not directly associated with your application can nonetheless require that bits of your program code are executed. For example, if the user drags the window of another application that is executing alongside your program and this action uncovers part of the client area of the window devoted to your application, your application must redraw the part of the application window that has been exposed.

Windows Messages

Events in a Windows application are occurrences such as the user clicking the mouse or pressing a key, or a timer reaching zero. The Windows operating system records each event in a *message* and places the message in a *message queue* for the program for which the message is intended. A Windows message is simply a record of the data relating to an event, and the message queue for an application is just a sequence of such messages waiting to be processed. By sending a message, Windows can tell your program that something needs to be done, or that some information has become available, or that an event such as a mouse click has occurred. If your program is properly organized, it will respond in the appropriate way to the message. There are many different kinds of messages and they can occur very frequently — several times per second when the mouse is being dragged for example.

A Windows program must contain a function specifically for handling these messages. The function is often called `WndProc()` or `WindowProc()`, although it doesn't have to have a particular name because Windows accesses the function through a pointer to a function that you supply. So the sending of a message to your program boils down to Windows calling a function that you provide that is typically called `WindowProc()`, and passing any necessary data to your program by means of arguments to this function. Within your `WindowProc()` function, it is up to you to work out what the message is from the data supplied and decide what to do about it.

Fortunately, you don't need to write code to process every message that Windows sends to your application. You can filter out those that are of interest, deal with those in whatever way you want, and pass the rest back to Windows. You pass a message back to Windows by calling a standard function called `DefWindowProc()`, which provides default message processing.

The Windows API

All of the communications between a Windows application and Windows itself use the Windows application programming interface, otherwise known as the *Windows API*. This consists of literally hundreds of functions that are provided as a standard with the Windows operating system

that provide the means by which an application communicates with Windows, and vice versa. The Windows API was developed in the days when C was the primary language in use, long before the advent of C++, and for this reason structures rather than classes are frequently used for passing data between Windows and your application program.

The Windows API covers all aspects of the communications between Windows and your application. Because there is such a large number of functions in the API, using them in the raw can be very difficult — just understanding what they all are is a task in itself. This is where Visual C++ makes the life of the application developer very much easier. Visual C++ packages the Windows API in a way that structures the functions in an object-oriented manner, and provides an easier way to use the interface in C++ with more default functionality. This takes the form of the Microsoft Foundation Classes, MFC.

Visual C++ also provides Application Wizards that create basic applications of various kinds, including MFC applications. The Application Wizard can generate a complete working application that includes all of the boilerplate code necessary for a basic Windows application, leaving you just to customize this for your particular purposes. The example in Chapter 1 illustrated how much functionality Visual C++ is capable of providing without any coding effort at all on your part. I will discuss this in more detail when we get to write some more examples using the Application Wizard.

Windows Data Types

Windows defines a significant number of data types that are used to specify function parameter types and return types in the Windows API. These Windows-specific types also propagate through to functions that are defined in MFC. Each of these Windows types will map to some C++ type, but because the mapping between Windows types and C++ types can change over time, you should always use the Windows type where this applies. For example, in the past the Windows type WORD has been defined in one version of Windows as type `unsigned short` and in another Windows version as type `unsigned int`. On 16-bit machines these types are equivalent, but on 32-bit machines they are decidedly different so anyone using the C++ type rather than the Windows type could run into problems.

You can find the complete list of Windows data types in the documentation, but here are a few of the most common you are likely to meet:

BOOL or BOOLEAN	A Boolean variable can have the values TRUE or FALSE. Note that this is not the same as the C++ type <code>bool</code> , which can have the values <code>true</code> or <code>false</code> .
BYTE	An 8-bit byte.
CHAR	An 8-bit character.
DWORD	A 32-bit unsigned integer that corresponds to type <code>unsigned long</code> in C++.
HANDLE	A handle to an object — a handle being a 32-bit integer value that records the location of an object in memory, or 64-bit when compiling for 64-bit.
HBRUSH	A handle to a brush, a brush being used to fill an area with color.

HCURSOR	A handle to a cursor.
HDC	Handle to a device context — a device context being an object that enables you to draw on a window.
HINSTANCE	Handle to an instance.
LPARAM	A message parameter.
LPCTSTR	LPCWSTR if <code>_UNICODE</code> is defined, otherwise LPCSTR.
LPCWSTR	A pointer to a constant null-terminated string of 16-bit characters.
LPCSTR	A pointer to a constant null-terminated string of 8-bit characters.
LPHANDLE	A pointer to a handle.
LRESULT	A signed value that results from processing a message.
WORD	A 16-bit unsigned integer, so it corresponds to type <code>unsigned short</code> in C++.

I'll introduce any other Windows types we are using in examples as the need arises. All Windows types and the prototypes of the Windows API functions are contained in the header file `windows.h`, so you need to include this header file when you put your basic Windows program together.

Notation in Windows Programs

In many Windows programs, variable names have a prefix, which indicates what kind of value the variable holds and how it is used. There are quite a few prefixes and they are often used in combination. For example, the prefix `lpfn` signifies a long pointer to a function. A sample of the prefixes you might come across is:

PREFIX	MEANING
b	a logical variable of type <code>BOOL</code> , equivalent to <code>int</code>
by	type <code>unsigned char</code> ; a byte
c	type <code>char</code>
dw	type <code>DWORD</code> , which is <code>unsigned long</code>
fn	a function
h	a handle , used to reference something
i	type <code>int</code>

continues

(continued)

PREFIX	MEANING
I	type long
lp	long pointer
n	type unsigned int
p	a pointer
s	a string
sz	a zero terminated string
w	type WORD, which is unsigned short

The use of these prefixes is called *Hungarian notation*. It was introduced to minimize the possibility of misusing a variable by interpreting it differently from how it was defined or intended to be used. Such misinterpretation is easily done in the C language. With C++ and its stronger type checking you don't need to make such a special effort with your notation to avoid such problems. The compiler always flags an error for type inconsistencies in your program, and many of the kinds of bugs that plagued earlier C programs can't occur with C++.

On the other hand, Hungarian notation can still help to make programs easier to understand, particularly when you are dealing with a lot of variables of different types that are arguments to Windows API functions. Because Windows programs are still written in C, and, of course, because parameters for Windows API functions are still defined using Hungarian notation, the method is still used quite widely.

You can make up your own mind as to the extent to which you want to use Hungarian notation, as it is by no means obligatory. You may choose not to use it at all, but in any event, if you have an idea of how it works, you will find it easier to understand what the arguments to the Windows API functions are. There is a small caveat, however. As Windows has developed, the types of some of the API function arguments have changed slightly, but the variable names that are used remain the same. As a consequence, the prefix may not be quite correct in specifying the variable type.

THE STRUCTURE OF A WINDOWS PROGRAM

For a minimal Windows program that just uses the Windows API, you will write two functions. These are a `WinMain()` function, where execution of the program begins and basic program initialization is carried out, and a `WindowProc()` function that is called by Windows to pass messages to the application. The `WindowProc()` part of a Windows program is usually the larger portion because this is where most of the application-specific code is, responding to messages caused by user input of one kind or another.

Although these two functions make up a complete program, they are not directly connected. `WinMain()` does not call `WindowProc()`, Windows does. Windows also calls `WinMain()`. This is illustrated in Figure 11-2.

The `WinMain()` function communicates with Windows by calling Windows API functions. The same applies to `WindowProc()`. The integrating factor in your Windows desktop application is Windows itself, which links to both `WinMain()` and `WindowProc()`. After looking into what the pieces are that make up `WinMain()` and `WindowProc()` you will assemble them into a working example of a simple Windows program.

The `WinMain()` Function

The `WinMain()` function is the equivalent of `main()` in a console program. It's where execution starts and where the basic initialization for the program is carried out. To allow Windows to pass data to it, `WinMain()` has four parameters and a return value of type `int`. Its prototype is:

```
int WINAPI WinMain(HINSTANCE hInstance,
                    HINSTANCE hPrevInstance,
                    LPSTR lpCmdLine,
                    int nCmdShow
    );
```

Following the return type specifier, `int`, you have a specification for the function, `WINAPI`. This is a Windows-defined macro that causes the function name and arguments to be handled in a special way that is specific to Windows API functions. This is different from the way functions are normally handled in C++. The precise details are unimportant — this is simply the way Windows requires things to be, so you need to put the `WINAPI` macro name in front of the names of functions called by Windows.




FIGURE 11-2

NOTE If you really want to know about calling conventions, they are described in the documentation that comes with Visual C++. `WINAPI` is defined as `_stdcall`, and putting this modifier before a function name indicates that the standard Windows calling convention is to be used. This requires that the parameters are pushed on the stack in reverse order and that the function that is called will clean up the stack when it ends. The `CALLBACK` modifier that you will see later in this chapter is also defined as `_stdcall` and is therefore the equivalent of `WINAPI`. The standard C++ calling convention is specified by the `_cdecl` modifier.

The four arguments that are passed to your `WinMain()` function contain important data:

- `hInstance` is of type `HINSTANCE`, which is a handle to an instance — an instance here being a running program. A *handle* is an integer value that identifies an object of some kind — in this case, the instance of the application. The actual integer value of a handle is not important. There can be several programs in execution at any given instant. This raises the possibility of several copies of the same application being active at once, and this needs to be recognized. Hence, the `hInstance` handle identifies a particular copy. If you start more than one copy of a program, each one has its own unique `hInstance` value. As you will see, handles are used to identify all sorts of other things.
- `hPrevInstance` is a legacy from the old 16-bit versions of the Windows operating system, and you can safely ignore it. On current versions of Windows, it is always `NULL`.
- `lpCmdLine` is a pointer to a string containing the command line that started the program. This pointer allows you to pick up any parameter values that may appear in the command line. The type `LPSTR` is another Windows type, specifying a 32-bit (long) pointer to a string, or 64-bit when compiling in 64-bit mode. There is also a version of `WinMain()` that accepts `LPWSTR` for Unicode builds.
- `nCmdShow` determines how the window is to look when it is created. It could be displayed normally or it might need to be minimized; for example, if the shortcut for the program specifies that the program should be minimized when it starts. This argument can take one of a fixed set of `int` values that are defined by symbolic constants such as `SW_SHOWNORMAL` and `SW_SHOWMAXIMIZED`. There are nine other constants like these that define the way a window is to be displayed, and they all begin `SW_`. You don't usually need to examine the value of `nCmdShow`. You typically pass it directly to the Windows API function responsible for displaying your application window.

NOTE If you want to know what all the constants are that specify how a window displays, you can find a complete list of the possible values if you search for `WinMain` in the MSDN Library. You can access the MSDN library online at <http://msdn.microsoft.com/en-us/library/default.aspx>.

The `WinMain()` function in your program needs to do four things:

- Tell Windows what kind of window the program requires
- Create the program window
- Initialize the program window
- Retrieve Windows messages intended for the program

We will take a look at each of these in turn and then create a complete `WinMain()` function.

Specifying a Program Window

The first step in creating a window is to define just what sort of window it is that you want to create. Windows defines a special `struct` type called `WNDCLASSEX` to contain the data specifying a window. The data that is stored in an instance of the `struct` defines a window class, which determines the type of window. You need to create a variable of type `WNDCLASSEX`, and give values to each of its members. After you've filled in the variables, you can pass it to Windows (via a function that you'll see later) to register the class. When that's been done, whenever you want to create a window of that class, you can tell Windows to look up the class that you have already registered.

The definition of the `WNDCLASSEX` structure is:

```
struct WNDCLASSEX
{
    UINT cbSize;           // Size of this object in bytes
    UINT style;            // Window style
    WNDPROC lpfnWndProc;  // Pointer to message processing function
    int cbClsExtra;        // Extra bytes after the window class
    int cbWndExtra;        // Extra bytes after the window instance
    HINSTANCE hInstance;   // The application instance handle
    HICON hIcon;           // The application icon
    HCURSOR hCursor;       // The window cursor
    HBRUSH hbrBackground; // The brush defining the background color
    LPCTSTR lpszMenuName; // A pointer to the name of the menu resource
    LPCTSTR lpszClassName; // A pointer to the class name
    HICON hIconSm;          // A small icon associated with the window
};
```

You construct an object of type `WNDCLASSEX` in the way that you saw when I discussed structures, for example:

```
WNDCLASSEX WindowClass;           // Create a window class object
```

You can now fill in values for the members of `WindowClass`. They are all `public` by default because `WindowClass` is a `struct`. Setting the value for the `cbSize` member of the `struct` is easy when you use the `sizeof` operator:

```
WindowClass.cbSize = sizeof(WNDCLASSEX);
```

The `style` member of the `struct` determines various aspects of the window's behavior, in particular, the conditions under which the window should be redrawn. You can select from a number of options for this member's value, each defined by a symbolic constant beginning with `cs_`.

NOTE You'll find all the possible constant values for `style` if you search for "Window Class Styles" in the MSDN Library that you'll find at <http://msdn.microsoft.com/en-us/library/ms123401.aspx>.

Where two or more options are required, the constants can be combined to produce a composite value using the bitwise OR operator, |. For example:

```
WindowClass.style = CS_HREDRAW | CS_VREDRAW;
```

The option `CS_HREDRAW` indicates to Windows that the window is to be redrawn if its horizontal width is altered, and `CS_VREDRAW` indicates that it is to be redrawn if the vertical height of the window is changed. In the preceding statement, you have elected to have the window redrawn in either case. As a result, Windows sends a message to your program indicating that you should redraw the window whenever the width or height of the window is altered by the user. Each of the possible options for the window style is defined by a unique bit in a 32-bit word being set to 1. That's why the bitwise OR is used to combine them. These bits indicating a particular style are usually called *flags*. Flags are used very frequently, not only in Windows but also in C++, because they are an efficient way of representing and processing features that are either there or not, or parameters that are either true or false.

The member `lpfnWndProc` stores a pointer to the function in your program that handles messages for the window you create. The prefix to the name signifies that this is a long pointer to a function. If you followed the herd and called the function to handle messages for the application `WindowProc()`, you would initialize this member with the statement:

```
WindowClass.lpfnWndProc = WindowProc;
```

The next two members, `cbClsExtra` and `cbWndExtra`, allow you to ask that extra space be provided internally to Windows for your own use. An example of this could be when you want to associate additional data with each instance of a window to assist in message handling for each window instance. Normally you won't need extra space allocated for you, in which case you set the `cbClsExtra` and `cbWndExtra` members to zero.

The `hInstance` member holds the handle for the current application instance, so you should set this to the `hInstance` value that was passed to `WinMain()` by Windows:

```
WindowClass.hInstance = hInstance;
```

The members `hIcon`, `hCursor`, and `hbrBackground` are handles that in turn reference objects that represent:

- The application when minimized
- The cursor the window uses
- The background color of the client area of the window

As you saw earlier, a handle is just a 32-bit integer (or 64-bit when compiled in 64-bit mode) used as an ID to represent something. These members are set using Windows API functions. For example:

```
WindowClass.hIcon = LoadIcon(nullptr, IDI_APPLICATION);
WindowClass.hCursor = LoadCursor(nullptr, IDC_ARROW);
WindowClass.hbrBackground = static_cast<HBRUSH>(GetStockObject(GRAY_BRUSH));
```

All three members are set to standard Windows values by these function calls. The icon is a default provided by Windows and the cursor is the standard arrow cursor used by the majority of Windows applications. A brush is a Windows object used to fill an area, in this case the client area of the window. The function `GetStockObject()` returns a generic type for all stock objects, so you need to cast it to type `HBRUSH`. In the preceding example, it returns a handle to the standard gray brush, and the background color for our window is thus set to gray. This function can also be used to obtain other standard objects for a window, such as fonts, for example. You could also set the `hIcon` and `hCursor` members to `NULL`, in which case Windows would provide the default icon and cursor. If you set `hbrBackground` to `NULL`, your program is expected to paint the window background, and messages are sent to your application whenever this becomes necessary.

The `lpszMenuName` member is set to the name of a resource defining the window menu, or to `NULL` if there is no menu for the window:

```
WindowClass. lpszMenuName = NULL;
```

You will look into creating and using menu resources when you use the AppWizard.

The `lpszClassName` member of the `struct` stores the name that you supply to identify this particular class of window. You would usually use the name of the application for this. You need to keep track of this name because you will need it again when a window is created. This member would therefore be typically set with the statements:

```
static LPCTSTR szAppName = _T("OFWin");      // Define window class name
WindowClass.lpszClassName = szAppName;         // Set class name
```

I have defined `szAppName` using the `_T()` macro that is defined in the `tchar.h` header. The `LPCTSTR` type is defined as `const wchar_t*` if `UNICODE` is defined for the application, or `const char*` if it is not. The `_T()` macro will create a string of the correct type automatically.

The last member is `hIconSm`, which identifies a small icon associated with the window class. If you specify this as `NULL`, Windows searches for a small icon related to the `hIcon` member and uses that.

Creating a Program Window

After you have set the members of your `WNDCLASSEX` structure to the values required, the next step is to tell Windows about it. You do this by calling the Windows API function `RegisterClassEx()`. Given that your `WNDCLASSEX` structure object is `WindowClass`, the statement to do this would be:

```
RegisterClassEx(&WindowClass);
```

Easy, isn't it? The address of the `struct` is passed to the function, and Windows extracts and squirrels away all the values that you have set in the structure members. This process is called *registering* the window class. Just to remind you, the term *class* here is used in the sense of classification and is not the same as the idea of a *class* in C++, so don't confuse the two. Each instance of the application must make sure that it registers the window classes that it needs.

After Windows knows the characteristics of the window that you want, and the function that is going to handle messages for it, you can go ahead and create it. You call the `CreateWindow()`

function for this. The window class that you have created determines the broad characteristics of the application window, and further arguments to `CreateWindow()` add additional characteristics. Because an application may have several windows in general, `CreateWindow()` returns a handle to the window it created that you can store to enable you to refer to that particular window later. There are many API calls that require you to specify the window handle as a parameter. Let's look at a typical use of `CreateWindow()`. This might be:

```
HWND hWnd; // Window handle  
...  
hWnd = CreateWindow(  
    szAppName, // the window class name  
    _T("A Basic Window the Hard Way"), // The window title  
    WS_OVERLAPPEDWINDOW, // Window style as overlapped  
    CW_USEDEFAULT, // Default screen position of upper left  
    CW_USEDEFAULT, // corner of our window as x,y.  
    CW_USEDEFAULT, // Default window size, width...  
    CW_USEDEFAULT, // ...and height  
    NULL, // No parent window  
    NULL, // No menu  
    hInstance, // Program Instance handle  
    NULL // No window creation data  
) ;
```

The `hWnd` variable of type `HWND` is a 32-bit integer handle to a window, or 64-bit in 64-bit mode. You use this variable to record the window handle that `CreateWindow()` returns. The first argument that you pass to `CreateWindow()` is the class name. This is used to identify the `WNDCLASSEX` object that you passed to the operating system previously in the `RegisterClassEx()` function call, so that information from this struct can be used in the window creation process.

The second argument to `CreateWindow()` defines the text that is to appear on the title bar. The third argument specifies the style that the window has after it is created. The option specified here, `WS_OVERLAPPEDWINDOW`, actually combines several options. It defines the window as having the `WS_OVERLAPPED`, `WS_CAPTION`, `WS_SYSMENU`, `WS_THICKFRAME`, `WS_MINIMIZEBOX`, and `WS_MAXIMIZEBOX` styles. This results in an overlapped window, which is a window intended to be the main application window, with a title bar and a thick frame, which has a title bar icon, system menu, and maximize and minimize buttons. A window that you specify as having a thick frame has borders that can be resized.

The next four arguments determine the position and size of the window on the screen. The first two are the screen coordinates of the upper-left corner of the window, and the second two define the width and height of the window. The value `CW_USEDEFAULT` indicates that you want Windows to assign the default position and size for the window. This tells Windows to arrange successive windows in cascading positions down the screen. `CW_USEDEFAULT` only applies to windows specified as `WS_OVERLAPPED`.

The next argument value is `NULL`, indicating that the window being created is not a child window (i.e., not a window that is dependent on a parent window). If you wanted it to be a child window, you would set this argument to the handle of the parent window. The next argument is also `NULL`, indicating that no menu is required. You then specify the handle of the current instance of the

program that was passed to the program by Windows. The last argument for window creation data is NULL because you just want a simple window in the example. If you wanted to create a multiple-document interface (MDI) client window, the last argument would point to a structure related to this. You'll learn more about MDI windows later in the book.

NOTE *The Windows API also includes a CreateWindowEx() function that you use to create a window with extended style information.*

After you call `CreateWindow()`, the window exists but is not yet displayed on the screen. You must call another Windows API function to get it displayed:

```
ShowWindow(hWnd, nCmdShow); // Display the window
```

Only two arguments are required here. The first identifies the window and is the handle returned by `CreateWindow()`. The second is the `nCmdShow` value that was passed to `WinMain()`, which indicates how the window is to appear on-screen.

Initializing the Program Window

After calling `ShowWindow()`, the window appears on-screen but still has no application content, so you need to get your program to draw in the client area of the window. You could just put together some code to do this directly in the `WinMain()` function, but this would be most unsatisfactory: in this case, the contents of the client area would not be permanent — if you want the client area contents to be retained, you can't just output what you want and forget about it. Any action on the part of the user that modifies the window in some way, such as dragging a border or dragging the whole window, typically requires that the window *and* its client area are redrawn.

When the client area needs to be redrawn for any reason, Windows sends a particular message to your program, and your `WindowProc()` function needs to respond by reconstructing the client area of the window. Therefore, the best way to get the client area drawn in the first instance is to put the code to draw the client area in the `WindowProc()` function and get Windows to send the message requesting that the client area be redrawn to your program. Whenever you know in your program that the window should be redrawn (when you change something, for example), you need to tell Windows to send a message back to get the window redrawn.

You can ask Windows to send your program a message to redraw the client area of the window by calling another Windows API function, `UpdateWindow()`. The statement to accomplish this is:

```
UpdateWindow(hWnd); // Cause window client area to be drawn
```

This function requires only one argument: the window handle `hWnd`, which identifies your particular program window. The result of the call is that Windows sends a message to your program requesting that the client area be redrawn.

Dealing with Windows Messages

The last task that `WinMain()` needs to address is dealing with the messages that Windows may have queued for your application. This may seem a bit odd because I said earlier that you needed the function `WindowProc()` to deal with messages, but let me explain a little further.

Queued and Non-Queued Messages

I oversimplified Windows messaging when I introduced the idea. There are, in fact, two kinds of Windows messages:

There are *queued messages* that Windows places in a queue, and the `WinMain()` function must extract these messages from the queue for processing. The code in `WinMain()` that does this is called the *message loop*. Queued messages include those arising from user input from the keyboard, moving the mouse, and clicking the mouse buttons. Messages from a timer and the Windows message to request that a window be redrawn are also queued.

There are *non-queued messages* that result in the `WindowProc()` function being called directly by Windows. A lot of the non-queued messages arise as a consequence of processing queued messages. What you are doing in the message loop in `WinMain()` is retrieving a message that Windows has queued for your application and then asking Windows to invoke your `WindowProc()` function to process it. Why can't Windows just call `WindowProc()` whenever necessary? Well, it could, but it just doesn't work this way. The reasons have to do with how Windows manages multiple applications executing simultaneously.

The Message Loop

As I said, retrieving messages from the message queue is done using a standard mechanism in Windows programming called the *message pump* or *message loop*. The code for this would be:

```
MSG msg;                                // Windows message structure
while( GetMessage(&msg, NULL, 0, 0) == TRUE) // Get any messages
{
    TranslateMessage(&msg);                // Translate the message
    DispatchMessage(&msg);                // Dispatch the message
}
```

This involves three steps in dealing with each message:

- `GetMessage()` — Retrieves a message from the queue.
- `TranslateMessage()` — Performs any conversion necessary on the message retrieved.
- `DispatchMessage()` — Causes Windows to call the `WindowProc()` function in your application to deal with the message.

The operation of `GetMessage()` is important because it has a significant contribution to the way Windows works with multiple applications, so we should explore it in a little more detail.

The `GetMessage()` function retrieves a message queued for the application window and stores information about the message in the variable `msg`, pointed to by the first argument. The `msg` variable is

a struct of type `MSG` that contains members that you are not accessing here. Still, for completeness, the definition of the structure looks like this:

```
struct MSG
{
    HWND    hwnd;           // Handle for the relevant window
    UINT    message;        // The message ID
    WPARAM wParam;         // Message parameter (32-bits)
    LPARAM lParam;         // Message parameter (32-bits)
    DWORD   time;          // The time when the message was queued
    POINT   pt;             // The mouse position
};
```

The `wParam` member is an example of a slightly misleading Hungarian notation prefix that I mentioned is now possible. You might assume that it was of type `WORD` (a 16-bit unsigned integer), which used to be true in earlier Windows versions, but now it is of type `WPARAM`, which is a 32-bit integer value.

The exact contents of the `wParam` and `lParam` members are dependent on what kind of message it is. The message ID in the member `message` is an integer value and can be one of a set of values that are predefined in the header file, `windows.h`, as symbolic constants. Message IDs for general windows all start with `WM_`; typical examples are shown in the following table. General windows messages cover a wide variety of events and include messages relating to mouse and menu events, keyboard input, and window creation and management.

ID	DESCRIPTION
WM_PAINT	The window should be redrawn.
WM_SIZE	The window has been resized.
WM_LBUTTONDOWN	The left mouse button is down.
WM_RBUTTONDOWN	The right mouse button is down.
WM_MOUSEMOVE	The mouse has moved.
WM_CLOSE	The window or application should close.
WM_DESTROY	The window is being destroyed.
WM_QUIT	The program should be terminated.

The function `GetMessage()` always returns `TRUE` unless the message is `WM_QUIT` to end the program, in which case the value returned is `FALSE`, or unless an error occurs, in which case the return value is `-1`. Thus, the `while` loop continues until a quit message is generated to close the application or until an error condition arises. In either case, you need to end the program by passing the `wParam` value back to Windows in a `return` statement.

NOTE There are prefixes other than WM for messages destined for other types of windows than a general window.

The second argument in the call to `GetMessage()` is the handle of the window for which you want to get messages. This parameter can be used to retrieve messages for one application window separately from another. If this argument is `NULL`, as it is here, `GetMessage()` retrieves all messages for an application. This is an easy way of retrieving all messages for an application regardless of how many windows it has. It is also the safest way because you are sure of getting all the messages for your application. When the user of your Windows program closes the application window for example, the window is closed before the `WM_QUIT` message is generated. Consequently, if you only retrieve messages by specifying a window handle to the `GetMessage()` function, you cannot retrieve the `WM_QUIT` message and your program is not able to terminate properly.

The last two arguments to `GetMessage()` are integers that hold minimum and maximum values for the message IDs you want to retrieve from the queue. This allows messages to be retrieved selectively. A range is usually specified by symbolic constants. Using `WM_MOUSEFIRST` and `WM_MOUSELAST` as these two arguments would select just mouse messages, for example. If both arguments are zero, as you have them here, all messages are retrieved.


Multitasking

If there are no messages queued, the `GetMessage()` function does not return control to your program. Windows allows execution to pass to another application, and you will only get a value returned from calling `GetMessage()` when a message appears in the queue.

This mechanism was fundamental in enabling multiple applications to run under older versions of Windows and is referred to as *cooperative multitasking* because it depends on concurrent applications giving up control of the processor from time to time. After your program calls `GetMessage()`, unless there is a message for it another application is executed and your program gets another opportunity to do something only if the other application releases the processor, perhaps by a call to `GetMessage()` when there are no messages queued for it, but this is not the only possibility.

With current versions of Windows, the operating system can interrupt an application after a period of time and transfer control to another application. This mechanism is called *pre-emptive multitasking* because an application can be interrupted at any time. With pre-emptive multitasking, however, you must still program the message loop in `WinMain()` using `GetMessage()` as before, and make provision for relinquishing control of the processor to Windows from time to time in a long-running calculation (this is usually done using the `PeekMessage()` API function). If you don't do this, your application may be unable to respond to messages to repaint the application window when these arise. This can be for reasons that are quite independent of your application — when an overlapping window for another application is closed, for example.

The conceptual operation of the `GetMessage()` function is illustrated in Figure 11-3.

**FIGURE 11-3**

Within the `while` loop, the first call to `TranslateMessage()` requests Windows to do some conversion work for keyboard-related messages. Then the call to `DispatchMessage()` causes Windows to *dispatch* the message, which it does by calling the `WindowProc()` function in your program to process the message. The return from `DispatchMessage()` does not occur until `WindowProc()` has finished processing the message. A `WM_QUIT` message indicates that the program should end, so this results in `FALSE` being returned to the application, which stops the message loop.

A Complete WinMain() Function

You have looked at all the bits that need to go into WinMain() so now you can assemble them into a complete function:

```
// Listing OFWIN_1
int WINAPI WinMain(HINSTANCE hInstance, HINSTANCE hPrevInstance,
                    LPSTR lpCmdLine, int nCmdShow)
{
    WNDCLASSEX WindowClass;           // Structure to hold our window's attributes

    static LPCTSTR szAppName = _T("OFGWin");      // Define window class name
    HWND hWnd;                           // Window handle
    MSG msg;                            // Windows message structure

    WindowClass.cbSize = sizeof(WNDCLASSEX);        // Set structure size

    // Redraw the window if the size changes
    WindowClass.style   = CS_HREDRAW | CS_VREDRAW;

    // Define the message handling function
    WindowClass.lpfnWndProc = WindowProc;

    WindowClass.cbClsExtra = 0;          // No extra bytes after the window class
    WindowClass.cbWndExtra = 0;          // structure or the window instance

    WindowClass.hInstance = hInstance;       // Application instance handle

    // Set default application icon
    WindowClass.hIcon = LoadIcon(NULL, IDI_APPLICATION);

    // Set window cursor to be the standard arrow
    WindowClass.hCursor = LoadCursor(NULL, IDC_ARROW);

    // Set gray brush for background color
    WindowClass.hbrBackground = static_cast<HBRUSH>(GetStockObject(GRAY_BRUSH));

    WindowClass.lpszMenuName = NULL;        // No menu
    WindowClass.lpszClassName = szAppName;   // Set class name
    WindowClass.hIconSm = NULL;             // Default small icon

    // Now register our window class
    RegisterClassEx(&WindowClass);

    // Now we can create the window
    hWnd = CreateWindow(
        szAppName,                         // the window class name
        _T("A Basic Window the Hard Way"), // The window title
        WS_OVERLAPPEDWINDOW,               // Window style as overlapped
        CW_USEDEFAULT,                     // Default position of upper left
        CW_USEDEFAULT,                     // corner of our window as x,y...
        CW_USEDEFAULT,                     // Default window size
        CW_USEDEFAULT,                     // ....
        NULL,                             // No parent window
```

```

        NULL,                                // No menu
        hInstance,                            // Program Instance handle
        NULL                                 // No window creation data
    );

ShowWindow(hWnd, nCmdShow);           // Display the window
UpdateWindow(hWnd);                  // Redraw window client area

// The message loop
while(GetMessage(&msg, NULL, 0, 0) == TRUE) // Get any messages
{
    TranslateMessage(&msg);             // Translate the message
    DispatchMessage(&msg);             // Dispatch the message
}

return static_cast<int>(msg.wParam);   // End, so return to Windows
}

```

You need a `WindowProc()` implementation to make this into a working Windows application. We will look at that after we explore how this code works.

How It Works

After declaring the variables that you need in `WinMain()`, all the members of the `WindowClass` structure are initialized and the window is registered. Next you call the `CreateWindow()` function to create the data for the physical appearance of the window based on the arguments and the data established in the `WindowClass` structure that was previously passed to Windows using the `RegisterClassEx()` function. The call to `ShowWindow()` causes the window to be displayed according to the mode specified by `nCmdShow`, and the `UpdateWindow()` function signals that a message to draw the window client area should be generated.

The message loop retrieves messages until a `WM_QUIT` message is issued for the application. When this occurs, the `GetMessage()` function returns `FALSE` and the loop ends. The value of the `wParam` member of the `msg` structure is passed back to Windows in the `return` statement.

Processing Windows Messages

The `WinMain()` function contains nothing that was application-specific beyond the general appearance of the application window. All of the code that makes the application behave in the way that you want is included in the message processing part of the program. This is the function `WindowProc()` that you identify to Windows in the `WindowClass` structure. Windows calls this function each time a message for your main application window is dispatched. Because you identify your `WindowProc()` function to Windows by a function pointer, you can use any name for the function that you like. I'll continue to call it `WindowProc()`.

This example is simple, so you will be putting all the code to process messages in the one function, `WindowProc()`. More generally, though, the `WindowProc()` function is responsible for analyzing what a given message is and which window it is destined for and then calling one of a whole range of functions, each of which would be geared to handling a particular message in the context

of the window concerned. However, the overall sequence of operations and the way in which `WindowProc()` analyzes an incoming message is much the same in most application contexts.

The `WindowProc()` Function

The prototype of the `WindowProc()` function is:

```
LRESULT CALLBACK WindowProc(HWND hWnd, UINT message,
                           WPARAM wParam, LPARAM lParam);
```

The return type is `LRESULT`, which is a Windows type that is normally equivalent to type `long`. Because the function is called by Windows through a pointer (you set up the pointer with the address of `WindowProc()` in `WinMain()` in the `WNDCLASSEX` structure), you need to qualify the function as `CALLBACK`. I mentioned this specifier earlier, and its effect is the same as the `WINAPI` specifier that determines how the function arguments are handled. You could use `WINAPI` here instead of `CALLBACK`, although the latter expresses better what this function is about. The four arguments that are passed to `WindowProc()` provide information about the message causing the function to be called. The meaning of each argument is described in the following table:

ARGUMENT	MEANING
<code>HWND hWnd</code>	A handle to the window in which the event causing the message occurred.
<code>UINT message</code>	The message ID, which is a 32-bit value indicating the type of message.
<code>WPARAM wParam</code>	A 32-bit (or 64-bit in 64-bit mode) value containing additional information depending on what sort of message it is.
<code>LPARAM lParam</code>	A 32-bit (or 64-bit in 64-bit mode) value containing additional information depending on what sort of message it is.

The window that the incoming message relates to is identified by the first argument, `hWnd`. In this case, you have only one window, so you can ignore it.

Messages are identified by the `message` value that is passed to `WindowProc()`. You can test this value against predefined symbolic constants, each of which identifies a particular message. General windows messages begin with `WM_`, and typical examples are `WM_PAINT`, which corresponds to a request to redraw part of the client area of a window, and `WM_LBUTTONDOWN`, which indicates that the left mouse button was pressed. You can find the whole set of these by searching for `WM_` in the MSDN Library.

Decoding a Windows Message

Decoding the message that Windows sends is usually done using a `switch` statement in the `WindowProc()` function, based on the value of `message`. You select the message types that you want to process by putting a `case` statement for each message ID in the `switch`. The typical structure of such a `switch` statement is:

```

switch(message)
{
    case WM_PAINT:
        // Code to deal with drawing the client area
        break;

    case WM_LBUTTONDOWN:
        // Code to deal with the left mouse button being pressed
        break;

    case WM_LBUTTONUP:
        // Code to deal with the left mouse button being released
        break;

    case WM_DESTROY:
        // Code to deal with a window being destroyed
        break;

    default:
        // Code to handle any other messages
}

```

Every Windows program has something like this somewhere, although it will be hidden from sight in the Windows programs that you will write later using MFC. Each case corresponds to a particular message ID and provides suitable processing for that message. Any messages that a program does not want to deal with individually are handled by the default statement, which should hand the messages back to Windows by calling `DefWindowProc()`. This is the Windows API function that provides default message handling.

In a complex program dealing with a wide range of possible Windows messages, this `switch` statement can become large and rather cumbersome. When you get to use the Application Wizard to generate a Windows application that uses the MFC, you won't have to worry about this because it is all taken care of for you and you never see the `WindowProc()` function. You just need to supply the code to process the messages in which you are interested.

Drawing the Window Client Area

Windows sends a `WM_PAINT` message to the program to signal that the client area of an application should be redrawn. So you need to draw the client area of the window in response to the `WM_PAINT` message.

You can't go drawing in the window willy-nilly. Before you can write to the application window, you need to tell Windows that you want to do so, and get Windows' authority to go ahead. You do this by calling the Windows API function `BeginPaint()`, which should only be called in response to a `WM_PAINT` message. It is used like this:

```

HDC hDC;                                // A display context handle
PAINTSTRUCT PaintSt;                     // Structure defining area to be redrawn
hDC = BeginPaint(hWnd, &PaintSt);          // Prepare to draw in the window

```

The `HDC` type represents a handle to a *display context*, or more generally a *device context*. A device context provides the link between the device-independent Windows API functions for outputting information to the screen or a printer, and the device drivers that support writing to the specific devices attached to your PC. You can also regard a device context as a token of authority that is handed to you on request by Windows and grants you permission to output some information. Without a device context, you simply can't generate any output.

The `BeginPaint()` function returns a handle to a display context. It requires two arguments. The first argument is a handle, `hWnd`, for the window to which you want to write. The second argument is the address of a `PAINTSTRUCT` variable `PaintSt`, in which Windows will place information about the area that is to be redrawn in response to the `WM_PAINT` message. I will ignore the details of this because you are not going to use it. You will just redraw the whole of the client area. You can obtain the coordinates of the client area in a `RECT` structure with the statements:

```
RECT aRect;                                // A working rectangle
GetClientRect(hWnd, &aRect);
```

The `GetClientRect()` function supplies the coordinates of the upper-left and lower-right corners of the client area for the window specified by the first argument. These coordinates are stored in the `RECT` structure `aRect` that you create, and you pass the address of this structure as the second argument. You can use `aRect` to identify the area in the client area where the text is to be written by the `DrawText()` function. Because your window has a gray background, you should alter the background of the text to be transparent, to allow the gray to show through; otherwise, the text appears against a white background. You can do this with this API function call:

```
SetBkMode(hDC, TRANSPARENT);                // Set text background mode
```

The first argument identifies the device context and the second sets the background mode. The default option is `OPAQUE`.

You can now write the text with the statement:

```
DrawText(hDC,                               // Device context handle
         _T("But, soft! What light through yonder window breaks?"),
         -1,                                     // Indicate null terminated string
         &aRect,                                 // Rectangle in which text is to be drawn
         DT_SINGLELINE|                         // Text format - single line
         DT_CENTER|                            // - centered in the line
         DT_VCENTER);                          // - line centered in aRect
);
```

The first argument to the `DrawText()` function is your certificate of authority to draw on the window, the display context `hDC`. The next argument is the text string that you want to output. You could equally well have defined this in a variable and passed the pointer to the text as the second argument in the function call. The next argument, with the value `-1`, signifies that your string is terminated with a null character. If it weren't, you would put the count of the number of characters in the string here. The fourth argument is a pointer to a `RECT` structure defining a rectangle in which you want to write the text. In this case, it is the whole client area of the window defined in `aRect`. The last argument defines the format for the text in the rectangle. Here you have combined three specifications with a bitwise OR (`|`). The string is written as a single line, with the text centered on

the line and the line centered vertically within the rectangle. This places it nicely in the center of the window. There are also a number of other options, which include the possibility to place text at the top or the bottom of the rectangle, and to left- or right-justify it.

After you have written all that you want to display, you must tell Windows that you have finished drawing the client area. For every `BeginPaint()` function call, there must be a corresponding `EndPaint()` function call. Thus, to end processing of the `WM_PAINT` message, you need the statement:

```
EndPaint(hWnd, &PaintSt);           // Terminate window redraw operation
```

The `hWnd` argument identifies your program window, and the second argument is the address of the `PAINTSTRUCT` structure that was filled in by the `BeginPaint()` function.

Ending the Program

You might assume that closing the window closes the application, but to get this behavior, you actually have to add some more code. The reason that the application won't close by default when the window is closed is that you may need to do some clearing up. It is also possible that the application may have more than one window. When the user closes the window by double-clicking the title bar icon or clicking the Close button, this causes a `WM_DESTROY` message to be generated. Therefore, to close the application, you need to process the `WM_DESTROY` message in `WindowProc()`. You do this by generating a `WM_QUIT` message:

```
PostQuitMessage(0);
```

The argument here is an exit code. This API function does exactly what its name suggests: it posts a `WM_QUIT` message in the message queue for your application. This results in the `GetMessage()` function that is called in `WinMain()` returning `FALSE` and ending the message loop, thus ending the program.

A Complete WindowProc() Function

You have covered all the elements necessary to assemble the complete `WindowProc()` function for the example. The code for the function is:

```
// Listing OFWIN_2
LRESULT CALLBACK WindowProc(HWND hWnd, UINT message,
                           WPARAM wParam, LPARAM lParam)
{
    switch(message)           // Process selected messages
    {
        case WM_PAINT:       // Message is to redraw the window
            HDC hDC;          // Display context handle
            PAINTSTRUCT PaintSt; // Structure defining area to be drawn
            RECT aRect;        // A working rectangle
            hDC = BeginPaint(hWnd, &PaintSt); // Prepare to draw the window

            // Get upper left and lower right of client area
            GetClientRect(hWnd, &aRect);
```

```

SetBkMode(hDC, TRANSPARENT);           // Set text background mode

// Now draw the text in the window client area
DrawText(
    hDC,                           // Device context handle
    _T("But, soft! What light through yonder window breaks?"),
    -1,                            // Indicate null terminated string
    &aRect,                         // Rectangle in which text is to be drawn
    DT_SINGLELINE|                // Text format - single line
    DT_CENTER|                   // - centered in the line
    DT_VCENTER);                 // - line centered in aRect

EndPaint(hWnd, &PaintSt);          // Terminate window redraw operation
return 0;

case WM_DESTROY:                  // Window is being destroyed
    PostQuitMessage(0);
    return 0;
}
return DefWindowProc(hWnd, message, wParam, lParam);
}

```

How It Works

Apart from the last statement, the entire function body is just a `switch` statement. A particular case is selected based on the message ID that is passed to the function through the `message` parameter. Because this example is simple, you need to process only two types of message: `WM_PAINT` and `WM_DESTROY`. You hand all other messages back to Windows by calling the `DefWindowProc()` function after the `switch` statement. The arguments to `DefWindowProc()` are those that were passed to the function, so you are just passing them back as they are. Note the `return` statement at the end of processing each message type. For the messages that you handle, a zero value is returned.

TRY IT OUT A Simple Windows API Program

Because you have written `WinMain()` and `WindowProc()` to handle messages, you have enough to create a complete source file for a Windows program using just the Windows API. Of course, you'll need to create a project for this program, but instead of choosing Win32 Console Application as you've done up to now, you should create this project using the Win32 Project template. You should elect to create it as an empty project with the name `Ex11_01` and add the `Ex11_01.cpp` file that will contain the following code:

```

// Ex11_01.cpp  Native windows program to display text in a window
#include <windows.h>

LRESULT CALLBACK WindowProc(HWND hWnd, UINT message,
                           WPARAM wParam, LPARAM lParam);

// Insert code for WinMain() here (Listing OFWIN_1)

// Insert code for WindowProc() here (Listing OFWIN_2)

```

If you build and execute the example, it produces the window shown in Figure 11-4.

Note that the window has a number of properties provided by the operating system that require no programming effort on your part to manage. The boundaries of the window can be dragged to resize it, and the whole window can be moved about on-screen. The maximize and minimize buttons also work. Of course, all of these actions do affect the program. Every time you modify the position or size of the window, a `WM_PAINT` message is queued and your program has to redraw the client area, but all the work of drawing and modifying the window itself is done by Windows.

The system menu and Close button are also standard features of your window because of the options that you specified in the `WindowClass` structure. Again, Windows takes care of the management. The only additional effect on your program arising from this is the passing of a `WM_DESTROY` message if you close the window, as previously discussed.




FIGURE 11-4

THE MICROSOFT FOUNDATION CLASSES

The *Microsoft Foundation Classes* (*MFC*) are a set of predefined classes that make it easy to develop Windows desktop applications with Visual C++. These classes represent an object-oriented approach to Windows programming that encapsulates the Windows API. MFC does not adhere strictly to the object-oriented principles of encapsulation and data hiding, principally because much of the MFC code was written before such principles were well established.

The process of writing a Windows program involves creating and using MFC objects or objects of classes derived from MFC. In the main, you'll derive your own classes from MFC, with considerable assistance from the specialized tools in Visual C++ that make this easy. The objects of these MFC-based class types incorporate member functions for communicating with Windows, for processing Windows messages, and for sending messages to each other. Your derived classes inherit all of the members of their base classes. These inherited functions do practically all of the general grunt work necessary for a Windows application to work. All you need to do is to add data and function members to the classes to provide the application-specific functionality that you need in your program. In doing this, you'll apply most of the techniques that you've been grappling with in the preceding chapters, particularly those involving class inheritance and virtual functions.

MFC Notation

All the classes in MFC have names beginning with C, such as `CDocument` or `CView`. If you use the same convention when defining your own classes, or when deriving them from those in the MFC library, your programs will be easier to follow. Data members of an MFC class are prefixed with `m_`. I'll also follow this convention in the MFC examples.

You'll find that the MFC uses Hungarian notation for many variable names, particularly those that originate in the Windows API. As you recall, this involves using a prefix of `p` for a pointer, `n` for an `unsigned int`, `l` for `long`, `h` for a handle, and so on. The name `m_lpCmdLine`, for example, refers to a data member of a class (because of the `m_` prefix) that is of type 'long pointer to a string'. Because C++ has strong type checking that picks up the sort of misuse that used to happen regularly in C, this kind of notation isn't essential, so I won't use it generally for variables in the examples in the book. I will, however, retain the `p` prefix for pointers and some of the other simple type denotations because this helps to make the code more readable.

How an MFC Program Is Structured

You know from Chapter 1 that you can produce a Windows program using the Application Wizard without writing a single line of code. Of course, this uses the MFC library, but it's quite possible to write a Windows program that uses MFC without using the Application Wizard. If you first scratch the surface by constructing the minimum MFC-based program, you'll get a clearer idea of the fundamental elements involved.

The simplest program that you can produce using MFC is slightly less sophisticated than the example that you wrote earlier in this chapter using the raw Windows API. The example you'll produce here has a window, but no text displayed in it. This is sufficient to show the fundamentals, so try it out.

TRY IT OUT A Minimal MFC Application

Create a new project using the `File` \Rightarrow `New` \Rightarrow `Project` menu option, as you've done many times before. You won't use the Application Wizard that creates the basic code here, so select the template for the project as `Win32 Project` and choose `Windows Application` and the `Empty` project options in the second dialog. After the project is created, select `Project` \Rightarrow `Ex11_02` properties from the main menu, and on the `General` sub-page from Configuration Properties, click the `Use of MFC` property to set its value to `Use MFC in a Shared DLL`.

With the project created, you can create a new source file in the project as `Ex11_02.cpp`. So that you can see all the code for the program in one place, put the class definitions you need together with their implementations in this file. To achieve this, just add the code manually in the edit window — there isn't very much of it.

To begin with, add a statement to include the header file `afxwin.h`, as this contains the definitions for many MFC classes. This allows you to derive your own classes from MFC:

```
#include <afxwin.h> // For the class library
```

To produce the complete program, you'll only need to derive two classes from MFC: an *application class* and a *window class*. You won't even need to write a `WinMain()` function, as you did in the previous example in this chapter, because this is automatically provided by the MFC library behind the scenes. Take a look at how you define the two classes that you need.

The Application Class

The `CWinApp` class is fundamental to any Windows program written using the MFC. An object of this class type includes everything necessary for starting, initializing, running, and closing the application.

You need to derive your own application class from `CWinApp` to produce your application type. You will define a specialized version of the class to suit your application needs. The code for this is as follows:

```
class COurApp: public CWinApp
{
public:
    virtual BOOL InitInstance() override;
};
```

As you might expect for a simple example, there isn't a great deal of specialization necessary. You've only included one member in the definition of the class: the `InitInstance()` function. This function is defined as a virtual function in the base class, so it's an override in your derived class; you are simply redefining the base class function for your application class. All the other data and function members that you need in the class are inherited from `CWinApp`.

The application class is endowed with quite a number of data members, many of which correspond to variables that are used as arguments in Windows API function calls. For example, the `m_pszAppName` member stores a pointer to a string that defines the name of the application. The `m_nCmdShow` member specifies how the application window is to be shown when the application starts up. You don't need to go into all the inherited data members now. You'll see how they are used as the need arises in developing application-specific code.

In deriving your own application class from `CWinApp`, you must implement `InitInstance()`. Your version will be called by the version of `WinMain()` that's provided by the MFC, and you'll include code in the function to create and display your application window. However, before you write `InitInstance()`, I should introduce you to an MFC class that defines a window.

The Window Class

Your MFC application needs a window to provide the interface to the user; this is referred to as a *frame window*. You derive a window class for the application from the MFC class `CFrameWnd`, which is designed specifically for this purpose. Because `CFrameWnd` provides everything for creating and managing an application window, all you need to add to the derived class is a constructor. This will enable you to specify the title bar text for the window to suit the application context:

```
class COurWnd: public CFrameWnd
{
public:
    // Constructor
    COurWnd()
    {
        Create(NULL, _T("Our Dumb MFC Application"));
    }
};
```

The `Create()` function that you call in the constructor is inherited from the base class. It creates the window and attaches it to the `COurWnd` object that is being created. Note that the `COurWnd` object is not the same thing as the window that is displayed by Windows — the class object and the physical window are distinct entities.

The first argument value for the `Create()` function, `NULL`, specifies that you want to use the base class default attributes for the window — you'll recall that you needed to define window attributes in the previous example in this chapter that used the Windows API directly. The second argument specifies the text that is to be displayed in the window title bar. You won't be surprised to learn that there are other parameters to the function `Create()`, but they all have default values that are quite satisfactory so you can ignore them here.

Completing the Program

Having defined a window class for the application, you can implement the `InitInstance()` function in our `COurApp` class:

```
BOOL COurApp::InitInstance(void)
{
    m_pMainWnd = new COurWnd;           // Construct a window object...
    m_pMainWnd->ShowWindow(m_nCmdShow); // ...and display it
    return TRUE;
}
```

This overrides the virtual function defined in the base class `CWinApp`, and as I said previously, it is called by the `WinMain()` function that's automatically supplied by the MFC library. The `InitInstance()` function constructs a main window object for the application in the free store by using the operator `new`. You store the address that is returned in the variable `m_pMainWnd`, which is an inherited member of your `COurApp` class. The effect of this is that the window object is owned by the application object. You don't even need to worry about freeing the memory for the object you have created — the supplied `WinMain()` function takes care of any cleanup necessary.

The only other item you need for a complete, albeit rather limited, program is to define an application object. An instance of our application class, `COurApp`, must exist before `WinMain()` is executed, so you must declare it at global scope with the statement:

```
COurApp AnApplication; // Define an application object
```

The reason that this object needs to exist at global scope is that it encapsulates the application, and the application needs to exist before it can start executing. The `WinMain()` function that is provided by the MFC calls the `InitInstance()` member of the application object to construct the window object, which implies that the application object must already exist.

The Finished Product

Now that you've seen all the code, you can add it to the `Ex11_02.cpp` source file in the project. Classes are usually defined in `.h` files and the member functions that are not defined within the class definitions are defined in `.cpp` files. This application is so short that you may as well put it all in a single `.cpp` file. The merit of this is that you can view the whole lot together. The program code is:

```
// Ex11_02.cpp An elementary MFC program
#include <afxwin.h> // For the class library

// Application class definition
class COurApp:public CWinApp
{
```

```

public:
    virtual BOOL InitInstance() override;
};

// Window class definition
class COurWnd:public CFrameWnd
{
public:
    // Constructor
    COurWnd()
    {
        Create(NULL, _T("Our Dumb MFC Application"));
    }
};

// Function to create an instance of the main application window
BOOL COurApp::InitInstance(void)
{
    m_pMainWnd = new COurWnd;           // Construct a window object...
    m_pMainWnd->ShowWindow(m_nCmdShow); // ...and display it
    return TRUE;
}

// Application object definition at global scope
COurApp AnApplication;             // Define an application object

```

That's all you need. It looks a bit odd because no `WinMain()` function appears, but as I noted previously, there is a `WinMain()` function supplied by the MFC library.

How It Works

Now you're ready to roll, so build and run the application. Select the `Build` \Rightarrow `Build Ex11_02.exe` menu item, click the appropriate toolbar button, or just press F7 to build the solution. You should end up with a clean compile and link, in which case you can press `Ctrl+F5` to run it. Your minimum MFC program appears as shown in Figure 11-5.




FIGURE 11-5

You can resize the window by dragging the border, move the whole thing around, and minimize or maximize it in the usual ways. The only other function that the program supports is “close,” for which you can use the system menu, the Close button at the upper right of the window, or just key Alt+F4. It doesn’t look like much, but considering that there are so few lines of code, it’s quite impressive.

SUMMARY

In this chapter you’ve seen two ways of creating an elementary Windows application with Visual C++. You should now have a feel for the relationship between these two approaches. In subsequent chapters you’ll be exploring in more depth how you develop applications using the MFC.

► WHAT YOU LEARNED IN THIS CHAPTER

TOPIC	CONCEPT
Windows API	The Windows API provides a standard programming interface by which a desktop application communicates with the Windows operating system.
Windows messages	Windows communicates with a desktop application by passing messages to it. A message typically indicates that an event of some kind has occurred that requires action on the part of the application.
Windows application structure	All Windows desktop applications must include two functions, <code>WinMain()</code> and <code>WindowProc()</code> , that will be called by the operating system. You can use any name you like for the <code>WindowProc()</code> function.
The <code>WinMain()</code> function	The <code>WinMain()</code> function is called by the operating system to begin execution of an application. The function includes code to set up the initial conditions required by the application, to specify the application window, and to retrieve messages from the operating system that are intended for the application.
The <code>WindowProc()</code> function	The Windows operating system calls a particular function that is usually called <code>WindowProc()</code> to process messages. A desktop application identifies the message processing function for each application window in <code>WinMain()</code> by passing a pointer to the message processing function to a Windows API function as part of a <code>WNDCLASSEX</code> structure.
The Microsoft Foundation Classes	The MFC consists of a set of classes that encapsulate the Windows API and greatly simplify the development of Windows desktop applications.

12

Windows Programming with the Microsoft Foundation Classes (MFC)

WHAT YOU WILL LEARN IN THIS CHAPTER:

- The basic elements of an MFC-based program
- The difference between Single Document Interface (SDI) applications and Multiple Document Interface (MDI) applications
- How to use the MFC Application Wizard to generate SDI and MDI programs
- The files generated by the MFC Application Wizard and what they contain
- How an MFC Application Wizard-generated program is structured
- The key classes in an MFC Application Wizard-generated program, and how they are interconnected
- How to customize an MFC Application Wizard-generated program

WROX.COM CODE DOWNLOADS FOR THIS CHAPTER

You can find the wrox.com code downloads for this chapter on the Download Code tab at www.wrox.com/remtitle.cgi?isbn=9781118368084. The code is in the Chapter 12 download and individually named according to the names throughout the chapter.

THE MFC DOCUMENT/VIEW CONCEPT

When you write applications using the MFC, it implies acceptance of a specific structure for your program, with application data being stored and processed in a particular way. This may sound restrictive, but it really isn't for the most part, and the benefits in speed and ease of implementation you gain far outweigh any conceivable disadvantages. The structure of an MFC program incorporates two application-oriented entities — a document and a view — so let's look at what they are and how they're used.

What Is a Document?

A *document* is a collection of data in your application with which the user interacts. Although the word *document* seems to imply something of a textual nature, it isn't limited to text. It could be data for a game, a geometric model, a text file, a collection of data on the distribution of orange trees in California, or, indeed, anything you want. The term document is just a convenient label for the application data in your program, treated as a unit.

You won't be surprised to hear that a document is defined as an object of a document class. Your document class is derived from the `CDocument` class in the MFC library, and you add your own data members to store items that your application requires, and member functions to support processing of that data. Your application is not limited to a single document type; you can define multiple document classes when there are several different kinds of documents involved in your application.

Handling application data in this way enables standard mechanisms to be provided within the MFC for managing a collection of application data as a unit and for storing the data on disk. These mechanisms are inherited by your document class from `CDocument`, so you get a broad range of functionality built into your application automatically, without having to write any code.

Document Interfaces

You have a choice as to whether your program deals with just one document at a time, or with several. The *Single Document Interface (SDI)* is supported by the MFC for programs that require only one document to be open at a time. A program using this interface is an *SDI application*.

For programs needing several documents to be open at one time, you can use the *Multiple Document Interface (MDI)*. With the MDI, as well as being able to open multiple documents of one type, your program can also be organized to handle documents of different types simultaneously with each document displayed in its own window. Of course, you need to supply the code to deal with processing all the types of documents you intend to use. In an MDI application, each document is displayed in a child window of the application window. You also have an application variant called the *multiple top-level document architecture* where each document window is a child of the desktop.

What Is a View?

A *view* always relates to a particular document object. A document object contains a set of application data in your program, and a view is an object that provides a mechanism for displaying some or all of that data. A view defines how the data is to be displayed in a window and how the user can

interact with it. You define a view class by deriving it from the MFC class, `CVIEW`. Note that a view object and the window, in which it is displayed, are distinct. The window in which a view appears is called a *frame window*. A view is displayed in its own window that exactly fills the client area of a frame window. Figure 12-1 illustrates how a document might be displayed in two views.




FIGURE 12-1

In Figure 12-1, each view displays all the data that the document contains in a different form, although a view could display just part of the data if that's what's required.

A document object can have as many view objects associated with it as you want. Each view object can provide a different presentation of the document data or a subset of the data. If you were dealing with text, for example, different views could display independent blocks of text from the same document. For a program handling graphical data, you could display the document data at different scales in separate windows, or in different formats, such as a textual representation of the elements that form the image. Figure 12-1 illustrates a document that contains numerical data — product sales data by month — where one view provides a bar chart representation of sales performance and a second view shows the data in the form of a graph.

Linking a Document and Its Views

The MFC incorporates a mechanism for integrating a document with its views, and each frame window with a currently active view. A document object automatically maintains a list of pointers to its associated views, and a view object has a data member holding a pointer to the document to which it relates. Each frame window stores a pointer to the currently active view object. The coordination between a document, a view, and a frame window is established by another MFC class of objects called document templates.

Document Templates

A *document template* manages the document objects in your program, as well as the windows and views associated with each of them. There is one document template for each type of document that you have in your application. If you have two or more documents of the same type, you need only one document template to manage them. A document template object creates document objects and frame window objects, and views for a document are created by a frame window object. The application object that is fundamental to every MFC application creates the document template object. Figure 12-2 shows a graphical representation of these interrelationships.




FIGURE 12-2

Figure 12-2 uses dashed arrows to show how pointers are used to relate objects. These pointers enable function members of one class object to access the public data or function members in the interface of another object.

Document Template Classes

The MFC has two document template classes. `CSingleDocTemplate` is used for SDI applications. This is relatively straightforward because an SDI application has only one document and usually just one view. MDI applications are rather more complicated. They have multiple documents active at

one time and the `CMultiDocTemplate` class defines the document template. You'll see more of these classes as you develop application code.

Your Application and MFC

Figure 12-3 shows the four basic classes that are going to appear in virtually all your MFC-based Windows applications:




FIGURE 12-3

- The application class `CMyApp`
- The frame window class `CMyWnd`
- The view class `CMyView`, which defines how data contained in `CMyDoc` is to be displayed in the client area of a window created by a `CMyWnd` object
- The document class `CMyDoc`, defining a document to contain the application data

The names for these classes are specific to an application, but the derivation from the MFC is much the same, although there can be alternative base classes, particularly with the view class. The

MFC provides several variations of the view class that provide a lot of prepackaged functionality, saving you lots of coding. You normally don't need to extend the document template class so the standard `CSingleDocTemplate` class usually suffices in an SDI program. `CMultiDocTemplate` is the document template class in an MDI program and this is also derived from `CDocTemplate`. An MDI application also contains an additional class that defines a child window.

The arrows in Figure 12-3 point from a derived class to a base class. The MFC classes shown here form quite a complex inheritance structure, but these are just a very small part of the complete MFC structure. You need not be concerned about the details of the complete MFC hierarchy, but it is important to have a general appreciation of it if you want to understand what the inherited members of your classes are. You will not see any of the definitions of the base classes in your code, but the inherited members in a derived class are accumulated from the direct base class and each of the indirect base classes in the hierarchy. To determine what members one of your program's classes has, you need to know from which classes it inherits. After you know that, you can look up its members using the Help facility.

You don't need to worry about remembering which classes you need to have in your program and what base classes to use in their definition. As you'll see next, all of this is taken care of for you by Visual C++.

CREATING MFC APPLICATIONS

You use four primary tools in the development of your MFC-based Windows programs:

1. An *Application Wizard* for creating the basic application program code when you start. You use an Application Wizard whenever you create a project.
2. The *project context menu* in Class View enables you to add new classes and resources to a project. You display this menu by right-clicking the project name in the Class View pane and using the Add/Class menu item to add a new class. Resources are composed of non-executable data such as bitmaps, icons, menus, and dialog boxes. The Add/Resource menu item from the same menu helps you to add a new resource.
3. The *class context menu* in Class View enables you to extend and customize classes in your program. You use the Add/Add Function and Add/Add Variable menu items to do this.
4. You use a *Resource Editor* for creating or modifying resources such as menus and toolbars.

There are several resource editors; the one you use in any particular situation depends on the kind of resource that you're editing. You'll look at editing resources in the next chapter, but for now, let's jump in and create an MFC application.

Creating an MFC application is just as straightforward as creating a console program; there are just a few more choices along the way. As you have already seen, you start by creating a new project by selecting the File \Rightarrow New \Rightarrow Project menu item, or you can use the shortcut and press Ctrl+Shift+N. The New Project dialog box is displayed, where you can choose MFC as the project type and MFC Application as the template to be used. You also need to enter a name for the project, which can be anything you want — I've used `TextEditor`. You won't be developing this particular example into a serious application, so you can use any name you like.

The name that you assign to the project — `TextEditor` in this case — is used as the name of the folder that contains all the project files. It is also used as the basis for creating the names for classes that the Application Wizard generates for your project. When you click OK in the New Project dialog window, you'll see the MFC Application Wizard dialog, where you can choose options for the application, as shown in Figure 12-4.




FIGURE 12-4

The dialog explains the project settings that are currently in effect, and in the left pane you have a range of options you can select. You can choose any of these to have a look if you want — you can always get back to the base dialog box by selecting the Overview option. Selecting any of the options on the left presents you with a range of further choices, so there are a lot of options in total. I won't discuss all of them — I'll just outline the ones that you are most likely to be interested in and leave you to investigate the others. Selecting Application Type enables you to choose from an SDI application, an MDI application that optionally can be tabbed, a dialog-based application, or an application with multiple top-level documents. Let's create an SDI application first and explore what some of the choices are.

Creating an SDI Application

Select the Application Type option from the list in the left dialog pane. The default option selected is Multiple documents with the tabbed option, which selects the MDI with each document in its own tabbed page; the appearance of this is shown at the top left in the dialog so that you'll know what to expect. Select the Single document Application type option, the MFC standard Project style option, and the Windows Native/Default option from the drop-down list of visual styles. The representation for the application that is shown top-left changes to a single window, as shown in Figure 12-5.




FIGURE 12-5

Some of the other options you have for the application type are:

OPTION	DESCRIPTION
Dialog based	The application window is a dialog window rather than a frame window.
Multiple top-level documents	Documents are displayed in child windows of the desktop rather than child windows of the application as they are with an MDI application.
Document/View architecture support	This option is selected by default so you get code built in to support the document/view architecture. If you uncheck this option, the support is not provided and it's up to you to implement whatever you want.
Resource language	The list box displays the choices available that apply to resources such as menus and text strings.
Use Unicode libraries	Support for Unicode is provided through Unicode versions of the MFC libraries. If you want to use them, you must check this option. Some functionality in MFC is only available when you use Unicode libraries.
Project style	Here you can choose the visual appearance of the application window. Your choice will depend on the environment in which you want to run the application and the kind of application. For example, you would select the Office option for a Microsoft Office-related application.

If you hover the mouse cursor over any of the options, a tooltip will be displayed explaining the option. You can leave the Use Unicode libraries option checked by default. If you uncheck it, some of the capabilities that the MFC offers will not be available.

You have several options for the Project style. I'll select the MFC Standard option and suggest that you do the same. I also selected Windows Native /Default from the Visual style and colors drop-down list. This makes the application appearance the same as your current operating system. If you have Windows 7 installed, you can select the Windows 7 option.

You can also choose how the MFC library is used in your project. The default choice of using the MFC library as a shared DLL (*Dynamic Link Library*) means that your program links to MFC routines at run time. This reduces the size of the executable file that you'll generate, but requires the MFC DLL to be on the machine that's running it. Your application's .exe module and the MFC .dll together may be bigger than if you statically link the MFC library. If you opt for static linking, the MFC library routines are included in the executable module for your program when it is built. Statically linked applications run slightly faster than those that are dynamically linked, so it's a tradeoff between memory usage and speed of execution. If you keep the default option, several programs running simultaneously using the dynamic link library can all share a single copy of the library in memory.

If you select Document Template Properties in the left pane of the dialog, you can enter a file extension for files that the program creates in the right pane. The extension `.txt` is a good choice for this example. You can also enter a Filter Name, which is the name of the filter that will appear in Open and Save As dialogs to filter the file list so only files with your file extension are displayed.

If you select User Interface Features from the list in the left pane, you get a further set of options that can be included in your application:

OPTION	DESCRIPTION
Thick Frame	Enables you to resize the application window by dragging a border. It is selected by default.
Minimize box	This is also selected by default and provides a minimize box at the top right of the application window.
Maximize box	This option is also selected by default and provides a maximize box at the top right of the application window.
Minimized	If you select this option, the application starts with the window minimized so it appears as an icon.
Maximized	With this option selected, the application starts with the window maximized.
System Menu	This provides the main application window with a control-menu box in the title bar.
About box	This provides your application with an About dialog.
Initial status bar	This adds a status bar at the bottom of the application window containing indicators for CAPS LOCK, NUM LOCK, and SCROLL LOCK and a message line that displays help strings for menus and toolbar buttons. It also adds menu commands to hide or show the status bar.
Split window	This provides a splitter bar for each of the application's main views.

In the Command bars sub-options you can choose whether you use a classic Windows menu with a docking toolbar, an Internet Explorer style toolbar, a menu bar and toolbar that you can customize at run time, or a ribbon. The User-defined toolbars and images sub-option allows the toolbar and images to be customized at run time. The Personalized menu behavior sub-option enables menus to display only the items used most frequently. You would typically use a ribbon with applications that complement Microsoft Office. In this example, we will use the classic menu with a classic docking toolbar.

You should be aware of a couple of features under the Advanced Features set of options. One is Printing and print preview, which is selected by default, and the other is the number of files on the recent file list. You can increase the latter to whatever you think is useful for the application. Printing and print preview add the standard Page Setup, Print Preview, and Print items to the File menu, and the Application Wizard also provides code to support these functions. You can uncheck all the other options for the example.

The Generated Classes option in the left pane of the dialog displays a list of the classes that will be generated, as shown in Figure 12-6.

You can highlight any class in the list by clicking it, and the boxes below show the class name, the header filename in which the class definition will be stored, the base class, and the name of the source file containing the implementation of the class. The class definition is always in an .h file, and the member function definitions are always in a .cpp file.




FIGURE 12-6

You can alter everything except the base class for the `CTextEditorDoc` class. The only thing you can change for `CTextEditorApp` is the class name. Try clicking the other classes in the list. For `CMainFrame`, you can alter everything except the base class, and for the `CTextEditorView` class shown in Figure 12-6, you can change the base class as well. Click the down arrow to display the list of other classes that you can have as a base class. The capability built into your view class depends on which base class you select:

BASE CLASS	VIEW CLASS CAPABILITY
CEditView	Provides simple multiline text-editing capability, including find and replace, and printing.
CFormView	Provides a view that is a form; a form is a dialog that can contain controls for displaying data and for input.
CHtmlEditView	Extends the CHtmlView class and adds the ability to edit HTML pages.
CHtmlView	Provides a view in which web pages and local HTML documents can be displayed.
CLListView	Enables you to use the document-view architecture with list controls.
CRichEditView	Provides the capability to display and edit documents containing rich edit text.
CScrollView	Provides a view that automatically adds scrollbars when the data that is displayed requires them.
CTreeView	Provides the capability to use the document-view architecture with tree controls.
CView	Provides the basic capability for viewing a document.

Because you've called the application `TextEditor`, with the notion that it is able to edit text, choose `CEditView` to get basic text editing. You can now click Finish to generate the program files for a fully working base program using the options you've chosen. This will take a little while.

MFC Application Wizard Output

All the program files generated by the Application Wizard are stored in the `TextEditor` project folder, which is a subfolder to the solution folder with the same name. There are resource files in the `res` subfolder to the project folder. The IDE provides several ways for you to view the information relating to your project:

TAB/PANE	CONTENTS
Solution Explorer	Shows the files included in your project. The files are categorized in virtual folders with the names <code>Header Files</code> , <code>Resource Files</code> , and <code>Source Files</code> .
Class View	Displays the classes in your project and their members and any global entities. The classes are shown in the upper pane, and the lower pane displays the members for the class selected in the upper pane. By right-clicking entities in Class View, you can display a menu that you can use to view the definition of the entity or where it is referenced.
Resource View	Displays resources such as menu items and toolbar buttons used by your project. Right-clicking a resource displays a menu for editing the resource or adding new resources.

continues

(continued)

TAB/PANE	CONTENTS
Property Manager	Displays the versions you can build for your project. The debug version includes extra facilities to make debugging easier. The release version results in a smaller executable, and you build this version when your code is fully tested. By right-clicking a version you can display a context menu where you can add a property sheet or display the properties currently set for that version. A property sheet enables you to set options for the compiler and linker.

You can switch to view any of these by selecting from the View menu or clicking on a tab label. If you right-click `TextEditor` in the Solution Explorer pane and select Properties from the pop-up, the project properties window is displayed, as shown in Figure 12-7.

The left pane shows the property groups you can select to be displayed in the right pane. Currently, the General group of properties is displayed. You can change the value for a property in the right pane by clicking it and selecting a new value from the drop-down list box to the right of the property name or, in some cases, by entering a new value.

At the top of the property pages window, you can see the current project configuration and the target platform when the project is built. You can change these by selecting from the drop-down list for each. By selecting All Configurations you can change properties for both the Debug and Release configurations.




FIGURE 12-7

Viewing Project Files

The left pane in the IDE can display several tabs. The most useful are the Solution Explorer, Class View, and Resource View tabs.

You can hide the currently visible tab by clicking the down arrow in the top right of the pane and selecting Hide from the menu. I'll just show the three interesting tabs in figures. I'll also show the pane as an undocked window, which you get by dragging its title bar away from the edge of the main window.

If you select the Solution Explorer tab and expand the list by clicking the arrow symbol for `TextEditor` files and then click the arrow symbol for each of the Source Files, Header Files, and Resource Files folders, you'll see the complete list of files for the project, as shown in Figure 12-8. To collapse any expanded branch of the tree, just click the arrow symbol.

There are a total of 18 files shown in the project, excluding `ReadMe.txt`. You can view the contents of any file by double-clicking the filename. The contents of the file selected are displayed in the Editor window. Try it out with the `ReadMe.txt` file. You'll see that it contains a brief explanation of the contents of each of the files that make up the project. I won't repeat the descriptions of the files here, because they are very clearly summarized in `ReadMe.txt`.




FIGURE 12-8

Viewing Classes

The Class View tab is often more convenient than the Solution Explorer tab because classes are the basis for the organization of the application. When you want to look at the code, it's typically a class definition or the implementation of a member function you want, and from Class View you can go directly to either. The Solution Explorer pane comes in handy when you want to check the `#include` directives in a .cpp file. From Solution Explorer you can open the file you're interested in directly.

In the Class View pane, you can expand the `TextEditor` classes item to show the classes defined for the application. Clicking the name of any class shows the members of that class in the lower pane. In the Class View pane shown in Figure 12-9, the `CTextEditorDoc` class has been selected.

The icons characterize the things that are displayed. You will find a key to what the icons indicate in the Class View documentation. Search for “Class View and Object Browser Icons.” You can see that you have the four classes that I discussed earlier that are fundamental to an MFC application: `CTextEditorApp` for the application, `CMainFrame`




FIGURE 12-9

for the application frame window, `CTextEditorDoc` for the document, and `CTextEditorView` for the view. You also have a `CAboutDlg` class that defines objects that support the dialog box that appears when you select the menu item Help \Rightarrow About in the application. If you select Global Functions and Variables, you'll see that it contains three items, as in Figure 12-10.

The application object, `theApp`, appears twice because there is an `extern` statement for `theApp` in `TextEditor.h` and a definition for it in `TextEditor.cpp`. If you double-click either of the appearances of `theApp`, it will take you to the corresponding statement. `indicators` is an array of four IDs for items that appear in the status bar: a separator, caps lock status, num lock status, and scroll lock status.

To view the code for a class definition in the Editor pane, you double-click the class name in Class View. Similarly, to view the code for a member function, double-click the function name. Note that you can drag the edges of any of the panes in an IDE window to view its contents or your code more easily. You can hide or show the set of panes by clicking the close button at the right end of the pane title bar.

The Class Definitions

I won't go into the application classes in complete detail here — you'll just get a feel for how they look and I'll highlight a few important aspects. The precise content of each class that is generated depends on the options you select when creating the project. If you double-click the name of a class in the Class View, the code defining the class is displayed.

The Application Class

Take a look at the application class, `CTextEditorApp`, first. The definition for this class is shown here:

```
// TextEditor.h : main header file for the TextEditor application
//
#pragma once

#ifndef __AFXWIN_H__
#error "include 'stdafx.h' before including this file for PCH"
#endif

#include "resource.h"           // main symbols

// CTextEditorApp:
// See TextEditor.cpp for the implementation of this class
//
```




FIGURE 12-10

```

class CTextEditorApp : public CWinApp
{
public:
    CTextEditorApp();

// Overrides
public:
    virtual BOOL InitInstance();

// Implementation
    afx_msg void OnAppAbout();
    DECLARE_MESSAGE_MAP()
};

extern CTextEditorApp theApp;

```

The `CTextEditorApp` class derives from `CWinApp` and includes a constructor, a virtual function `InitInstance()`, a function `OnAppAbout()`, and a macro `DECLARE_MESSAGE_MAP()`.

NOTE A macro is not C++ code. It's a name defined by a `#define` pre-processor directive that will be replaced by some text that will normally be code but could also be constants or symbols of some kind.

The `DECLARE_MESSAGE_MAP()` macro is concerned with defining which Windows messages are handled by which function members of the class. The macro appears in the definition of any class that can process Windows messages. Of course, our application class inherits a lot of functions and data members from the base class, and you will be looking further into these as you expand the program examples. If you look at the beginning of the code for the class definition, you will notice that the `#pragma once` directive prevents the file being included more than once. Following that is a group of preprocessor directives that ensure that the `stdafx.h` file is included before this file.

The Frame Window Class

The application frame window for our SDI program is created by an object of the class `CMainFrame`, which is defined by the following code:

```

// MainFrm.h : interface of the CMainFrame class
//

#pragma once

class CMainFrame : public CFrameWnd
{

```

```

protected: // create from serialization only
    CMainFrame();
DECLARE_DYNCREATE(CMainFrame)

// Attributes
public:

// Operations
public:

// Overrides
public:
    virtual BOOL PreCreateWindow(CREATESTRUCT& cs);

// Implementation
public:
    virtual ~CMainFrame();
#ifdef _DEBUG
    virtual void AssertValid() const;
    virtual void Dump(CDumpContext& dc) const;
#endif

protected: // control bar embedded members
    CToolBar         m_wndToolBar;
    CStatusBar       m_wndStatusBar;

// Generated message map functions
protected:
    afx_msg int OnCreate(LPCREATESTRUCT lpCreateStruct);
DECLARE_MESSAGE_MAP()

};


```

This class is derived from `CFrameWnd`, which provides most of the functionality required for our application frame window. The derived class includes two protected data members — `m_wndToolBar`, and `m_wndStatusBar`, which are instances of the MFC classes `CToolBar`, and `CStatusBar`, respectively. The toolbar provides buttons to access standard menu functions, and the status bar appears at the bottom of the application window.

The Document Class

The definition of the `CTextEditorDoc` class that was created is:

```

// TextEditorDoc.h : interface of the CTextEditorDoc class
//

#pragma once

class CTextEditorDoc : public CDocument
{
protected: // create from serialization only

```

```

CTextEditorDoc();
DECLARE_DYNCREATE(CTextEditorDoc)

// Attributes
public:

// Operations
public:

// Overrides
public:
    virtual BOOL OnNewDocument();
    virtual void Serialize(CArchive& ar);
#ifndef SHARED_HANDLERS
    virtual void InitializeSearchContent();
    virtual void OnDrawThumbnail(CDC& dc, LPRECT lprcBounds);
#endif // SHARED_HANDLERS

// Implementation
public:
    virtual ~CTextEditorDoc();
#ifndef _DEBUG
    virtual void AssertValid() const;
    virtual void Dump(CDumpContext& dc) const;
#endif

protected:

// Generated message map functions
protected:
    DECLARE_MESSAGE_MAP()

#ifndef SHARED_HANDLERS
    // Helper function that sets search content for a Search Handler
    void SetSearchContent(const CString& value);
#endif // SHARED_HANDLERS

#ifndef SHARED_HANDLERS
private:
    CString m_strSearchContent;
    CString m_strThumbnailContent;
#endif // SHARED_HANDLERS
};

```

Most of the meat comes from the base class and is therefore not apparent here. The `DECLARE_DYNCREATE()` macro that appears after the constructor (and was also used in `CMainFrame`) enables an object of the class to be created dynamically by synthesizing it from data from a file. When you save an SDI document object, the frame window that contains the view is saved along with your data. This allows everything to be restored when you read it back. Reading and writing a document object to a file is supported by a process called *serialization*. You will see how to serialize your own documents and then read them back in the examples we will develop.

The document class also includes the `DECLARE_MESSAGE_MAP()` macro to enable Windows messages to be handled by class member functions.

The View Class

The view class in our SDI application is defined as:

```
// TextEditorView.h : interface of the CTextEditorView class
//

#pragma once

class CTextEditorView : public CEditView
{
protected: // create from serialization only
    CTextEditorView();
    DECLARE_DYNCREATE(CTextEditorView)

// Attributes
public:
    CTextEditorDoc* GetDocument() const;

// Operations
public:

// Overrides
public:
    virtual BOOL PreCreateWindow(CREATESTRUCT& cs);
protected:
    virtual BOOL OnPreparePrinting(CPrintInfo* pInfo);
    virtual void OnBeginPrinting(CDC* pDC, CPrintInfo* pInfo);
    virtual void OnEndPrinting(CDC* pDC, CPrintInfo* pInfo);

// Implementation
public:
    virtual ~CTextEditorView();
#ifndef _DEBUG
    virtual void AssertValid() const;
    virtual void Dump(CDumpContext& dc) const;
#endif

protected:

// Generated message map functions
protected:
    DECLARE_MESSAGE_MAP()
};

#ifndef _DEBUG // debug version in TextEditorView.cpp
inline CTextEditorDoc* CTextEditorView::GetDocument() const
    { return reinterpret_cast<CTextEditorDoc*>(m_pDocument); }
#endif
```

As you specified in the Application Wizard dialog, the view class is derived from `CEditView`, which already includes basic text handling facilities. The `GetDocument()` function returns a pointer to the document object corresponding to the view, and you use this to access data in the document object.

when you add your own extensions to the view class that allow user interactions to add to or modify the document data.

There are two implementations for the `GetDocument()` member of the `CTextEditorView` class in the code generated by Application Wizard. The one in the `.cpp` file for the `CTextEditorView` class is used for the debug version of the program. You will normally use this during program development because it provides validation of the pointer value stored for the document. (This is stored in the inherited data member `m_pDocument` in the view class.) The version that applies to the release version of your program you can find after the class definition in the `TextEditorView.h` file. This version is declared as `inline` and it does not validate the document pointer. The `GetDocument()` function provides the view object with access to the document object. You can call any of the functions in the interface to the document class using the pointer to the document that the function returns.

By default, you have debug capability included in your program. As well as the special version of `GetDocument()`, there are lots of checks in the MFC code that are included in this case. If you want to change this, you can use the drop-down list box in the Build toolbar to choose the release configuration, which doesn't contain the debug code.

Creating an Executable Module

To compile and link the program, you can click Build \Leftrightarrow Build Solution, or press F7, or click the Build icon in the toolbar.

The first time you compile and link a program, it will take some time. The second and subsequent times should be quite a bit faster because of a feature of Visual C++ called *precompiled headers*. During the initial compilation, the compiler saves the output from compiling header files in a special file with the extension `.pch`. On subsequent builds, if the source in a header has not changed, the compiler will skip compiling the header and use the precompiled code, thus saving the compilation time for the header.

You can determine whether or not precompiled headers are used and control how they are handled through the Properties dialog. Right-click `TextEditor` in Class View and select Properties from the menu. If you expand the C/C++ node in the dialog, you can select Precompiled Headers to set or unset this property.

Running the Program

To execute the program, press Ctrl+F5. Because you chose `CEditView` as the base class for the `CTextEditorView` class, the program is a fully functioning, simple text editor. You can enter text in the window, as shown in Figure 12-11.

Note that the application has scroll bars for viewing text outside the visible area within the window, and, of course, you can resize the window by dragging the boundaries. All the items under all menus are fully operational so you can save and retrieve files, you can cut and paste text, and you can print the




FIGURE 12-11

text in the window — and all that without writing a single line of code! As you move the cursor over the toolbar buttons or the menu options, prompts appear in the status bar describing their functions, and if you let the cursor linger on a toolbar button, a tooltip is displayed showing its purpose. (You'll learn about tooltips in more detail in Chapter 13.)

How the Program Works

The application object is created at global scope in the program. You can see this if you expand the Global Functions and Variables item in the Class View, and then double-click `theApp`. In the Editor window, you'll see this statement:

```
CTextEditorApp theApp;
```

This declares `theApp` as an instance of our application class `CTextEditorApp`. The statement is in `TextEditor.cpp`, which also contains member function declarations for the application class, and the definition of the `CAboutDlg` class.

After `theApp` has been created, the MFC-supplied `WinMain()` function is called. This calls two member functions of the `theApp` object. First, it calls `InitInstance()`, which provides for any initialization of the application that is necessary, and then the `Run()` function that is inherited from `CWinApp`, which provides initial handling for Windows messages. If you want to see the code for `CWinApp` functions, extend the tree for `CTextEditorApp` in Class View and extend Base Types. You can then click on `CWinApp` to see the members in the lower pane. `WinMain()` does not appear explicitly in the project source code, because it is supplied by the MFC class library and is called automatically when the application starts.

The `InitInstance()` Function

You can access the code for the `InitInstance()` function by double-clicking its entry in the Class View after highlighting the `CTextEditorApp` class — or, if you're in a hurry, you can just look at the code immediately following the line defining the `theApp` object. There's a lot of code in the version created by the MFC Application Wizard, so I just want to remark on a couple of fragments in this function. The first is:

```
SetRegistryKey(_T("Local AppWizard-Generated Applications"));
LoadStdProfileSettings(4); // Load standard INI file options (including MRU)
```

The string passed to the `SetRegistryKey()` function defines a registry key under which program information is stored. You can change this to whatever you want. If I changed the argument to "Horton," information about our program would be stored under the registry key:

```
HKEY_CURRENT_USER\Software\Horton\TextEditor\
```

All the application settings are stored under this key, including the most recently used files list. The call to `LoadStdProfileSettings()` loads the application settings that were saved last time around. Of course, the first time you run the program, there aren't any.

A document template object is created dynamically within `InitInstance()` by the following statement:

```
pDocTemplate = new CSingleDocTemplate(
    IDR_MAINFRAME,
```

```
RUNTIME_CLASS(CTextEditorDoc),
RUNTIME_CLASS(CMainFrame),           // main SDI frame window
RUNTIME_CLASS(CTextEditorView));
```

The first parameter to the `CSingleDocTemplate` constructor is a symbol, `IDR_MAINFRAME`, which defines the menu and toolbar to be used with the document type. The following three parameters define the document, the mainframe window, and the View Class objects that are to be bound together within the document template. Because you have an SDI application here, there is only one of each in the program, managed through one document template object. `RUNTIME_CLASS()` is a macro that enables the type of a class object to be determined at run time.

There's a lot of other stuff here for setting up the application instance that you need not worry about. You can add any initialization of your own that you need for the application to the `InitInstance()` function.

The Run() Function

The `CTextEditorApp` class inherits the `Run()` function from `CWinApp`. Because the function is declared as *virtual*, you could replace the inherited version of the function `Run()` with your own, but this is not usually necessary. `Run()` receives all the messages from Windows destined for the application and ensures that each message is passed to the function in the program designated to service it, if one exists. Therefore, this function continues executing as long as the application runs.

You can boil the operation of the application down to four steps:

- 1.** Creating an application object, `theApp`.
- 2.** Executing `WinMain()`, which is supplied by MFC.
- 3.** `WinMain()` calling `InitInstance()`, which creates the document template, the mainframe window, the document, and the view.
- 4.** `WinMain()` calling `Run()`, which executes the main message loop to acquire and dispatch Windows messages.

Creating an MDI Application

Now let's create an MDI application using the MFC Application Wizard. Press **Ctrl+Shift+N** and give the project the name **Sketcher** — and plan on keeping it. You'll be expanding this into a sketching program during subsequent chapters. You should have no trouble with this procedure, because there are only a few things that you need to do differently from creating the SDI application.

- 1.** For the Application Type group of options:
 - Leave the default option, Multiple documents, but opt out of Tabbed documents.
 - Keep Document/View architecture support.
 - Select MFC standard as the project style and Windows Native/Default as the Visual style and colors option.
 - Keep the Use Unicode libraries option.

- 2.** Compound Document Support options should be the default selection, `None`.
- 3.** For the Document Template Properties set of options in the dialog:
 - Specify the file extension as `ske`. You'll see that you automatically get a filter for `*.ske` documents defined.
 - Change the `Doc` type name to `Sketch`.
 - Change the `File new` short name to `Sketch`.
- 4.** Leave the Database Support options at the default settings, `None`.
- 5.** For the User Interface Features options:
 - Keep `Use a classic menu`, and the sub-option, `Use a classic docking toolbar`.
 - Keep the other options that are selected by default: `Thick frame`, `Minimize box`, `Maximize box`, `System menu`, `Initial status bar`, `Child minimize box` and `Child maximize box`.
- 6.** For the Advanced features set of options:
 - Keep the `Printing` and `print preview` option.
 - Deselect `ActiveX controls`, `Common Control Manifest`, and `Support Restart Manager`.
- 7.** Leave the Generated Classes options at the default settings so the base class for the `CSketcherView` class is `CView`.

You can see in the dialog with Generated Classes selected that you get an extra class for your application compared with the `TextEditor` example, the `cChildFrame` class, which is derived from `CMDIChildWnd`. This class provides a frame window for a view of the document that appears inside the application window created by a `CMainFrame` object. With an SDI application, there is a single document with a single view, so the view is displayed in the client area of the mainframe window. In an MDI application, you can have multiple documents open, and each document can have multiple views. To provide for this, each document view has its own child frame window created by a `cChildFrame` object. As you saw earlier, a view is displayed in a separate window, but one which exactly fills the client area of a frame window. Finally, click `Finish` to generate the project.

Running the Program

You can build and run the program by pressing `Ctrl+F5`. You get the application window shown in Figure 12-12.

In addition to the main application window, you have a separate document window with the caption `Sketch1`. `Sketch1` is the default name for the initial document, and it has the extension `.ske` if you save it. You can create additional views for




FIGURE 12-12

the document by selecting the Window \Rightarrow New Window menu option. You can also create a new document by selecting File \Rightarrow New, so that there will be two active documents in the application. The situation with two views open for a document, is shown in Figure 12-13.

You can expand either sketch window to fill the client area. You can then switch between the sketch windows through the Window drop-down menu. You can't yet actually create any data in the application because we haven't added any code to do that, but all the code for creating documents and views has already been included by the Application Wizard.




FIGURE 12-13

SUMMARY

In this chapter, you've been concerned mainly with the mechanics of using the MFC Application Wizard. You have seen the basic components of the MFC programs that the Application Wizard generates for both SDI and MDI applications. All our MFC examples are created by the MFC Application Wizard, so it's a good idea to keep the general structure and broad class relationships in mind. You probably won't feel too comfortable with the detail at this point, but don't worry about that now. You'll find that it becomes much clearer after you begin developing applications in the succeeding chapters.

EXERCISES

It isn't possible to give programming examples for this chapter, because it really just introduced the basic mechanics of creating MFC applications. There aren't solutions to all the exercises because you will either see the answer for yourself on the screen, or be able to check your answer back with the text.

- 1.** What is the relationship between a document and a view?
- 2.** What is the purpose of the document template in an MFC Windows program?
- 3.** Why do you need to be careful, and plan your program structure in advance, when using the Application Wizard?
- 4.** Code up the simple text editor program. Build both debug and release versions, and examine the types and sizes of the files produced in each case.
- 5.** Generate the text editor application several times, trying different project styles from the Application Type in Application Wizard.

► WHAT YOU LEARNED IN THIS CHAPTER

TOPIC	CONCEPT
The Application Wizard	The MFC Application Wizard generates a complete, working, framework Windows application for you to customize to your requirements.
SDI and MDI programs	The Application Wizard can generate single-document interface (SDI) applications that work with a single document and a single view, or multiple-document interface (MDI) programs that can handle multiple documents with multiple views simultaneously.
Classes in SDI programs	The four essential classes in an SDI application that are derived from the foundation classes are the application class, the frame window class, the document class, and the view class.
The application object	A program can have only one application object. This is defined automatically by the Application Wizard at global scope.
Document objects	A document class object stores application-specific data, and a view class object displays the contents of a document object.
Document templates	A document template class object is used to tie together a document, a view, and a window. For an SDI application, a <code>CSingleDocTemplate</code> class does this, and for an MDI application, the <code>CMultiDocTemplate</code> class is used. These are both foundation classes, and application-specific versions do not normally need to be derived.

13

Working with Menus and Toolbars

WHAT YOU WILL LEARN IN THIS CHAPTER:

- How an MFC-based program handles messages
- How you create and modify menu resources
- How you create and modify menu properties
- How to create functions to service menu messages
- How to add handlers to update menu properties
- How to add toolbar buttons associated with menu items

WROX.COM CODE DOWNLOADS FOR THIS CHAPTER

You can find the wrox.com code downloads for this chapter on the Download Code tab at www.wrox.com/remtitle.cgi?isbn=9781118368084. The code is in the Chapter 13 download and individually named according to the names throughout the chapter.

COMMUNICATING WITH WINDOWS

Windows communicates with your program by sending messages to it. Most of the drudgery of message handling is taken care of in an MFC application, so you don't have to worry about providing a `WndProc()` function. The MFC enables you to provide functions to handle the individual messages that you're interested in and to ignore the rest. These functions are referred to as *message handlers* or just *handlers*. In an MFC-based program, a message handler is always a member of one of your application's classes.

The association between a particular message and a function in your program that is to service it is established by a *message map*, and each class in your program that handles Windows messages will have one. A message map is a table of member functions that handle Windows messages and the map bounded by a couple of macros. The start of a message map is indicated by a `BEGIN_MESSAGE_MAP()` macro, and the end is marked by an `END_MESSAGE_MAP()` macro. Each entry in the message map associates a member function with a particular message; when a given message occurs, the corresponding function is called. Only the messages that are relevant to a class appear in its message map.

A message map for a class is created by the MFC Application Wizard when you create a project, or by Class Wizard when you add a class that handles messages. Additions to, and deletions from, a message map are mainly managed by Class Wizard, but there are circumstances in which you need to modify a message map manually. Let's look into how a message map operates using the Sketcher example.

Understanding Message Maps

A message map is established by the MFC Application Wizard for each of the classes in your program. In Sketcher `CSketcherApp`, `CSketcherDoc`, `CSketcherView`, `CMainFrame`, and `CCChildFrame` each have a message map. The message map for a class appears in the `.cpp` file. Of course, the functions that are in the message map are also declared in the class, but they are identified in the message map in a special way. Look at the definition for `CSketcherApp` in `Sketcher.h`:

```
class CSketcherApp : public CWinApp
{
public:
    CSketcherApp();

// Overrides
public:
    virtual BOOL InitInstance();
    virtual int ExitInstance();

// Implementation
afx_msg void OnAppAbout();
DECLARE_MESSAGE_MAP()
};
```

`OnAppAbout()` is the only message handler declared in the class. The `afx_msg` at the beginning of the line declaring the `OnAppAbout()` function identifies it as a message handler. `afx_msg` has no other purpose and is converted to white space by the preprocessor, so it has no effect when the program is compiled.

The `DECLARE_MESSAGE_MAP()` macro indicates that the class can contain members that are message handlers and therefore will have a message map in the `.cpp` file. Any class that has `CCmdTarget` as a direct or indirect base class can have message handlers, so such classes will always have this macro included as part of the class definition, either by the MFC Application Wizard or by the Add Class Wizard that you use to add a new class. The `CSketcherApp` class has `CCmdTarget` as an indirect

base and therefore always includes the `DECLARE_MESSAGE_MAP()` macro. All the other application classes in Sketcher are ultimately derived from `CCmdTarget` too, so they all can handle Windows messages.

When you add your own members directly to a class, it's best to leave the `DECLARE_MESSAGE_MAP()` macro as the last line in the class definition. If you do add members after `DECLARE_MESSAGE_MAP()`, you'll need to include an access specifier for them: `public`, `protected`, or `private`.

Message Handler Definitions

A class definition that includes the `DECLARE_MESSAGE_MAP()` macro will have the `BEGIN_MESSAGE_MAP()` and `END_MESSAGE_MAP()` macros in its `.cpp` file. If you look in `Sketcher.cpp`, you'll see the following code as part of the implementation of `CSketcherApp`:

```
BEGIN_MESSAGE_MAP(CSketcherApp, CWinApp)
    ON_COMMAND(ID_APP_ABOUT, &CSketcherApp::OnAppAbout)
    // Standard file based document commands
    ON_COMMAND(ID_FILE_NEW, &CWinApp::OnFileNew)
    ON_COMMAND(ID_FILE_OPEN, &CWinApp::OnFileOpen)
    // Standard print setup command
    ON_COMMAND(ID_FILE_PRINT_SETUP, &CWinApp::OnFilePrintSetup)
END_MESSAGE_MAP()
```

This is a message map. The `BEGIN_MESSAGE_MAP()` and `END_MESSAGE_MAP()` macros define its boundaries, and each message handler in the class appears between these macros. These message handlers are all dealing with the same type of message, `WM_COMMAND` messages. These are called *command messages*. A command message is generated when the user selects a menu option or enters an accelerator key. (There's another kind of `WM_COMMAND` message called a *control notification message*, which provides information about the activity of a control.)

The message map identifies the menu item or key press that will cause a handler to be called by an identifier (ID) that's included in the message handler macro. There are four `ON_COMMAND` macros in the preceding code, one for each of the command messages to be handled by the `CSketcherApp` object. The first argument to an `ON_COMMAND` macro is an ID identifying a particular command source, and the macro ties the address of a function (i.e., a pointer to a function) to commands originating from the source specified by the ID. Thus, when a command message corresponding to the identifier `ID_APP_ABOUT` is received, the `OnAppAbout()` function is called. Similarly, for a command message corresponding to the `ID_FILE_NEW` identifier, `OnFileNew()` is called. This handler is inherited from the base class, `CWinApp`, as are the two remaining handlers.

The `BEGIN_MESSAGE_MAP()` macro has two arguments. The first identifies the class name for which the message map is defined, and the second identifies the base class that will be searched for a message handler when a handler isn't found in the class that defined the message map.

Command IDs for messages from standard menu items and toolbar buttons such as `ID_APP_ABOUT` are defined in the MFC. The `ID_` prefix identifies a command as associated with a menu item or a toolbar button, as you'll see when I discuss resources later. For example, `ID_FILE_NEW` is the ID that corresponds to the selection of the File ⇔ New menu item, and `ID_APP_ABOUT` corresponds to Help ⇔ About.

The `WM_` prefix for message IDs stands for “Windows message.” There are many other identifiers for Windows messages and these are defined in `winuser.h` along with a lot of other stuff. This header is included in `Windows.h`. If you want to look at the message IDs, you’ll find `winuser.h` in the `C:\Program Files (x86)\Windows Kits\8.0\Include\um` folder.

NOTE There’s a nice shortcut for viewing any `.h` file that appears in an `#include` directive in the editor window — you can right-click the name and select Open Document “`Filename.h`” from the menu. This works with standard library header files as well as those you have created.

Windows messages often have additional data values that refine the identification of a particular message specified by a given ID. The `WM_COMMAND` message, for instance, is sent for a range of commands, including those originating from the selection of a menu item or a toolbar button.

When you are adding message handlers manually, you should not map a message (or, in the case of command messages, a command ID) to more than one message handler. If you do, it won’t break anything, but the second message handler is never called. Normally, you add message handlers through the Properties window for a class, and in this case you will not be able to map a message to more than one handler. To see the Properties window for a class such as `CSketcherApp`, right-click its name in Class View and select Properties from the menu. You add a message handler by selecting the Messages button at the top of the Properties window that is displayed (see Figure 13-1). To determine which button is the Messages button, simply hover the cursor over each button until the tooltip displays.

Clicking the Messages button brings up a list of message IDs; however, before I go into what you do next, I’ll explain a little more about the types of messages you may be handling.




FIGURE 13-1

Message Categories

Many Windows messages are identified by an ID with the prefix `WM_`. There are many categories, and the category to which a message belongs determines how it is handled. The categories of Windows messages that your program may be dealing with include:

MESSAGE CATEGORY	DESCRIPTION
Standard Windows messages	These are Windows messages that begin with the <code>WM_</code> prefix other than <code>WM_COMMAND</code> messages. Examples of these messages are <code>WM_PAINT</code> , which indicates that you need to redraw the client area of a window, and <code>WM_LBUTTONDOWN</code> , which signals that the left mouse button has been released.

MESSAGE CATEGORY	DESCRIPTION
Control notification messages	These are WM_COMMAND messages sent from controls (such as a list box) to the window that created the control or from a child window to a parent window. Parameters associated with a WM_COMMAND message enable messages from the controls in your application to be differentiated.
Command messages	These are WM_COMMAND messages that originate from user interface elements such as menu items and toolbar buttons. MFC defines unique identifiers for standard menu and toolbar command messages.

You'll be writing handlers for standard Windows messages in the first category in the next chapter. The messages in the second category are a particular group of WM_COMMAND messages that you'll see in Chapter 16 when you work with dialogs. You'll deal with command messages originating from menus and toolbars in this chapter. In addition to the message IDs defined by the MFC for the standard menus and toolbars, you can define your own message IDs for menus and toolbar buttons that you create. If you don't supply IDs for these, MFC generates IDs for you, based on the menu text.

Handling Messages in Your Program

You can't put message handlers anywhere you like. The classes where you can implement a handler depend on the kind of message. The first two categories of message in the previous section — standard Windows messages and control notification messages — are always handled by objects of classes that are ultimately derived from CWnd. Frame window classes and view classes, for example, have CWnd as an indirect base class, so they can handle Windows messages and control notification messages. Application classes, document classes, and document template classes are not derived from CWnd, so they can't handle these messages.

Using the Properties window for a class to add a handler solves the headache of remembering where to place handlers, because it only offers you the IDs allowed for the class. For example, you won't be offered any of the WM_ messages in the Properties window for the CSketcherDoc class.

The CWnd class provides default message handling for standard Windows messages. If your class doesn't include a handler for one of these, it will be processed by the default handler in the CWnd class. If you do provide a handler in your class, you sometimes still need to call the base class handler from your handler function to ensure that the message is processed properly. When you're creating your own handler through the Properties window for a class, a skeleton implementation is provided that includes a call to the base handler where necessary.

You have much more flexibility with handling command messages than you have with standard Windows messages. You can put handlers for command messages in the application class, the document and document template classes, and in the window and view classes. So what happens when a command message is sent to your application, bearing in mind that there are a lot of options as to where it is handled?

How Command Messages Are Processed

All command messages are sent to the main frame window for the application. The main frame window then tries to get the message handled by routing it in a specific sequence to the classes in your program. If one class can't process the message, the main frame window passes it on to the next.

For an SDI program, the sequence in which classes are offered an opportunity to handle a command message is:

1. The view object
2. The document object
3. The document template object
4. The main frame window object
5. The application object

The view object is given the opportunity to handle a command message first, and, if no handler has been defined, the next class object has a chance to process it. If none of the classes has a handler defined, default Windows processing takes care of it, essentially throwing the message away.

For an MDI program, things are only a little more complicated. Although you have the possibility of multiple documents, each with multiple views, only the active view and its associated document are involved in the routing of a command message. The sequence for routing a command message in an MDI program is:

1. The active view object
2. The document object associated with the active view
3. The document template object for the active document
4. The frame window object for the active view
5. The main frame window object
6. The application object

It's possible to alter the sequence for routing messages, but this is so rarely necessary that I won't go into it in this book.

EXTENDING THE SKETCHER PROGRAM

You're going to add code to the Sketcher program you created in the previous chapter to implement the functionality you need to create sketches. You'll provide code for drawing lines, circles, rectangles, and curves with various colors and line thicknesses, and for adding annotations to a sketch. The data for a sketch will be stored in a document object, and you'll allow multiple views of the same document at different scales.

It will take several chapters to learn how to add everything that I've described. A good starting point would be to add menu items to enable you to choose the type of element that you want to draw, and to select a drawing color. You'll make the element type and color selection persistent, which means that once a color and an element type has been selected, they will remain in effect until you choose another color or element type.

You'll work through the following steps to add menus to Sketcher:

1. Define the menu items that will appear on the main menu bar and the items in each of the corresponding drop-down menus.
2. Decide which class will handle messages for each menu item.
3. Add message handling functions to the classes for the menu messages.
4. Add functions to the classes that update the appearance of the menus to show the current selection in effect.
5. Add a toolbar button complete with tooltips for each menu item.

ELEMENTS OF A MENU

You'll look at two aspects of dealing with menus with the MFC: the creation and modification of the menu as it appears in your application, and the processing necessary when a menu item is selected — the definition of a message handler for it. Let's look first at how you create new menu items.

Creating and Editing Menu Resources

Menus and other user interface elements are defined separately from the program code in a *resource file*, and the specification of an interface element is referred to as a *resource*. You can include many kinds of resources in your application: typical examples are menus, icons, dialogs, toolbars, and toolbar buttons. You'll be seeing more on these as you extend Sketcher.

Having a menu defined by a resource allows you to change the physical appearance of the menu without affecting the code that processes menu messages. For example, you could change your menu items from English to French, or Norwegian or whatever, without having to modify or recompile the program code. The code to handle a message doesn't need to be concerned with how the menu looks, only with the fact that it was selected. Of course, if you do add items to a menu, you must add code to handle messages for each of them to ensure that they actually do something!

Sketcher already has a menu, which means that it already has a resource file and menu resources. You can access the resource file contents for Sketcher by selecting the Resource View pane, or, if you have the Solution Explorer pane displayed, you can double-click `Sketcher.rc`. This switches you to the Resource View, which displays the resources. If you display the menu resources by double-clicking `Menu`, you'll see that it includes menus with the identifiers `IDR_MAINFRAME` and `IDR_SketchTYPE`. The `IDR_MAINFRAME` menu will be displayed when there are no documents open in the application, and the `IDR_SketchTYPE` menu will be displayed when you have a document open. The `IDR_` prefix identifies a resource that defines a complete menu for a window.

You're only going to modify the menu that has the identifier `IDR_SketchTYPE`. You don't need to change `IDR_MAINFRAME`, because your new menu items will be relevant only when a document is open. You can open a resource editor for a menu by double-clicking its menu ID in Resource View. If you do this for `IDR_SketchTYPE`, the Resource Editor pane appears, as shown in Figure 13-2, where I show it as a floating window.




FIGURE 13-2

Adding a Menu Item to the Menu Bar

To add a new menu item to the menu bar, click the menu box on the menu bar with the text “Type Here” to select it, and then type in your menu name. If you insert an ampersand (&) in front of a letter in the menu item, that letter will be a shortcut key to invoke the menu from the keyboard. Type the first menu item as `E&lement`. This selects `l` as the shortcut letter, so you will be able to select the menu item and display its pop-up by typing `Alt+L`. You can't use `E` as the shortcut letter because it's already used by `Edit`. When you finish typing the name, you can right-click the menu item and select Properties from the pop-up to display its properties, as shown in Figure 13-3.

Properties are parameters with values that determine how the menu item will appear and behave. Figure 13-3 displays the properties grouped by category. If you want them displayed in alphabetical sequence, click the second button from the left. Note that the `Popup` property is set to `True` by default because the new `Element` menu item is at the top level on the menu bar, so it would normally present a pop-up menu when it is selected. Clicking any property in the left column enables you to modify its value in the right column. In this case, you want to leave everything as it is,




FIGURE 13-3

so you can just close the Properties window. No ID is necessary for a pop-up menu item, because selecting it just displays the menu beneath and there's no event for your code to handle. Note that you get a new blank menu box for the first item in the pop-up menu, as well as one on the main menu bar.

It would be better if the `Element` menu appeared between the `View` and `Window` menus, so place the mouse cursor on the menu item and, keeping the left mouse button pressed, drag it to a position between the `View` and `Window` menu items and release the mouse button. After positioning the new menu item, the next step is to add items to its pop-up menu.

Adding Items to the Element Menu

Select the first item (currently labeled “Type Here”) in the `Element` pop-up by clicking it; then, type `Line` as the caption and press `Enter`. You can see the properties for this item by right-clicking it and selecting `Properties`; the properties for this item are shown in Figure 13-4.

The properties determine the appearance of the menu item and specify the ID of the message passed to your program when the item is selected. Here, you have the ID already specified as `ID_ELEMENT_LINE`, but you can change it to something else if you want. Sometimes it's convenient to specify the ID yourself, such as when the generated ID is too long or its meaning is unclear. If you define your own ID, you should use the MFC convention of prefixing it with `ID_` to indicate that it's a command ID for a menu item.

The `Popup` property is `False` here. When the `Popup` property for a menu item is `True`, clicking the item displays a pop-up menu. As you see in Figure 13-4, you can display the possible values for the `Popup` property by selecting the down arrow. Don't you love the way pop-ups pop up all over the place?

You can enter a text string for the value of the `Prompt` property that will appear in the status bar for `Sketcher` when the menu item is highlighted. If you leave it blank, nothing is displayed. I suggest you enter `Draw lines` as the value for the `Prompt` property. You get a brief indication of the purpose of a selected property at the bottom of the Properties window. The `Break` property can alter the appearance of the pop-up by shifting the item into a new column. You don't need that here, so leave it as it is. Close the Properties window and click the Save icon in the toolbar to save the values you have set.

Modifying Existing Menu Items

If you make a mistake and want to change an existing menu item, or even if you just want to verify that you set the properties correctly, it's very easy to go back to an item. Just double-click the item you're interested in, and the Properties window for that item is displayed. If the Properties pane is already open, just single-clicking an item will display its properties. You can then change the properties in any way you want. If the item you want to access is in a pop-up menu that isn't displayed, just click the item on the menu bar to display the pop-up.




FIGURE 13-4

Completing the Menu

Now, you can create the remaining `Element` pop-up menu items that you need: `Rectangle`, `Circle`, and `Curve`. You can accept the default IDs, `ID_ELEMENT_RECTANGLE`, `ID_ELEMENT_CIRCLE`, and `ID_ELEMENT_CURVE`, respectively. You could also set the values for the `Prompt` property value to `Draw rectangles`, `Draw circles`, and `Draw curves`.

You also need a `Color` menu on the menu bar, with pop-up menu items for `Black`, `Red`, `Green`, and `Blue`. You can create these, starting at the empty menu entry on the menu bar, using the same procedure that you just went through. You can use the default IDs (`ID_COLOR_BLACK`, etc.) as the IDs for the menu items. You can also add the status bar prompt for each as the value of the `Prompt` property. After you've finished, if you drag `Color` so that it's just to the right of `Element`, the menu should be as in Figure 13-5.




FIGURE 13-5

You need to take care not to use the same shortcut letter more than once in the main menu. There's no check made as you create menu items, but if you right-click with the cursor on the menu bar when you've finished editing it, you'll get a pop-up containing `Check Mnemonics`. Selecting this checks for duplicate shortcut keys. It's a good idea to do this every time you edit a menu, because it's easy to create duplicates by accident.

That completes extending the menu for elements and colors. Don't forget to save the file to make sure that the additions are safely stored away. Next, you'll decide which classes will deal with messages from your menu items, and add member functions to handle each of them. For that, you'll be using the Event Handler Wizard.

ADDING MENU MESSAGE HANDLERS

To create an event handler for a menu item, right-click the item and select `Add Event Handler` from the pop-up displayed. If you try this with the `Black` menu item in the `Color` menu pop-up, you'll see the dialog shown in Figure 13-6.




FIGURE 13-6

The wizard has already chosen a name for the handler function. You could change it, but OnColorBlack seems like a good name to me.

You obviously need to specify the message type as one of the choices shown in the dialog. The “Message type:” box in the window in Figure 13-6 shows the two kinds of messages that can arise for a particular menu ID. Each type of message serves a distinct purpose in dealing with a menu item.

MESSAGE TYPE	DESCRIPTION
COMMAND	This type of message is issued when a particular menu item has been selected. The handler should provide the action appropriate to the menu item being selected, such as by setting the current color in the document object or setting the element type.
UPDATE_COMMAND_UI	This is issued when the menu should be updated — checked or unchecked, for example — depending on its status. This message occurs before a pop-up menu is displayed so you can set the appearance of the menu item before the user sees it.

The way these messages work is quite simple. When you click a menu item in the menu bar, an UPDATE_COMMAND_UI message is sent for each item in that menu before the menu is displayed. This provides the opportunity to do any necessary updating of the menu items’ properties before the user sees it. When these messages are handled and any changes to the items’ properties are completed,

the menu is drawn. When you then click one of the items in the menu, a `COMMAND` message for that menu item is sent. I'll deal with the `COMMAND` messages now, and come back to the `UPDATE_COMMAND_UI` messages a little later in this chapter.

Because events for menu items result in command messages, you can choose to handle them in any of the classes that are currently defined in the Sketcher application. So how do you decide where you should process a message for a menu item?

Choosing a Class to Handle Menu Messages

Before you can decide which class should handle the messages for the menu items you've added, you need to decide what you want to do with the messages.

You want the element type and the element color to be modal — that is, whatever is set for the element type and element color should remain in effect until it is changed. This enables you to create as many blue circles as you want, and when you want red circles, you just change the color. You have two basic possibilities for handling the setting of a color and the selection of an element type: setting them by view or by document. You could set them by view, in which case, if there's more than one view of a document, each will have its own color and element set. This means that you might draw a red circle in one view, switch to another view, and find that you're drawing a blue rectangle. This would be confusing and in conflict with how you would probably want your tools to work.

It would be better, therefore, to have the current color and element selection apply to a document. You can then switch from one view to another and continue drawing the same element in the same color. There might be other differences between the views that you implement, such as the scale at which the document is displayed, perhaps, but the drawing operation will be consistent across multiple views.

This suggests that you should store the current color and element in the document object. These could then be accessed by any view object associated with the document object. Of course, if you had more than one document active, each document would have its own color and element type settings. It would therefore be sensible to handle the messages for your new menu items in the `CSketcherDoc` class and to store information about the current selections in an object of this class. I think you're ready to dive in and create a handler for the `Black` menu item.

Creating Menu Message Handlers

Highlight the `CSketcherDoc` class name in the Event Handler Wizard dialog by clicking it. You'll also need to select the `COMMAND` message type. You can then click the Add and Edit button. This closes the dialog, and the code for the handler you have created in the `CSketcherDoc` class is displayed in the edit window. The function looks like this:

```
void CSketcherDoc::OnColorBlack()
{
    // TODO: Add your command handler code here
}
```

The highlighted line is where you'll put your code that handles the event that results from the user selecting the `Black` menu item. The wizard also has updated the `CSketcherDoc` class definition:

```
class CSketcherDoc : public CDocument
{
    ...
    // Generated message map functions
protected:
    DECLARE_MESSAGE_MAP()

#ifndef SHARED_HANDLERS
    // Helper function that sets search content for a Search Handler
    void SetSearchContent(const CString& value);
#endif // SHARED_HANDLERS
public:
    afx_msg void OnColorBlack();
};
```

The `OnColorBlack()` method has been added as a public member of the class, and the `afx_msg` prefix marks it as a message handler.

You can now add `COMMAND` message handlers to `CSketcherDoc` for the other color menu items and all the `Element` menu items in exactly the same way as this one. You can create each of the handler functions for the menu items with just four mouse clicks. Right-click the menu item, click the Add Event Handler menu item, click the `CSketcherDoc` class name in the dialog for the Event Handler Wizard, and click the Add and Edit button for the dialog.

The Event Handler Wizard should now have added the handlers to the `CSketcherDoc` class, which now looks like this:

```
class CSketcherDoc: public CDocument
{
    ...
    // Generated message map functions
protected:
    DECLARE_MESSAGE_MAP()

#ifndef SHARED_HANDLERS
    // Helper function that sets search content for a Search Handler
    void SetSearchContent(const CString& value);
#endif // SHARED_HANDLERS
public:
    afx_msg void OnColorBlack();
    afx_msg void OnColorRed();
    afx_msg void OnColorGreen();
    afx_msg void OnColorBlue();
    afx_msg void OnElementLine();
    afx_msg void OnElementRectangle();
    afx_msg void OnElementCircle();
    afx_msg void OnElementCurve();
};
```

A declaration has been added for each handler that you've created using the Event Handler Wizard dialog. Each function declaration is prefixed with `afx_msg` to indicate that it is a message handler.

The Event Handler Wizard automatically updates the message map in your `CSketcherDoc` class implementation with the new message handlers. If you look in `SketcherDoc.cpp`, you'll see the message map:

```
BEGIN_MESSAGE_MAP(CSketcherDoc, CDocument)
ON_COMMAND(ID_COLOR_BLACK, &CSketcherDoc::OnColorBlack)
ON_COMMAND(ID_COLOR_RED, &CSketcherDoc::OnColorRed)
ON_COMMAND(ID_COLOR_GREEN, &CSketcherDoc::OnColorGreen)
ON_COMMAND(ID_COLOR_BLUE, &CSketcherDoc::OnColorBlue)
ON_COMMAND(ID_ELEMENT_LINE, &CSketcherDoc::OnElementLine)
ON_COMMAND(ID_ELEMENT_RECTANGLE, &CSketcherDoc::OnElementRectangle)
ON_COMMAND(ID_ELEMENT_CIRCLE, &CSketcherDoc::OnElementCircle)
ON_COMMAND(ID_ELEMENT_CURVE, &CSketcherDoc::OnElementCurve)
END_MESSAGE_MAP()
```

The Event Handler Wizard has added an `ON_COMMAND()` macro for each handler. This associates the pointer to a handler function with the message ID, so, for example, `OnColorBlack()` will be called to service a `COMMAND` message for the menu item with the `ID_COLOR_BLACK` ID.

Each handler generated by the Event Handler Wizard is just a skeleton. For example, look at the code provided for `OnColorBlue()`. This also appears in `SketcherDoc.cpp` so you can scroll down to find it, or go directly to it by switching to the Class View, clicking `CSketcherDoc` in the upper pane and double-clicking the function name in the lower pane.

```
void CSketcherDoc::OnColorBlue()
{
    // TODO: Add your command handler code here
}
```

The function takes no arguments and returns nothing. It also does nothing at the moment, but this is hardly surprising. The Event Handler Wizard has no way of knowing what you want to do with these messages!

Implementing Menu Message Handlers

Now let's consider what you should do with the `COMMAND` messages for the new menu items. I said earlier that you want to record the current element and color in the document, so you need to add data members to the `CSketcherDoc` class to store these.

Adding Members to Store Color and Element Mode

You could add the data members to `CSketcherDoc` just by editing the class definition directly, but let's use the Add Member Variable Wizard to do it. Display the dialog for the wizard by right-clicking the `CSketcherDoc` class name in the Class View and then selecting `Add` \leftrightarrow `Add Variable` from the pop-up menu that appears. You then see the dialog for the wizard, as shown in Figure 13-7.




FIGURE 13-7

I've already entered the information in the dialog for the `m_Element` variable that stores the current element type to be drawn. I have selected `protected` as the access because it should not be accessible directly from outside the class. I have also entered the type as `ElementType`. You will define this type in the next section. When you click the `Finish` button, the variable is added to the class definition in the `SketcherDoc.h` file.

Add the `CSketcherDoc` class member to store the element color manually just to show that you can. Its name is `m_Color` and its type is `ElementColor`, which we will define in the next section. You can add the declaration for the `m_Color` member to the `CSketcherDoc` class like this:

```
class CSketcherDoc : public CDocument
{
...
// Generated message map functions
protected:
    DECLARE_MESSAGE_MAP()
...
public:
    afx_msg void OnColorBlack();
    afx_msg void OnColorRed();
    afx_msg void OnColorGreen();
    afx_msg void OnColorBlue();
    afx_msg void OnElementLine();
    afx_msg void OnElementRectangle();
    afx_msg void OnElementCircle();
```

```
afx_msg void OnElementCurve();

protected:
    ElementType m_Element;           // Current element type
    ElementColor m_Color;           // Current drawing color
};
```

Of course, you could have used the Add Member Variable Wizard dialog as you did for `m_Element`; you would type `ElementColor` in the “Variable type” box, rather than selecting from the drop-down list. The `m_Color` member is protected, because there’s no reason to allow public access. You can add functions to access or change the values of protected or private class members, with the advantage that you then have complete control over what values can be set. Add the following functions to `CSketcherDoc` in a public section of the class:

```
ElementType GetElementType() const { return m_Element; }
ElementColor GetElementColor() const { return m_Color; }
```

Now an external class object, a view for instance, can discover the current element type and color.

Defining Element and Color Types

You can define `ElementType` as an `enum class` type in a new header file, `ElementType.h`. The definition is:

```
#pragma once

// Standard Sketcher element type identifiers
enum class ElementType{LINE, RECTANGLE, CIRCLE, CURVE};
```

Because it’s an `enum` type, each of the possible values is automatically defined as a unique integer value, type `int` by default. Because it’s an `enum class` type, the enumerators are type safe and must be prefixed with the type name to access them. If you need to add further types in the future, it will be very easy to add them here. You can add an `#include` directive for `ElementType.h` to `SketcherDoc.h`.

You can define another `enum class` type for the standard drawing colors in Sketcher in `ElementColor.h`:

```
#pragma once

// Standard Sketcher drawing colors
enum class ElementColor : COLORREF{BLACK = RGB(0,0,0),    RED = RGB(255,0,0),
                                     GREEN = RGB(0,255,0),  BLUE = RGB(0,0,255)};
```

You can define enumerators to be of any integer type. A color in Windows is of type `COLORREF`, which is an unsigned 32-bit integer, so the enumerators in `ElementColor` can be specified as this type. A color value is composed of three 8-bit unsigned integer values, packed into the 32-bit word, that correspond to the intensities of the red, green, and blue components of the color. The values are stored as `0x00bbggrr`, where `bb`, `gg`, and `rr` are hexadecimal color component values.

Each `ElementColor` enumerator is initialized by the `RGB()` macro, which is used to define `COLORREF` values. The macro is defined in the `Wingdi.h` header file that is included as part of `Windows.h`, so you can add an `#include` for `windows.h` to `ElementColor.h` after the `#pragma once` directive. The three arguments to the macro define the red, green, and blue components of the color value, respectively. Each argument must be an integer between 0 and 255, 0 being no color component and 255 being the maximum color component. `RGB(0, 0, 0)` corresponds to black because there are no components of red, green, or blue. `RGB(255, 0, 0)` creates a color value with a maximum red component and no green or blue contribution. `RGB(0, 255, 0)` and `RGB(0, 0, 255)` correspond to green and blue with maximum intensity. You can create other colors by combining red, green, and blue components with other intensities. Add an `#include` for `ElementColor.h` to `SketcherDoc.h`. The `ElementType` and `ElementColor` types should now be visible in Class View.

Initializing the Color and Element Type Members

It's important to make sure that the data members you have added to the `CSketcherDoc` class are initialized appropriately when a document is created. You can add the code to do this to the class constructor in `SketcherDoc.cpp`, as shown here:

```
CSketcherDoc::CSketcherDoc() :
    m_Element(ElementType::LINE), m_Color(ElementColor::BLACK)
{
    // TODO: add one-time construction code here
}
```

enum class types require that enumerators are explicitly qualified by the class name.

Implementing Menu Command Message Handlers

Now, you're ready to add the code for the handler functions that you created for the `Element` and `Color` menu items. You can do this from the Class View. Double-click the name of the first handler function, `OnColorBlack()`. You just need to add one line to the function, so the code for it becomes:

```
void CSketcherDoc::OnColorBlack()
{
    m_Color = ElementColor::BLACK;           // Set the drawing color to black
}
```

The only job that the handler has to do is to set the appropriate color. In the interest of conciseness, the new line replaces the comment provided originally. You can go through and add one line to each of the `Color` menu handlers setting the appropriate color value.

The element menu handlers are much the same. The handler for the `Element > Line` menu item is:

```
void CSketcherDoc::OnElementLine()
{
    m_Element = ElementType::LINE;           // Set element type as a line
}
```

With this model, it's not too difficult to write the other handlers for the `Element` menu. That's eight message handlers completed. You can now rebuild the example and see how it works.

Running the Extended Example

Assuming that there are no typos, the compiled and linked program should run without error. When you run the program, you should see the window shown in Figure 13-8.

The new menus are in place on the menu bar, and you can see that the items you have added to the menu are all there and you should see the prompt message in the status bar that you provided in the properties box when the mouse cursor is over a menu item. You can also verify that Alt+C and Alt+L work. Ideally, the currently selected items in the Color and Element menus should be checked as a cue to the current state. Let's look at how you can arrange for that to happen.

Adding Menu Update Message Handlers

To set the checkmark correctly for the new menus, you need to add the second kind of message handler, **UPDATE_COMMAND_UI** (signifying “update command user interface”) for each of the new menu items. These message handlers are intended for updating the properties of the menu items in a menu before the menu is displayed.

Go back to viewing the **IDR_SketchTYPE** menu in the editor window. Right-click the Black item in the Color menu and select Add Event Handler. You can then select **CSketcherDoc** as the class and **UPDATE_COMMAND_UI** as the message type, as shown in Figure 13-9.




FIGURE 13-8




FIGURE 13-9

The name for the update function has been generated as `OnUpdateColorBlack()`. This seems a reasonable name for the function so click the Add and Edit button and have the Event Handler Wizard generate it. The skeleton function definition is added in `SketcherDoc.cpp` and its declaration is added to the class definition. An entry for it is also made in the message map in the `SketcherDoc.cpp` that looks like this:

```
ON_UPDATE_COMMAND_UI(ID_COLOR_BLACK, &CSketcherDoc::OnUpdateColorBlack)
```

This uses the `ON_UPDATE_COMMAND_UI()` macro that identifies the function you have just generated as the handler to deal with update messages corresponding to the `ID_COLOR_BLACK` ID. You can now enter the code for the new handler, but before you do that, add command update handlers for each of the menu items for both the Color and Element menus first.

Coding a Command Update Handler

You can access the code for the `OnUpdateColorBlack()` handler in `CSketcherDoc` by selecting the function in Class View. This is the skeleton code for the function:

```
void CSketcherDoc::OnUpdateColorBlack(CCmdUI* pCmdUI)
{
    // TODO: Add your command update UI handler code here
}
```

The argument passed to the handler is a pointer to an object of type `CCmdUI`. This is an MFC class type that is used only with update handlers, and it applies to toolbar buttons as well as menu items. `pCmdUI` points to an object that identifies the item that originated the message, so you use this to operate on the item to update it before it is displayed. The `CCmdUI` class has five member functions that act on user interface items. The operations that each of these provides are as follows:

FUNCTION	DESCRIPTION
<code>ContinueRouting()</code>	Passes the message on to the next priority handler.
<code>Enable()</code>	Enables or disables the relevant interface item.
<code>SetCheck()</code>	Sets a checkmark for the relevant interface item.
<code>SetRadio()</code>	Sets a button in a radio group on or off.
<code>SetText()</code>	Sets the text for the relevant interface item.

We'll use the function `SetCheck()` as that seems to do what we want. The function is declared in the `CCmdUI` class as:

```
virtual void SetCheck(int nCheck = 1);
```

This function sets a menu item as checked if you pass 1 as the argument, and unchecked if you pass 0 as the argument. The parameter has a default value of 1, so if you just want to set a checkmark for an item, you can call this function without specifying an argument.

For Sketcher, you want to set a Color menu item as checked if it corresponds with the current color. You can, therefore, write the update handler for `OnUpdateColorBlack()` as:

```
void CSketcherDoc::OnUpdateColorBlack(CCmdUI* pCmdUI)
{
    // Set menu item Checked if the current color is black
    pCmdUI->SetCheck(m_Color == ElementColor::BLACK);
}
```

This calls `SetCheck()` for the Color \Rightarrow Black menu item with the argument `m_Color==ElementColor::BLACK`. This results in `true` if `m_Color` is `ElementColor::BLACK`, which will convert to 1, or `false`, which will convert to 0. The effect is to check the menu item only if the current color stored in `m_Color` is `ElementColor::BLACK`, which is precisely what you want. You can implement the update handlers for the other Color menu items in the same way. Update handlers for menu items are always called before the menu is displayed, so the items are always displayed reflecting their current state.

A typical Element menu item update handler is coded as follows:

```
void CSketcherDoc::OnUpdateElementLine(CCmdui* pCmdUI)
{
    // Set Checked if the current element is a line
    pCmdUI->SetCheck(m_Element==ElementType::LINE);
}
```

You can now code all the other update handlers for items in the Element menu in a similar manner.

Exercising the Update Handlers

When you've added the code for all the update handlers, you can build and execute the Sketcher application again. Now, when you change a color or an element type selection, this is reflected in the menu, as shown in Figure 13-10.

You have completed all the code that you need for the menu items. Make sure that you have saved everything before embarking on the next stage. Toolbars are a must in any Windows program of consequence, so the next step is to look at how you add toolbar buttons to support the new menus.




FIGURE 13-10

ADDING TOOLBAR BUTTONS

Select the Resource View and extend the toolbar resource. You'll see that the toolbar resource has the same ID as the main menu, `IDR_MAINFRAME`. This provides you with toolbar icons that have four-bit color pixels (16 colors).

If you double-click `IDR_MAINFRAME`, the editor window shown in Figure 13-11 appears.




FIGURE 13-11

A toolbar button is a 16×15 (width \times height) array of pixels that contains a pictorial representation of the function it initiates. Each pixel in this toolbar is a 4-bit color, so a button is a 16-color bitmap. You can see in Figure 13-11 that the resource editor provides an enlarged view of a toolbar button so that you can see and manipulate individual pixels. It also provides you with a color palette to the right (not shown in Figure 13-11), from which you can choose the current working color. If it is not already visible, you can display the palette from which you can choose a color by right-clicking a toolbar button icon and selecting Show Colors Window from the menu.

If you click the new button icon at the right end of the row, you'll be able to draw this icon. Before starting editing, drag the new icon about half a button-width to the right on the toolbar. This separates the button from its neighbor on the left to start a new block. You should keep toolbar buttons in the same sequence as the items on the menu bar, so you'll create the buttons corresponding to the Element menu first. You'll probably want to use the editing buttons provided by the resource editor, which appear in the IDE application window toolbar and include:

- Pencil for drawing individual pixels
- Eraser for erasing individual pixels
- Fill an area with the current color
- Zoom the view of the button
- Draw a line
- Draw a rectangle
- Draw an ellipse
- Draw a curve

You select a foreground color by left-clicking a color from the palette, and a background color by right-clicking.

The first icon will be for the toolbar button corresponding to the Element ↳ Line menu option. You can let your creative juices flow and draw whatever representation you like here to depict the act of drawing a line, but I'll keep it simple. If you want to follow my approach, make sure that black is selected as the foreground color and use the line tool to draw a diagonal line in the enlarged image of the new toolbar button icon. In fact, if you want the icon to appear a bit bigger, you can use the Magnification Tool editing button to make it up to eight times its actual size: just click the down arrow alongside the button and select the magnification you want. I drew a double black line.

If you make a mistake, you can select the Undo button or you can change to the Erase Tool editing button and use that, but in the latter case, you need to make sure that the color selected corresponds to the background color for the button you are editing. You can also erase individual pixels by clicking them using the right mouse button, but again, you need to be sure that the background color is set correctly when you do this. After you're happy with what you've drawn, the next step is to edit the toolbar button properties.

Editing Toolbar Button Properties

Right-click your new button icon in the toolbar and select Properties from the pop-up to bring up its Properties window, as shown in Figure 13-12.

The Properties window shows a default ID for the button, but you want to associate the button with the menu item Element ↳ Line that you have already defined, so click ID and then click the down arrow to display alternative values. You can then select `ID_ELEMENT_LINE` from the drop-down list. If you look at the Prompt property, you'll find that the same prompt value appears because the prompt is recorded along with the ID. You can click Save to complete the button definition.

You can now move on to designing the other three element buttons. You can use the rectangle editing button to draw a rectangle and the ellipse button to draw a circle. You can draw a curve using the pencil to set individual pixels, or use the curve button. You need to associate each button with the ID for the equivalent menu item that you defined earlier.

Now add the buttons for the colors. You should also drag the first button for selecting a color to the right, so that it starts a new group of buttons. You could keep the color buttons very simple and just color the whole button with the color it selects. You can do this by selecting the appropriate foreground color, then selecting the Fill editing button and clicking on the enlarged button image. Again, you need to use `ID_COLOR_BLACK`, `ID_COLOR_RED`, and so on as IDs for the buttons. The toolbar editing window should look like the one shown in Figure 13-13.




FIGURE 13-12




FIGURE 13-13

That's all you need for the moment, so save the resource file and give Sketcher another spin.

Exercising the Toolbar Buttons

Build the application once again and execute it. You should see the application window shown in Figure 13-14.

There are some amazing things happening here. The toolbar buttons that you added already reflect the default settings that you defined for the new menu items, and the selected button is shown depressed. If you let the cursor linger over one of the new buttons, the prompt for the button appears in the status bar. The new buttons work as a complete substitute for the menu items, and any new selection made, with either the menu or the toolbar, is reflected by the toolbar button being shown depressed.

If you close the document view window, Sketch1, you'll see that your toolbar buttons are automatically grayed and disabled and your menu items disappear. If you open a new document window, the toolbar buttons are automatically enabled once again and your menu items reappear. You can also drag the toolbar with the cursor. You can move it to either side of the application window, or have it free-floating. You got all this toolbar function without writing a single additional line of code!




FIGURE 13-14

Adding Tooltips

There's one further tweak that you can add to your toolbar buttons that is remarkably easy: tooltips. A tooltip is a small box that appears adjacent to the toolbar button when you let the cursor linger on the button. The tooltip contains a text string that is an additional clue to the purpose of the toolbar button.

To add a tooltip for a toolbar button, select the button in the toolbar editor tab. Select the Prompt property for the button in the Properties pane and enter `\n` followed by the text for the tooltip. For example, for the toolbar button with the ID `ID_ELEMENT_LINE`, you could enter the Prompt property value as `\nDraw lines`. The tooltip text will be displayed when you hover the mouse cursor over the toolbar button but you won't get the status bar text for the corresponding menu item.

You can have status bar text displayed for the menu item and different tooltip text for the toolbar button, though. Set the value for the Prompt property for the Line menu item as `Draw lines\nLines`. This will display "Draw lines" in the status bar when you hover the mouse cursor over the menu item. When you hover the mouse over the toolbar button, the status bar text will be displayed and the tooltip text will appear a short while afterwards.

You can change the Prompt property text for each of the toolbar buttons corresponding to the Element and Color menus in a similar way. That's all you have to do. After saving the resource file, you can now rebuild the application and execute it. Placing the cursor over one of the new toolbar buttons causes the prompt text to appear in the status bar and the tooltip to be displayed after a second or two.

SUMMARY

In this chapter, you learned how MFC connects a message with a class member function to process it, and you wrote your first message handlers. Much of the work in writing a Windows program is writing message handlers, so it's important to have a good grasp of what happens in the process. When we get to consider other message handlers, you'll see that the process for adding them is just the same.

You have also extended the standard menu and the toolbar in the MFC Application Wizard-generated program, which provides a good base for the application code that you add in the next chapter. Although there's no functionality under the covers yet, the menu and toolbar operation looks very professional, courtesy of the Application Wizard-generated framework and the Event Handler Wizard.

In the next chapter, you'll add the code necessary to draw elements in a view, and use the menus and toolbar buttons that you created here to select what to draw and in which color. This is where the Sketcher program begins to live up to its name.

EXERCISES

- 1.** Add an `Ellipse` menu item to the `Element` menu.
- 2.** Implement the command and command update handlers for the `Ellipse` menu item in the document class.
- 3.** Add a toolbar button corresponding to the `Ellipse` menu item, and add status bar text and a tooltip for the button.
- 4.** Modify the command update handlers for the color menu items so that the currently selected menu item displays in uppercase, and the others in lowercase.

► WHAT YOU LEARNED IN THIS CHAPTER

TOPIC	CONCEPT
Message maps	MFC defines the message handlers for a class in a message map that appears in the .cpp file for the class.
Handling command messages	Command messages that arise from menus and toolbars can be handled in any class that's derived from CCmdTarget. These include the application class, the frame and child frame window classes, the document class, and the view class.
Handling non-command messages	Messages other than command messages can be handled only in a class derived from CWnd. This includes frame window and view classes, but not application or document classes.
Identifying a message handler for command messages	MFC has a predefined sequence for searching the classes in your program to find a message handler for a command message.
Adding message handlers	You should always use the Event Handler Wizard to add message handlers to your program.
Resource files	The physical appearances of menus and toolbars are defined in resource files, which are edited by the built-in resource editor.
Menu IDs	Items in a menu that can result in command messages are identified by a symbolic constant with the prefix ID. These IDs are used to associate a handler with the message from the menu item.
Relating toolbar buttons to menu items	To associate a toolbar button with a particular menu item, give it the same ID as the menu item.
Adding tooltips	To add a tooltip to a toolbar button corresponding to a menu item in your MFC application, select the Prompt property for the button in the Properties pane and enter \n, followed by the text for the tooltip as the property value.

14

Drawing in a Window

WHAT YOU WILL LEARN IN THIS CHAPTER:

- The coordinate systems you use to draw in a window
- How to use a device context to draw shapes
- How and when your program draws in a window
- How to define handlers for mouse messages
- How to define your own shape classes
- How to program the mouse to draw shapes
- How to capture the mouse

WROX.COM CODE DOWNLOADS FOR THIS CHAPTER

You can find the wrox.com code downloads for this chapter on the Download Code tab at www.wrox.com/remtitle.cgi?isbn=9781118368084. The code is in the Chapter 14 download and individually named according to the names throughout the chapter.

BASICS OF DRAWING IN A WINDOW

When you draw in the client area of a window, you must obey the rules. You must redraw the client area whenever a `WM_PAINT` message is sent to your application. This is because there are many external events that require that your application window is redrawn — the user resizing the window for example or moving another window to expose part of your window that was hidden. Windows sends information along with the `WM_PAINT` message that enables you to determine which part of the client area needs to be re-created. This means that you don't have to draw all the client area in response to a `WM_PAINT` message, just the area identified as the *update region*. In an MFC application, the MFC intercepts the `WM_PAINT` message and redirects it to a function in one of your classes. I'll explain how you handle this message later in this chapter.

The Window Client Area

A window doesn't have a fixed position on-screen, or even a fixed visible area, because the user can drag a window around and resize it by dragging its borders. How, then, do you know where to draw on-screen?

Fortunately, you don't. Windows provides you with a consistent way of drawing in a window that is independent of where it is on-screen; without this, drawing in a window would be inordinately complicated. Windows does this by maintaining a coordinate system for the client area of a window that is local to the window. It always uses the upper-left corner of the client area as its reference point. All points within the client area are defined relative to this point, as shown in Figure 14-1.




FIGURE 14-1

The horizontal and vertical distances of a point in the client area from the upper-left corner will always be the same, regardless of where the window is on-screen or how big it is. Of course, Windows keeps track of where the window is, and when you draw something at a point in the client area, it has to figure out where that point actually is on-screen.

The Windows Graphical Device Interface

You don't write data to the screen in any direct sense. All output to your display is graphical, regardless of whether it is lines and circles or text. Windows insists that you define this output using

the *Graphical Device Interface (GDI)*. The GDI enables you to program graphical output in a way that is independent of the hardware on which it is displayed, meaning that your program will work on different machines with different display hardware without change. The GDI also supports printers and plotters, so outputting data to those involves essentially the same mechanism as writing to the screen.

Working with a Device Context

When you draw something on a graphical output device such as a display, you must use a *device context*. A device context is a Windows data structure that contains information that allows Windows to translate your output requests in the form of device-independent GDI function calls, into actions on the particular physical output device. The MFC class, `CDC`, encapsulates a device context so you do all drawing by calling functions for an object of this type. A pointer to a `CDC` object is supplied to the `OnDraw()` member of your view class object and you implement this to draw in the client area represented by the view. You also use a device context when you want to send output to other graphical devices.

A device context provides you with a choice of coordinate systems called *mapping modes*, which are automatically converted to client area coordinates. You can alter parameters (called *attributes*) that affect the output to a device context by calling functions for a `CDC` object. Examples of attributes that you can change are the drawing color, the background color, the line thickness to be used when drawing, and the font for text output.

Mapping Modes

Each mapping mode in a device context is identified by an ID, much like a Windows message. Each ID has the prefix `MM_` to indicate that it defines a mapping mode. The mapping modes provided by Windows are:

MAPPING MODE	DESCRIPTION
<code>MM_TEXT</code>	A logical unit is one device pixel with positive x from left to right, and positive y from top to bottom of the window client area.
<code>MM_LOENGLISH</code>	A logical unit is 0.01 inches with positive x from left to right, and negative y from top to bottom of the client area.
<code>MM_HIENGLISH</code>	A logical unit is 0.001 inches with the x and y directions as in <code>MM_LOENGLISH</code> .
<code>MM_LOMETRIC</code>	A logical unit is 0.1 millimeters with the x and y directions as in <code>MM_LOENGLISH</code> .
<code>MM_HIMETRIC</code>	A logical unit is 0.01 millimeters with the x and y directions as in <code>MM_LOENGLISH</code> .
<code>MM_ISOTROPIC</code>	A logical unit is of arbitrary length, but the same along both axes. The x and y directions are as in <code>MM_LOENGLISH</code> .

continues

(continued)

MAPPING MODE	DESCRIPTION
MM_ANISOTROPIC	This is similar to MM_ISOTROPIC, but allows the length of a logical unit on the x-axis to be different from that of a logical unit on the y-axis.
MM_TWIPS	A logical unit is a TWIP, which is a twentieth of an inch point and a point is 1/72 of an inch. Thus, a TWIP corresponds to 1/1440 of an inch, or 6.9×10^{-4} of an inch. (A point is a font size measurement unit). The axes are as in MM_LOENGLISH.

You will not use all these mapping modes with this book; however, the ones you will use form a good cross-section of those available, so you should not have any problem using the others when you need to.

MM_TEXT is the default mapping mode for a device context. If you need to use a different mapping mode, you have to change it. Note that the direction of the positive y-axis in the MM_TEXT mode is the opposite of what you saw in high-school coordinate geometry, as Figure 14-1 shows.

By default, the origin point with the coordinates (0,0) is at the upper-left corner of the client area in every mapping mode, although it's possible to move it. For example, an application that presents data in graphical form might move the origin to the center of the client area to make plotting the data easier. You might also define shapes relative to (0,0) and then move the origin to the position where a shape is to be drawn. This means that a shape can be drawn using the same code, regardless of where it is.

With the default origin position in MM_TEXT mode, a point 50 pixels from the left border and 100 pixels down from the top of the client area has the coordinates (50,100). Because the units are pixels, the physical distance of the point from the upper-left corner of the client area on your screen depends on the resolution of your monitor. If the resolution is set to 1280×1024 the point will be nearer to the origin than if it's set to 1024×768 because the pixels are smaller. An object drawn in this mapping mode will be smaller at the 1280×1024 resolution than at 1024×768 . Note that the DPI setting for your display also affects presentation in all mapping modes. The default settings assume 96 DPI, so if the DPI for your display is different, this affects how things look. Coordinates are always 32-bit signed integers. The maximum physical size of the area you can draw varies with the length of a coordinate unit, which depends on the mapping mode.

The directions of the coordinate axes in all mapping modes other than MM_TEXT are the same, but different from MM_TEXT in that the y-coordinate axis is in the opposite direction. The coordinate system for MM_LOENGLISH is shown in Figure 14-2. Although the positive y-direction is consistent with what you learned in high school (y-values increase as you move up the screen), MM_LOENGLISH is still slightly odd because the origin is at the upper-left corner of the client area, so y is always negative for points within the visible client area.




FIGURE 14-2

In the `MM_LOENGLISH` mapping mode, the units along the axes are 0.01 inches, so a point at the position (50, -100) is half an inch from the left border and one inch down from the top of the client area. An object is the same size in the client area and the same distance from the origin, regardless of the resolution of the monitor on which it's displayed. Anything you draw in `MM_LOENGLISH` mode with negative x- or positive y-coordinates will be outside the client area and therefore not visible. You can move the origin by calling the `SetViewportOrg()` member of the `CDC` class that encapsulates a device context, which I'll discuss shortly.

THE MFC DRAWING MECHANISM

The MFC encapsulates the Windows interface to your screen and printer and relieves you of the need to worry about much of the details involved in programming graphical output. As you saw in the last chapter, an Application Wizard-generated program already contains a class derived from `CVIEW` that's specifically designed to display document data on-screen.

The View Class in Your Application

The primary purpose of the Application Wizard-generated `CSketcherView` class is to display information from a document object in the client area of a document window. The class definition includes overrides for several virtual functions, but the one of particular interest here is the `OnDraw()` function. This is called whenever the client area of the document window needs to be

redrawn. It's the function that's called by the application framework when a WM_PAINT message is received by your program.

The OnDraw() Member Function

The implementation of the `OnDraw()` function that's created by the MFC Application Wizard looks like this:

```
void CSketcherView::OnDraw(CDC* /*pDC*/)
{
    CSketcherDoc* pDoc = GetDocument();
    ASSERT_VALID(pDoc);
    if(!pDoc)
        return;

    // TODO: add draw code for native data here
}
```

A pointer to a `CDC` class object is passed to the `OnDraw()` member of the view class when it is called. This object has member functions that call the Windows API functions that enable you to draw in a device context. The parameter name is commented out: you must uncomment it or substitute your own name before you can use the pointer.

Because you'll put all the code to draw a document in this function, the Application Wizard includes a declaration for the `pDoc` pointer and initializes it using the `GetDocument()` function that returns the address of the document object for the current view:

```
CSketcherDoc* pDoc = GetDocument();
```

The `GetDocument()` function in `CSketcherView` retrieves the pointer to the document from `m_pDocument`, an inherited member of the view object. The function performs the important task of casting the pointer stored in this member to the type corresponding to the document class in the application, `CSketcherDoc`. This is so you can use the pointer to access the members of the document class that you've defined; otherwise, you could use the pointer only to access the members of the base class. Thus `pDoc` points to the document object in your application that is associated with the current view, and you will use it to access the data that you've stored in the document.

The next line is:

```
ASSERT_VALID(pDoc);
```

This macro ensures that `pDoc` contains a valid address, and the `if` statement that follows verifies that `pDoc` is not `nullptr`. `ASSERT_VALID` is ignored in a release version of the application.

The parameter name, `pDC`, for the `OnDraw()` function stands for “pointer to device context.” The `CDC` object pointed to by `pDC` is the key to drawing in a window. It provides a device context for the client area of the view, plus the tools you need to write graphics and text to it, so you need to look at this in more detail.

The CDC Class

You should do all the drawing in your program using members of the `CDC` class. All objects of this class and classes derived from it contain a device context and the member functions you need for sending graphics and text to your display or your printer. There are also member functions for retrieving information about the physical output device you are using.

Because a `CDC` object provides almost everything you're likely to need in the way of graphical output, there are a lot of member functions of this class — in fact, well over a hundred. You'll look only at the ones you're going to use in the Sketcher program in this chapter; I'll go into others as you need them later on.

The MFC includes some more specialized classes for graphics output that are derived from `CDC`. For example, you will be using `CCClientDC` objects. The `CCClientDC` class has the advantage over `CDC` that it always contains a device context that represents only the client area of a window, and this is precisely what you want in most circumstances.

Displaying Graphics

You draw entities such as lines, circles, and text relative to the *current position* in a device context. The current position is a point in the client area that was set either by the previous entity that was drawn or by you calling a function to set it. For example, you could extend the `OnDraw()` function to set the current position like this:

```
void CSketcherView::OnDraw(CDC* pDC)
{
    CSketcherDoc* pDoc = GetDocument();
    ASSERT_VALID(pDoc);
    if(!pDoc)
        return;

    pDC->MoveTo(50, 50); // Set the current position as 50,50
}
```

The first line is bolded because I changed it. You must uncomment the parameter name if the code is to compile. The second bolded line calls the `MoveTo()` function for the `CDC` object pointed to by `pDC`. This function sets the current position to the x- and y-coordinates you specify as arguments. The default mapping mode is `MM_TEXT` so the coordinates are in pixels. The current position will be set to a point 50 pixels to the right from the inside-left border of the window, and 50 pixels down from the top of the client area.

The `CDC` class overloads the `MoveTo()` function to provide flexibility as to how you specify the current position that you want to set. There are two versions declared in the `CDC` class as:

```
CPoint MoveTo(int x, int y);      // Move to position x,y
CPoint MoveTo(POINT aPoint);     // Move to position defined by aPoint
```

The first version accepts the x- and y-coordinates as separate arguments. The second accepts one argument of type `POINT`. This is a structure that is defined as:

```
typedef struct tagPOINT
{
    LONG x;
    LONG y;
} POINT;
```

The coordinates are the `x` and `y` members of the struct and are of type `LONG`, which is a type defined in the Windows API as a 32-bit signed integer. You may prefer to use a class instead of a structure, in which case, you can use a `CPoint` object anywhere that a `POINT` object can be used. The `CPoint` class has data members `x` and `y` of type `LONG`, and using `CPoint` objects has the advantage that the class also defines functions that operate on both `CPoint` and `POINT` objects. This may seem weird because `CPoint` would seem to make `POINT` objects obsolete, but remember that the Windows API was built before the MFC was around, and `POINT` objects are used in the Windows API and have to be dealt with sooner or later. I'll use `CPoint` objects in examples, so you'll see some of the functions in action.

The `MoveTo()` function returns a `CPoint` object that specifies the current position as it was *before* the move. You might think this is a little odd, but consider the situation in which you want to move to a new position, draw something, and then move back. You may not know the current position before the move, and it is lost after the move occurs, so returning the position as it was before the move makes sure it's available to you if you need it.

Drawing Lines

You can follow the call to `MoveTo()` in the `OnDraw()` function with a call to the `LineTo()` function, which draws a line in the client area from the current position to the point specified by the arguments, as illustrated in Figure 14-3.




FIGURE 14-3

The `CDC` class defines two versions of the `LineTo()` function that have the following prototypes:

```
BOOL LineTo(int x, int y);    // Draw a line to position x,y
BOOL LineTo(POINT aPoint);    // Draw a line to position defined by aPoint
```

This offers you the same flexibility for the arguments as `MoveTo()`. You can use a `CPoint` object as the argument to the second version of the function. The function returns `TRUE` if the line is drawn and `FALSE` otherwise.

When the `LineTo()` function executes, the current position is changed to the point at the end of the line. This enables you to draw a series of connected lines by just calling the `LineTo()` function for each line. Look at the following version of the `OnDraw()` function:

```
void CSketcherView::OnDraw(CDC* pDC)
{
    CSketcherDoc* pDoc = GetDocument();
    ASSERT_VALID(pDoc);
    if (!pDoc)
        return;

    pDC->MoveTo(50,50);           // Set the current position
    pDC->LineTo(50,200);         // Draw a vertical line down 150 units
    pDC->LineTo(150,200);        // Draw a horizontal line right 100 units
    pDC->LineTo(150,50);         // Draw a vertical line up 150 units
    pDC->LineTo(50,50);         // Draw a horizontal line left 100 units
}
```

If you plug this code into the Sketcher program and execute it, it will display the document window shown in Figure 14-4. Don't forget to uncomment the parameter name.

The four calls to `LineTo()` draw the rectangle counterclockwise starting with the upper-left corner. The first uses the current position set by the `MoveTo()` function; the succeeding calls use the current position set by the previous `LineTo()` function call. You can use this method to draw any figure consisting of a sequence of lines, each connected to the previous line. Of course, you can use `MoveTo()` to change the current position at any time.

Drawing Circles

You have a choice of several `CDC` member functions for drawing circles, but they're all designed to draw ellipses. As you know from high-school geometry, a circle is a special case of an ellipse that has its major and minor axes equal. You can, therefore, use the `Ellipse()` member to draw a circle. Like other closed shapes supported by the `CDC` class, the `Ellipse()` function fills the interior of the shape with a color that you set. The interior color is determined by a *brush* that is selected into the device context. A brush is one example of a GDI object that is used to draw in a window and is encapsulated by the MFC `CBrush` class. The current brush in the device context determines how any closed shape is filled. There are two versions of the `Ellipse()` function:

```
BOOL Ellipse(int x1, int y1, int x2, int y2);
BOOL Ellipse(LPCRECT lpRect);
```




FIGURE 14-4

The first draws an ellipse bounded by the rectangle defined by the points x_1, y_1 , and x_2, y_2 . The second version defines the ellipse by a `RECT` object that is pointed to by the argument. The function also accepts a pointer to an object of the MFC `CRect` class, which has four public data members: `left`, `top`, `right`, and `bottom`. These correspond to the x- and y-coordinates of the upper-left and lower-right points of the rectangle. `CRect` provides function members that operate on `CRect` objects, and you will be using some of these later. `Ellipse()` returns `TRUE` if the operation is successful and `FALSE` if it is not. With either function, the ellipse that is drawn extends up to, but does not include, the right and bottom sides of the rectangle. This means that the width and height of the ellipse are $x_2 - x_1$ and $y_2 - y_1$, respectively.

You can set the color of a `CBrush` object and also define a pattern to be produced when you are filling a closed shape such as an ellipse. If you want to draw a closed shape that isn't filled, you can select a null brush into the device context, which leaves the interior of the shape empty. I'll come back to brushes a little later in this chapter.

Another way to draw circles that aren't filled is to use the `Arc()` function, which doesn't involve brushes. This is because the curve drawn by the `Arc()` function is not closed, and therefore cannot be filled. `Arc()` has the advantage that you can draw any arc of an ellipse. There are two versions of this function in the `CDC` class:

```
BOOL Arc(int x1, int y1, int x2, int y2, int x3, int y3, int x4, int y4);
BOOL Arc(LPCRECT lpRect, POINT startPt, POINT endPt);
```

In the first version, (x_1, y_1) and (x_2, y_2) define the upper-left and lower-right corners of a rectangle enclosing the complete curve. If these coordinates are the corners of a square, the curve drawn is a segment of a circle. The points (x_3, y_3) and (x_4, y_4) define the start and end points of the segment to be drawn. The segment is drawn counterclockwise from (x_3, y_3) to (x_4, y_4) . If you make (x_4, y_4) identical to (x_3, y_3) , you'll generate a complete ellipse, although it will not be a closed curve.

In the second version of `Arc()`, the enclosing rectangle is defined by a `RECT` object, and a pointer to this object is passed as the first argument. The `POINT` objects `startPt` and `endPt` define the start and end of the arc to be drawn, respectively.

Here's some code that calls the `Ellipse()` and `Arc()` functions:

```
void CSketcherView::OnDraw(CDC* pDC)
{
    CSketcherDoc* pDoc = GetDocument();
    ASSERT_VALID(pDoc);
    if (!pDoc)
        return;

    pDC->Ellipse(50,50,150,150);           // Draw the 1st (large) circle

    // Define the bounding rectangle for the 2nd (smaller) circle
    CRect rect(250,50,300,100);
    CPoint start(275,100);                 // Arc start point
```

```

    CPoint end(250,75);           // Arc end point
    pDC->Arc(&rect, start, end); // Draw the second circle
}

```

You use a `CRect` class object instead of a `RECT` structure to define the bounding rectangle, and you use `CPoint` objects instead of `POINT` structures. You'll be using `CRect` objects again later, and they have some limitations, as you'll see. The `Arc()` and `Ellipse()` functions do not require a current position to be set because the position and extent of the curve are completely defined by the arguments you supply. The current position is unaffected by the drawing of an arc or an ellipse — it remains exactly wherever it was before the shape was drawn. Now, try running Sketcher with this code in the `OnDraw()` function. You should get the results shown in Figure 14-5.

Try moving the borders of the window. The client area is automatically redrawn as you cover or uncover the arcs. Remember that screen resolution affects the scale of what is displayed. The lower the screen resolution, the larger and farther from the upper-left corner of the client area the arcs will be.

Drawing in Color

Everything that you've drawn so far has appeared on the screen in black. Drawing always uses a *pen object* that specifies the color, thickness, and line type (solid, dotted, dashed, and so on) that is drawn. A pen is another GDI object. You have been using the default pen object that is provided in a device context up to now. You're not obliged to do this, of course — you can create your own pen with a given thickness, color, and line type. MFC defines the class `CPen` to help you do this.

Creating a Pen

The simplest way to create a pen is first to define an object of the `CPen` class using the default class constructor:

```
CPen aPen;           // Declare a pen object
```

This object must be initialized with the properties you want and you do this by calling the `CreatePen()` function for the object. This function is declared in the `CPen` class as:

```
BOOL CreatePen (int aPenStyle, int aWidth, COLORREF aColor);
```




FIGURE 14-5

The function returns `TRUE` as long as the pen is successfully initialized and `FALSE` otherwise. The first argument defines the line style, which must be one of the following symbolic values:

PEN STYLE	DESCRIPTION
<code>PS_SOLID</code>	The pen draws a solid line.
<code>PS_DASH</code>	The pen draws a dashed line. This line style is valid only when the pen width is 1.
<code>PS_DOT</code>	The pen draws a dotted line. This line style is valid only when the pen width is 1.
<code>PS_DASHDOT</code>	The pen draws a line with alternating dashes and dots. This line style is valid only when the pen width is 1.
<code>PS_DASHDOTDOT</code>	The pen draws a line with alternating dashes and double dots. This line style is valid only when the pen width is 1.
<code>PS_NULL</code>	The pen doesn't draw anything.
<code>PS_INSIDEFRAME</code>	The pen draws a solid line but, unlike with <code>PS_SOLID</code> , the points that specify the line occur on the edge of the pen rather than in the center, so that the drawn object never extends beyond the defining rectangle for closed shapes such as ellipses.

NOTE There is another `CPen` class constructor that enables you to create your own line styles. You specify a line style by an array of values that specify the lengths of the dashes and spaces in the line.

The second argument to `CreatePen()` defines the line width. If `aWidth` is 0, the line is one pixel wide, regardless of the mapping mode in effect. For values of 1 or more, the pen width is in units determined by the mapping mode. For example, a value of 2 for `aWidth` in `MM_TEXT` mode is two pixels; in `MM_LOENGLISH` mode, the pen width is 0.02 inches.

The last argument specifies the line color, so you could initialize a pen with the following statement:

```
aPen.CreatePen(PS_SOLID, 2, RGB(255,0,0)); // Create a red solid pen
```

If the mapping mode is `MM_TEXT`, this pen draws a solid red line that is two pixels wide. `RGB` is the macro that you met in Chapter 13. It creates a 24-bit color value composed from three unsigned byte integer values that are the intensities of the red, green, and blue components of the color.

You can also create a pen object with specified line type, width, and color using the constructor:

```
CPen aPen(PS_SOLID, 2, RGB(0, 255, 0)); // Create a green solid pen
```

When you create a pen of your own in this way, you are creating a Windows GDI **PEN** object that is encapsulated by the **CPen** object. When the **CPen** object is destroyed, the **CPen** destructor will delete the GDI pen object automatically. If you create a GDI **PEN** object explicitly, you must delete the object by calling **DeleteObject()** with the **PEN** object as the argument.

Using a Pen

To use a pen, you must select it into the device context. You call the **SelectObject()** function for the **CDC** object to do this. To select a pen, you call this function with the address of the pen object as the argument. The function returns a pointer to the previous pen object, so that you can save the old pen and restore it when you have finished drawing. A typical statement selecting a pen is:

```
CPen* pOldPen = pDC->SelectObject(&aPen); // Select aPen as the pen
```

You must always return a device context to its original state once you have finished with whatever you have selected into it. To restore the old pen when you're done, you call **SelectObject()** again, passing the pointer returned from the original call as the argument:

```
pDC->SelectObject(pOldPen); // Restore the old pen
```

You can see all this in action if you amend the previous version of the **OnDraw()** function in **CSketcherView** to the following:

```
void CSketcherView::OnDraw(CDC* pDC)
{
    CSketcherDoc* pDoc = GetDocument();
    ASSERT_VALID(pDoc);
    if(!pDoc)
        return;

    // Declare a pen object and initialize it as
    // a red solid pen drawing a line 2 pixels wide
    CPen aPen;
    aPen.CreatePen(PS_SOLID, 2, RGB(255, 0, 0));

    CPen* pOldPen = pDC->SelectObject(&aPen); // Select aPen as the pen
    pDC->Ellipse(50,50,150,150); // Draw the 1st (large) circle

    // Define the bounding rectangle for the 2nd (smaller) circle
    CRect rect(250,50,300,100);
    CPoint start(275,100); // Arc start point
    CPoint end(250,75); // Arc end point
    pDC->Arc(&rect,start, end); // Draw the second circle
    pDC->SelectObject(pOldPen); // Restore the old pen
}
```

If you build and execute Sketcher with this version of **OnDraw()**, you get the same curves drawn as before, but this time, the lines will be thicker and they'll be red. You could usefully experiment with

this example by trying different combinations of arguments to the `CreatePen()` function and seeing their effects. Note that we have ignored the value returned from the `CreatePen()` function, so you run the risk of the function failing and not detecting it in the program. It doesn't matter here, as the program is trivial, but as you develop the program, it is important to check for failures of this kind.

Creating a Brush

An object of the `CBrush` class encapsulates a Windows brush. You can define a brush to be solid, hatched, or patterned. A brush is actually an eight-by-eight block of pixels that's repeated over the region to be filled.

To define a brush with a solid color, you just specify the color when you create the object. For example:

```
CBrush aBrush(RGB(255,0,0));           // Define a red brush
```

This statement defines a red brush. The value passed to the `CBrush` constructor must be of type `COLORREF`, which is the type produced by the `RGB()` macro so this is a good way to specify the color here.

Another constructor is available to define a hatched brush. It requires two arguments: the first defines the type of hatching, and the second specifies the color, as before. The hatching argument can be any of the following:

HATCHING STYLE	DESCRIPTION
<code>HS_HORIZONTAL</code>	Horizontal hatching
<code>HS_VERTICAL</code>	Vertical hatching
<code>HS_BDIAGONAL</code>	Downward hatching from left to right at 45 degrees
<code>HS_FDIAGONAL</code>	Upward hatching from left to right at 45 degrees
<code>HS_CROSS</code>	Horizontal and vertical crosshatching
<code>HS_DIAGCROSS</code>	Crosshatching at 45 degrees

To obtain a red, 45-degree crosshatched brush, you could define the `CBrush` object with the following statement:

```
CBrush aBrush(HS_DIAGCROSS, RGB(255,0,0));
```

You can initialize a `CBrush` object much as you do a `CPen` object, by calling the `CreateSolidBrush()` member for a `CBrush` object to initialize it as a solid brush, and the `CreateHatchBrush()` member for a hatched brush. They require the same arguments as the equivalent constructors. For example, you could create the same hatched brush as before with the following statements:

```
CBrush aBrush; // Define a brush object
aBrush.CreateHatchBrush(HS_DIAGCROSS, RGB(255,0,0));
```

Using a Brush

To use a brush, you select the brush into the device context by calling the `SelectObject()` member of the `CDC` object much as you did for a pen. This member function is overloaded to support selecting brush objects into a device context. This selects the brush defined previously:

```
CBrush* pOldBrush = pDC->SelectObject(&aBrush); // Select the brush into the DC
```

`SelectObject()` returns a pointer to the old brush, or `NULL` if the operation fails. You use the pointer that is returned to restore the old brush in the device context when you are done.

There are seven standard brushes available that are identified by predefined constants. They are:

GRAY_BRUSH	LTGRAY_BRUSH	DKGRAY_BRUSH
BLACK_BRUSH	WHITE_BRUSH	
HOLLOW_BRUSH	NULL_BRUSH	

The names of these brushes are quite self-explanatory. To use one, call the `SelectStockObject()` member of the `CDC` object, with the symbolic name for the brush that you want to use as the argument. To select the null brush that leaves the interior of a closed shape unfilled, you would write this:

```
CBrush* pOldBrush = dynamic_cast<CBrush*>(pDC->SelectStockObject(NULL_BRUSH));
```

`pDC` is a pointer to the `CDC` object, as before. You can also select one of a range of standard pens with the `SelectStockObject()` function. The symbols for standard pens are `BLACK_PEN`, `NULL_PEN` (which doesn't draw anything), and `WHITE_PEN`. `SelectStockObject()` works with a variety of object types. You've seen pens and brushes in this chapter but it also works with fonts. The return type for `SelectStockObject()` is `CGdiObject*`. `CGdiObject` is a base class for all the GDI object classes, so a pointer to this class type can store the address of any GDI object. You can store the pointer returned by `SelectObject()` or `SelectStockObject()` as type `CGdiObject*` and pass that to `SelectObject()` when you want to restore it. However, it is better to `dynamic_cast` the pointer value to the appropriate type so that you can keep track of the types of objects you are restoring.

The typical coding pattern for using a stock brush and later restoring the old brush when you're done is this:

```
CBrush* pOldBrush = dynamic_cast<CBrush*>(pDC->SelectStockObject(NULL_BRUSH));
// draw something...
pDC->SelectObject(pOldBrush); // Restore the old brush
```

You'll be using this pattern in an example later in the chapter.

DRAWING GRAPHICS IN PRACTICE

You now know how to draw lines and arcs, so it's about time to consider how a user is going to draw in Sketcher. In other words, you need to decide how the user interface is going to work.

Because Sketcher is to be a sketching tool, you don't want the user to worry about coordinates. The easiest mechanism for drawing is using just the mouse. To draw a line for instance, users could position the mouse cursor where the line is to start and press the left mouse button; they could then define the end of the line by moving the cursor to where they want with the left button held down, then releasing it. It would be ideal if you could arrange for the line to be continuously drawn as the cursor is moved with the left button down (this is known as "rubber-banding"). The line would be fixed when the left mouse button is released. Figure 14-6 illustrates this process.




FIGURE 14-6

Circles can be drawn in a similar fashion. The point where the left mouse button is pressed defines the center, and as the cursor is dragged with the button down, the program tracks and redraws the circle continuously with the cursor position defining a point on the circumference. Like the line, the circle is fixed when the left mouse button is released. Figure 14-7 shows this process.




FIGURE 14-7

You can draw a rectangle as easily as you draw a line, as illustrated in Figure 14-8.




FIGURE 14-8

The first point is defined by the cursor position when the left mouse button is pressed. This is one corner of the rectangle. The cursor position when the mouse is moved with the left button held down defines the diagonally opposite corner of the rectangle. The rectangle stored is the one defined when the mouse button is released.

A curve is somewhat different. An arbitrary number of points may define a curve. The mechanism you'll use is illustrated in Figure 14-9. As with the other shapes, the first point is defined by the cursor position when the left mouse button is pressed. Successive cursor positions that are recorded as the mouse cursor is moved are connected by straight line segments to form the curve, so the mouse cursor track defines the curve to be drawn.




FIGURE 14-9

Now that you know how the user is going to define elements, the next step in understanding how you can implement this process is to get a grip on how the mouse is programmed.

PROGRAMMING FOR THE MOUSE

To program the drawing of Sketcher elements in the way that I have discussed, you need to identify how the mouse will be used:

- Pressing a mouse button signals the start of a drawing operation.
- The location of the cursor when the mouse button is pressed provides a first defining point for the shape.
- A mouse movement after detecting that a mouse button has been pressed is a cue to draw a shape, and the cursor position provides a second defining point for the shape.
- Releasing the mouse button signals the end of the drawing operation and that the final version of the shape should be drawn using the last cursor position.

As you may have guessed, all the information about what is happening with the mouse and its buttons is provided by Windows in the form of messages sent to your program. The implementation of the process for drawing lines, rectangles, circles, and curves consists almost entirely of writing message handlers.

Messages from the Mouse

When the users of your program are drawing an element, they will interact with a particular document view. The view class is, therefore, the obvious place to put the message handlers for the mouse. Right-click the CSketcherView class name in Class View and then display its properties window by selecting Properties from the menu. If you then click the messages button (wait for the button tooltips to display if you don't know which it is) you'll see the list of IDs for the standard Windows messages that are sent to the class, which are prefixed with WM_ (see Figure 14-10).

You need to know about three mouse messages at the moment:




FIGURE 14-10

MESSAGE	DESCRIPTION
WM_LBUTTONDOWN	Occurs when the left mouse button is pressed
WM_LBUTTONUP	Occurs when the left mouse button is released
WM_MOUSEMOVE	Occurs when the mouse is moved

These messages are quite independent of one another and are sent to the document views in your program even if you haven't supplied handlers for them. It's quite possible for a window to receive a WM_LBUTTONUP message without having previously received a WM_LBUTTONDOWN message. This can happen if the button is pressed with the cursor over another window and the cursor is then moved to your view window before being released, so you must keep this in mind when coding handlers for these messages.

If you look at the list in the Properties window, you'll see there are other mouse messages that can occur. You can choose to process any or all of these, depending on your application. Let's define in general terms what we want to do with the three messages we are currently interested in, based on the process we have defined for drawing lines, rectangles, curves, and circles.

WM_LBUTTONDOWN

This message starts the process of drawing an element. You should do the following:

1. Record that the element-drawing process has started.
2. Store the current cursor position as the first defining point for an element.

WM_MOUSEMOVE

This message is an intermediate stage in drawing an element in which you want to create and draw a temporary version of it, but only if the left mouse button is down. Complete the following steps:

1. Verify that the left button is down.
2. If the left button is down, delete any previous version of the current element that was drawn.
3. If the left button isn't down, then exit the element creation operation.
4. Record the current cursor position as the second defining point for the current element.
5. Cause the current element to be drawn using the two defining points.

WM_LBUTTONUP

This message indicates that the element drawing process is finished. You need to do the following:

1. Store the final version of the element defined by the first point recorded, together with the last cursor position when the button was released for the second point.
2. Record the end of the process of drawing an element.

Now you are ready to generate handlers for these messages.

Mouse Message Handlers

Display the Properties for the `CSketcherView` class and click the `Messages` icon to display the messages this class can handle. You can create a handler for a mouse message by clicking its ID in the Properties window to select it and then selecting from the list that is displayed when you click the down arrow in the adjacent column position. Try selecting `<add> OnLButtonUp` for the `WM_LBUTTONUP` message, for example. Repeat the process for the `WM_LBUTTONDOWN` and `WM_MOUSEMOVE` messages. The functions generated in `CSketcherView` are `OnLButtonDown()`, `OnLButtonUp()`, and `OnMouseMove()`. You don't get the option of changing the names of these, because you're adding overrides for versions already defined in the base class. Now, we'll look at how you implement these handlers.

You can start with the `WM_LBUTTONDOWN` message handler. This is the skeleton code that's generated:

```

void CSketcherView::OnLButtonDown(UINT nFlags, CPoint point)
{
    // TODO: Add your message handler code here and/or call default

    CView::OnLButtonDown(nFlags, point);
}

```

There is a call to the base class handler in the skeleton version. This ensures that the base handler is called if you don't add any code. You don't need to call the base class handler when you handle this message yourself, although you can if you want to. Whether you need to call a base class message handler depends on the circumstances.

Generally, the comment in the implementation of your handler that indicates where you should add your code is a good guide. Where it suggests, as in the present instance, that calling the base class handler is optional, you can omit it when you add your own code. The position of the comment in relation to the base class handler call is also important, because sometimes you must call the base class handler before your code, and sometimes afterwards. The comment indicates where your code should appear in relation to the base class handler call.

The WM_LBUTTONDOWN handler is passed two arguments:

- `nFlags` is of type `UINT` and contains a number of status flags indicating which keys and/or mouse buttons are down. The `UINT` type is defined in the Windows API and corresponds to a 32-bit unsigned integer.
- The `CPoint` object, `point`, defines the cursor position when the left mouse button was pressed.

The value of `nFlags` can be any combination of the following values:

FLAG	DESCRIPTION
<code>MK_CONTROL</code>	The control key is pressed.
<code>MK_LBUTTON</code>	The left mouse button is down.
<code>MK_MBUTTON</code>	The middle mouse button is down.
<code>MK_RBUTTON</code>	The right mouse button is down.
<code>MK_XBUTTON1</code>	The first extra mouse button is down.
<code>MK_XBUTTON2</code>	The second extra mouse button is down.
<code>MK_SHIFT</code>	The shift key is pressed.

Being able to detect if a key is pressed enables you to support different actions for the message, depending on the states of the key. `nFlags` may contain more than one of these flags, each of which corresponds to a unique single bit in the word. You can test if a particular flag bit is 1 using the bit-wise AND operator. For example, to test if the control key is pressed you could write:

```

if(nFlags & MK_CONTROL)
    // Do something...

```

The expression `nFlags & MK_CONTROL` will be a non-zero value that converts to `true` only if `nFlags` has the `MK_CONTROL` bit set. In this way, you can perform different actions when the left mouse button is pressed, depending on whether or not the control key is pressed. You use the bitwise `AND` operator here, which `ANDs` corresponding bits together. Don't confuse this with the logical `AND`, `&&`, which would not do what you want here.

The arguments passed to the other two message handlers are the same as those for `OnLButtonDown()`; the code generated for them is:

```
void CSketcherView::OnLButtonUp(UINT nFlags, CPoint point)
{
    // TODO: Add your message handler code here and/or call default

    CView::OnLButtonUp(nFlags, point);
}

void CSketcherView::OnMouseMove(UINT nFlags, CPoint point)
{
    // TODO: Add your message handler code here and/or call default

    CView::OnMouseMove(nFlags, point);
}
```

The skeleton code is more or less the same for each.

If you look at the end of the code for the `CSketcherView` class definition, you'll see that three function declarations have been added:

```
// Generated message map functions
protected:
    DECLARE_MESSAGE_MAP()
public:
    afx_msg void OnLButtonDown(UINT nFlags, CPoint point);
    afx_msg void OnLButtonUp(UINT nFlags, CPoint point);
    afx_msg void OnMouseMove(UINT nFlags, CPoint point);
};
```

These identify the functions that you added as message handlers. Now that you understand the information that is passed to the mouse message handlers, you can add your own code to make them do what you want.

Drawing Using the Mouse

For the `WM_LBUTTONDOWN` message, you want to record the cursor position as the first defining point for an element. You also want to record the cursor position after a mouse move. The obvious place to store these positions is in the `CSketcherView` class, so you can add data members for these. Right-click the `CSketcherView` class name in Class View and select `Add` \Rightarrow `Add Variable` from the pop-up. You'll then be able to add details of the variable to be added to the class, as Figure 14-11 shows.




FIGURE 14-11

The drop-down list of types includes only fundamental types, so you must enter the variable type as `CPoint`. The new data member should be `protected` to prevent direct modification of it from outside the class so change the Access value to that from the list. Enter the name as `m_FirstPoint`. When you click the Finish button, the variable will be created and an initial value will be set arbitrarily as 0 in the initialization list for the constructor. You'll need to amend the initial value to `CPoint(0,0)`, so the code in `SketcherView.cpp` is as follows:

```
CSketcherView::CSketcherView(): m_FirstPoint(CPoint(0,0))
{
    // TODO: add construction code here
}
```

This initializes the member to a `CPoint` object at position (0,0). You can now add `m_SecondPoint` as a protected member of type `CPoint` to the `CSketcherView` class that stores the next point for an element and amend the initialization list for the constructor to initialize it to `CPoint(0,0)`.

You can now implement the handler for the `WM_LBUTTONDOWN` message as follows:

```
void CSketcherView::OnLButtonDown(UINT nFlags, CPoint point)
{
    m_FirstPoint = point;           // Record the cursor position
}
```

All the handler does is record the point passed by the second argument. You can ignore the first argument in this situation altogether.

You can't complete the `WM_MOUSEMOVE` message handler yet, but you can have a stab at outlining the code for it:

```
void CSketcherView::OnMouseMove(UINT nFlags, CPoint point)
{
    if(nFlags & MK_LBUTTON)           // Verify the left button is down
    {
        m_SecondPoint = point;       // Save the current cursor position

        // Test for a previous temporary element
        {
            // We get to here if there was a previous mouse move
            // so add code to delete the old element
        }

        // Add code to create new element
        // and cause it to be drawn
    }
}
```

It's important to verify that the left mouse button is down because you want to handle the mouse move only when this is the case. Without the check, you would be processing the event when the right button was down or when the mouse was moved with no buttons pressed.

If the left mouse button is down, you save the current cursor position. This is the second defining point for an element. The rest of the logic is clear in general terms, but you need to establish a few more things before you can complete the function. You have no means of defining an element — you'll want to define an element as a class object, so you must define some classes. You must also devise a way to delete an element and get one drawn when you create a new one. A brief digression is called for.

Getting the Client Area Redrawn

Drawing or erasing elements involves redrawing all or part of the client area of a window. As you've already discovered, the client area gets drawn by the `OnDraw()` member function of the `CSketcherView` class, and this function is called when a `WM_PAINT` message is received by the Sketcher application. Along with the basic message to repaint the client area, Windows supplies information about the area of the client area that needs to be redrawn. This can save a lot of time when you're displaying complicated images because only the area specified needs to be redrawn, and this may be a very small proportion of the total area.

You can tell Windows that a particular area should be redrawn by calling the `InvalidateRect()` member of your view class. The function requires two arguments. The first is a pointer to a `RECT` or `CRect` object that defines the rectangle in the client area to be redrawn. Passing `nullptr` causes the whole client area to be redrawn. The second argument is a `BOOL` value, which is `TRUE` if the background to the rectangle is to be erased and `FALSE` otherwise. This argument has a default value of `TRUE`, because you normally want the background erased before the rectangle is redrawn, so you don't need to supply it most of the time.

A typical situation in which you will want to cause an area to be redrawn will be where something has changed in a way that makes it necessary — moving something displayed in the client area entity is one example. In this case, you want to erase the background to remove the old representation of what was displayed before you draw the new version. When you want to draw over an existing background, you pass `FALSE` as the second argument to `InvalidateRect()`.

Calling `InvalidateRect()` doesn't directly cause any part of the window to be redrawn; it just communicates the rectangle that you would like to have redrawn to Windows. Windows maintains a cumulative update region — actually, a rectangle — that identifies the total area in a window that needs to be redrawn, and this may be due to several `InvalidateRect()` calls. The area specified in your call to `InvalidateRect()` is added to the current update region, so the new update region encloses the old region plus the new rectangle you have identified as invalid. When a `WM_PAINT` message is sent to a window, the update region is passed to the window object along with the message. When processing of the `WM_PAINT` message is complete, the update region is reset to the empty state. Calling the `UpdateWindow()` function that is inherited in the view class causes a `WM_PAINT` message to be sent to the view.

Thus, to get a newly created element drawn you need to:

1. Make sure that the `OnDraw()` function in your view includes the newly created element when it redraws the window.
2. Call `InvalidateRect()` with a pointer to the rectangle bounding the element to be redrawn as the first argument.
3. Cause a `WM_PAINT` message to be sent to the view by calling the inherited `UpdateWindow()` function for the view.

Similarly, if you want an element removed from the client area of a window, you need to do the following:

1. Remove the element from the items that the `OnDraw()` function will draw.
2. Call `InvalidateRect()` with the first argument pointing to the rectangle bounding the element that is to be removed.
3. Cause a `WM_PAINT` message to be sent to the view by calling the inherited `UpdateWindow()` function for the view.

Because the background to the update region is automatically erased, the element disappears as long as the `OnDraw()` function doesn't draw the element again. Of course, this means that you need to be able to obtain the rectangle bounding any element that you create, so you'll include a function to return this rectangle as a member of the classes that define Sketcher elements.

Defining Element Classes

Thinking ahead a bit, as well as storing sketch elements in a document in some way, you will want to store the document in a file for subsequent retrieval if a sketch is to have any permanence. I'll deal with the details of file operations later on, but for now, it's enough to know that the MFC class `CObject` includes the tools for you to do this, so you'll use `CObject` as a base class for the classes that define sketch elements.

You don't know in advance what sequence of element types a user will create, so Sketcher must be able to handle any sequence of elements. This suggests that using a base class pointer to store the address of the latest element that was created might simplify things a bit. You'll be able to call element class functions without knowing precisely what kind of element it is. For example, you don't need to know what an element is to draw it. As long as you are accessing the element through a base class pointer, you can always get an element to draw itself by calling a `virtual` function. All you must do to achieve this is to make sure that the classes that define elements share a common base class and that you declare all the functions you want to be called polymorphically at run time as `virtual` in the base class. You could organize the element classes as shown in Figure 14-12.




FIGURE 14-12

Each arrow in the diagram points toward a base class. If you need to add another type of element, you derive another class from `CElement`.

You can create the `CElement` class by right-clicking Sketcher in Class View and selecting Add \leftrightarrow Class from the pop-up. Select MFC from the list of installed templates, and then select MFC Class in the center pane. When you click the Add button in the dialog, another dialog displays in which you can specify the class name and select the base class, as shown in Figure 14-13.




FIGURE 14-13

I have already filled in the class name as `CElement` and selected `CObject` from the drop-down list as the base class. When you click the Finish button, the code for the class definition is generated:

```
#pragma once

// CELEMENT command target

class CELEMENT : public CObject
{
public:
    CELEMENT();
    virtual ~CELEMENT();
};
```

The only members that have been declared for you are a constructor and a virtual destructor, and skeleton definitions for these appear in the `Element.cpp` file. You can see that the Class Wizard has included a `#pragma once` directive to ensure that the contents of the header file cannot be included into another file more than once.

You can add the other element classes using essentially the same process. Because the other element classes have `CELEMENT` rather than an MFC class as the base class, you should set the class category as `C++` and the template as `C++ class`. Select the Virtual destructor option. For the `CLine` class, the Class Wizard dialog should look like Figure 14-14.




FIGURE 14-14

The Class Wizard supplies the names of the header file and .cpp file as `Line.h` and `Line.cpp` by default, but you can change these to use different names or have the code added to existing files. You get an `#include` directive for `Element.h` for the base class definition. When you have created the `CLine` class definition, do the same for `CRectangle`, `CCircle`, and `CCurve`. When you are done, you should have .h files containing the definitions of all four subclasses of `CElement`, each with a constructor and a virtual destructor declared.

Storing a Temporary Element in the View

When I discussed how sketch elements would be drawn, it was evident that as the mouse was dragged with the left mouse button down, a series of temporary element objects would be created and drawn. The base class for all elements is `CElement`, so you can add a smart pointer of type `std::shared_ptr<CElement>` to the view class to store the address of a temporary element. You could consider `unique_ptr` as a candidate for this but eventually you will need access to a pointer to an element in the mouse event handler functions, while the same pointer is stored in a container in the document object. A `unique_ptr` would not allow this.

First, you can add `#include` directives for the `memory` header and `Element.h` following the `#pragma once` directive. Next, right-click `CSketcherView` and select the `Add` \leftrightarrow `Add Variable` option. The `m_pTempElement` variable will be of type `std::shared_ptr<CElement>`, and it should be protected like the previous two data members that you added. You'll be able to use the `m_pTempElement` pointer in the `WM_MOUSEMOVE` message handler as a test for whether a previous temporary element exists because it will be `nullptr` when there are none.

The CElement Class

You'll be developing the element class definitions incrementally as you increase the functionality of Sketcher — but what do you need right now? Some data items, such as color and position, are common to all types of elements, so you can put those in the `CElement` base class so that they are inherited in the derived classes. Other data members that define specific element properties will be declared in the derived class to which they belong.

The `CElement` class will contain virtual functions that will be implemented in the derived classes, plus data and function members that are common to all the derived classes. The virtual functions will be those that are selected polymorphically for a particular object through a `CElement*` pointer. You could use the Add Member Wizard to add these members to the `CElement` class, but modify the class manually for a change. For now, you can modify the `CElement` class definition to the following:

```
class CElement: public CObject
{
protected:
    CPoint m_StartPoint;           // Element position
    int m_PenWidth;               // Pen width
    COLORREF m_Color;             // Color of an element
    CRect m_EnclosingRect;        // Rectangle enclosing an element

public:
    virtual ~CElement();
    virtual void Draw(CDC* pDC) {} // Virtual draw operation

    // Get the element enclosing rectangle
    const CRect& GetEnclosingRect() const { return m_EnclosingRect; }

protected:
    // Constructors protected so they cannot be called outside the class
    CElement();
    CElement(const CPoint& start, COLORREF color, int penWidth = 1);
};
```

I have made the constructors `protected` to prevent them from being called from outside the class. The new constructor will only be called from a derived class. It has three parameters with a default value for the pen width because most of the time the pen width will be 1. At the moment, the data members to be inherited in the derived classes store the position, the color, and the pen width for an element, and the enclosing rectangle that identifies the area occupied by an element.

There are two member function definitions within the class:

- `GetEnclosingRect()` returns `m_EnclosingRect`. This will be used when the area an element occupies needs to be invalidated.
- A virtual `Draw()` function that will be implemented in the derived classes to draw an element. The `Draw()` function needs a pointer to a `CDC` object passed to it to provide access to the functions that you need to draw in a device context.

You might be tempted to declare the `Draw()` member as a pure virtual function in the `CElement` class and leave it to the derived classes to define — after all, it can have no meaningful content here. Normally, you would do this, but `CElement` inherits a facility from `CObject` called *serialization* that you'll use later to store element objects in a file. Serialization requires that `CElement` is not abstract so an object of this type can be created. If you want to use MFC's serialization capability, your classes must not be abstract and they must have a no-arg constructor.

NOTE *Serialization is a general term for writing objects to a file.*

You can add the definition for the new constructor to `Element.cpp`:

```
CElement::CElement(const CPoint& start, COLORREF color, int penWidth) :
    m_StartPoint(start), m_PenWidth(penWidth), m_Color(color) {}
```

All members are initialized in the initialization list so there is no code required for the body of the constructor.

The CLine Class

You can amend the definition of the `CLine` class to the following:

```
class CLine: public CElement
{
public:
    virtual ~CLine(void);
    virtual void Draw(CDC* pDC) override; // Function to display a line

    // Constructor for a line object
    CLine(const CPoint& start, const CPoint& end, COLORREF aColor);

protected:
    CPoint m_EndPoint; // End point of line

protected:
    CLine(void); // Default constructor should not be used
};
```

A line is defined by two points, `m_StartPoint` that is inherited from `CElement` and `m_EndPoint`. The class has a `public` constructor that has parameters for the values that define a line, and the no-arg default constructor has been moved to the `protected` section of the class to prevent its use externally. The constructor parameters are `const` references to avoid copying the arguments. Using the `override` keyword with the `OnDraw()` member declaration ensures that the compiler will verify that it overrides the base class function correctly.

Implementing the CLine Class

You put the implementations of the `CLine` member functions in the `Line.cpp` file that was created by the Class Wizard. The `stdafx.h` file that is included into this file makes the standard system

header files available and the contents of `stdafx.h` will be precompiled. Any of your headers that you do not anticipate changing can be included in `stdafx.h` to have them precompiled too. You can now add the basic code for the `CLine` constructor to `Line.cpp`.

The `CLine` Constructor

The code for the constructor is as follows:

```
// CLine class constructor
CLine::CLine(const CPoint& start, const CPoint& end, COLORREF color) :
    CEElement(start, color), m_EndPoint(end) {}
```

You initialize the inherited `m_StartPoint` and `m_Color` members by calling the `CEElement` base class constructor. The pen width is set to 1 by default in this constructor when you omit the third argument. The `m_EndPoint` member of `CLine` is initialized in the initialization list for the constructor. You'll add a bit more code to this later.

Drawing a Line

The `CPen` object you need to draw lines will be the same for all elements. You could usefully add a function within the `CEElement` class definition to create it:

```
// Create a pen
void CreatePen(CPen& aPen)
{
    if(!aPen.CreatePen(PS_SOLID, m_PenWidth, m_Color))
    {
        // Pen creation failed
        AfxMessageBox(_T("Pen creation failed."), MB_OK);
        AfxAbort();
    }
}
```

This will only be called by derived class objects so you can put the definition in a protected section of the class. Defining the function within the class definition will make it inline. The reference parameter allows the function to modify the `aPen` object that is defined in the calling function. Calling `CreatePen()` for a `CPen` object creates a pen and attaches it to the object. You create a pen of the appropriate color and with a line thickness specified by `m_PenWidth`, and you make sure that the creation works. In the unlikely event that it doesn't, the most likely cause is that you're running out of memory, which is a serious problem. This is almost invariably caused by an error in the program, so you have written the function to call `AfxMessageBox()`, which is an MFC global function to display a message box, and then call `AfxAbort()` to terminate the program. The first argument to `AfxMessageBox()` specifies the message that is to appear, and the second specifies that it should have an OK button. You can get more information on either of these functions by placing the cursor within the function name in the Editor window and then pressing F1.

Without this function in the base class, you would have to repeat this code in the `Draw()` function in every derived class.

WARNING Device contexts, pens, brushes, fonts, and other objects you use to draw in a window are GDI objects. You must not attempt to copy or assign GDI objects. If you do, your code will not compile. This has implications. It means, for example, that you cannot pass a GDI object by value to another function.

The `Draw()` function for the `CLine` class isn't too difficult, although you do need to take account of the color that is to be used when the line is drawn:

```
// Draw a CLine object
void CLine::Draw(CDC* pDC)
{
    // Create a pen for this object and initialize it
    CPen aPen;
    CreatePen(aPen);

    CPen* pOldPen = pDC->SelectObject(&aPen);           // Select the pen

    // Now draw the line
    pDC->MoveTo(m_StartPoint);
    pDC->LineTo(m_EndPoint);

    pDC->SelectObject(pOldPen);                         // Restore the old pen
}
```

Calling the inherited `CreatePen()` function sets up the pen in `aPen`. After selecting the pen into the device context, you move the current position to the start of the line, defined in `m_StartPoint`, and then draw the line from this point to `m_EndPoint`. Finally, you restore the old pen in the device context and you are done.

Creating Enclosing Rectangles

At first sight, obtaining the enclosing rectangle for an element looks trivial. For example, a line is always a diagonal of a rectangle, and a circle is defined by a rectangle, but there are a couple of slight complications. The element must lie *completely* inside the enclosing rectangle; otherwise, part of the element may not be drawn or erased. You must take account of how the element is drawn in relation to its defining parameters and allow for the thickness of the line used to draw it. How you work out adjustments to the coordinates that define the enclosing rectangle depends on the mapping mode, so you must take that into account too.

Different mapping modes only affect how you adjust the y-coordinates of the corners of a defining rectangle to obtain the enclosing rectangle; adjustment of the x-coordinate is the same for all mapping modes; you subtract the line thickness from the x-coordinate of the top-left corner and add it to the x-coordinate of the bottom-right corner. To adjust the y-coordinate of the top-left corner of the defining rectangle in the `MM_TEXT` mapping mode, you *subtract* the line thickness from it. However, in `MM_LOENGLISH` (and all the other mapping modes), the y-axis increases in the opposite direction, so you need to *add* the line thickness to the y-coordinate of the upper-left corner of the defining rectangle. You'll create the enclosing rectangle for an element in the constructor for each element type.

WARNING The data members of a CRect object are left and top storing the x- and y-coordinates of the top-left corner, and right and bottom storing the coordinates of the bottom-right corner. These are all public members, so you can access them directly. A mistake often made, especially by me, is to write the coordinate pair as (top, left) instead of the correct order: (left, top).

Normalized Rectangles

A *normalized rectangle* is a rectangle where the value of the `left` coordinate is less than the `right`, and the `top` coordinate is less than the `bottom`. If a rectangle is not normalized, functions that operate on CRect objects won't work correctly. For example, the `InflateRect()` member of the CRect class works by subtracting the argument values from the `top` and `left` members of the rectangle and adding them to the `bottom` and `right`. This means that you may find that your rectangle decreases in size when you apply `InflateRect()` to it if you don't make sure that the rectangle is normalized. As long as your rectangles are normalized, `InflateRect()` will work correctly whatever the mapping mode. You can normalize a CRect object by calling its `NormalizeRect()` member.

Calculating the Enclosing Rectangle for a Line

You can add code in the CLine constructor to calculate the enclosing rectangle:

```
CLine::CLine(const CPoint& start, const CPoint& end, COLORREF color):
    CEElement(start, color), m_EndPoint(end)
{
    // Define the enclosing rectangle
    m_EnclosingRect = CRect(start, end);
    m_EnclosingRect.NormalizeRect();
    m_EnclosingRect.InflateRect(m_PenWidth, m_PenWidth);
}
```

You ensure that the enclosing rectangle has `left` and `top` values that are less than its `right` and `bottom` values, regardless of the relative positions of the `start` and `end` points of the line, by calling the `NormalizeRect()` member of the `m_EnclosingRect` object. Calling `InflateRect()` enlarges the rectangle by the pen width. The first argument is the adjustment for the left and right sides and the second is the adjustment for the top and bottom. One overload of `InflateRect()` has a single parameter of type `SIZE`, which also accepts a `CSIZE` object that encapsulates the `SIZE` struct. A `CSIZE` object defines a size by public members `cx` and `cy` of type `long`.

The CRectangle Class

You'll be defining a rectangle object with the same data that you use to define a line; the points define opposite corners. You can define the class as:

```
class CRectangle: public CEElement
{
public:
    virtual ~CRectangle(void);
    virtual void Draw(CDC* pDC) override; // Function to display a rectangle

    // Constructor for a rectangle object
```

```

CRectangle(const CPoint& start, const CPoint& end, COLORREF color);

protected:
    CPoint m_BottomRight;           // Bottom-right point for the rectangle
    CRectangle(void);              // Default constructor - should not be used
};

```

The no-arg constructor is protected to prevent its use externally. The definition of the rectangle class is very simple — just a constructor, the virtual `Draw()` function, plus the no-arg constructor in the protected section of the class.

The CRectangle Constructor

The code for the new `CRectangle` class constructor is a little more complicated than that for `CLine`:

```

// CRectangle constructor
CRectangle:: CRectangle (
    const CPoint& start, const CPoint& end, COLORREF color) :
    CEElement(start, color)
{
    // Normalize the rectangle defining points
    m_StartPoint = CPoint((std::min)(start.x, end.x), (std::min)(start.y, end.y));
    m_BottomRight = CPoint((std::max)(start.x, end.x), (std::max)(start.y, end.y));

    // Ensure width and height between the points is at least 2
    if((m_BottomRight.x - m_StartPoint.x) < 2)
        m_BottomRight.x = m_StartPoint.x + 2;
    if((m_BottomRight.y - m_StartPoint.y) < 2)
        m_BottomRight.y = m_StartPoint.y + 2;

    // Define the enclosing rectangle
    m_EnclosingRect = CRect(m_StartPoint, m_BottomRight);
    m_EnclosingRect.InflateRect(m_PenWidth, m_PenWidth);
}

```

You call the `CElement` constructor in the initialization list to get the color and pen width initialized. The `CElement` constructor also initializes `m_StartPoint`, but you will replace this. You can only draw a `CRect` object that has a width and height of at least 2, so you adjust the coordinates of the two defining points if necessary, after arranging that the points define a normalized rectangle. Because you adjusted the points, there's no need to call `NormalizeRect()`. `std::min()` and `std::max()` are template functions defined in the `algorithm` header that return the minimum and maximum of their arguments, respectively. Add an `#include` directive for the `algorithm` header to `Rectangle.cpp`.

WARNING The parentheses around `std::min` and `std::max` in the code are essential. This is not typical with other C++ compilers but is a peculiarity of Visual C++. The `windows.h` header defines macros for `min` and `max` and without the parentheses, the preprocessor will make the substitution for these macros before the compiler starts. This will cause the compiler to generate error messages. The parentheses prevent the preprocessor macro substitutions.

Drawing a Rectangle

The `Rectangle()` member of the `CDC` class draws a rectangle. This function draws a closed figure and fills it with the current brush. You want to draw rectangles as outlines and selecting a `NULL_BRUSH` into the device context will do that. Just so you know, there's also a `PolyLine()` member of `CDC` that draws shapes consisting of multiple line segments from an array of points. You could also use `LineTo()` to draw the four sides of the rectangle, but the easiest approach is to use the `Rectangle()` function:

```
// Draw a CRectangle object
void CRectangle::Draw(CDC* pDC)
{
    // Create a pen for this object and initialize it
    CPen aPen;
    CreatePen(aPen);

    // Select the pen and the null brush
    CPen* pOldPen = pDC->SelectObject(&aPen);
    CBrush* pOldBrush = dynamic_cast<CBrush*>(pDC->SelectStockObject(NULL_BRUSH));

    // Now draw the rectangle
    pDC->Rectangle(m_StartPoint.x, m_StartPoint.y,
                     m_BottomRight.x, m_BottomRight.y);

    pDC->SelectObject(pOldBrush);           // Restore the old brush
    pDC->SelectObject(pOldPen);           // Restore the old pen
}
```

After setting up the pen and the brush, you call the `Rectangle()` function to draw the rectangle element. The arguments are the coordinates of the top-left and bottom-right corners. There's an overload of this function that accepts a `CRect` object as an argument to specify the rectangle. All that remains to do is to restore the device context's old pen and brush.

The CCircle Class

The `CCircle` class interface is similar to that of the `CRectangle` class. You draw a circle using the `Ellipse()` member of the `CDC` class, which draws an ellipse bounded by a rectangle. As long as the defining rectangle is square, the ellipse will be a circle. You will define a circle from its two defining points, the center and a point on the circumference, so the class definition is:

```
class CCircle: public CEElement
{
public:
    virtual ~CCircle(void);
    virtual void Draw(CDC* pDC) override;      // Function to display a circle

    // Constructor for a circle object
    CCircle(const CPoint& start, const CPoint& end, COLORREF color);

protected:
    CPoint m_BottomRight;                      // Bottom-right point for defining rectangle
    CCircle(void);                            // Default constructor - should not be used
};
```

You have defined a public constructor that creates a circle from two points and its drawing color, and the no-arg constructor is protected to prevent its use externally. You have also added a declaration for the draw function override to the class that will draw a circle.

Implementing the CCircle Class

When you create a circle, the point at which you press the left mouse button will be the center, and the point at which you release the button will be a point on the circumference. The job of the constructor is to obtain the corner points of the defining rectangle from these points.

The CCircle Class Constructor

The point at which you release the left mouse button can be anywhere on the circumference, so the coordinates of the points specifying the defining rectangle need to be calculated in the way I've illustrated in Figure 14-15.




FIGURE 14-15

From Figure 14-15, you can see that you can calculate the coordinates of the upper-left and lower-right points of the enclosing rectangle relative to the center of the circle (x_1, y_1). Assuming that the mapping mode is `MM_TEXT`, you get the (left, top) point by subtracting the radius from each of the coordinates of the center. Similarly, you obtain the (right, bottom) point by adding the radius to the coordinates of the center. You can calculate the radius as the square root of the expression in Figure 14-15. Based on this you can code the constructor as follows:

```
// Constructor for a circle object
CCircle::CCircle(const CPoint& start, const CPoint& end, COLORREF color) :
    CEElement(start, color)
```

```

{
    // Calculate the radius using floating-point values
    // because that is required by sqrt() function (in cmath)
    long radius = static_cast<long> (sqrt(
        static_cast<double>((end.x-start.x)*(end.x-start.x) +
        (end.y-start.y)*(end.y-start.y))));

    if(radius < 1L) radius = 1L;           // Circle radius must be >= 1

    // Define left-top and right-bottom points of rectangle for MM_TEXT mode
    m_StartPoint = CPoint(start.x - radius, start.y - radius);
    m_BottomRight = CPoint(start.x + radius, start.y + radius);

    // Define the enclosing rectangle
    m_EnclosingRect = CRect(m_StartPoint.x, m_StartPoint.y,
                           m_BottomRight.x, m_BottomRight.y);
    m_EnclosingRect.InflateRect(m_PenWidth, m_PenWidth);
}

```

To use the `sqrt()` function, you need an `#include` directive for the `cmath` header at the beginning of the `Circle.cpp` file. The maximum point coordinate values are 32 bits, and the `CPoint` members `x` and `y` are declared as `long`, so converting the value returned from `sqrt()` to type `long` should produce accurate results. The result of the square root calculation is of type `double`, so you cast it to type `long` to use it as an integer. The radius must be at least 1, otherwise nothing will be drawn by the `Ellipse()` member of `CDC`.

You store a `CPoint` object in `m_StartPoint` with the coordinates of the top left of the defining rectangle that you obtain by subtracting `radius` from the coordinates of the center. The `m_BottomRight` point is produced by adding `radius` to the coordinates of the center.

Drawing a Circle

The implementation of the `Draw()` function in the `CCircle` class is:

```

// Draw a circle
void CCircle::Draw(CDC* pDC)
{
    // Create a pen for this object and initialize it
    CPen aPen;
    CreatePen(aPen);

    CPen* pOldPen = pDC->SelectObject(&aPen); // Select the pen

    // Select a null brush
    CBrush* pOldBrush = dynamic_cast<CBrush*>(pDC->SelectStockObject(NULL_BRUSH));

    // Now draw the circle
    pDC->Ellipse(m_StartPoint.x, m_StartPoint.y,
                  m_BottomRight.x, m_BottomRight.y);

    pDC->SelectObject(pOldPen);                   // Restore the old pen
    pDC->SelectObject(pOldBrush);                 // Restore the old brush
}

```

After selecting a pen of the appropriate color and a null brush into the device context, you draw the circle by calling the `Ellipse()` function. The arguments are the coordinates of the corner points of the defining rectangle. An overload of `Ellipse()` accepts a `CRect` argument.

The CCurve Class

The `CCurve` class is different from the others in that it needs to deal with a variable number of defining points. A curve is defined by two or more points, and you can store these in an STL container. It won't be necessary to remove points from a curve, so a `vector<CPoint>` container is a good candidate. You looked at the `vector<T>` template in some detail back in Chapter 10. However, before you can complete the `CCurve` class definition, you need to explore how a curve will be created and drawn by a user.

Drawing a Curve

Drawing a curve is different from drawing a line, a rectangle, or a circle. With these elements, as you move the cursor with the left button down you are creating a succession of different elements that share a common reference point — the point at which the left mouse button was pressed. This is not the case when you draw a curve, as shown in Figure 14-16.




FIGURE 14-16

When you move the mouse cursor drawing a curve, you're not creating a sequence of new curves, but extending the same curve. Each new cursor position after the first adds a segment to the curve. Therefore, you must create a `CCurve` object as soon as you have the two points from the `WM_LBUTTONDOWN` message and the first `WM_MOUSEMOVE` message. Points that are defined with subsequent mouse move messages should add segments to the initial `CCurve` object. To make this possible you can add an `AddSegment()` function to the `CCurve` class that will extend a curve.

A further point to consider is how you are to calculate the enclosing rectangle. You can define this by getting the minimum-x and minimum-y pair from all the defining points to establish the upper-left corner of the rectangle, and the maximum-x and maximum-y pair for the bottom right. The easiest way of generating the enclosing rectangle is to compute it initially in the constructor based on the first two points and then re-compute it incrementally in the AddSegment() function as points are added to the curve.

Add an #include directive for the vector header to Curve.h. You can modify the CCurve class definition to the following:

```
class CCurve: public CEElement
{
public:
    virtual ~CCurve(void);
    virtual void Draw(CDC* pDC) override; // Function to display a curve

    // Constructor for a curve object
    CCurve(const CPoint& first, const CPoint& second, COLORREF color);

    void AddSegment(const CPoint& point); // Add a segment to the curve

protected:
    std::vector<CPoint> m_Points; // Points defining the curve
    CCurve(void); // Default constructor - should not be used
};
```

You can add the definition for the constructor in Curve.cpp:

```
// Constructor for a curve object
CCurve::CCurve(const CPoint& first, const CPoint& second, COLORREF color) :
    CEElement(first, color)
{
    // Store the second point in the vector
    m_Points.push_back(second);
    m_EnclosingRect = CRect(
        (std::min)(first.x, second.x), (std::min)(first.y, second.y),
        (std::max)(first.x, second.x), (std::max)(first.y, second.y));
    m_EnclosingRect.InflateRect(m_PenWidth, m_PenWidth);
}
```

The constructor receives the first two defining points as arguments so it defines a curve with only one segment. The first point is stored in the `m_StartPoint` member by the `CElement` constructor. The second point is stored in the vector, `m_Points`. I'm sure you recall that the `push_back()` function adds an element to the end of a vector. You use the `std::min()` and `std::max()` template functions in the creation of the enclosing rectangle so you'll need an `#include` directive for the algorithm header in `Curve.cpp`.

You can define the `Draw()` function for a curve like this:

```
// Draw a curve
void CCurve::Draw(CDC* pDC)
{
```

```

// Create a pen for this object and initialize it
CPen aPen;
CreatePen(aPen);

CPen* pOldPen = pDC->SelectObject(&aPen); // Select the pen

// Now draw the curve
pDC->MoveTo(m_StartPoint);
for(auto& point : m_Points)
    pDC->LineTo(point);

pDC->SelectObject(pOldPen); // Restore the old pen
}

```

The `Draw()` function has to provide for a curve with an arbitrary number of points. Once the pen has been set up, the first step is to move the current position in the device context to `m_StartPoint`. Line segments for the curve are drawn in the `for` loop, one segment for each point in the vector. A `LineTo()` operation moves the current position to the end of the line it draws, so each function call draws a line from the current position to the next point in the vector. In this way, you draw all the segments that make up the curve.

You can implement the `AddSegment()` function like this:

```

// Add a segment to the curve
void CCurve::AddSegment(const CPoint& point)
{
    m_Points.push_back(point); // Add the point to the end

    // Modify the enclosing rectangle for the new point
    m_EnclosingRect.DeflateRect(m_PenWidth, m_PenWidth);
    m_EnclosingRect = CRect((std::min)(point.x, m_EnclosingRect.left),
                           (std::min)(point.y, m_EnclosingRect.top),
                           (std::max)(point.x, m_EnclosingRect.right),
                           (std::max)(point.y, m_EnclosingRect.bottom));
    m_EnclosingRect.InflateRect(m_PenWidth, m_PenWidth);
}

```

You add `point` to the vector and adjust the enclosing rectangle by ensuring the top-left point is the minimum `x` and `y`, and the bottom-right is the maximum `x` and `y`. The enclosing rectangle for the complete curve is the rectangle corresponding to the minimum `x` and `y` of all the defining points for the left-top corner, and the maximum of all the point coordinates for bottom right. You then want to inflate the resulting rectangle by the pen width. For this reason, you must reduce `m_EnclosingRect` by the pen width before you find the coordinates of the top-left and bottom right-corners here. Otherwise you will not end up with the correct enclosing rectangle. Calling the `DeflateRect()` member of `CRect` does the opposite of `InflateRect()`, so this is just what you want here.

Completing the Mouse Message Handlers

You can now return to the `WM_MOUSEMOVE` message handler and fill out the details. You can get to it through selecting `CSketcherView` in Class View and double-clicking the handler name, `OnMouseMove()`.

Except when creating a `CCurve` element, this handler is concerned with drawing a succession of temporary elements as you move the cursor, and the final element is created when you release the left mouse button. You can therefore treat the drawing of temporary elements as being entirely local to this function, leaving the final version of an element to be drawn by the `OnDraw()` member of the view. With this approach, the drawing of the temporary elements will be reasonably efficient because it won't involve the `OnDraw()` member of `CSketcherView` that draws the entire document.

You can implement this very easily with the help of a `CDC` class member that is particularly useful in rubber-banding operations: the `SetROP2()` function.

Setting the Drawing Mode

Calling `SetROP2()` sets the *drawing mode* for all subsequent output operations in the device context associated with a `CDC` object. The “ROP” bit of the function name stands for Raster OPeration, because the setting of drawing modes applies to raster displays. In case you’re wondering what `SetROP1()` is — it doesn’t exist. The whole function name stands for Set Raster OPeration to, not Set Raster OPeration 2!

The drawing mode determines how the color of the pen combines with the background color in the window to produce the color of the entity that you will see. You specify the drawing mode with a single argument to the `SetROP2()` function that can be any of the following values:

DRAWING MODE	EFFECT
<code>R2_BLACK</code>	All drawing is in black.
<code>R2_WHITE</code>	All drawing is in white.
<code>R2_NOP</code>	Drawing operations do nothing.
<code>R2_NOT</code>	Drawing is in the inverse of the screen color. This ensures that the output is always visible because it draws in the inverse color to the background.
<code>R2_COPYPEN</code>	Drawing is in the pen color. This is the default drawing mode if you don't set a mode.
<code>R2_NOTCOPYPEN</code>	Drawing is in the inverse of the pen color.
<code>R2_MERGEPPENNOT</code>	Drawing is in the color produced by OR-ing the pen color with the inverse of the background color.
<code>R2_MASKPENNOT</code>	Drawing is in the color produced by AND-ing the pen color with the inverse of the background color.
<code>R2_MERGENOTPEN</code>	Drawing is in the color produced by OR-ing the background color with the inverse of the pen color.
<code>R2_MASKNOTPEN</code>	Drawing is in the color produced by AND-ing the background color with the inverse of the pen color.

continues

(continued)

DRAWING MODE	EFFECT
R2_MERGESEN	Drawing is in the color produced by OR-ing the background color with the pen color.
R2_NOTMERGESEN	Drawing is in the color that is the inverse of the R2_MERGESEN color.
R2_MASKSEN	Drawing is in the color produced by AND-ing the background color with the pen color.
R2_NOTMASKSEN	Drawing is in the color that is the inverse of the R2_MASKSEN color.
R2_XORSEN	Drawing is in the color produced by exclusive OR-ing the pen and background colors. The result is a color composed of the RGB components that are in the pen and background colors but not in both.
R2_NOTXORSEN	Drawing is in the color that is the inverse of the R2_XORSEN color.

These symbols are predefined values of type `int`. There are a lot of options here, but the one that can work some magic for us is the last of them, `R2_NOTXORSEN`.

When you set the mode as `R2_NOTXORSEN`, the first time you draw on the default white background, the element is drawn normally in the pen color. If you draw the same element overwriting the first, the element disappears. This is because the color for the element as it appears on the screen is produced by exclusive OR-ing the pen color with itself, which results in a white element on a white background. You can see more clearly why this happens by working through an example.

White is formed from equal proportions of the maximum intensities for red, green, and blue, 255,255,255, so each component value has all bits 1. For simplicity I'll represent this as 1,1,1 — the three values represent the RGB components of the color. In the same scheme, I'll define red as 1,0,0 instead of 255,0,0. These combine as follows:

	R	G	B
Background —white, the window background color	1	1	1
Pen —red	1	0	0
XOR-ed —produces the complement of red	0	1	1
NOT XOR —produces red, the drawing color	1	0	0

So, the first time you draw a red line on a white background, it comes out red, as the last line in the table indicates. If you now draw the same line a second time, overwriting the existing line, the background pixels you are writing over are red. The resultant drawing color works out as follows:

	R	G	B
Background —red, the pixels that you drew last time	1	0	0
Pen —red	1	0	0
XOR-ed —produces black	0	0	0
NOT XOR —produces white, the window background color	1	1	1

As the last line indicates, the line appears in white, and because the window background is white, the line disappears.

You need to choose the right background color for this technique to work. You should be able to see that drawing with a white pen on a red background is not going to work too well, as the first time you draw something, it is red and, therefore, invisible. The second time, it appears as white. If you draw on a black background, things appear and disappear as on a white background, but they are not drawn in the pen color you choose.

Coding the OnMouseMove() Handler

You can now add the code to create an element after a mouse move message. Because you are going to draw the element in the handler function, you need to create a device context that you can draw in. The most convenient class to use for this is `CCClientDC`, which is derived from `CDC`. An object of this type automatically takes care of destroying the device context for you when you are done, so you can create a `CCClientDC` object, use it, and forget it. You can create a `CCClientDC` object by passing a pointer to the window for which you want a device context to the `CCClientDC` constructor. The device context that it creates corresponds to the client area of the window, so if you pass a pointer to the view, you'll get exactly what you want.

The logic for drawing an element is a little complicated. You can draw a shape using the `R2_NOTXOROPEN` mode as long as the shape is not a curve. When a curve is being created, you don't want to draw a new curve each time the mouse moves. You just want to extend the curve by adding a new segment. This means you must treat creating a curve as a special case. You also want to delete any previous temporary element, but only when it is not a curve. Here's how you can implement that:

```
void CSketcherView::OnMouseMove(UINT nFlags, CPoint point)
{
    // Define a Device Context object for the view
    CCClientDC aDC(this);                                // DC is for this view
    if(nFlags & MK_LBUTTON)                               // Verify the left button is down
    {
        m_SecondPoint = point;                          // Save the current cursor position
        if(m_pTempElement)
        {
            // An element was created previously
            if(ElementType::CURVE == GetDocument()->GetElementType()) // A curve?
            {
                // We are drawing a curve so add a segment to the existing curve
                std::static_pointer_cast<CCurve>(m_pTempElement)->AddSegment(m_

```

```

SecondPoint);
    m_pTempElement->Draw(&aDC);           // Now draw it
    return;                                // We are done
}
else
{
    // If we get to here it's not a curve so
    // redraw the old element so it disappears from the view
    aDC.SetROP2(R2_NOTXORPEN);            // Set the drawing mode
    m_pTempElement->Draw(&aDC);          // Redraw the old element to erase it
}
}

// Create a temporary element of the type and color that
// is recorded in the document object, and draw it
m_pTempElement.reset(CreateElement());
m_pTempElement->Draw(&aDC);
}
}

```

The first line of code creates a local `CCClientDC` object. The `this` pointer that you pass to the constructor identifies the current view object, so the `CCClientDC` object is a device context that corresponds to the client area of the current view. This object has all the drawing functions you need because they are inherited from the `CDC` class.

A previous temporary element exists if `m_pTempElement` is not `nullptr`. You want to do different things depending on whether or not `m_pTempElement` points to a curve, so you need to check for this. The `shared_ptr<T>` type supports conversion to type `bool` so you can use it in an `if` expression. You call the `GetElementType()` function for the document object to get the current element type. If the current element type is `ElementType::CURVE`, you cast `m_pTempElement` to type `shared_ptr<CCurve>` so you can call the `AddSegment()` function for the object to add the next segment to the curve. You must use a special conversion, `static_pointer_cast`, to convert a smart pointer; this is the equivalent of `static_cast` for ordinary pointers. You also have `dynamic_pointer_cast` and `const_pointer_cast` available for use with smart pointers. These operations are defined by function templates in the `memory` header and in the `std` namespace. Finally, you draw the curve and return. You must add an `#include` for `Curve.h` to `SketcherView.cpp`. You'll be referring to the other element classes in the view class eventually so you can include the headers for the other three element classes too.

When the current element exists, but is not a curve, you redraw the old element after calling the `SetROP2()` function of the `aDC` object to set the mode to `R2_NOTXORPEN`. This erases the old element on the display. There is no need to reset `m_pTempElement` because you will replace the pointer it contains after the `if` statement.

The code after the `if` statement is executed when there is a temporary element that is not a curve, or when there is no temporary element. In either case you want to create a new element of the current type and color and draw it normally. You create the new element and store its address in `m_pTempElement` by passing it as the argument to its `reset()` member. This decrements the reference count for the current pointer that `m_pTempElement` contains before replacing it with the argument. In our case, the reference count for the previous element will reduce to zero if it exists, so it will be

destroyed. If `m_pTempElement` contains `nullptr`, then that will be replaced by the new element pointer. There is a second overload of the `reset()` function that has no parameters. Calling this will decrement the count for the current pointer if there is one, and replace the current pointer in the `shared_ptr` object by `nullptr`. The code automatically rubber-bands the element being created, so it will appear to be attached to the mouse cursor as it moves.

Using the smart pointer to the new element, you call its `Draw()` member to get the object to draw itself. The address of the `CCClientDC` object is passed as the argument. Because you defined the `Draw()` function as `virtual` in the `CElement` base class, the function for whatever type of element `m_pTempElement` is pointing to is automatically selected. The new element is drawn normally with the `R2_NOTXORPEN` mode, because you are drawing it for the first time on a white background.

Creating an Element

Add the `CreateElement()` function declaration as a `protected` member in the Implementation section of the `CSketcherView` class:

```
class CSketcherView: public CView
{
    // Rest of the class definition as before...

    // Implementation
    // Rest of the class definition as before...

protected:
    CElement* CreateElement(void) const; // Create a new element on the heap

    // Rest of the class definition as before...
};


```

You can either amend the class definition directly by adding the bolded lines, or you can right-click on the class name, `CSketcherView`, in Class View, select Add \Rightarrow Add Function from the context menu, and add the function through the dialog. The function is `protected` because it is called only from within the view class.

If you added the declaration to the class definition manually, you'll need to add the complete definition for the function to the `.cpp` file. This is as follows:

```
// Create an element of the current type
CElement* CSketcherView::CreateElement(void) const
{
    // Get a pointer to the document for this view
    CSketcherDoc* pDoc = GetDocument();
    ASSERT_VALID(pDoc); // Verify the pointer is good

    // Get the current element color
    COLORREF color = static_cast<COLORREF>(pDoc->GetElementType());

    // Now select the element using the type stored in the document
    switch(pDoc->GetElementType())
    {
```

```

case ElementType::RECTANGLE:
    return new CRectangle(m_FirstPoint, m_SecondPoint, color);

case ElementType::CIRCLE:
    return new CCircle(m_FirstPoint, m_SecondPoint, color);

case ElementType::CURVE:
    return new CCurve(m_FirstPoint, m_SecondPoint, color);

case ElementType::LINE:
    return new CLine(m_FirstPoint, m_SecondPoint, color);

default:
    // Something's gone wrong
    AfxMessageBox(_T("Bad Element code"), MB_OK);
    AfxAbort();
    return nullptr;
}
}

```

You first get a pointer to the document object by calling `GetDocument()`, as you've seen before. For safety, you use the `ASSERT_VALID()` macro to ensure that a good pointer is returned. In the debug version of your application, this macro calls the `AssertValid()` member of the object, which is specified as the argument to the macro. This checks the validity of the current object, and if the pointer is `NULL` or the object is defective in some way, an error message is displayed. In the release version of your application, the `ASSERT_VALID()` macro does nothing.

You cannot use the `ElementColor` enumerator that the `GetElementColor()` function returns as a color value when you create an element because it's the wrong type. However, the numerical value of each enumerator is a `COLORREF` color value so you can cast an enumerator to type `COLORREF` to get the color value. The switch statement selects the element to be created based on the type returned by `GetElementType()`. In the unlikely event that the type is not an `ElementType` enumerator, you display a message box and end the program. You need `#include` directives for the header files for the four derived element classes in `SketcherView.cpp`.

Dealing with WM_LBUTTONDOWN Messages

The `WM_LBUTTONDOWN` message completes the process of creating an element. The job of this message handler is to pass the final version of the element to the document object, and then to clean up the view object data members. You can add an STL container object in the `CSketcherDoc` class to store elements. You will also need a document class function that you can call when you want to add an element. It's likely that you will want to delete elements from the document at some point. In this case a `vector<T>` will be faster but I'll use a list container here for the experience because you'll be using a vector container to store the points for a curve. Add the following `protected` data member to `CSketcherDoc`:

```
std::list<std::shared_ptr<CElement>> m_Sketch;      // A list containing the sketch
```

Sketch elements are created on the heap so you can store smart pointers to elements rather than the elements themselves. Add `#include` directives for the `list` and `memory` headers and `Element.h` to

`SketcherDoc.h`. When the document object is destroyed, `m_Sketch` will also be destroyed along with all the elements pointed to by the smart pointers it contains.

Add the following function definitions to the Implementation section of the `CSketcherDoc` class as `public` members:

```
// Add a sketch element
void AddElement(std::shared_ptr<CElement>& pElement)
{
    m_Sketch.push_back(pElement);
}

// Delete a sketch element
void DeleteElement(std::shared_ptr<CElement>& pElement)
{
    m_Sketch.remove(pElement);
}
```

The first function adds the smart pointer for an element that you pass as the argument to the list, `m_Sketch`. The second removes the pointer from the list, which will also delete the element from the heap. You will implement the UI mechanism for deleting sketch elements in the next chapter.

You can now implement the `OnLButtonUp()` handler. Add the following lines to the function definition in `SketcherView.cpp`:

```
void CSketcherView::OnLButtonUp(UINT nFlags, CPoint point)
{
    // Make sure there is an element
    if(m_pTempElement)
    {
        // Add the element pointer to the sketch
        GetDocument()->AddElement(m_pTempElement);
        InvalidateRect(&m_pTempElement->GetEnclosingRect());
        m_pTempElement.reset();                      // Reset the element pointer
    }
}
```

The `if` statement verifies that `m_pTempElement` is not `nullptr` before processing it. It's always possible that the user could press and release the left mouse button without moving the mouse, in which case, no element would have been created. As long as there is an element, the pointer to the element is passed to the document object function that adds it to the sketch. Finally, the `m_pTempElement` pointer is reset, ready for the next time the user draws an element.

DRAWING A SKETCH

All the elements that make up a sketch are safely stored in the document object. You now need a way to display the sketch in the view. The `OnDraw()` function in `CSketcherView` will do this. Obviously, it will need access to the data for a sketch that is owned by the document object, and ideally this should happen without the document object exposing it to external modification. One way to achieve this is for the document object to make `const` iterators available. The iterator type name

for a sketch is a little long-winded and you can economize on typing by adding the following type definition to `SketcherDoc.h` after the `#include` directives:

```
typedef std::list<std::shared_ptr<CElement>>::const_iterator SketchIterator;
```

You can now use `SketchIterator` in the code to specify the type for a `const` iterator for the sketch list container. By adding the following functions to the `CSketcherDoc` class definition you will enable the view object to obtain the iterators it needs to draw a sketch:

```
// Provide a begin iterator for the sketch
SketchIterator begin() const { return std::begin(m_Sketch); }

// Provide an end iterator for the sketch
SketchIterator end() const { return std::end(m_Sketch); }
```

These should be `public`, and you can put them in the Operations section of `CSketcherDoc`. A `const` iterator can be incremented and dereferenced but it cannot be used to modify what it points to.

You can use these functions to implement the `OnDraw()` member of `CSketcherView`:

```
void CSketcherView::OnDraw(CDC* pDC)
{
    CSketcherDoc* pDoc = GetDocument();
    ASSERT_VALID(pDoc);
    if (!pDoc)
        return;

    // Draw the sketch
    for(auto iter = pDoc->begin() ; iter != pDoc->end() ; ++iter)
    {
        std::shared_ptr<CElement> pElement(*iter);
        if(pDC->RectVisible(pElement->GetEnclosingRect())) // Element visible?
            pElement->Draw(pDC);                                // Yes, draw it.
    }
}
```

The iterator returned by the `begin()` member of the document object points to a list element, which is a smart pointer to a sketch element. You must dereference the iterator and store the smart pointer that results in order to call functions for the element object. You only want to draw an element when it is visible in the client area of the view. Drawing elements that do not appear in the view just consumes processor time to no effect. The `RectVisible()` member of a `CDC` object returns `TRUE` if any part of the rectangle that you pass as the argument is within the client area, otherwise it returns `FALSE`. Calling this in the `if` statement ensures that only visible elements are drawn. You draw a sketch element by calling its `Draw()` member with the pointer to the device context as the argument.

Running the Example

After making sure that you have saved all the source files, build the program. If you haven't made any mistakes entering the code, you'll get a clean compile and link, so you can execute the program.

You can draw lines, circles, rectangles, and curves in any of the four colors the program supports. A typical window is shown in Figure 14-17.

Try experimenting with the user interface. Note that you can move the window around and that the elements are drawn automatically if you expose them after they are hidden. However, all is not as it should be. If you try drawing a shape while dragging the cursor outside the client view area, you'll notice some peculiar effects. Outside the view window, you lose track of the mouse, which stops the rubber-banding mechanism from working while the cursor is not in the client area. What's going on?




FIGURE 14-17

Capturing Mouse Messages

The problem is caused by Windows sending the mouse messages to the window under the cursor. As soon as the cursor leaves the client area of your application view window, the WM_MOUSEMOVE messages are being sent elsewhere. You can fix this with the aid of some inherited members of the CSketcherView class.

The view class inherits the SetCapture() function from CWnd. You can call this function to tell Windows that you want your view window to receive all mouse messages until such time as you say otherwise. This is referred to as *capturing the mouse*. You can stop capturing the mouse by calling another inherited function, ReleaseCapture().

You can capture the mouse as soon as the left button is pressed by modifying the handler for the WM_LBUTTONDOWN message:

```
// Handler for left mouse button down message
void CSketcherView::OnLButtonDown(UINT nFlags, CPoint point)
{
    m_FirstPoint = point;           // Record the cursor position
    SetCapture();                  // Capture subsequent mouse messages
}
```

Now, you must call the ReleaseCapture() function in the WM_LBUTTONUP handler. If you don't do this, other programs cannot receive any mouse messages as long as your program continues to run. Of course, you should release the mouse only if you've captured it earlier. The GetCapture() function that the view class inherits returns a pointer to the window that has captured the mouse, and this gives you a way of telling whether or not you have captured mouse messages. You just need to add the following to the handler for WM_LBUTTONUP:

```
void CSketcherView::OnLButtonUp(UINT nFlags, CPoint point)
{
    if(this == GetCapture())
        ReleaseCapture();                                // Stop capturing mouse messages

    // Make sure there is an element
    if(m_pTempElement)
    {
        GetDocument()->AddElement(m_pTempElement);
        m_pTempElement.reset();                         // Reset the element pointer
    }
}
```

If the pointer returned by the `GetCapture()` function is equal to the pointer `this`, your view has captured the mouse, so you release it.

The final alteration you should make is to modify the `WM_MOUSEMOVE` handler so that it deals only with messages that have been captured by the view. You can do this with one small change:

```
void CSketcherView::OnMouseMove(UINT nFlags, CPoint point)
{
    // Define a Device Context object for the view
    CClientDC aDC(this);                            // DC is for this view

    // Verify the left button is down and mouse messages are captured
    if((nFlags & MK_LBUTTON) && (this == GetCapture()))
    {
        // Code as before...
    }
}
```

The handler now processes the message only if the left button is down *and* the mouse has been captured by your view window.

If you rebuild Sketcher with these additions you'll find that the problems that arose earlier when the cursor was dragged off the client area no longer occur.

SUMMARY

After completing this chapter, you should have a good grasp of how to write message handlers for the mouse, and how to organize drawing operations in your Windows programs. You have seen how using polymorphism with the shape classes makes it possible to operate on any shape in the same way, regardless of its actual type.

EXERCISES

- 1.** Add a menu item and Toolbar button to Sketcher for an ellipse element. Add an element type for ellipses and define a class to support drawing ellipses defined by two points on opposite corners of their enclosing rectangle.
- 2.** Which functions must you modify to support drawing ellipses? Modify the program to draw ellipses.
- 3.** Which functions must you modify in the example from the previous exercise so that the first point defines the center of the ellipse, and the current cursor position defines a corner of the enclosing rectangle? Modify the example to work this way. (Hint: look up the `CPoint` class members in Help.)
- 4.** Add a new `Pen Style` menu to the menu bar to allow solid, dashed, dotted, dash-dotted, and dash-dot-dotted lines to be specified.
- 5.** Which parts of the program need to be modified to support the operation of the menu, and the drawing of elements in the line types listed in the previous exercise?
- 6.** Implement support for the new menu and drawing all elements in any of the line types.

► WHAT YOU LEARNED IN THIS CHAPTER

TOPIC	CONCEPT
The client coordinate system	By default, Windows addresses the client area of a window using a client coordinate system with the origin in the upper-left corner of the client area. The positive x-direction is from left to right, and the positive y-direction is from top to bottom.
Drawing in the client area	You can draw in the client area of a window only by using a device context.
Device contexts	A device context provides a range of logical coordinate systems called mapping modes for addressing the client area of a window.
Mapping modes	The default origin position for a mapping mode is the upper-left corner of the client area. The default mapping mode is <code>MM_TEXT</code> , which provides coordinates measured in pixels. The positive x-axis runs from left to right in this mode, and the positive y-axis from top to bottom.
Drawing in a window	Your program should always draw the permanent contents of the client area of a window in response to a <code>WM_PAINT</code> message, although temporary entities can be drawn at other times. All the drawing for your application document should be controlled from the <code>OnDraw()</code> member function of a view class. This function is called when a <code>WM_PAINT</code> message is received by your application.
Redrawing a window	You can identify the part of the client area you want to have redrawn by calling the <code>InvalidateRect()</code> function member of your view class. The area passed as an argument is added by Windows to the total area to be redrawn when the next <code>WM_PAINT</code> message is sent to your application.
Mouse messages	Windows sends standard messages to your application for mouse events. You can create handlers to deal with these messages by using the Class Wizard.
Capturing mouse messages	You can cause all mouse messages to be routed to your application by calling the <code>SetCapture()</code> function that is inherited in your view class. You must release the mouse when you're finished with it by calling the <code>ReleaseCapture()</code> function. If you fail to do this, other applications are unable to receive mouse messages.

TOPIC	CONCEPT
Rubber-banding	You can implement rubber-banding during the creation of geometric entities by drawing them in the message handler for mouse movements.
Selecting a drawing mode	The <code>SetROP2()</code> member of the <code>CDC</code> class enables you to set drawing modes. Selecting the right drawing mode greatly simplifies rubber-banding operations.
Adding event handlers	The Properties window for a GUI component also enables you to add event handler functions automatically.
Casting smart pointers	You can cast a smart pointer to another smart pointer type using <code>static_pointer_cast</code> , <code>dynamic_pointer_cast</code> , and <code>const_pointer_cast</code> .

15

Improving the View

WHAT YOU WILL LEARN IN THIS CHAPTER:

- How to draw and update multiple views
- How to implement scrolling in a view
- How to create a context menu at the cursor
- How to highlight the element nearest the cursor to provide feedback to the user
- How to program the mouse to move and delete elements

WROX.COM CODE DOWNLOADS FOR THIS CHAPTER

You can find the wrox.com code downloads for this chapter on the Download Code tab at www.wrox.com/remtitle.cgi?isbn=9781118368084. The code is in the Chapter 15 download and individually named according to the names throughout the chapter.

SKETCHER LIMITATIONS

There are still some limitations in Sketcher. For instance:

- 1.** You can open another view window for the current sketch by using the Window ↗ New Window menu option. This capability is built into an MDI application. However, if you draw in one window the elements are not drawn in the other window. Elements never appear in windows other than the one in which they were created unless the area they occupy is redrawn for some other reason.
- 2.** You can draw only in the client area you can see. It would be nice to be able to scroll the view and draw over a bigger area.

3. Even though the document object can delete an element from the sketch, you have no user interface mechanism for deleting an element. If you make a mistake, you either live with it or start over with a new document.
4. You can't view a sketch window at different scales. Being able to view a sketch at a larger scale would make it easier to add fine detail.
5. You can't print a sketch. If you want to show your artistic capabilities to someone, you have to bring your computer along.
6. You can't save a sketch in a file so it has no permanence at all.

These are quite serious deficiencies that limit the usability of the program. You'll overcome the first three before the end of this chapter. You'll remove the remaining limitations before the end of the book.

IMPROVING THE VIEW

The first item that you can fix is the updating of all the document view windows when an element is drawn. The problem arises because only the view in which you draw an element knows about it. Each view is acting independently of the others, and there is no communication between them. If you can arrange for all the views to be notified when an element is added to the document, they can take the appropriate action.

Updating Multiple Views

The document class contains the `UpdateAllViews()` function to help with this particular problem. The function provides a means for the document to send a message to all its views. You just need to call it from the `AddElement()` function in `CSketcherDoc` that adds a new element:

```
void AddElement(std::shared_ptr<CElement>& pElement)
{
    m_Sketch.push_back(pElement);
    UpdateAllViews(nullptr, 0, pElement.get());           // Tell all the views
}
```

The inherited `UpdateAllViews()` function is called whenever an element is added to the document. This communicates with the views by calling the `OnUpdate()` member of each view. The `UpdateAllViews()` function has three parameters, two of which have default values. The arguments that you can supply are:

1. A pointer to the current view object. This identifies the view for which the `OnUpdate()` function should not be called. This is a useful feature when the current view is up to date and you have a pointer to it. You could arrange for this if you needed to by adding an extra parameter of type `CSketcherView*` to `AddElement()` and passing the `this` pointer for the view to it when it was called. Another possibility is that you could call `UpdateAllViews()` from a view object when an element is created. When you specify `nullptr` as the argument

as in this instance, `OnUpdate()` will be called for all views. This will be passed on as the first argument in all `OnUpdate()` function calls.

2. A `long` integer value that has a default value of zero. This is intended to provide a hint about the region to be updated. If you supply a value for this, it will be passed as the second argument in the call to the `OnUpdate()` function for each view object.
3. A pointer of type `CObject*` with a default value of `NULL`. If you supply this argument, it will be passed as the third argument in the `OnUpdate()` function call for each view. It should point to an object that provides information about the region to be updated. In our case it should be a pointer to the new element; a smart pointer cannot be used. Calling `get()` for the smart pointer, `pElement`, returns the `CElement*` pointer that `pElement` contains.

To process the information passed to the `UpdateAllViews()` function, you must add an override for the `OnUpdate()` member of the view class. You can do this through the Properties window for `CSketcherView`. Just to remind you, you display the properties for a class by right-clicking the class name in Class View and selecting Properties from the menu. If you click the Overrides button in the Properties window, you'll be able to find `OnUpdate` in the list of functions. Click the function name, then the <Add> `OnUpdate` option that shows in the drop-down list in the adjacent column. You'll be able to edit the code for the `OnUpdate()` override you have added in the Editor pane. You only need to add the following highlighted code to the function definition:

```
void CSketcherView::OnUpdate(CView* pSender, LPARAM lHint, CObject* pHint)
{
    // Invalidate the area corresponding to the element pointed to
    // by the third argument, otherwise invalidate the whole client area
    if(pHint)
    {
        InvalidateRect(static_cast<CElement*>(pHint)->GetEnclosingRect());
    }
    else
    {
        InvalidateRect(nullptr);
    }
}
```

Note that you must uncomment the parameter names; otherwise, it won't compile with the additional code. The three arguments passed to the `OnUpdate()` function correspond to the arguments that you passed in the `UpdateAllViews()` function call. Thus, `pHint` contains the address of the new element. However, you can't assume that this is always the case. The `OnUpdate()` function is also called when a view is first created, but with `nullptr` for the third argument. Therefore, the function verifies that `pHint` isn't `nullptr` and only then calls `GetEnclosingRect()` to obtain the rectangle enclosing the element. It invalidates this area in the client area of the view by passing the rectangle to the `InvalidateRect()` function. This area is redrawn by the `OnDraw()` function in this view when the next `WM_PAINT` message is sent to the view. If `pHint` is `nullptr`, the whole client area is invalidated.

You might be tempted to consider redrawing the new element in the `OnUpdate()` function. This isn't a good idea. You should do permanent drawing only in response to a Windows `WM_PAINT` message. This means that the `OnDraw()` function in the view should be the only thing that's initiating any

drawing operations for document data. This ensures that the view is drawn correctly whenever Windows deems it necessary.

Come to think of it, the views ought to be notified when an element is deleted from the document. You can modify the `DeleteElement()` member of the document class to take care of it:

```
void DeleteElement(std::shared_ptr<CElement>& pElement)
{
    m_Sketch.remove(pElement);
    UpdateAllViews(nullptr, 0, pElement.get()); // Tell all the views
}
```

Calling `remove()` for the list removes the element that matches the argument by calling its destructor. This will cause the smart pointer that was in the list to be destroyed. The element to which it points will not be destroyed because there is another `shared_ptr` referencing it, namely the object that was passed to `DeleteElement()`. You use this to pass the element pointer to `UpdateAllViews()`. The smart pointer that was passed to `DeleteElement()` and the element to which it points will be destroyed when the `DeleteElement()` function ends.

If you build and execute Sketcher with the new modifications, you should find that you can create multiple views of the document and draw in any of them. All the views get updated to reflect the contents of the document.

Scrolling Views

Adding scrolling to a view looks remarkably easy at first sight, but the water is, in fact, deeper and murkier than it at first appears. We will jump in anyway. The first step is to change the base class for `CSketcherView` from `CView` to `CScrollView`. This new base class has the scrolling functionality built in, so you can alter the definition of the `CSketcherView` class to this:

```
class CSketcherView: public CScrollView
{
    // Class definition as before...
};
```


You must also modify two lines of code at the beginning of the `SketcherView.cpp` file that refer to the base class for `CSketcherView`. You need to replace `CView` with `CScrollView` as the base class:

```
IMPLEMENT_DYNCREATE(CSketcherView, CScrollView)

BEGIN_MESSAGE_MAP(CSketcherView, CScrollView)
```

However, this is still not quite enough. The new view class needs to know some things about the area you are drawing on and want to scroll, such as its size and how far the view is to be scrolled when you use the scroller. This information must be supplied before the view is drawn. You can put the code to do this in the `OnInitialUpdate()` function in the view class because this will be called after the view is attached to the document but before the view is displayed.

You supply the information required for scrolling by calling the `SetScrollSizes()` function that is inherited from the `CScrollView` class. The arguments to this function are explained in Figure 15-1.

**FIGURE 15-1**

Scrolling a distance of one line occurs when you click on the up or down arrow on the scroll bar; a page scroll occurs when you click the scrollbar itself. You have an opportunity to change the mapping mode here. `MM_LOENGLISH` would be a good choice for the Sketcher application, but we will first get scrolling working with the `MM_TEXT` mapping mode because there are still some difficulties to be uncovered.

To add the code to call `SetScrollSizes()`, you need to override the default version of the `OnInitialUpdate()` function in the view. You access this in the same way as for the `OnUpdate()` function override — through the Properties window for `CSketcherView`. After you have added the override, add the code to the function where indicated by the comment:

```

void CSketcherView::OnInitialUpdate()
{
    CScrollView::OnInitialUpdate();

    CSize DocSize(20000,20000); // The document size

    // Set mapping mode and document size
    SetScrollSizes(MM_TEXT, DocSize, CSize(500,500), CSize(20,20));
}
  
```

This maintains the mapping mode as `MM_TEXT` and defines the total extent that you can draw on as 20,000 pixels in each direction. It also specifies a page scroll increment as 500 pixels in each direction and a line scroll increment as 20 pixels, because the defaults would be too large.

This is enough to get scrolling working after a fashion. Rebuild Sketcher and execute it with these additions. You'll be able to draw a few elements and then scroll the view. However, although the window scrolls OK, if you try to draw more elements with the view scrolled, things don't work as they should. The elements appear in a different position from where you draw them and they're not displayed properly. What's going on?

Logical Coordinates and Client Coordinates

The problem is because of the coordinate systems you're using — and that plural is deliberate. You have been using *two* coordinate systems in all the examples up to now, although you may not have noticed because they were coincident. When you call a function such as `LineTo()` for a `CDC` object it assumes that the arguments you pass to it are *logical coordinates*. The device context has its own system of logical coordinates. The mapping mode, which is a property of the device context, determines what the unit of measurement is for the coordinates when you draw something.

The coordinate data that you receive along with the mouse messages has nothing to do with the device context or the `CDC` object — and outside of a device context, logical coordinates don't apply. The points passed to the `OnLButtonDown()` and `OnMouseMove()` handlers have coordinates that are always in device units — that is, pixels — and are measured relative to the upper left corner of the client area. These are referred to as *client coordinates*. Similarly, when you call `InvalidateRect()`, the rectangle is assumed to be defined in terms of client coordinates.

In `MM_TEXT` mode, client coordinates and the logical coordinates in the device context are both in pixels, and so they are the same — *as long as you don't scroll the window*. In all the previous examples, there was no scrolling, so everything worked without any problems. With the latest version of Sketcher, it all works well until you scroll the view, whereupon the logical coordinates origin (the 0,0 point) is moved by the scrolling mechanism, so it's no longer in the same place as the client coordinates origin. The *units* for logical coordinates and client coordinates are the same, but the *origins* for the coordinates systems are different. This situation is illustrated in Figure 15-2.




FIGURE 15-2

The left side of Figure 15-2 shows the position in the client area where you draw, and the points that are the mouse cursor positions defining the line. These are recorded in client coordinates. The right side shows where the line is actually drawn. Drawing is in logical coordinates, but you have been using client coordinate values as arguments to the drawing functions. When the view is scrolled, the line appears displaced because the logical origin has been relocated.

This means that you are using the wrong values to define elements in Sketcher. When you invalidate areas of the client area to get them redrawn, the enclosing rectangles you pass to the function are also wrong — hence, the weird behavior of the program. With other mapping modes, it gets worse. Not only are the units of measurement in the two coordinate systems different, but the y-axes may be in opposite directions!

Dealing with Client Coordinates

Let's consider what needs to be done to fix the problem. There are two things you have to address:

- You must convert the client coordinates that you got with mouse messages to logical coordinates before you can use them to create elements.
- You must convert a bounding rectangle that you created in logical coordinates back to client coordinates if you want to use it in a call to `InvalidateRect()`.

These amount to making sure that you always use logical coordinates with device context functions, and always use client coordinates for other communications about the window. The functions that will do the conversions between client coordinates and logical coordinates are members of a device context object, so you need to obtain a device context whenever you want to convert from logical coordinates to client coordinates or vice versa. The coordinate conversion functions are defined in the `CDC` class and inherited by `CCClientDC` so you can use an object of this type to do the work.

The revised version of the `OnLButtonDown()` handler incorporating this is as follows:

```
// Handler for left mouse button down message
void CSketcherView::OnLButtonDown(UINT nFlags, CPoint point)
{
    CCClientDC aDC(this);           // Create a device context
    OnPrepareDC(&aDC);            // Get origin adjusted
    aDC.DPtoLP(&point);           // Convert point to logical coordinates
    m_FirstPoint = point;          // Record the cursor position
    SetCapture();                  // Capture subsequent mouse messages
}
```

You obtain a device context for the current view by creating a `CCClientDC` object and passing the pointer `this` to the constructor. As you're using `CScrollView`, the inherited `OnPrepareDC()` member function must be called to set the origin for the logical coordinate system in the device context to correspond with the scrolled position. After you have set the origin by this call, you call the `DPtoLP()` function that converts from Device Points to Logical Points. This converts the `point` value that was passed to `OnLButtonDown()` and is in client coordinates to logical coordinates. You then store the point in logical coordinates in `m_FirstPoint`, ready for creating an element in the `OnMouseMove()` handler.

The new code for the `OnMouseMove()` handler is as follows:

```
void CSketcherView::OnMouseMove(UINT nFlags, CPoint point)
{
    CClientDC aDC(this);           // Device context for the current view
    OnPrepareDC(&aDC);           // Get origin adjusted
    aDC.DPtoLP(&point);          // Convert point to logical coordinates

    // Verify the left button is down and mouse messages captured
    if((nFlags&MK_LBUTTON)&&(this==GetCapture()))
    {
        m_SecondPoint = point;   // Save the current cursor position

        // Rest of the function as before...
    }
}
```

The code for converting `point` is essentially the same as in the previous handler, and that's all you need here for the moment. The last function that you must change is easy to overlook: the `OnUpdate()` function in the view class. This needs to be modified to the following:

```
void CSketcherView::OnUpdate(CView* pSender, LPARAM lHint, CObject* pHint)
{
    // Invalidate the area corresponding to the element pointed to
    // if there is one, otherwise invalidate the whole client area
    if(pHint)
    {
        CClientDC aDC(this);           // Create a device context
        OnPrepareDC(&aDC);           // Get origin adjusted

        // Get the enclosing rectangle and convert to client coordinates
        CRect aRect = static_cast<CElement*>(pHint)->GetEnclosingRect();
        aDC.LPtodP(aRect);
        InvalidateRect(aRect);         // Get the area redrawn
    }
    else
    {
        InvalidateRect(nullptr);      // Invalidate the client area
    }
}
```

The function now creates a `CClientDC` object and uses an overloaded version of the `LPtoDP()` member to convert the enclosing rectangle for the element to client coordinates.

You must do the same thing in `OnLButtonUp()` when you invalidate the enclosing rectangle for the element:

```
void CSketcherView::OnLButtonUp(UINT nFlags, CPoint point)
{
    if(this == GetCapture())
        ReleaseCapture();           // Stop capturing mouse messages

    // Make sure there is an element
```

```

if(m_pTempElement)
{
    CRect aRect = m_pTempElement->GetEnclosingRect(); // Get enclosing rectangle

    GetDocument()->AddElement(m_pTempElement); // Add element pointer to sketch

    CCClientDC aDC(this); // Create a device context
    OnPrepareDC(&aDC); // Get origin adjusted
    aDC.LPtodP(aRect); // Convert to client coordinates
    InvalidateRect(aRect); // Get the area redrawn
    m_pTempElement.reset(); // Reset pointer to nullptr
}
}

```

If you now compile and execute Sketcher with these modifications and are lucky enough not to have introduced any typos, it will work correctly, regardless of the scroller position. If you have a mouse wheel, you can scroll a view using that.

Using MM_LOENGLISH Mapping Mode

The advantage of using the `MM_LOENGLISH` mapping mode is that it provides drawings in logical units of 0.01 inches, which ensures that the drawing size is the same on displays at different resolutions. This makes the application much more satisfactory from the user's point of view.

You can set the mapping mode in the call to `SetScrollSizes()` made from the `OnInitialUpdate()` function in the view class. You also need to specify the total drawing area: if you define it as 3,000 by 3,000, this provides a drawing area of 30 inches by 30 inches, which should be adequate. The default scroll distances for a line and a page are satisfactory, so you don't need to specify those. You can use the Class View to get to the `OnInitialUpdate()` function and then change it to the following:

```

void CSketcherView::OnInitialUpdate(void)
{
    CScrollView::OnInitialUpdate();

    CSize DocSize(3000,3000); // Document 30x30ins in MM_LOENGLISH
    SetScrollSizes(MM_LOENGLISH, DocSize); // Set mapping mode and document size
}

```

That's all you need to enable the view to work in `MM_LOENGLISH`. Note that you are not limited to setting the mapping mode once and for all. You can change the mapping mode in a device context at any time and draw different parts of a view using different mapping modes. A function, `SetMapMode()`, is used to do this, but I won't be going into this any further here. Whenever you create a `CCClientDC` object for the view and call `OnPrepareDC()`, the device context that it owns has the mapping mode you've set in the `OnInitialUpdate()` function. That should do it for the program as it stands. If you rebuild Sketcher, you should have scrolling working, with support for multiple views.

DELETING AND MOVING ELEMENTS

Being able to delete shapes is a fundamental requirement in a drawing program. The document object already has the facility for deleting a sketch element but you still have to decide on the user interface mechanism for this. How are you going to select the element you want to delete?

Of course, after you decide on a mechanism for selecting an element, this will apply equally well to selecting an element to move it. This suggests that you can treat moving and deleting elements as related problems. But first, let's consider how you might initiate move and delete operations in the user interface.

A neat way of providing these functions would be to have a *context menu* popup at the cursor position when you click the right mouse button. You could then include Move and Delete as items on the menu. A pop-up menu that works like this is a very handy facility in lots of situations.

NOTE Context menus are also referred to as pop-up menus or as shortcut menus.

How should the context menu work? The standard way is that the user moves the mouse over a particular element that is displayed and right-clicks it. This selects the element and pops up a menu containing a list of menu items offering actions that can be performed on that element. The element provides the context for the menu. Naturally, different elements can have different context menus. You have seen this in action in the IDE for Visual C++. When you right-click a class name in Class View, you get a menu that applies to the class, and that's different from the one you get if you right-click a filename in Solution Explorer. You have two contexts to consider in Sketcher. You could right-click with the mouse cursor over a sketch element, or you could right-click when there is no element under the cursor.

How can you implement this functionality in Sketcher? First you need to create two menus, one for when you have an element under the cursor and one for when you don't. You can check if there's an element under the cursor when the user clicks the right mouse button. If there *is* an element under the cursor, you can highlight it by changing its color so that the user knows exactly the element to which the context menu relates.

First, I'll explain how you can create and display a menu at the mouse cursor position in response to a right-click, then I'll discuss how you can implement the details of the move and delete operations.

IMPLEMENTING A CONTEXT MENU

You need two menus for the context menu: one for when there is an element under the mouse cursor and another for when there isn't. Change to Resource View and expand the list of resources. Right-click the Menu folder to bring up a context menu — another demonstration of what you are now trying to create in the Sketcher application. Select Insert Menu to create a new menu resource.

This has a default ID `IDR_MENU1` assigned, but you can change this. Select the name of the new menu in the Resource View and display the Properties window for the resource by pressing Alt+Enter (this is a shortcut to the View \Rightarrow Other Windows \Rightarrow Properties Window menu item). You can then edit the resource ID in the Properties window by clicking the value for the ID. You could change it to something more suitable, such as `IDR_CONTEXT_MENU`, in the right column. Note that the name for a menu resource must start with `IDR`. Pressing the Enter key saves the new name.

The next step is to create a drop-down menu containing Move and Delete as menu items that will apply when an element is under the cursor. The other drop-down menu will contain menu items from the Element and Color menus to allow the current selections to be changed. You can enter a name for the new item on the menu bar in the Editor pane. This can have any old caption because it won't actually be seen by the user; the caption "element" will be OK. Now you can add the Move and Delete items to this menu. The default IDs of `ID_ELEMENT_MOVE` and `ID_ELEMENT_DELETE` will do fine, but you can change them if you want in the Properties window for each item.

Create a second drop-down menu with the menu name "no element". Figure 15-3 shows how the element menu looks with the no element menu added.




FIGURE 15-3

The no element menu is going to contain menu items for the available element types and colors, identical to those on the Element and Color menus. The IDs you use for these items will be the same as the ones for the `IDR_SketchTYPE` menu items. The handler for a menu item is associated with the menu ID. Messages for menu items with the same ID will call the same handler, so the same handler will be called for a Line menu item regardless of whether the message originates from an item in the main Element menu or from the no element context menu.

There is a shortcut that saves you from having to re-create all these menu items. If you display the `IDR_SketchTYPE` menu and extend the Element menu, you can select all the menu items by clicking the first item and then clicking the last item while holding down the Shift key. You can then right-click the selection and select Copy from the pop-up or simply press Ctrl+C. If you then return to the `IDR_CONTEXT_MENU` and right-click the first item on the no element menu, you can insert the complete contents of the Element menu by selecting Paste from the pop-up or by pressing Ctrl+V. The copied menu items will have the same IDs as the originals. To insert a separator before you add the color menu items, right-click the empty menu item and select Insert Separator from the menu.

Add the items from the Color menu to the no element menu after the separator and you're done. Close the properties box and save the resource file. At the moment, all you have is the definition of the context menus in a resource file. It isn't connected to the code in the Sketcher program. You now need to associate these menus and their IDs with the view class. You also must create command handlers for the menu items in the pop-up corresponding to the IDs `ID_ELEMENT_MOVE` and `ID_ELEMENT_DELETE`.

To choose the appropriate menu to display when the right mouse button is clicked, you'll need to know whether or not there is an element under the cursor. You can add a protected `shared_ptr<CElement>` member to the view class to track this:

```
std::shared_ptr<CElement> m_pSelected;           // Records element under the cursor
```

Initialize this with `nullptr` in the `CSketcherView` constructor. You'll store the address of the element under the cursor in this member, when there is one; otherwise, it will contain `nullptr`.

Associating a Menu with a Class

To associate the context menu with the view class in Sketcher, go to the Class View pane and display the Properties window for `CSketcherView` by right-clicking the class name and selecting Properties from the pop-up. If you click the Messages button in the Properties window, you'll be able to add a handler for the `WM_CONTEXTMENU` message by selecting <Add>`OnContextMenu` from the adjacent cell in the right column. This handler is called when the user right-clicks in the view. The first argument passed to the handler is a pointer to the window in which the user right-clicked, and the second argument is the cursor position in screen coordinates.

Add the following code to the handler:

```
void CSketcherView::OnContextMenu(CWnd* pWnd, CPoint point)
{
    CMenu menu;
    menu.LoadMenu(IDR_CONTEXT_MENU);           // Load the context menu
    CMenu* pContext = menu.GetSubMenu(m_pSelected ? 0 : 1);
    ASSERT(pContext != nullptr);               // Ensure it's there

    pContext->TrackPopupMenu(TPM_LEFTALIGN | TPM_RIGHTBUTTON,
                             point.x, point.y, this);
}
```

Don't forget to uncomment the parameter names. This handler displays the first menu in the context menu when `m_pSelected` points to an element, and the second menu when it does not. Calling the `LoadMenu()` function for the menu object loads the menu resource corresponding to the ID supplied as the argument and attaches it to the `CMenu` object. The `GetSubMenu()` function returns a pointer to the context menu corresponding to the integer argument that specifies the position of the context menu in the `CMenu` object, with 0 being the first, 1 being the second, and so on. After ensuring the pointer returned by `GetSubMenu()` is not `nullptr`, you display the context menu by calling `TrackPopupMenu()`. The `ASSERT` macro only operates in the debug version of the program. It produces no code in the release version.

The first argument to the `TrackPopupMenu()` function consists of two flags ORed together. One flag specifies how the pop-up menu should be positioned and can be any of the following values:

`TPM_CENTERALIGN` centers the pop-up horizontally relative to the x-coordinate supplied as the second argument to the function.

`TPM_LEFTALIGN` positions the pop-up so that the left side of the menu is aligned with the x-coordinate supplied as the second argument to the function.

`TPM_RIGHTALIGN` positions the pop-up so that the right side of the menu is aligned with the x-coordinate supplied as the second argument to the function.

This is just a selection of the options. There are more options available which you can find in the documentation.

The other flag specifies the mouse button and can be either of the following values:

`TPM_LEFTMOUSEBUTTON` specifies that the pop-up only tracks the left mouse button.

`TPM_RIGHTMOUSEBUTTON` specifies that the pop-up tracks either the left or the right mouse button.

The next two arguments to `TrackPopupMenu()` specify the x- and y-coordinates of the context menu in screen coordinates. The y-coordinate determines the position of the top of the menu. The fourth argument specifies the window that owns the menu and that should receive all `WM_COMMAND` messages from the menu.

Now you can add the handler for the item in the context menu for moving elements. Return to the Resource View and double-click on `IDR_CONTEXT_MENU`. Right-click the Move menu item and then select Add Event Handler from the menu. It's a `COMMAND` handler and you create it in the `CSketcherView` class. Click the Add and Edit button to create the handler function. You can follow the same procedure to create the handler for the Delete menu item.

Checking Context Menu Items

You don't have to do anything for `COMMAND` events for the no element menu items, as you already have handlers for them in the document class. These will automatically take care of the messages from the pop-up items. However, the menu items are in a separate resource, and the menu items will not get checked to reflect the currently selected element type and color. You can fix this in the `OnContextMenu()` handler, before the context menu is displayed.

The `CMenu` class has a `CheckMenuItem()` member that checks a menu item. This function checks or unchecks any item in the menu. The first argument selects which item in the menu is to be checked or unchecked; the second argument is a combination of two flags, one of which determines how the first argument specifies which item is to be checked, and the other specifies whether the menu item is to be checked or unchecked. Because each flag is a single bit in a `UINT` value, you combine the two using the bitwise OR. The second argument can contain the flag `MF_BYCOMMAND` if the first parameter is a menu ID or it can contain the flag `MF_BYPOSITION` which implies the first argument is an index. You can use the former because you know the element IDs. If the second argument

contains the MF_CHECKED flag, the item will be checked; the MF_UNCHECKED flag indicates the opposite. Here's how you can implement checking for the no element menu items:

```

void CSketcherView::OnContextMenu(CWnd* pWnd, CPoint point)
{
    CMenu menu;
    menu.LoadMenu(IDR_CONTEXT_MENU); // Load the context menu
    CMenu* pContext(nullptr);
    if(m_pSelected)
    {
        pContext = menu.GetSubMenu(0);
    }
    else
    {
        pContext = menu.GetSubMenu(1);

        // Check color menu items
        ElementColor color = GetDocument()->GetElementColor();
        menu.CheckMenuItem(ID_COLOR_BLACK,
            (ElementColor::BLACK == color ? MF_CHECKED : MF_UNCHECKED) | MF_BYCOMMAND);
        menu.CheckMenuItem(ID_COLOR_RED,
            (ElementColor::RED == color ? MF_CHECKED : MF_UNCHECKED) | MF_BYCOMMAND);
        menu.CheckMenuItem(ID_COLOR_GREEN,
            (ElementColor::GREEN == color ? MF_CHECKED : MF_UNCHECKED) | MF_BYCOMMAND);
        menu.CheckMenuItem(ID_COLOR_BLUE,
            (ElementColor::BLUE == color ? MF_CHECKED : MF_UNCHECKED) | MF_BYCOMMAND);

        // Check element menu items
        ElementType type = GetDocument()->GetElementType();
        menu.CheckMenuItem(ID_ELEMENT_LINE,
            (ElementType::LINE == type ? MF_CHECKED : MF_UNCHECKED) | MF_BYCOMMAND);
        menu.CheckMenuItem(ID_ELEMENT_RECTANGLE,
            (ElementType::RECTANGLE == type ? MF_CHECKED : MF_UNCHECKED) | MF_BYCOMMAND);
        menu.CheckMenuItem(ID_ELEMENT_CIRCLE,
            (ElementType::CIRCLE == type ? MF_CHECKED : MF_UNCHECKED) | MF_BYCOMMAND);
        menu.CheckMenuItem(ID_ELEMENT_CURVE,
            (ElementType::CURVE == type ? MF_CHECKED : MF_UNCHECKED) | MF_BYCOMMAND);
    }
    ASSERT(pContext != nullptr); // Ensure it's there

    pContext->TrackPopupMenu(TPM_LEFTALIGN | TPM_RIGHTBUTTON,
        point.x, point.y, this);
}

```

That's the context menu finished. You need to identify when an element is under the cursor next.

IDENTIFYING AN ELEMENT UNDER THE CURSOR

It will be a very simple mechanism for identifying the element under the mouse cursor. A sketch element will be under the cursor whenever the cursor is within the enclosing rectangle for the element. For this to be effective, Sketcher must track whether or not there is an element under the cursor at all times.

You can add code to the `OnMouseMove()` handler in the `CSketcherView` class to determine which element is under the cursor. This handler is called every time the mouse cursor moves, so all you have to do is add code to determine whether there's an element under the current cursor position and set `m_pSelected` accordingly. The test for whether a particular element is under the cursor is simple: if the cursor position is inside the enclosing rectangle for an element, that element is under the cursor. Here's how you can modify the `OnMouseMove()` handler to determine whether there's an element under the cursor:

```
void CSketcherView::OnMouseMove(UINT nFlags, CPoint point)
{
    // Define a Device Context object for the view
    CClientDC aDC(this);           // DC is for this view
    OnPrepareDC(&aDC);           // Get origin adjusted
    aDC.DPtoLP(&point);          // Convert point to logical coordinates

    // Verify the left button is down and mouse messages captured
    if((nFlags & MK_LBUTTON) && (this == GetCapture()))
    {
        // Code as before...
    }
    else
    { // We are not creating an element, so select an element
        m_pSelected = GetDocument()->FindElement(point);
    }
}
```

The new code is one statement that is executed only when you are not creating a new element. The `else` clause calls the `FindElement()` function for the document object that you'll add shortly and stores the smart pointer that is returned in `m_pSelected`. The `FindElement()` function has to search the document for the first element that has an enclosing rectangle that encloses `point`. You can add `FindElement()` to the `CSketcherDoc` class definition as a `public` member and implement it like this:

```
// Finds the element under the point
std::shared_ptr<CElement> FindElement(const CPoint& point) const
{
    for(auto& pElement : m_Sketch)
    {
        if(pElement->GetEnclosingRect().PtInRect(point))
            return pElement;
    }
    return nullptr;
}
```

You use a range-based `for` loop to search the list from the beginning. Because elements are added to the back of the list, the most recently created element will be tested last. The `GetEnclosingRect()` member of a sketch element object returns its enclosing rectangle. The `PtInRect()` member of the `CRect` class returns `TRUE` if the point you pass as the argument lies within the rectangle, and `FALSE` otherwise. You use this function to test whether or not `point` lies within any enclosing rectangle for a sketch element. The function returns the address of the first element for which this is true, or `nullptr` if no element in the sketch is found. You can now test the context menus.

Exercising the Context Menus

You have added all the code you need to make the context menus operate, so you can build and execute Sketcher to try them out. When you right-click the mouse a context menu will be displayed. If there are no elements under the cursor, the second context pop-up appears, enabling you to change the element type and color. These options work because they generate exactly the same messages as the main menu options for which you have already written handlers.

If there is an element under the cursor, the first context menu will appear with Move and Delete on it. It won't do anything at the moment, as you've yet to implement the handlers for the messages. Try right-button clicks outside the view window. Messages for these are not passed to the view window in your application, so the pop-up is not displayed.

Highlighting Elements

Ideally, the user will want to know which element is under the cursor *before* right-clicking to get the context menu. When you intend to delete an element, you want to be sure which element you are operating on. If there are concentric circles displayed, only one will be selected but you won't know which. Equally, when you want to use the other context menu — to change the drawing color for example — you must be sure no element is under the cursor when you right-click the mouse, otherwise you'll get the Move/Delete menu displayed. To show which element is under the cursor, you need to highlight it in some way before a right-button click occurs.

You can change the `Draw()` member function for each element type to accommodate this. You can pass an extra argument to the `Draw()` function to indicate when the element should be highlighted. If you pass the address of the currently selected element that you save in the `m_pSelected` member of the view to the `Draw()` function for an element, you can pass it on to the `CreatePen()` function, which can compare it to the `this` pointer to decide the color of the pen.

Highlighting will work in the same way for all element types, so let's take the `CLine` member as an example. You can add similar code to each of the classes for the other element types. Before you start changing `CLine`, you must first amend the definition of the base class `CElement`:

```
static const COLORREF SELECT_COLOR(RGB(255,0,180));      // Highlight color

class CElement : public COObject
{
protected:
    CPoint m_StartPoint;                      // Element position
    int m_PenWidth;                          // Pen width
    COLORREF m_Color;                        // Color of an element
    CRect m_EnclosingRect;                   // Rectangle enclosing an element

public:
    virtual ~CElement();
    // Virtual draw operation
    virtual void Draw(CDC* pDC, std::shared_ptr<CElement> pElement=nullptr) {}
```

```

// Get the element enclosing rectangle
const CRect& GetEnclosingRect() const
{
    return m_EnclosingRect;
}

protected:
    // Constructors protected so they cannot be called outside the class
    CEElement();
    CEElement(const CPoint& start, COLORREF color, int penWidth = 1);

    // Create a pen
    void CreatePen(CPen& aPen, std::shared_ptr<CElement> pElement)
    {
        if(!aPen.CreatePen(PS_SOLID, m_PenWidth,
                           this == pElement.get() ? SELECT_COLOR : m_Color))
        {
            // Pen creation failed
            AfxMessageBox(_T("Pen creation failed"), MB_OK);
            AfxAbort();
        }
    }
}:

```

You need an #include directive for the memory header in `Element.h`. `SELECT_COLOR` is the highlight color for all elements and this is a static constant that is defined and initialized at global scope. A second parameter has been added to the virtual `Draw()` function. This is a pointer to an element and it will be used when an element is to be highlighted because it is under the mouse cursor. With the second parameter initialized to `nullptr`, the function can still be called with just one argument; the second argument will be `nullptr` by default.

The `CreatePen()` function also has an additional argument that is a pointer to an element. When `pElement` contains the address of the current element, the pen is created using the highlight color.

You need to modify the declaration of the `Draw()` function in each of the definitions for the classes derived from `CElement` in exactly the same way. For example, you should change the `CLine` class definition to:

```

class CLLine :
    public CEElement
{
public:
    virtual ~CLLine(void);
    // Function to display a line
    virtual void Draw(CDC* pDC, std::shared_ptr<CEElement> pElement=nullptr)
        override;

    // Rest of the class as before...
}:

```

The implementations for the `Draw()` functions for the derived classes also need to be extended in the same way. For the `CLine` class it is:

```
void CLine::Draw(CDC* pDC, std::shared_ptr<CElement> pElement)
{
    // Create a pen for this object and initialize it
    CPen aPen;
    CreatePen(aPen, pElement);

    // Rest of the function body as before...
}
```

This is a very simple change. The second argument to the `CreatePen()` function call is the `pElement` smart pointer that is passed as the second argument to the `Draw()` function.

You have nearly implemented element highlighting. The derived classes of the `CElement` class are now able to draw themselves as highlighted when required — you just need a mechanism to cause an element to *be* selected. So where should you create this? You can determine which element, if any, is under the cursor in the `OnMouseMove()` handler in the `CSketcherView` class, so that's obviously the place to expedite the highlighting.

The amendments to the `OnMouseMove()` handler are as follows:

```
void CSketcherView::OnMouseMove(UINT nFlags, CPoint point)
{
    // Define a Device Context object for the view
    CClientDC aDC(this);                                // DC is for this view
    OnPrepareDC(&aDC);                                 // Get origin adjusted
    aDC.DPtoLP(&point);                               // Convert point to logical coordinates

    // Verify the left button is down and mouse messages captured
    if((nFlags & MK_LBUTTON) && (this == GetCapture()))
    {
        // Code as before...
    }
    else
    { // We are not creating an element, so do highlighting
        auto pOldSelected(m_pSelected);                // Copy previous
        m_pSelected = GetDocument()->FindElement(point);
        if(m_pSelected != pOldSelected)
        {
            if(m_pSelected)
                GetDocument()->UpdateAllViews(nullptr, 0, m_pSelected.get());
            if(pOldSelected)
                GetDocument()->UpdateAllViews(nullptr, 0, pOldSelected.get());
        }
    }
}
```

You must keep track of any previously highlighted element before you store the address of a new one. If there's a new element to be highlighted, you must un-highlight the old one. To do this,

you save a copy of `m_pSelected` in `pOldSelected` before you check for a selected element. You then store the smart pointer returned by the `FindElement()` function for the document object in `m_pSelected`.

If `pOldSelected` and `m_pSelected` are equal, then either they both contain the address of the same element or they are both `nullptr`. If they both contain a valid address, the element will already have been highlighted last time around. If they are both `nullptr`, nothing is highlighted and nothing needs to be done. Thus, in either case, you do nothing.

Thus, you want to do something only when `m_pSelected` is not equal to `pOldSelected`. If `m_pSelected` is not `nullptr`, you need to get it redrawn, so you call `UpdateAllViews()` with the first argument as `nullptr` to get all views updated, and the third argument as `m_pSelected.get()` identify the region to be updated. If `pOldSelected` is also not `nullptr`, you must un-highlight the old element by updating its area in the same way. The updating of each view will be done by its `OnUpdate()` member, which will invalidate the rectangle enclosing the element. Only the currently active view will have element highlighting active.

Drawing Highlighted Elements

You still need to arrange that the highlighted element is actually drawn highlighted. Somewhere, the `m_pSelected` pointer must be passed to the draw function for each element. The only place to do this is in the `OnDraw()` function for the view object:

```
void CSketcherView::OnDraw(CDC* pDC)
{
    CSketcherDoc* pDoc = GetDocument();
    ASSERT_VALID(pDoc);
    if (!pDoc)
        return;

    // Draw the sketch
    for(auto iter = pDoc->begin(); iter != pDoc->end(); ++iter)
    {
        std::shared_ptr<CElement> pElement(*iter);
        if(pDC->RectVisible(pElement->GetEnclosingRect())) // Element visible?
            pElement->Draw(pDC, m_pSelected);                // Yes, draw it.
    }
}
```

You need to change only one line. The second argument to the `Draw()` function call for an element is the address of the element to be highlighted.

Exercising the Highlights

This is all that's required for the highlighting to work all the time. It wasn't trivial but, on the other hand, it wasn't terribly difficult. You can build and execute Sketcher to try it out. Any time there is an element under the cursor, the element is drawn in magenta. This makes it obvious which element the context menu is going to act on before you right-click the mouse, and means that you know in advance which context menu will be displayed.

Implementing Move and Delete

The next step is to provide code in the bodies of the handlers in the view class for the Move and Delete menu items that you added earlier. You can add the code for Delete first because that's the simpler of the two.

Deleting an Element

The code that you need in the `OnElementDelete()` handler in the `CSketcherView` class to delete the currently selected element is simple:

```
void CSketcherView::OnElementDelete()
{
    if(m_pSelected)
    {
        GetDocument()->DeleteElement(m_pSelected);           // Delete the element
        m_pSelected.reset();
    }
}
```

The code to delete an element is executed only if `m_pSelected` is not `nullptr`, indicating that there is an element to be deleted. You get a pointer to the document and call the function `DeleteElement()` for the document object. You have already added this function to `CSketcherDoc`. When the element has been removed from the document, you call `reset()` for the smart pointer to change its pointer to `nullptr`.

That's all you need in order to delete elements. You should now have a Sketcher program in which you can draw in multiple scrolled views, and delete any of the elements in your sketch from any of the views.

Moving an Element

Moving the selected element is a bit more involved. The element should move along with the mouse cursor, so you need to add code to the `OnMouseMove()` method to provide for this behavior. Because this message handler is also used to draw elements, you need a mechanism for indicating when you're in "move" mode. The easiest way to do this is to have a flag in the view class, which you can call `m_MoveMode`. You can define it as type `bool`, with the value `false` indicating that move mode is not in effect.

You'll also have to keep track of the cursor during the move, so you can add another data member in the view class for this. You can call it `m_CursorPos`, and it will be of type `CPoint`. Another thing you should provide for is the possibility of aborting a move. For this you must remember the position of the cursor when the move operation started, so you can move the element back when necessary. This is another member of type `CPoint`, and it is called `m_FirstPos`. Add the three new members to the protected section of the view class:

```

class CSketcherView: public CScrollView
{
    // Rest of the class as before...

protected:
CPoint m_FirstPoint;           // First point recorded for an element
CPoint m_SecondPoint;          // Second point recorded for an element
CPoint m_CursorPos;         // Cursor position
CPoint m_FirstPos;          // Original position in a move
std::shared_ptr<CElement> m_pTempElement;
std::shared_ptr<CElement> m_pSelected; // Records element under the cursor
bool m_MoveMode;            // Move element flag

    // Rest of the class as before...
};


```

These can be initialized in the CSketcherView constructor:

```

CSketcherView::CSketcherView():
    m_FirstPoint(CPoint(0,0)), m_SecondPoint(CPoint(0,0)),
    m_pTempElement(nullptr), m_pSelected(nullptr),
    m_CursorPos(CPoint(0,0)), m_FirstPos(CPoint(0,0)),
    m_MoveMode(false)
{
    // TODO: add construction code here
}

```

The element move process starts when the Move menu item from the context menu is selected. You can add the code to the message handler for the Move menu item to set up the conditions necessary for the operation:

```

void CSketcherView::OnElementMove()
{
    CCClientDC aDC(this);
    OnPrepareDC(&aDC);           // Set up the device context
    GetCursorPos(&m_CursorPos); // Get cursor position in screen coords
    ScreenToClient(&m_CursorPos); // Convert to client coords
    aDC.DPtoLP(&m_CursorPos);   // Convert to logical
    m_FirstPos = m_CursorPos;    // Remember first position
    m_MoveMode = true;           // Start move mode
}

```

You are doing four things in this handler:

- 1.** You get the coordinates of the current mouse cursor position because the move operation starts from this reference point.
- 2.** You convert the cursor position to logical coordinates because your elements are defined in logical coordinates.
- 3.** You record the initial cursor position in case the user wants to abort the move later.
- 4.** You set `m_MoveMode` to `true`. This is a flag for the `OnMouseMove()` handler to recognize move mode.

The `GetCursorPos()` function is a Windows API function that stores the current cursor position in `m_CursorPos`. Note that you pass a pointer to this function. The cursor position is in screen coordinates (i.e., coordinates measured in pixels relative to the upper-left corner of the screen). All operations with the mouse cursor are in screen coordinates. You want the cursor position in logical coordinates, so you must do the conversion in two steps. The `ScreenToClient()` function is inherited from `CWnd` in the view class. It converts a `CPoint` or `CRect` argument from screen to client coordinates. You apply the `DPTOLP()` function member of the `ADC` object to `m_CursorPos`, which is now in client coordinates, to convert it to logical coordinates. Now that you have set the move mode flag, you can update the mouse move message handler to deal with moving an element.

Modifying the WM_MOUSEMOVE Handler to Move an Element

Moving an element only occurs when move mode is on and the cursor is being moved. Therefore, all you need in `OnMouseMove()` is a block of code to handle moving an element that gets executed only when `m_MoveMode` is true. The new code to do this is as follows:

```
void CSketcherView::OnMouseMove(UINT nFlags, CPoint point)
{
    CClientDC aDC(this);           // DC is for this view
    OnPrepareDC(&aDC);           // Get origin adjusted

    aDC.DPTOLP(&point);          // Convert point to logical coordinates

    // If we are in move mode, move the selected element and return
    if(m_MoveMode)
    {
        MoveElement(aDC, point);   // Move the element
    }
    else if((nFlags & MK_LBUTTON) && (this == GetCapture()))
    {
        // Rest of the mouse move handler as before...
    }
}
```

This addition doesn't need much explaining, really, does it? When `m_MoveMode` is true you're in move mode so you call the `MoveElement()` function that does what is necessary for the move. If `m_MoveMode` is false, everything continues as before. All you have to do now is implement `MoveElement()`.

Add the declaration for `MoveElement()` as a protected member of `CSketcherView` by adding the following at the appropriate point in the class definition:

```
void MoveElement(CClientDC& aDC, const CPoint& point); // Move an element
```

As always, you can also right-click the class name in Class View to do this. The function needs access to the device context object for the view, `aDC`, and the current cursor position, `point`, so both of these are reference parameters. The basic implementation of the function in the `SketcherView.cpp` file is:

```

void CSketcherView::MoveElement(CClientDC& aDC, const CPoint& point)
{
    CSize distance = point - m_CursorPos; // Get move distance
    m_CursorPos = point; // Set current point as 1st for
                          // next time

    // If there is an element selected, move it
    if(m_pSelected)
    {
        aDC.SetROP2(R2_NOTXORPEN);
        m_pSelected->Draw(&aDC, m_pSelected); // Draw element to erase it
        m_pSelected->Move(distance); // Now move the element
        m_pSelected->Draw(&aDC, m_pSelected); // Draw the moved element
    }
}

```

The distance to move the element that is currently selected is stored locally as a `CSize` object, `distance`. The `CSize` class is designed to represent a relative coordinate position and has two public data members, `cx` and `cy`, which correspond to *x* and *y* increments. These are calculated as the difference between the current cursor position, stored in `point`, and the previous cursor position, saved in `m_CursorPos`. This uses the subtraction operator, which is overloaded in the `CPoint` class. The version you are using here returns a `CSize` object, but there is also a version that returns a `CPoint` object. You can usually operate on `CSize` and `CPoint` objects combined. You save the current cursor position in `m_CursorPos` for use the next time this function is called, which occurs if there is a further mouse move message during the current move operation.

You implement moving an element in the view using the `R2_NOTXORPEN` drawing mode, because it's easy and fast. This is exactly the same as what you have been using during the creation of an element. You call `Draw()` for the selected element in its current color (`SELECT_COLOR` because it is selected) to reset it to the background color, and then call the `Move()` member of the element object to relocate it by the distance specified by `distance`. You'll add this function to the element classes in a moment. When the element has moved itself, you call its `Draw()` function once more to display it highlighted at the new position. The color of the element will revert to normal when the move operation ends, because the `OnLButtonUp()` handler will redraw all the views normally.

Updating Other Views

There's something we must not overlook. The view in which you are moving an element may not be the only view. If there are other views, then the element should move in those too. You can call `UpdateAllViews()` for the document object in `MoveElement()` and pass this as the first argument so that it doesn't update the current view. You need to do this before and after you move an element. Here's how that looks:

```

void CSketcherView::MoveElement(CClientDC& aDC, const CPoint& point)
{
    CSize distance = point - m_CursorPos; // Get move distance
    m_CursorPos = point; // Set current point as 1st for
                          // next time

    // If there is an element selected, move it

```

```

if(m_pSelected)
{
    CSketcherDoc* pDoc = GetDocument(); // Get the document pointer
    pDoc->UpdateAllViews(this, 0L, m_pSelected.get()); // Update all except this

    aDC.SetROP2(R2_NOTXORPEN);
    m_pSelected->Draw(&aDC, m_pSelected); // Draw element to erase it
    m_pSelected->Move(distance); // Now move the element
    m_pSelected->Draw(&aDC, m_pSelected); // Draw the moved element

    pDoc->UpdateAllViews(this, 0 , m_pSelected.get()); // Update all except this
}
}

```

By passing `m_pSelected` as the third argument to `UpdateAllViews()`, only the region occupied by the element pointed to will be redrawn. The first call to `UpdateAllViews()` invalidates the area occupied by the element before the move in each of the other views. The second call invalidates the area after the move.

Getting the Elements to Move Themselves

Add the `Move()` function as a virtual member of the base class, `CElement`. Modify the class definition to the following:

```

class CElement : public CObject
{
protected:
    CPoint m_StartPoint; // Element position
    int m_PenWidth; // Pen width
    COLORREF m_Color; // Color of an element
    CRect m_EnclosingRect; // Rectangle enclosing an element

public:
    virtual ~CElement();
    virtual void Draw(CDC* pDC, std::shared_ptr<CElement> pElement=nullptr) {}
    virtual void Move(const CSize& aSize){} // Move an element

    // Rest of the class as before...
};

```

As I discussed earlier in relation to the `Draw()` member, although an implementation of `Move()` has no meaning here, you can't make it a pure virtual function because of the requirements of serialization.

You can now add a declaration for the `Move()` function as a public member of each of the classes derived from `CElement`. It is the same in each:

```
virtual void Move(const CSize& aSize) override; // Function to move an element
```

Next, you can add the implementation of `Move()` for the `CLine` class to `Line.cpp`:

```
void CLine::Move(const CSize& aSize)
{
    m_StartPoint += aSize;           // Move the start point
    m_EndPoint += aSize;            // and the end point
    m_EnclosingRect += aSize;       // Move the enclosing rectangle
}
```

The overloaded `+=` operators in the `CPoint` and `CRect` classes make this easy. They all work with `CSize` objects, so you just add the relative distance specified by `aSize` to the start and end points for the line and to the enclosing rectangle.

Moving a `CRectangle` object is just as easy:

```
void CRectangle::Move(const CSize& aSize)
{
    m_StartPoint += aSize;           // Move the start point
    m_BottomRight += aSize;         // Move the bottom right point
    m_EnclosingRect += aSize;        // Move the enclosing rectangle
}
```

Because the rectangle is defined by the opposite corner points, the code to move it is essentially the same as that for moving a line.

The `Move()` member of the `CCircle` class is identical:

```
void CCircle::Move(const CSize& aSize)
{
    m_StartPoint += aSize;           // Move the start point
    m_BottomRight += aSize;          // Move the bottom right point
    m_EnclosingRect += aSize;         // Move the enclosing rectangle
}
```

Moving a `CCurve` object is a little more complicated, because it's defined by an arbitrary number of points. You can implement the function as:

```
void CCurve::Move(const CSize& aSize)
{
    m_EnclosingRect += aSize;         // Move the rectangle
    m_StartPoint += aSize;            // Move the start point
    // Now move all the other points
    for(auto& p : m_Points)
        p += aSize;
}
```

There's still not a lot to it. You first move the enclosing rectangle stored in `m_EnclosingRect`, using the overloaded `+=` operator for `CRect` objects. You then move the first point. You move the remaining points by using a range-based `for` loop to iterate over the points in the `m_Points` vector.

Dropping the Element

Once you have clicked on the Move menu item, the element under the cursor will move around as you move the mouse. All that remains is to add the capability to drop the element in position once the user has finished moving it, or to abort the whole move. To drop the element in its new position, the user will click the left mouse button, so you can manage this operation in the `OnLButtonDown()` handler. To abort the operation, the user will click the right mouse button — so you can add the code to the `OnRButtonDown()` handler to deal with this.

You can take care of dropping the element in `OnLButtonDown()` first. You'll have to provide for this as a special action when move mode is on. The changes are highlighted:

```
void CSketcherView::OnLButtonDown(UINT nFlags, CPoint point)
{
    CClientDC aDC(this);                      // Create a device context
    OnPrepareDC(&aDC);                       // Get origin adjusted
    aDC.DPtoLP(&point);                      // convert point to logical coordinates

    if(m_MoveMode)
    {
        // In moving mode, so drop the element
        m_MoveMode = false;                   // Kill move mode
        auto pElement(m_pSelected);          // Store selected address
        m_pSelected.reset();                // De-select the element
        GetDocument()->UpdateAllViews(nullptr, 0,
                                         pElement.get()); // Redraw all the views
    }
    else
    {
        m_FirstPoint = point;              // Record the cursor position
        SetCapture();                     // Capture subsequent mouse messages
    }
}
```

The code is pretty simple. You first check for move mode. If this is the case, you just set the move mode flag back to `false`. You save the address of the selected element in a local pointer because you want to use it to identify the area to be redrawn in the views. You then deselect the element and call the document's `UpdateAllViews()` function, causing all the views to be redrawn. This is all that's required because you've been moving the element along with the mouse cursor, so it's already in the right place.

Add a handler for the `WM_RBUTTONDOWN` message to `CSketcherView` using the Properties window for the class. The implementation for aborting a move must do two things. It must move the element back to where it was and turn off move mode. You can move the element back in the right-button-down handler, but you must leave switching off move mode to the right-button-up handler to allow the context menu to be suppressed. The code to move the element back is as follows:

```
void CSketcherView::OnRButtonDown(UINT nFlags, CPoint point)
{
    if(m_MoveMode)
    {
        // In moving mode, so drop element back in original position
```

```

    CCClientDC aDC(this);
    OnPrepareDC(&aDC);                                // Get origin adjusted
    MoveElement(aDC, m_FirstPos);                     // Move element to original position
    m_pSelected.reset();                             // De-select element
    GetDocument()->UpdateAllViews(nullptr);          // Redraw all the views
}
}

```

You first create a `CCClientDC` object for use in the `MoveElement()` function. You then call the `MoveElement()` function to move the currently selected element the distance from the current cursor position to the original cursor position that we saved in `m_FirstPos`. After the element has been repositioned, you just deselect the element and get all the views redrawn.

The last thing you must do is switch off move mode in the right-button-up handler so add it and implement it like this:

```

void CSketcherView::OnRButtonUp(UINT /* nFlags */, CPoint point)
{
    if(m_MoveMode)
    {
        m_MoveMode = false;
    }
    else
    {
        ClientToScreen(&point);
        OnContextMenu(this, point);
    }
}

```

This switches move mode off if it is on. The default handler was calling the `OnContextMenu()` handler every time. Now the context menu gets displayed only when it is not move mode.

Exercising the Application

Everything is now complete for the context pop-ups to work. If you build Sketcher, you can select the element type and color from the context menu when the cursor is not over an element. When it is over an element, you can move or delete that element using the other context menu.

DEALING WITH MASKED ELEMENTS

There's still a limitation that you ought to overcome. If the element you want to move or delete is enclosed by the bounding rectangle of another element that is drawn earlier in sequence, you won't be able to highlight it because Sketcher always finds the older element first. The older element completely masks the element it encloses. This is a result of the sequence of elements in the list. You add new elements to the back so the elements are ordered in the list from oldest to newest. You could fix this by adding a Send to Back item to the context menu that would move an element to the end of the list.

Add a separator and a menu item to the element menu in the `IDR_CONTEXT_MENU` resource, as shown in Figure 15-4.




FIGURE 15-4

The default ID will be `ID_ELEMENT_SENDTOBACK`, which is fine. You can try a different technique to add the message handler for the new item. You can add the handler for the item to the view class through the Properties window for the `CSketcherView` class. It's best to handle it in the view because that's where you record the selected element. Select the Events toolbar button in the Properties window for the class and double-click the message ID `ID_ELEMENT_SENDTOBACK`. You'll then be able to select `COMMAND` and `<Add>OnElementSendtoback` in the right column. You can implement the handler as follows:

```
void CSketcherView::OnElementSendtoback()
{
    GetDocument()->SendToBack(m_pSelected); // Move element to end of list
}
```

You'll get the document to do the work by passing the currently selected element pointer to a public function, `SendToBack()`, that you will implement in the `CSketcherDoc` class. Add it to the class definition with a `void` return type and a parameter of type `shared_ptr<CElement>&`. You can implement this function within the class definition as:

```
void SendToBack(std::shared_ptr<CElement>& pElement)
{
    if(pElement)
    {
        m_Sketch.remove(pElement);           // Remove the element from the list
        m_Sketch.push_back(pElement);        // Put it back at the end of the list
    }
}
```

After checking that the parameter is not `nullptr`, you remove the element from the list by calling `remove()`. You add the smart pointer back at the end of the list, using the `push_back()` function.

With the element moved to the end of the list, it cannot mask any of the others because you search for an element to highlight from the beginning. You will always find one of the other elements first if the applicable enclosing rectangle contains the current cursor position. The Send to Back menu option can always resolve any element masking problem in the view, although you may have to apply it to more than one masking element.

SUMMARY

You have improved the view capability in Sketcher in several ways. You've added scrolling to the views using the MFC class `CScrollView`, and you've introduced a pop-up at the cursor for moving and deleting elements. You have also implemented an element-highlighting feature to provide the user with feedback during the moving or deleting of elements.

EXERCISES

- 1.** Implement element highlighting so that the line type changes for the element under the cursor as well as the element color.
- 2.** Change the Sketcher program so that it uses a vector container to store a sketch instead of a list.

► WHAT YOU LEARNED IN THIS CHAPTER

TOPIC	CONCEPT
Windows coordinate systems	When you draw in a device context using the MFC, coordinates are in logical units that depend on the mapping mode set. Points in a window that are supplied along with Windows mouse messages are in client coordinates. The two coordinate systems are usually not the same.
Screen coordinates	Coordinates that define the position of the cursor are in screen coordinates that are measured in pixels relative to the upper-left corner of the screen.
Converting between coordinate systems	Functions to convert between client coordinates and logical coordinates are available in the <code>CDC</code> class.
Updating multiple views	To get multiple views updated when you change the document contents, you can call the <code>UpdateAllViews()</code> member of the document object. This causes the <code>OnUpdate()</code> member of each view object to be called.
Updating efficiently	You can pass information to the <code>UpdateAllViews()</code> function to indicate which area in the view needs to be redrawn. This makes redrawing the views faster.
Creating a context menu	You create a context menu as a menu resource. The resource can then be loaded into a <code>CMenu</code> object in the handler function for the context menu event.
Displaying a context menu	You can display a context menu at the cursor position in an MFC application in response to a right mouse button click by implementing the <code>OnContextMenu()</code> handler for a view. The menu is created as a normal pop-up at the cursor position.

16

Working with Dialogs and Controls

WHAT YOU WILL LEARN IN THIS CHAPTER:

- How to create dialog resources
- How to add controls to a dialog
- The basic varieties of controls available
- How to create a dialog class to manage a dialog
- How to program the creation of a dialog box, and how to get information back from the controls in it
- What are modal and modeless dialogs
- How to implement and use direct data exchange and validation with controls
- How to implement view-scaling
- How to use the status bar in an application

WROX.COM CODE DOWNLOADS FOR THIS CHAPTER

You can find the wrox.com code downloads for this chapter on the Download Code tab at www.wrox.com/remtitle.cgi?isbn=9781118368084. The code is in the Chapter 16 download and individually named according to the names throughout the chapter.

UNDERSTANDING DIALOGS

Of course, dialogs are not new to you. Most Windows programs of consequence use dialogs to manage some of their data input. You click a menu item and up pops a *dialog* with various *controls* that you use for entering information. Just about everything that appears in a dialog is a control. A dialog is actually a window and each control in a dialog is also a specialized window. Come to think of it, an application window under Microsoft Windows is composed almost entirely of windows within windows.

You need two things to create and display a dialog in an MFC program: the physical appearance of the dialog, which you define as a resource, and a dialog class object that you use to manage the operation of the dialog and its controls. MFC provides the `CDialog` and `CDialogEx` classes for you to use once you have defined your dialog resource.

UNDERSTANDING CONTROLS

Many different standard controls are available and in most cases there's flexibility to how they look and operate. Most of them fall into one of the categories shown in the following table.

CONTROL TYPE	WHAT THEY DO
Static controls	These are used to provide titles or descriptive information.
Button controls	Buttons provide a single-click input mechanism. There are basically three flavors of button controls: simple push buttons, radio buttons (of which only one may be in a selected state at any one time), and checkboxes (of which several may be in a selected state at one time).
Scrollbars	You have already seen scrollbars in Sketcher. Scrollbars are typically used to scroll text or images, either horizontally or vertically, within another control.
List boxes	These present a list of choices from which one or more selections can be made.
Edit controls	An edit control allows text input or editing of text that is displayed by the control.
Combo boxes	Combo boxes present a list of choices from which you can select, combined with the option of entering text yourself.

A control may or may not be associated with a class object. Static controls don't do anything directly, so an associated class object may seem superfluous; however, there's an MFC class, `CStatic`, that provides functions to enable you to alter the appearance of static controls.

Button controls can also be handled by the dialog object in many cases, but again, MFC provides the `CButton` class for when you need a class object to manage a control. MFC also provides a full complement of classes to support the other controls. All controls are windows so the MFC classes for controls are all derived from `CWnd`.

COMMON CONTROLS

The set of standard controls supported by the MFC and the Resource editor are called *common controls*. Common controls include all the controls I have just described, as well as other more complex controls such as the *animate control*, which can play an AVI (Audio Video Interleaved) file, and the *tree control*, which can display a hierarchy of items in a tree.

Another useful control in the set of common controls is the *spin button*. You can use this to increment or decrement values in an associated edit control. To go into all of the possible controls that you might use is beyond the scope of this book, so I'll just take a few examples (including one that uses a spin button) and show you how to implement them in Sketcher.

CREATING A DIALOG RESOURCE

Here's a concrete example. You could add a dialog to Sketcher to provide a choice of pen widths for drawing elements. This ultimately involves storing and modifying the current pen width in the document, as well as adding capability in the element classes to allow variable pen widths. You'll deal with all that, though, after you've gotten the dialog together.

Display the Resource View, expand the resource tree for Sketcher, and right-click the Dialog folder; then click Insert Dialog from the pop-up to add a new dialog resource to Sketcher. This results in the Dialog Resource editor swinging into action and displaying the dialog in the Editor pane, and the Toolbox showing a list of controls that you can add; if the Toolbox is not displayed, click Toolbox in the right-hand sidebar or press Ctrl+Alt+X.

The dialog has OK and Cancel button controls already in place. Adding more controls to the dialog is simplicity itself: you can just drag the control from the list in the Toolbox window to the position at which you want to place it in the dialog. Alternatively, you can click a control from the list to select it, and then click in the dialog where you want the control to be positioned. When it appears you'll still be able to move it around to set its exact position, and you'll also be able to resize it by dragging handles on the boundaries.

The dialog has a default ID assigned, `IDD_DIALOG1`, but it would be better to have an ID that's a bit more meaningful. You can edit the ID by right-clicking the dialog name in the Resource View pane and selecting Properties from the pop-up; this displays the properties for the dialog. Change the ID to something that relates to the purpose of the dialog, such as `IDD_PENWIDTH_DLG`. You can also display the properties for the dialog itself by right-clicking the dialog in the Dialog Editor pane and selecting Properties. Here you can change the Caption property value that appears in the title bar of the dialog to Set Pen Width.

Adding Controls to a Dialog

To provide a mechanism for entering a pen width, you will add controls to the basic dialog that is displayed initially until it looks like the one shown in Figure 16-1. You place a control on the dialog by dragging it with the mouse from the Toolbox to the dialog. The figure shows a grid that you can

use to position controls. If the grid is not displayed, you can select the appropriate toolbar button to display it; the button toggles the grid on and off.

Alternatively, you can display rules along the side and top of the dialog, which you can use to create guide lines, by clicking the Toggle Guides button. You create a horizontal guide by clicking in the appropriate rule where you want the guide to appear. Controls placed in contact with a guide will be attached to it and move with the guide. You can reposition a guide line by dragging the arrow for it along the rule. You can use one or more guides when positioning a control. You can toggle guides on and off by clicking the Toggle Guides toolbar button.

The dialog shown has six *radio buttons* that provide the pen width options. These are enclosed within a *group box* with the caption Pen Widths. The group box serves to enclose the radio buttons and make them operate as a group, for which only one member of the group can be checked at any given time. Each radio button has an appropriate label to identify the pen width that is set when it is selected. There are also the default OK and Cancel buttons that close the dialog. Each of the controls in the dialog has its own set of properties that you can access and modify, just as for the dialog itself. Let's press on with putting the dialog together.

The next step in the creation of the dialog shown in Figure 16-1 is to add the group box. As I said, the group box serves to associate the radio buttons in a group from an operational standpoint, and to provide a caption and a boundary for the group of buttons. Where you need more than one set of radio buttons, a means of grouping them is essential if they are to work properly. You can select the button corresponding to the group box from the common controls palette by clicking it; then click the approximate position in the dialog where you want to place the center of the group box. This places a group box of default size onto the dialog. You can then drag the borders of the group box to enlarge it to accommodate the six radio buttons that you add. To set the caption for the group box, type the caption you want while the group box is selected (in this case, type **Pen Widths**).

The last step is to add the radio buttons. Select the radio button control by clicking it, and then clicking the position in the dialog where you want to place a radio button within the group box. Do the same for all six radio buttons.

You can select each button by clicking it; then type in the caption to change it. You can also drag the border of the button to set its size, if necessary. To display the Properties window for a control, select it by right-clicking it; then select Properties from the pop-up. You can change the ID for each radio button in the Properties window for the control, in order to make the ID correspond better to its purpose:

`IDC_PENWIDTH0` for the one-pixel-width pen, `IDC_PENWIDTH1` for the 0.01-inch-width pen, `IDC_PENWIDTH2` for the 0.02-inch-pen, and so on.

You can position individual controls by dragging them around with the mouse. You can select a group of controls by selecting successive controls with the Shift key pressed, or by dragging the cursor with the left button pressed to create an enclosing rectangle for a group. To align a group of controls, or to space them evenly horizontally or vertically, select the appropriate button from the




FIGURE 16-1

Dialog Editor toolbar. If the Dialog Editor toolbar is not visible, you can show it by right-clicking in the toolbar area and selecting it from the list of toolbars that is displayed. You can also align controls in the dialog by selecting from the Format menu.

Testing the Dialog

The dialog resource is now complete. You can test it by selecting the toolbar button that appears at the left end of the Dialog Editor toolbar or by pressing Ctrl+T. This displays the dialog with the basic operations of the controls available, so you can try clicking on the radio buttons. When you have a group of radio buttons, only one can be selected at a time. As you select one, any other that was selected is reset. Click either the OK or Cancel button, or even the close icon in the title bar of the dialog, to end the test. After you save the dialog resource, you're ready to add code to support it.

PROGRAMMING FOR A DIALOG

There are two aspects to programming for a dialog: getting it displayed, and handling user interactions with its controls. Before you can display the dialog corresponding to the resource you've just created, you must define a dialog class for it. The Class Wizard helps with this.

Adding a Dialog Class

Right-click in the Resource Editor pane for the dialog and then select Add Class from the pop-up to display the Class Wizard dialog. You'll define a new dialog class derived from the MFC class `CDialogEx`, so select that class name from the "Base class" drop-down list if it's not already selected. You can enter the class name as `CPenDialog`. The Class Wizard dialog should look like Figure 16-2. Click the Finish button to create the new class.




FIGURE 16-2

The `CDialogEx` class is a window class (derived from `CWnd`) that's specifically for displaying and managing dialogs. The dialog resource will be automatically associated with a `CPenDialog` object because the `IDD` class member is initialized with the dialog resource ID:

```
class CPenDialog : public CDlgEx
{
    DECLARE_DYNAMIC(CPenDialog)

public:
    CPenDialog(CWnd* pParent = NULL); // standard constructor
    virtual ~CPenDialog();

// Dialog Data
enum { IDD = IDD_PENWIDTH_DLG };

protected:
    virtual void DoDataExchange(CDataExchange* pDX); // DDX/DDV support

    DECLARE_MESSAGE_MAP()
};
```

The boldfaced statement defines `IDD` as a symbolic name for the dialog ID in the enumeration. Incidentally, using an enumeration is one of two ways to get an initialized data member into a native C++ class definition. The other way is to define a static `const integral` member of the class, so the Class Wizard could have used the following in the class definition:

```
static const int IDD = IDD_PENWIDTH_DLG;
```

If you try putting an initial value for any regular non-static data member declaration in a class, it won't compile.

Having your own dialog class derived from `CDlgEx` means that you get all the functionality that that class provides. You can customize the dialog class by adding data members and functions to suit your particular needs. You'll often handle messages from controls within the dialog class, although you can also choose to handle them in a view or a document class.

Modal and Modeless Dialogs

There are two types of dialogs, *modal* and *modeless*, and they work in completely different ways. While a modal dialog is displayed, all operations in the other windows in the application are suspended until the dialog is closed, usually by the user clicking an OK or Cancel button. With a modeless dialog you can move the focus back and forth between the dialog window and other windows in your application just by clicking them, and you can continue to use the dialog at any time until you close it. The Class Wizard is an example of a modal dialog; the Properties window is a modeless dialog.

You can create a modeless dialog by calling the `Create()` member of the `CDlgEx` class in your dialog class constructor. You create a modal dialog by creating an object on the stack from your dialog class and calling its `DoModal()` function. You will be using only modal dialogs in Sketcher.

Displaying a Dialog

Where you put the code to display a dialog in your program depends on the application. In Sketcher it will be convenient to add a menu item that results in the pen width dialog being displayed. You can put this item in the IDR_SKETCHTYPE menu bar. The pen width and the drawing color are both associated with a pen, so you can rename the Color menu item as Pen. You do this by clicking the Color menu item in the Resource Editor pane to open its Properties window and changing the Caption property value to &Pen.

When you add the Width menu item to the Pen menu, it would be a good idea to separate it from the colors in the menu. Add a separator after the last color menu item by right-clicking the empty menu item and selecting Insert Separator. You can then enter the new Width... item as the next menu item. The Width... menu item ends with an ellipsis (three periods) to indicate that it displays a dialog; this is a standard Windows convention. Click the menu item to display its properties as in Figure 16-3.

The default ID, ID_PEN_WIDTH, is fine, so you don't need to change that. You can add a status bar prompt for the menu item, and because you'll add a toolbar button, you can include text for the tooltip as well. Remember, you just put the tooltip text after the status bar prompt text, separated from it by \n. Here, the value for the Prompt property is "Change pen width\nShow pen width options."

You need to add toolbar buttons corresponding to the Width... menu item to the toolbar resource. To add the toolbar button, double-click the IDR_MAINFRAME toolbar resource in Resource View. You can add a toolbar button to represent a pen width. The one shown in Figure 16-4 tries to represent a pen drawing a line.




FIGURE 16-3




FIGURE 16-4

To associate the new button with the menu item that you just added, open the Properties box for the button and specify its ID as ID_PEN_WIDTH, the same as that for the menu item.

Displaying the Dialog

The code to display the dialog goes in the handler for the Pen \leftrightarrow Width menu item. So, in which class should you implement this handler? The `CSketcherView` class is a candidate for dealing with pen widths, but following the logic for dealing with element color and type, it would be sensible to have the pen width selection in the document, so the handler should go in the `CSketcherDoc` class.

Right-click the Width... menu item in the Resource Editor pane for the `IDR_SketchTYPE` menu and select Add Event Handler from the pop-up. You can then create a function for the `COMMAND` message handler corresponding to `ID_PEN_WIDTH` in the `CSketcherDoc` class. Now edit this handler and enter the following code:

```
// Handler for the pen width menu item
void CSketcherDoc::OnPenWidth()
{
    CPenDialog aDlg;                      // Create a local dialog object
    aDlg.DoModal();                        // Display the dialog as modal
}
```

There are just two statements at the moment. The first creates a dialog object that is automatically associated with your dialog resource. The second displays the dialog by calling the `DoModal()` function for the `aDlg` object.

Because the handler creates a `CPenDialog` object, you must add an `#include` directive for `PenDialog.h` to the beginning of `SketcherDoc.cpp`. After you've done that, you can build Sketcher and try out the dialog. It should appear when you click the pen-width toolbar button. Of course, if the dialog is to do anything, you still have to add the code to support the operation of the controls; to close the dialog, you can use either of the buttons or the close icon in the title bar.

Code to Close the Dialog

The OK and Cancel buttons (and the close icon on the title bar) already close the dialog. The handlers to deal with the `BN_CLICKED` event handlers for the OK and Cancel button controls have been implemented for you. However, it's useful to know how the action of closing the dialog is implemented, in case you want to do more before the dialog is closed, or if you are working with a modeless dialog.

The `CDialog` base class for `CDialogEx` defines the `OnOK()` method that is called when you click the default OK button; this has `IDOK` as its ID. This function closes the dialog and causes the `DoModal()` method to return the ID of the default OK button, `IDOK`. The `OnCancel()` function is called when you click the default Cancel button in the dialog; this closes the dialog and `DoModal()` returns the button ID, which is `IDCANCEL`. You can override either or both of these functions in your dialog class to do what you want. You need to make sure that you call the corresponding base class function at the end of your function implementation. You'll probably remember by now that you can add an override to a class by clicking the Overrides button in the Properties window for the class. For example, you could implement an override for the `OnOK()` function as follows:

```

void CPenDialog::OnOK()
{
    // Your code for data validation or other actions...

    CDialogEx::OnOK();                                // Close the dialog

}

```

In a complicated dialog, you might want to verify that the options selected or the data that has been entered is valid. You could put code here to check the state of the dialog and fix up the data, or even to leave the dialog open if there are problems.

Calling the base class `OnOK()` function closes the dialog and causes `DoModal()` to return `IDOK`. Thus, you can use the value returned from `DoModal()` to detect when the dialog was closed via the OK button.

As I said, you can override the `OnCancel()` function in a similar way if you need to do extra cleanup operations before the dialog closes. Be sure to call the base class function at the end of your function implementation.

When you are using a modeless dialog you must implement the `OnOK()` and `OnCancel()` function overrides so that they call the inherited `DestroyWindow()` function to terminate the dialog. In this case you must not call the base class `OnOK()` or `OnCancel()` functions because they do not destroy the dialog window, but merely render it invisible.

SUPPORTING THE DIALOG CONTROLS

For the pen dialog you'll store the selected pen width in a data member, `m_PenWidth`, of the `CPenDialog` class. You can either add the data member by right-clicking the `CPenDialog` class name and selecting from the context menu, or you can add it directly to the class definition as follows:

```

class CPenDialog : public CDialogEx
{
// Construction
public:
    CPenDialog(CWnd* pParent = NULL);      // standard constructor

// Dialog Data
enum { IDD = IDD_PENWIDTH_DLG };

int m_PenWidth;                                // Record the current pen width

// Plus the rest of the class definition.....

};

```

NOTE If you use the context menu for the class to add `m_PenWidth`, be sure to add a comment to the member variable definition. This is a good habit to get into, even when the member name looks self-explanatory.

You'll use the `m_PenWidth` data member to set the radio button corresponding to the current pen width in the document as checked. You'll also arrange for the pen width that is selected in the dialog to be stored in this member, so that you can retrieve it when the dialog closes. At this point you can initialize `m_PenWidth` to 0 in the `CPenDialog` class constructor:

```
CPenDialog::CPenDialog(CWnd* pParent /*=NULL*/)
    : CDialogEx(CPenDialog::IDD, pParent), m_PenWidth(0)
{
}
```

Initializing Dialog Controls

You can initialize the radio buttons by overriding the `OnInitDialog()` function that is inherited from the `CDialog` base class. This is called in response to a `WM_INITDIALOG` message, which is sent during the execution of `DoModal()` just before the dialog is displayed. You can add the function to the `CPenDialog` class by selecting `OnInitDialog` in the list of overrides in the Properties window for the class. The implementation for the new version of `OnInitDialog()` is:

```
BOOL CPenDialog::OnInitDialog()
{
    CDialogEx::OnInitDialog();

    // Check the radio button corresponding to the pen width value
    switch(m_PenWidth)
    {
        case 1:
            CheckDlgButton(IDC_PENWIDTH1, 1);
            break;
        case 2:
            CheckDlgButton(IDC_PENWIDTH2, 1);
            break;
        case 3:
            CheckDlgButton(IDC_PENWIDTH3, 1);
            break;
        case 4:
            CheckDlgButton(IDC_PENWIDTH4, 1);
            break;
        case 5:
            CheckDlgButton(IDC_PENWIDTH5, 1);
            break;
        default:
            CheckDlgButton(IDC_PENWIDTH0, 1);
    }
    return TRUE; // return TRUE unless you set the focus to a control
                 // EXCEPTION: OCX Property Pages should return FALSE
}
```

You should leave the call to the base class function there because it does some essential setup for the dialog. The `switch` statement checks one of the radio buttons, depending on the value set in the

`m_PenWidth` data member. This implies that you must arrange to set `m_PenWidth` to a suitable value before you execute `DoModal()` because the `DoModal()` function causes the `WM_INITDIALOG` message to be sent, resulting in your version of `OnInitDialog()` being called.

The `CheckDlgButton()` function is inherited indirectly from `CWnd`. The first argument identifies the button, and the second argument of type `UINT` sets its check status. If the second argument is 1, it checks the button corresponding to the ID you specify in the first argument. If it's 0, the button is unchecked. This function works with checkboxes and radio buttons.

Handling Radio Button Messages

After the dialog is displayed, every time you click a radio button a message is generated and sent to the application. You can add handlers to the `CPenDialog` class to deal with these messages. Return to the dialog resource that you created, right-click each of the radio buttons in turn, and select Add Event Handler from the menu to create a handler for the `BN_CLICKED` message. Figure 16-5 shows the event handler dialog window for the button that has `IDC_PENWIDTH0` as its ID. Note that I have edited the name of the handler, as the default name was a little cumbersome.




FIGURE 16-5

The implementations of the BN_CLICKED event handlers for all of these radio buttons are similar because each just sets the pen width in the dialog object. As an example, the handler for IDC_PENWIDTH0 is as follows:

```
void CPenDialog::OnPenwidth0()
{
    m_PenWidth = 0;
}
```

You need to add the code for all six handlers to the CPenDialog class implementation, setting m_PenWidth to 1 in OnPenwidth1(), to 2 in OnPenwidth2(), and so on.

COMPLETING DIALOG OPERATIONS

You must now modify the OnPenWidth() handler in CSketcherDoc to make the dialog effective. Add the following code to the function:

```
// Handler for the pen width menu item
void CSketcherDoc::OnPenWidth()
{
    CPenDialog aDlg;                      // Create a local dialog object

    // Set pen width in the dialog to that in the document
    aDlg.m_PenWidth = m_PenWidth;

    if(aDlg.DoModal() == IDOK)           // Display the dialog as modal
        m_PenWidth = aDlg.m_PenWidth;     // When closed with OK, get the pen width
}
```

The m_PenWidth member of the aDlg object is set to the pen width stored in the m_PenWidth member of the document; you still have to add this member to CSketcherDoc. The DoModal() function call now occurs in the if statement condition, which is true if the DoModal() function returns IDOK. In this case you retrieve the pen width stored in the aDlg object and store it in the m_PenWidth member of the document. If the dialog is closed by the Cancel button, the keyboard escape key, or the close icon, IDOK won't be returned by DoModal() and the value of m_PenWidth in the document object will not be changed.

Note that even though the dialog is closed when DoModal() returns a value, the aDlg object still exists, so you can call its member functions. The aDlg object is destroyed on return from OnPenWidth().

All that remains to do to support variable pen widths in your application is to update the affected classes: CSketcherDoc, CElement, and the four element classes derived from CElement.

Adding Pen Widths to the Document

You need to add the m_PenWidth member to the document class, and the GetPenWidth() function to allow external access to the value stored. You should add the following bolded statements to the CSketcherDoc class definition:

```

class CSketcherDoc : public CDocument
{
// the rest as before...

// Operations
public:
// the rest as before...
    int GetPenWidth() const { return m_PenWidth; } // Get current pen width

// the rest as before...

protected:
// the rest as before...
    int m_PenWidth;                                // Current pen width

// the rest as before...
};

```

Because it's trivial, you can define the `GetPenWidth()` function in the definition of the class and gain the benefit of it being implicitly inline. You still need to add initialization for `m_PenWidth` to the constructor for `CSketcherDoc`, so modify the constructor in `SketcherDoc.cpp` to initialize `m_PenWidth` to 0.

Adding Pen Widths to the Elements

You have a little more work in the element classes. You already have a member `m_PenWidth` in `CElement` to store the pen width and the constructor has a parameter for a pen width. You must extend each of the derived class constructors to accept a pen width argument and set the member accordingly. The members that create or modify the enclosing rectangle for an element must be altered to deal with a pen width of 0.

Each of the constructors for `CLine`, `CRectangle`, `CCircle`, and `CCurve` must be modified to accept a pen width argument. In the `CLine` class, the constructor declaration becomes:

```
CLine(const CPoint& start, const CPoint& end, COLORREF aColor, int penWidth);
```

And the constructor implementation should be modified to this:

```

CLine::CLine(
    const CPoint& start, const CPoint& end,
    COLORREF color, int penWidth):
    CElement(start, color, penWidth), m_EndPoint(end)
{
    // Define the enclosing rectangle
    m_EnclosingRect = CRect(start, end);
    m_EnclosingRect.NormalizeRect();
    int width(penWidth == 0 ? 1 : penWidth); // Inflate rect by at least 1
    m_EnclosingRect.InflateRect(width, width);
}

```

The enclosing rectangle is now produced by inflating the defining rectangle by at least 1.

The CRectangle constructor implementation is:

```
CRectangle:: CRectangle (const CPoint& start, const CPoint& end,
                      COLORREF color, int penWidth):
                      CELEMENT(start, color, penWidth)
{
    // Normalize the rectangle defining points
    m_StartPoint = CPoint((std::min)(start.x, end.x),
                          (std::min)(start.y, end.y));
    m_BottomRight = CPoint((std::max)(start.x, end.x),
                           (std::max)(start.y, end.y));

    // Ensure width and height between the points is at least 2
    if((m_BottomRight.x - m_StartPoint.x) < 2)
        m_BottomRight.x = m_StartPoint.x + 2;
    if((m_BottomRight.y - m_StartPoint.y) < 2)
        m_BottomRight.y = m_StartPoint.y + 2;

    // Define the enclosing rectangle
    m_EnclosingRect = CRect(m_StartPoint, m_BottomRight);
    int width(penWidth == 0 ? 1 : penWidth); // Inflate rect by at least 1
    m_EnclosingRect.InflateRect(width, width);
}
```

Don't forget to add the pen width parameter to the constructor declaration in the class definition here and in the other element classes.

The CCircle constructor definition becomes:

```
CCircle::CCircle(const CPoint& start, const CPoint& end,
                  COLORREF color, int penWidth):
                  CELEMENT(start, color, penWidth)
{
    // Code as before...

    // Define the enclosing rectangle
    m_EnclosingRect = CRect(m_StartPoint.x, m_StartPoint.y,
                           m_BottomRight.x, m_BottomRight.y);
    int width(penWidth == 0 ? 1 : penWidth); // Inflate rect by at least 1
    m_EnclosingRect.InflateRect(width, width);
}
```

You must modify the constructor and the AddSegment() member of the CCurve class. Here's the revised constructor definition:

```
CCurve::CCurve(const CPoint& first, const CPoint& second,
                COLORREF color, int penWidth):
                CELEMENT(first, color, penWidth)
{
    // Store the second point in the vector
    m_Points.push_back(second);
    m_EnclosingRect = CRect(
        (std::min)(first.x, second.x),
```

```

        (std::min)(first.y, second.y),
        (std::max)(first.x, second.x),
        (std::max)(first.y, second.y));
    int width(penWidth == 0 ? 1 : penWidth);           // Inflate rect by at least 1
    m_EnclosingRect.InflateRect(width, width);
}

```

The AddSegment() member implementation should be changed to:

```

void CCurve::AddSegment(const CPoint& point)
{
    m_Points.push_back(point);                      // Add the point to the end

    // Modify the enclosing rectangle for the new point
    int width(m_PenWidth == 0 ? 1 : m_PenWidth); // Deflate rect by at least 1

    m_EnclosingRect.DeflateRect(width, width);
    m_EnclosingRect = CRect((std::min)(point.x, m_EnclosingRect.left),
                           (std::min)(point.y, m_EnclosingRect.top),
                           (std::max)(point.x, m_EnclosingRect.right),
                           (std::max)(point.y, m_EnclosingRect.bottom));
    m_EnclosingRect.InflateRect(width, width);
}

```

That's got the element classes covered. Now you must alter the rest of Sketcher to use the new element constructors.

Creating Elements in the View

The last change you need to make is to the CreateElement() member of CSketcherView. Because you have added the pen width as an argument to the constructors for each of the shapes, you must update the calls to the constructors to reflect this. Change the definition of CSketcherView::CreateElement() to the following:

```

CElement* CSketcherView::CreateElement() const
{
    // Get a pointer to the document for this view
    CSketcherDoc* pDoc = GetDocument();
    ASSERT_VALID(pDoc);                                // Verify the pointer is good

    // Get the current element color
    COLORREF color = static_cast<COLORREF>(pDoc->GetElementColor());

    int penWidth(pDoc->GetPenWidth());                // Get current pen width

    // Now select the element using the type stored in the document
    switch(pDoc->GetElementType())
    {
        case ElementType::RECTANGLE:
            return new CRectangle(m_FirstPoint, m_SecondPoint,
                                  color, penWidth);
    }
}

```

```

case ElementType::CIRCLE:
    return new CCircle(m_FirstPoint, m_SecondPoint,
                       color, penWidth);
case ElementType::CURVE:
    return new CCurve(m_FirstPoint, m_SecondPoint,
                      color, penWidth);
case ElementType::LINE:
    return new CLine(m_FirstPoint, m_SecondPoint,
                    color, penWidth);
default:           // Something's gone wrong
    AfxMessageBox(_T("Bad Element code"), MB_OK);
    AfxAbort();
    return nullptr;
}
}

```

Each constructor call now passes the pen width as an argument. This is retrieved from the document with the `GetPenWidth()` function that you added to the document class.

Exercising the Dialog

You can now build and run the latest version of Sketcher to see how the pen dialog works out. Selecting the Pen \leftrightarrow Width menu option or the associated toolbar button displays the dialog so that you can select the pen width. The screen shown in Figure 16-6 is typical of what you might see when the Sketcher program is executing.




FIGURE 16-6

Note that the dialog is a completely separate window. You can drag it around to position it where you want. You can even drag it outside the Sketcher application window.

USING A SPIN BUTTON CONTROL

Now you can look at how the spin button can help in Sketcher. The spin button is particularly useful when you want to constrain an input within a given integer range. It's normally used in association with another control, called a *buddy control*, that displays the value that the spin button modifies. The associated control is usually an edit control, but it doesn't have to be.

It would be nice to be able to draw at different viewing scales in Sketcher. If you had a way to change the scale, you could scale up whenever you wanted to fill in the fine detail in your masterpiece, and scale down again when working across the whole vista. You could apply the spin control to managing scaling in a document view. A drawing scale would be a view-specific property, and you would want the element drawing functions to take the current scale of a view into account. Altering the existing code to deal with view-scaling requires rather more work than setting up the control, so first look at how you create a spin button and make it work.

Adding a Scale Menu Item and Toolbar Button

The first step is to provide a means of displaying the scale dialog. Go to Resource View and open the `IDR_SketchTYPE` menu. You are going to add a Scale menu item to the end of the View menu. Enter the caption for the unused menu item in the View menu as `Scale... . . .`. This item will bring up the scale dialog, so you end the caption with an ellipsis to indicate this. The default ID is `ID_VIEW_SCALE`. You can add a separator before the new menu item by right-clicking it and selecting Insert Separator. The menu should now look as shown in Figure 16-7. Add a suitable Prompt property value for the menu item.




FIGURE 16-7

You can also add a toolbar button for this menu item with a bitmap image to represent scaling. Make sure that the ID for the button is also set to `ID_VIEW_SCALE`.

Creating the Spin Button

You've got the menu item; you need a dialog to go with it. In Resource View, add a new dialog by right-clicking the Dialog folder and selecting Insert Dialog. Change the ID for the resource to `IDD_SCALE_DLG` and the Caption property for the dialog to Set Drawing Scale.

Click the spin control in the Toolbox, and then click on the position in the dialog where you want it to be placed. Next, right-click the spin control to display its properties. Change its ID to something more meaningful than the default, such as `IDC_SPIN_SCALE`. Now take a look at the properties for the spin button. They are shown in Figure 16-8.

The Arrow Keys property is already set to `True`, enabling you to operate the spin button by using arrow keys on the keyboard. You should also set to `True` the value for both the `Set Buddy Integer` property that specifies the buddy control value as an integer, and `Auto Buddy` that provides for automatic selection of the buddy control. The effect of the latter is that the control selected as the buddy is automatically the previous control defined in the dialog. At the moment this is the Cancel button, which is not exactly ideal, but you'll see how to change this in a moment. The `Alignment` property determines how the spin button is displayed in relation to its buddy. You should set this to `Right Align` so that the spin button is attached to the right edge of its buddy control.

Next, add an edit control at the left side of the spin button by selecting the edit control from the Toolbox pane and clicking in the dialog where you want it positioned. Change the ID for the edit control to `IDC_SCALE`. You can change its `Align Text` property value to `Center`.

To make the contents of the edit control quite clear, you could add a static control just to the left of the edit control in the dialog and enter `View Scale:` as the caption. You can select all three controls by clicking them while holding down the Shift key. Pressing the F9 function key aligns the controls tidily, or you can use the Format menu.

The Controls' Tab Sequence

Controls in a dialog have what is called a *tab sequence*. This is the sequence in which the focus shifts from one control to the next when you press the Tab key, and it is determined initially by the sequence in which you add controls to the dialog. You can see the tab sequence for the current dialog by selecting Format \Rightarrow Tab Order from the main menu, or by pressing `Ctrl+D`. Figure 16-9 shows the tab order required for the spin control to work with its buddy control.




FIGURE 16-8




FIGURE 16-9

If the tab order you see is different, you have to change it. You really want the edit control to precede the spin button in the tab sequence, so you need to select the controls by clicking them in the order in which you want them to be numbered: OK button; Cancel button; edit control; spin button; and finally the static control. So, the tab order will be as in Figure 16-9. Now the edit control is selected as the buddy to the spin button.

Generating the Scale Dialog Class

After saving the resource file, you can right-click the dialog in the Resource Editor pane and select Add Class. You'll then be able to define the new class associated with the dialog resource that you have created. You should name the class `CSScaleDialog` and leave the base class as the default, `CDialogEx`. Clicking the Finish button adds the class to the Sketcher project.

You need a variable in the dialog class to store the value returned from the edit control, so right-click the `CSScaleDialog` class name in Class View and select Add \leftrightarrow Add Variable. The new data member is a special kind, called a *control variable*, so first check the “Control variable” box in the Add Member Variable Wizard dialog. A control variable is a variable that is to be associated with a control in the dialog. Select `IDC_SCALE` as the ID from the Control ID drop-down list and Value from the Category list box. Enter the variable name as `m_Scale`. You'll be storing an integer scale value, so select `int` as the variable type. The Add Member Variable Wizard displays edit boxes in which you can enter maximum and minimum values for the variable `m_Scale`. For our application, a minimum of 1 and a maximum of 8 would be good values. Note that this constraint applies only to the edit box with the ID `IDC_SCALE`; the spin control is independent of it.

Figure 16-10 shows how the window for the Add Member Variable Wizard should look when you are done.




FIGURE 16-10

When you click the Finish button, the wizard takes care of entering the code necessary to support your new control variable.

You will also need to access the spin control in the dialog, and you can use the Add Member Variable Wizard to create that, too. Right-click `CScaleDialog` in Class View once again, select Add variable..., and click the Control variable checkbox in the dialog. Leave the Category selection as Control and select `IDC_SPIN_SCALE` as the control ID: this corresponds to the spin control. The type will be automatically selected as `CSpinButtonCtrl`. You can now enter the variable name as `m_Spin`, select protected for the Access value and add a suitable comment. When you click the Finish button, the new variable will be added to the `CScaleDialog` class.

The class definition you'll end up with after the wizard has added the new members is as follows:

```
class CScaleDialog : public CDlgEx
{
    DECLARE_DYNAMIC(CScaleDialog)

public:
    CScaleDialog(CWnd* pParent = NULL);           // standard constructor
    virtual ~CScaleDialog();

// Dialog Data
enum { IDD = IDD_SCALE_DLG };

protected:
    virtual void DoDataExchange(CDataExchange* pDX); // DDX/DDV support

    DECLARE_MESSAGE_MAP()
public:
    int m_Scale;                                // Stores the current view scale
protected:
    CSpinButtonCtrl m_Spin;                      // Spin control for view scale
};
```

The interesting bits of the class definition are bolded. The class is associated with the dialog resource through the `enum` statement, initializing `IDD` with the ID of the resource. It contains the variable `m_Scale`, which is a `public` member of the class so you can set and retrieve its value in a `CScaleDialog` object directly. There's also some special code in the implementation of the class to deal with the new `m_Scale` member. The `m_Spin` variable references the `CSpinButtonCtrl` object so you can call functions for the spin control.

Dialog Data Exchange and Validation

A virtual function called `DoDataExchange()` has been included in the class by the Class Wizard. If you look in the `ScaleDialog.cpp` file, you'll find that the implementation looks like this:

```
void CScaleDialog::DoDataExchange(CDataExchange* pDX)
{
    CDlgEx::DoDataExchange(pDX);
    DDX_Text(pDX, IDC_SCALE, m_Scale);
    DDX_MinMaxInt(pDX, m_Scale, 1, 8);
    DDX_Control(pDX, IDC_SPIN_SCALE, m_Spin);
}
```

This function is called by the framework to carry out the exchange of data between variables in a dialog and the dialog's controls. This mechanism is called *dialog data exchange*, usually abbreviated to *DDX*. This is a powerful mechanism that can provide automatic transfer of information between a dialog and its controls in most circumstances, thus saving you the effort of programming to get the data yourself, as you did with the radio buttons in the pen width dialog.

DDX handles data transfers between the edit control and the variable `m_Scale` in the `CScaleDialog` class. The variable `pDX` that is passed to the `DoDataExchange()` function controls the direction in which data is transferred. After the base class `DoDataExchange()` function is called, the `DDX_Text()` function is called. The latter moves data between the `m_Scale` variable and the edit control.

The call to the `DDV_MinMaxInt()` function verifies that the value transferred is within the limits specified. This mechanism is called *dialog data validation*, or *DDV*. The `DoDataExchange()` function is called automatically before the dialog is displayed to pass the value stored in `m_Scale` to the edit control. When the dialog is closed with the OK button, it is automatically called again to pass the value in the control back to the variable `m_Scale` in the dialog object. All this is taken care of for you. You need only to ensure that the right value is stored in `m_Scale` before the dialog is displayed, and arrange to collect the result when the dialog closes.

Initializing the Dialog

You'll use an override of the inherited `OnInitDialog()` function to initialize the dialog, just as you did for the pen width dialog. This time you'll use it to set up the spin control. You'll initialize the `m_Scale` member a little later when you create the dialog in the message handler for the `Scale` menu item, because it should be set to the value of the scale that is stored in the view. For now, add an override for the `OnInitDialog()` function to the `CScaleDialog` class, using the class properties pane as you did for the previous dialog, and add code to initialize the spin control:

```
BOOL CScaleDialog::OnInitDialog()
{
    CDialogEx::OnInitDialog();

    m_Spin.SetRange(1, 8);                                // Set the spin control range

    return TRUE;   // return TRUE unless you set the focus to a control
                  // EXCEPTION: OCX Property Pages should return FALSE
}
```

There is only one line of code to add. This sets the upper and lower limits for the spin button object by calling its `SetRange()` member. Although you have set the range limits for the edit control, this doesn't affect the spin control directly. If you don't limit the values in the spin control here, you allow the spin control to insert values outside the limits in the edit control, and there will be an error message from the edit control. You can demonstrate this by commenting out the statement that calls `SetRange()` here and trying out Sketcher without it.

If you want to set the buddy control using code, rather than by setting the value of Auto buddy in the spin button's properties to True, the `CSpinButtonCtrl` class has a function member to do this. You would add the following statement following the `OnInitDialog()` call:

```
m_Spin.SetBuddy(GetDlgItem(IDC_SCALE));
```

NOTE You can access controls in a dialog programmatically. The `GetDlgItem()` function is inherited from `CWnd` via `CDialog` and `CDialogEx`, and you can use this member to retrieve the address of any control identified by the ID you pass as the argument. Thus, calling `GetDlgItem()` with `IDC_SPIN_SCALE` as the argument would return the address of the spin control. As you saw earlier, a control is just a specialized window, so the pointer returned is of type `CWnd*`. You have to cast it to the type appropriate to the particular control if you want to call member functions. The type would be `CSpinButtonCtrl*` in this case.

Displaying the Spin Button

The dialog is to be displayed when the Scale menu item or its associated toolbar button is selected. Add a `COMMAND` event handler to `CSketcherView` corresponding to the `ID_VIEW_SCALE` event through the Properties window for the class. You can then add code as follows:

```
void CSketcherView::OnViewScale()
{
    CScaleDialog aDlg;                      // Create a dialog object
    aDlg.m_Scale = m_Scale;                  // Pass the view scale to the dialog
    if(aDlg.DoModal() == IDOK)
    {
        m_Scale = aDlg.m_Scale;              // Get the new scale
        InvalidateRect(nullptr);           // Invalidate the whole window
    }
}
```

You create the dialog as a modal dialog, just as you did with the pen width dialog. Before the dialog is displayed by the `DoModal()` function call, you store the scale value from the `m_Scale` member of `CSketcherView` in the dialog member with the same name; this ensures that the control displays the current scale value when the dialog is displayed. If the dialog is closed with the OK button, you store the new scale from the `m_Scale` member of the dialog object in the view member with the same name. Because you have changed the view scale, you need to get the view redrawn with the new scale value applied. The call to `InvalidateRect()` does this. Don't forget to add an `#include` directive for `ScaleDialog.h` to `SketcherView.cpp`.

Of course, you must not forget to add the `m_Scale` data member to the definition of `CSketcherView`, so add the following line at the end of the other `protected` data members in the class definition:

```
int m_Scale;                                // Current view scale
```

You should also modify the `CSketcherView` constructor to initialize `m_Scale` to 1. This results in a view always starting out with a scale of 1 to 1. That's all you need to get the scale dialog and its spin control operational. You can build and run Sketcher to give it a trial spin before you add the code to use a view scale factor in the drawing process.

USING THE SCALE FACTOR

Scaling with Windows usually involves using one of the scalable mapping modes, `MM_ISOTROPIC` or `MM_ANISOTROPIC`. By using one of these mapping modes you can get Windows to do most of the work. Unfortunately, it's not as simple as just changing the mapping mode, because neither is supported by `CScrollView`. If you can get around that, however, you're home and dry. You'll use `MM_ANISOTROPIC` for reasons that you'll see in a moment, so let's first understand what's involved in using this mapping mode.

Scalable Mapping Modes

There are two mapping modes that allow the mapping between logical coordinates and device coordinates to be altered, and these are the `MM_ISOTROPIC` and `MM_ANISOTROPIC` modes. The `MM_ISOTROPIC` mode forces the scaling factor for both the x- and y-axes to be the same, which has the advantage that your circles will always be circles. The disadvantage is that you can't map a document to fit into a rectangle of a different aspect ratio. The `MM_ANISOTROPIC` mode, on the other hand, permits scaling of each axis independently. Because it's the more flexible mode of the two, you'll use `MM_ANISOTROPIC` for scaling operations in Sketcher.

Just to remind you:

- *Logical coordinates* (also referred to as page coordinates) are determined by the mapping mode. For example, the `MM_LOENGLISH` mapping mode has logical coordinates in units of 0.01 inches, with the origin in the upper-left corner of the client area, and the positive y-axis direction running from bottom to top. These are used by the device context drawing functions.
- *Device coordinates* (also referred to as *client coordinates* in a window) are measured in pixels in the case of a window, with the origin at the upper-left corner of the client area, and with the positive y-axis direction from top to bottom. These are used outside a device context — for example, for defining the position of the cursor in mouse message handlers.
- *Screen coordinates* are measured in pixels and have the origin at the upper-left corner of the screen, with the positive y-axis direction from top to bottom. These are used for getting or setting the cursor position.

The way in which logical coordinates are transformed to device coordinates in the `MM_ISOTROPIC` and `MM_ANISOTROPIC` mapping modes is dependent on the following parameters that you can set:

PARAMETER	DESCRIPTION
Window Origin	The logical coordinates of the upper-left corner of the window. You set this by calling <code>CDC::SetWindowOrg()</code> . For example, calling <code>SetWindowOrg(50, 50)</code> sets the window origin at the point (50,50).
Window Extent	The size of the window specified in logical coordinates. You set this by calling <code>CDC::SetWindowExt()</code> . For example, calling <code>SetWindowExt(250, 350)</code> sets the window extent 250 in the x-direction and 350 in the y-direction.
Viewport Origin	The coordinates of the upper-left corner of the window in device coordinates (pixels). You set this by calling <code>CDC::SetViewportOrg()</code> . For example, calling <code>SetViewportOrg(10, 10)</code> sets the viewport origin at the point (10,10).
Viewport Extent	The size of the viewport in device coordinates (pixels). You set this by calling <code>CDC::SetViewportExt()</code> . For example, calling <code>SetViewportExt(150, 150)</code> sets the viewport extent to 150 in both the x-direction and y-direction.

The *viewport* referred to here has no physical significance by itself; it only has meaning in relation to the window extent. The viewport extent together with the window extent determines how coordinates are transformed from logical coordinates to device coordinates. To put it another way, the `SetWindowExt()` and `SetViewportExt()` functions define corresponding rectangles that determine the transformation between logical coordinates and device coordinates. When you call `SetWindowExt()`, you are defining a rectangle in logical coordinates that corresponds to the rectangle in device coordinates that you define when you call `SetViewportExt()`.

The formulae used by Windows to convert from logical coordinates to device coordinates are:

$$x_{Device} = (x_{Logical} - x_{WindowOrigin}) \times \frac{x_{ViewportExtent}}{x_{WindowExtent}} + x_{ViewportOrigin}$$

$$y_{Device} = (y_{Logical} - y_{WindowOrigin}) \times \frac{y_{ViewportExtent}}{y_{WindowExtent}} + y_{ViewportOrigin}$$

With coordinate systems other than those provided by the `MM_ISOTROPIC` and `MM_ANISOTROPIC` mapping modes, the window extent and the viewport extent are fixed by the mapping mode and can't be changed. Calling `SetWindowExt()` or `SetViewportExt()` in the `CDC` object to change them has no effect, although you can still move the position of (0,0) in your logical reference frame by calling `SetWindowOrg()` or `SetViewportOrg()`. However, with the `MM_ISOTROPIC` or `MM_ANISOTROPIC` mapping modes, for a given document size that is expressed by the window extent in logical coordinate units, you can adjust the scale at which elements are displayed by setting the viewport extent appropriately. By setting the window and viewport extents, you can get the scaling done automatically.

Setting the Document Size

You need to define the size of the document in logical units in the document object. You can add a protected data member, `m_DocSize`, to the `CSketcherDoc` class definition to store the size of the document:

```
CSize m_DocSize; // Document size
```

You will want to access this data member from the view class, so add a public function to the `CSketcherDoc` class definition as follows:

```
CSize GetDocSize() const { return m_DocSize; } // Retrieve the document size
```

You must initialize the `m_DocSize` member in the constructor for the document so modify the implementation of `CSketcherDoc()` to:

```
CSketcherDoc::CSketcherDoc() :
    m_Element(ElementType::LINE), m_Color(ElementColor::BLACK),
    m_PenWidth(0),
    m_DocSize(CSize(3000,3000))
{
    // TODO: add one-time construction code here
}
```

You'll be using notional `MM_LOENGLISH` coordinates, so a logical unit is 0.01 inches, and the value for the document size gives you an area of 30 inches square to draw on.

Setting the Mapping Mode

You can set the mapping mode to `MM_ANISOTROPIC` in an override of the inherited `OnPrepareDC()` function in the `CSketcherView` class. This function is always called for any `WM_PAINT` message that is sent to the view and it allows you to set up the device context to your liking before the `OnDraw()` member is called. You have to do a little more than just set the mapping mode to get view-scaling working. You must figure out what you should set the viewport extent to, so that the sketch will be drawn at the scale that is set in the view.

You'll need to create the function override for `OnPrepareDC()` in `CSketcherView` before you can add the code. Open the Properties window for the `CSketcherView` class and click the

Overrides button. Add the override by selecting `OnPrepareDC` from the list and clicking <Add> `OnPrepareDC` in the adjacent column. You can now type the code directly into the Editor pane. The implementation of `OnPrepareDC()` is:

```
void CSketcherView::OnPrepareDC(CDC* pDC, CPrintInfo* pInfo)
{
    CScrollView::OnPrepareDC(pDC, pInfo);
    CSketcherDoc* pDoc = GetDocument();
    pDC->SetMapMode(MM_ANISOTROPIC);           // Set the map mode
    CSize DocSize = pDoc->GetDocSize();          // Get the document size

    pDC->SetWindowExt(DocSize);                  // Now set the window extent

    // Get the number of pixels per inch in x and y
    int xLogPixels = pDC->GetDeviceCaps(LOGPIXELSX);
    int yLogPixels = pDC->GetDeviceCaps(LOGPIXELSY);

    // Calculate the viewport extent in x and y for the current scale
    int xExtent = (DocSize.cx*m_Scale*xLogPixels)/100;
    int yExtent = (DocSize.cy*m_Scale*yLogPixels)/100;

    pDC->SetViewportExt(xExtent,yExtent); // Set viewport extent
}
```

The implementation of the override of `OnPrepareDC()` is unusual here in that you have left in the call to `CScrollView::OnPrepareDC()` and added the modifications after it, rather than where the comment in the default code suggests. If the class was derived from `CView`, you would replace the call to the base class version because it does nothing, but in the case of `CScrollView`, this isn't the case. You need the base class function to set some attributes before you set the mapping mode. Don't make the mistake of calling the base class function after your code — if you do, scaling won't work.

The window extent is set to the document size, which is in logical coordinate units. The `CDC` member function `GetDeviceCaps()` supplies information about the device with which the device context is associated. You can get various kinds of information about the device, depending on the argument you pass to the function. Here the arguments `LOGPIXELSX` and `LOGPIXELSY` cause the function to return the number of pixels per logical inch in the x- and y-directions, respectively. These values are the number of pixels in 100 units (1 inch) in your logical coordinates.

You use these values to calculate the x- and y-values for the viewport extent for the current scale, which you store in the local variables `xExtent` and `yExtent`. The document extent along an axis in logical units, divided by 100, gives the document extent in inches. When you multiply this by the number of logical pixels per inch for the device, you get the number of pixels for the document extent. If you were to use this value as the viewport extent, you would get the elements displayed at a scale of 1 to 1. When the window origin and the viewport origin are both (0,0), the equations for converting between device and logical coordinates are very simple:

$$x_{Device} = x_{Logical} \times \frac{x_{ViewportExtent}}{x_{WindowExtent}}$$

$$y_{Device} = y_{Logical} \times \frac{y_{ViewportExtent}}{y_{WindowExtent}}$$

If you multiply the viewport extent values by the view scale, `m_Scale`, the elements are drawn scaled by a factor of `m_Scale`. This logic is exactly represented by the expressions for the x- and y-viewport extents in your code. The simplified equations, with the scale included, are as follows:

$$x_{Device} = x_{Logical} \times \frac{m_Scale \times x_{ViewportExtent}}{x_{WindowExtent}}$$

$$y_{Device} = y_{Logical} \times \frac{m_Scale \times y_{ViewportExtent}}{y_{WindowExtent}}$$

You should be able to see from this that a given point (x,y) in device coordinates varies in proportion to the scale value. The coordinates at a scale of three are three times the coordinates at a scale of one. Of course, as well as making elements larger, increasing the scale also moves them away from the origin.

Unfortunately, at the moment scrolling won't work with scaling, so you need to see what you can do about that.

Implementing Scrolling with Scaling

`CScrollView` just won't work with the `MM_ANISOTROPIC` mapping mode, so clearly you must use another mapping mode to set up the scrollbars. The easiest way to do this is to use `MM_TEXT`, because in this case the units of logical coordinates are the same as the client coordinates — pixels, in other words. All you need to do, then, is figure out how many pixels are equivalent to the logical document extent for the scale at which you are drawing, which is easier than you might think. You can add a function to `CSketcherView` to take care of the scrollbars and implement it to work out the number of pixels corresponding to the logical document extent. Right-click the `CSketcherView` class name in Class View and add a `public` function, `ResetScrollSizes()`, with a `void` return type and no parameters. Add the code to the implementation, as follows:

```
void CSketcherView::ResetScrollSizes()
{
    CClientDC aDC(this);
    OnPrepareDC(&aDC);                                // Set up the device context
    CSize DocSize = GetDocument()->GetDocSize();      // Get the document size
    aDC.LPtodP(&DocSize);                            // Get the size in pixels
    SetScrollSizes(MM_TEXT, DocSize);                  // Set up the scrollbars
}
```

After creating a local `CClientDC` object for the view, you call `OnPrepareDC()` to set up the `MM_ANISOTROPIC` mapping mode. Because this takes scaling into account, the `LPtoDP()` member of the `aDC` object converts the document size stored in the local variable `DocSize` to the correct number

of pixels for the current logical document size and scale. The total document size in pixels defines how large the scrollbars must be in `MM_TEXT` mode — remember, `MM_TEXT` logical coordinates are in pixels. You can then get the `SetScrollSizes()` member of `CScrollView` to set up the scrollbars based on this by specifying `MM_TEXT` as the mapping mode.

It may seem strange that you can change the mapping mode in this way, but it's important to keep in mind that the mapping mode is nothing more than a definition of how logical coordinates are to be converted to device coordinates. Whatever mode (and therefore coordinate conversion algorithm) you've set up applies to all subsequent device context functions until you change it, and you can change it whenever you want. When you set a new mode, subsequent device context function calls just use the conversion algorithm defined by the new mode. You figure out how big the document is in pixels with `MM_ANISOTROPIC` because this is the only way you can get the scaling into the process; you then switch to `MM_TEXT` to set up the scrollbars because you need units for this in pixels for it to work properly. Simple really, when you know how.

Setting Up the Scrollbars

You must set up the scrollbars initially for the view in the `OnInitialUpdate()` member of `CSketcherView`. Change the previous implementation of the function to the following:

```
void CSketcherView::OnInitialUpdate()
{
    ResetScrollSizes();                      // Set up the scrollbars
    CScrollView::OnInitialUpdate();
}
```

All you do is call the `ResetScrollSizes()` function that you just added to the view. This takes care of everything — well, almost. The `CScrollView` object needs an initial extent to be set in order for `OnPrepareDC()` to work properly, so you need to add one statement to the `CSketcherView` constructor:

```
CSketcherView::CSketcherView():
    m_FirstPoint(CPoint(0,0)), m_SecondPoint(CPoint(0,0)),
    m_pTempElement(nullptr), m_pSelected(nullptr),
    m_CursorPos(CPoint(0,0)), m_FirstPos(CPoint(0,0)),
    m_MoveMode(false), m_Scale(1)
{
    SetScrollSizes(MM_TEXT, CSize(0,0));      // Set arbitrary scrollers
}
```

The additional statement just calls `SetScrollSizes()` with an arbitrary extent to get the scrollbars initialized before the view is drawn. When the view is drawn for the first time, the `ResetScrollSizes()` function call in `OnInitialUpdate()` sets up the scrollbars properly.

Of course, each time the view scale changes, you need to update the scrollbars before the view is redrawn. You can take care of this in the `OnViewScale()` handler in the `CSketcherView` class:

```
void CSketcherView::OnViewScale()
{
    CScaleDialog aDlg;                      // Create a dialog object
    aDlg.m_Scale = m_Scale;                  // Pass the view scale to the dialog
```

```

if(aDlg.DoModal() == IDOK)

{
    m_Scale = aDlg.m_Scale;           // Get the new scale
    ResetScrollSizes();              // Adjust scrolling to the new scale
    InvalidateRect(nullptr);         // Invalidate the whole window
}
}

```

With the `ResetScrollSizes()` function, taking care of the scrollbars isn't complicated. Everything is covered by the one additional line of code.

Now you can build the project and run the application. You'll see that the scrollbars work just as they should. Note that each view maintains its own scale factor, independently of the other views.

That's all you need in order to scale the view. You can have multiple scrolled views, all at different scales, and what you draw in one view displays at the appropriate scales in the other views.

WORKING WITH STATUS BARS

With each view now being scaled independently, there's a real need to have some indication of what the current scale in a view window is. A convenient way to do this would be to display the scale in the status bar for each view window. A status bar was created by default in the Sketcher main application window, but not in the view windows. Usually, a status bar appears at the bottom of a window, below the horizontal scrollbar, although you can arrange for it to be at the top of the client area. A status bar is divided into segments called *panes*; the status bar in the main application window in Sketcher has four panes. The one on the left contains the text "Ready," and the other three are the areas on the right that are used as indicators to record when Caps Lock, Num Lock, and Scroll Lock are in effect.

It's possible for you to write to the status bar that the Application Wizard supplied by default, but you need access to the `m_wndStatusBar` member of the `CMainFrame` object for the application, as this represents it. It's a protected member of the class, so you must either add a public member function that you can call from outside the class to modify the status bar, or add a member to return a reference to `m_wndStatusBar`.

You may well have several views of a sketch, each with its own view scale, so you really want each view window to display its own scale. A good approach would be to give each child window its own status bar. The `m_wndStatusBar` object in `CMainFrame` is an instance of the `CStatusBar` class. You can use the same class to implement your own status bars in the view windows.

Adding a Status Bar to a Frame


The `CStatusBar` class defines a control bar with multiple panes in which you can display information. The first step to using `CStatusBar` is to add a data member for the status bar to the definition of `CChildFrame`, which is the frame window for a view. Add the following declaration to the public section of the class:

```
CStatusBar m_StatusBar;           // Status bar object
```

NOTE A status bar should be part of the frame, not part of the view. You don't want to scroll a status bar or draw over it. It should just remain anchored to the bottom of the window. If you were to add a status bar to the view, it would appear inside the scrollbars and would be scrolled whenever you scrolled the view. Drawing over the part of the view containing the status bar would cause the bar to be redrawn, leading to an annoying flicker. Having the status bar as part of the frame avoids all these problems.

Creating Status Bar Panes

To create panes in a status bar, you call the `SetIndicators()` function for the status bar object. This function requires two arguments, a `const` array of indicators of type `UINT` and the number of elements in the array. Each element in the array is a resource symbol that will be associated with a pane in the status bar, and each resource symbol must have an entry in the *resource string table* that will define the default text in the pane. The IDs for status panes start with `ID_INDICATOR_` and there are standard resource symbols, such as `ID_INDICATOR_CAPS` and `ID_INDICATOR_NUM`, which are used to identify indicators for the Caps Lock and Num Lock keys, respectively. You can see these in use if you look at the implementation of the `OnCreate()` function in the `CMainFrame` class. The standard symbols appear in the MFC string table resource so you should take a look at that. Double-click the `String Table` resource in Resource View and double-click the String Table entry to display the table. The string table for Sketcher is shown in Figure 16-11 as a floating window.



The screenshot shows a Windows String Table editor window titled "Sketcher - Sketcher.rc - String Table [English (United States)]". The table has three columns: ID, Value, and Caption. The "Caption" column contains the displayed text for each entry. The "Value" column contains the unique integer value assigned to each ID. The "ID" column lists various resource IDs, many of which begin with "ID_INDICATOR_" followed by a symbol name like "CAPS" or "NUM".

ID	Value	Caption
IDR_MAINFRAME	128	Sketcher
IDR_SKETCHTYPE	130	\nSketch\nSketch\nSketch Files (*.ske)\n.ske\nSketch.Document\nSketch.Document
ID_ELEMENT_LINE	32771	Draw lines\nLines
ID_ELEMENT_RECTANGLE	32772	Draw rectangles\nRectangles
ID_ELEMENT_CIRCLE	32773	Draw circles\nCircles
ID_ELEMENT_CURVE	32774	Draw curves\nCurves
ID_COLOR_BLACK	32775	Draw in black\nBlack
ID_COLOR_RED	32776	Draw in red\nRed
ID_COLOR_GREEN	32777	Draw in green\nGreen
ID_COLOR_BLUE	32778	Draw in blue\nBlue
ID_PEN_WIDTH	32794	Change pen width\nShow pen width options.
ID_VIEW_SCALE	32797	Set drawing scale\nDrawing scale
AFX_IDS_APP_TITLE	57344	Sketcher
AFX_IDS_IDLEMESSAGE	57345	Ready
ID_FILE_NEW	57600	Create a new document\nNew
ID_FILE_OPEN	57601	Open an existing document\nOpen
ID_FILE_CLOSE	57602	Close the active document\nClose
ID_FILE_SAVE	57603	Save the active document\nSave

FIGURE 16-11

Figure 16-11 shows string table entries for our menu items. Each entry consists of three parts: the ID, the value for the ID, which is a unique integer value, and the string. If you scroll the string table down, you will find the status pane entries for the application window; the first has the ID `ID_INDICATOR_EXT`. Incidentally, clicking a column-heading in the string table pane will sort the entries in ascending order of that column.

You can create your own entries in the string table for indicator resource symbols. Right-click any entry in the string table and select New String from the menu. Alternatively, just press the Insert key. If you right-click the new entry and select Properties from the menu, you will be able to change its default ID to `ID_INDICATOR_SCALE` and the caption to `View Scale : 1`.

You should initialize the `m_StatusBar` member before the visible view window is displayed. Using the Properties window for the `CChildFrame` class, you can add a message handler to the class that will be called in response to the `WM_CREATE` message that is sent to the application when the window is to be created. Add the following code to the `OnCreate()` handler:

```
int CChildFrame::OnCreate(LPCREATESTRUCT lpCreateStruct)
{
    if(CMDIChildWnd::OnCreate(lpCreateStruct) == -1)
        return -1;

    // Create the status bar
    m_StatusBar.Create(this);
    static UINT indicators[] = {ID_SEPARATOR, ID_INDICATOR_SCALE};
    m_StatusBar.SetIndicators(indicators, _countof(indicators));
    return 0;
}
```

The generated code isn't bolded. There's a call to the base class version of `OnCreate()`, which takes care of creating the definition of the view window. It's important that you don't delete this function call; otherwise, the window is not created.

Calling the `Create()` function for the `CStatusBar` object creates the status bar. You pass the `this` pointer for the current `CChildFrame` object to the `Create()` function, setting up a connection between the status bar and the window that owns it. The indicators that define the panes in the status bar are typically defined as an array of `UINT` elements. Here you define `indicators` as an array that is initialized just with the ID for a separator and the symbol for your status pane. When you want to add more panes to a status bar, you can separate them by including `ID_SEPARATOR` symbols between your symbols in the `indicators` array. You call the `SetIndicators()` function for the status bar object with the address of `indicators` as the first argument and a count of the number of elements in the array as the second argument. Here, this creates a single pane to the right in the status bar.

When the first pane indicator is `ID_SEPARATOR`, the pane is automatically stretched to align subsequent panes to the right in the status bar. You can call `SetPaneStyle()` for a pane referenced by its index in the `indicators` array to set the pane style. The first argument to `SetPaneStyle()` is the pane index and the second a `UINT` value specifying the style or styles to be set. Only one pane can have the `SBPS_STRETCH` style, which stretches the pane to fill the available space in the status bar. Other styles you can set for a pane are as follows:

<code>SBPS_NORMAL</code>	No stretch, borders, or pop-out styles set.
<code>SBPS_POPOUT</code>	Border reversed, so text pops out.
<code>SBPS_NOBORDERS</code>	No 3D borders.
<code>SBPS_DISABLED</code>	No text drawn in the pane.

You just OR the styles together when you want to set more than one style for a pane.

Updating the Status Bar

If you build and run the code now, the status bars appear, but they show only a scale factor of one, no matter what scale factor is actually being used — not very useful. This is because there is no mechanism in place for updating the status bar. You need to add code somewhere to change the text in the status bar pane each time a different scale is chosen. The obvious place to do this is in the CSketcherView class because that's where the current view scale is recorded.

You can update a pane in the status bar by adding an UPDATE_COMMAND_UI handler that is associated with the indicator symbol for the pane. Right-click CSketcherView in Class View, and select Class Wizard from the pop-up. This will display the MFC Class Wizard dialog. As you can see, this enables you to create and edit a whole range of functions in a class and provides an alternative way to access any class member.

If it is not already visible, select the Commands tab in the dialog: this enables you to add command handlers to the class. Select ID_INDICATOR_SCALE in the Object IDs pane; this ID identifies the status bar pane you want to update. Then, select UPDATE_COMMAND_UI in the Messages pane. The dialog should look like Figure 16-12.




FIGURE 16-12

Click the Add Handler button to add the command handler to the class. Another dialog will be displayed that gives you the opportunity to change the handler function name to `OnUpdateScale`, which is a little more concise than the default. You can then click OK to close the dialog, and OK again to close the MFC Class Wizard dialog.

All you need is to complete the definition for the handler that was added, so add the following code to the function in `SketcherView.cpp`:

```
void CSketcherView::OnUpdateScale(CCmdUI *pCmdUI)
{
    pCmdUI->Enable();
    CString scaleStr;
    scaleStr.Format(_T(" View Scale : %d"), m_Scale);
    pCmdUI->SetText(scaleStr);
}
```

The parameter is a pointer to a `CCmdUI` object that encapsulates the status bar pane as a command target. You create a `CString` object and call its `Format()` function to generate the text string to be displayed in the pane. The first argument to `Format()` is a format control string in which you can embed conversion specifiers for subsequent arguments. The format string with the embedded specifiers is the same as for the C function, `printf()`. Each of the subsequent arguments is converted according to the corresponding format specifier in the first argument, so there must be one format specifier in the format string for each argument after the first. Here the `%d` specifier converts the value of `m_Scale` to a decimal string, and this is incorporated into the format string. Other common specifiers you can use are `%f` for floating point values and `%s` for string values. Calling `SetText()` for the `CCmdUI` object sets the string you supply as the argument in the status bar pane. Calling `Enable()` for the `CCmdUI` object causes the pane text to be displayed normally because the `BOOL` parameter has a default value of `TRUE`. An explicit argument of `FALSE` would make the pane text grayed out.

That's all you need for the view status bar. If you build Sketcher again, you should have multiple, scrolled windows, each at different scales, with the scale displayed in the status bar in each view.

THE CString CLASS

You used a `CString` object in the previous section, and there's more to it than you have seen so far. The `CString` class provides a convenient and easy-to-use mechanism for handling strings that you can use just about anywhere a string is required. To be more precise, you can use a `CString` object in place of strings of type `const char*`, or of type `LPCTSTR`, which is a type that comes up in Windows API functions. If you are using the DDX mechanism for strings, then you must use `CString`, otherwise DDX won't work.

The `CString` class provides the overloaded operators shown in the following table.

OPERATOR	USAGE
=	Copies one string to another, as in: <code>str1 = str2;</code> <code>str1 = _T("A normal string");</code>
+	Concatenates two or more strings, as in: <code>str1 = str2 + str3 + _T(" more");</code>
+=	Appends a string to an existing <code>CString</code> object, as in: <code>str1 += str2;</code>
==	Compares two strings for equality, as in: <code>if(str1 == str2) // do something...</code>
<	Tests if one string is less than another.
<=	Tests if one string is less than or equal to another.
>	Tests if one string is greater than another.
>=	Tests if one string is greater than or equal to another.

The variables `str1` and `str2` in the preceding table are `CString` objects.

`CString` objects automatically grow as necessary, such as when you add an additional string to the end of an existing object. For example:

```
CString str = _T("A fool and your money");
str += _T("are soon partners.");
```

The first statement declares and initializes the object `str`. The second statement appends an additional string to `str`, so the length of `str` automatically increases.

USING AN EDIT BOX CONTROL

An edit box control is for managing text entry to an application. You will use an edit box control to add annotations to a sketch in Sketcher. You'll need a new Sketcher element type, `CText`, that encapsulates a text string, and a menu item to set `TEXT` mode for creating elements. Because a text element needs only one reference point, you can create it in the `OnLButtonDown()` handler in the view class. You'll also need a new item in the Element menu to set `TEXT` mode. You'll add this text capability to Sketcher in the following sequence:

1. Create a dialog resource and its associated class with an edit box control for input.
2. Add the new menu item.

3. Add the code to open the dialog for creating a CText element.
4. Add support for creating CText elements.

Creating an Edit Box Resource

Create a new dialog resource in Resource View by right-clicking the Dialog folder and selecting Insert Dialog.

Change the ID for the new dialog to `IDD_TEXT_DLG`, and the Caption property value for the dialog to Enter Text.

To add an edit box, select the Edit Control icon in the Toolbox pane and click the position in the dialog where you want to place it. You can adjust the size of the edit control by dragging its borders, and you can alter its position in the dialog by dragging the whole thing around. You can display the properties for the edit box by right-clicking it and selecting Properties from the pop-up. You could first change its ID to `IDC_EDIT_TEXT`, as shown in Figure 16-13.

Some of the properties for this control are of interest at this point. First, select the `Multiline` property. Setting the value for this as `True` creates a multiline edit box in which the text you enter can span more than one line. This enables you to enter a long line of text that will still remain visible in its entirety in the edit box. The `Align text` property determines how the text is to be positioned in the multiline edit box. The value `Left` is fine here, but you also have the options for `Center` and `Right`.

If you were to change the value for the `Want return` property to `True`, pressing Enter on the keyboard while entering the text in the control would insert a return character into the text string. This enables you to analyze the string if you want to break it into multiple lines for display. You don't want this effect, so leave the property value as `False`. In this state, pressing Enter has the effect of selecting the default control (which is the OK button), which closes the dialog.

If you set the value of the `Auto HScroll` property to `False`, there is an automatic spill to the next line in the edit box when you reach the edge of the control while entering text. However, this is just for visibility in the edit box — it has no effect on the contents of the string. You could also change the value of the `Auto VScroll` property to `True` to allow text to continue beyond the number of lines that are visible in the control. If you set the `Vertical Scroll` property to `True`, the edit control will be supplied with a scrollbar that will allow you to scroll the text.




FIGURE 16-13

When you've finished setting the properties for the edit box, close its Properties window. Make sure that the edit box is first in the tab order by selecting the Format \Rightarrow Tab Order menu item or by pressing Ctrl+D. You can then test the dialog by selecting the Test Dialog menu item or by pressing Ctrl+T. The dialog is shown in Figure 16-14. You can even enter text into the dialog in test mode to see how it works. Clicking the OK or Cancel button closes the dialog.




FIGURE 16-14

Creating the Dialog Class

After saving the dialog resource, you can create a suitable dialog class corresponding to the resource, which you could call `CTextDialog`. To do this, right-click the dialog in the Editor pane and select Add Class. The base class should be `CDialogEx`. Next you can add a control variable to the `CTextDialog` class by right-clicking the class name in Class View and selecting Add \Rightarrow Add Variable. Select `IDC_EDIT_TEXT` as the control ID and `Value` as the category. Call the new variable `m_TextString` and leave its type as `CString`. You can also specify a maximum length for it in the `Max chars` edit box, as shown in Figure 16-15.




FIGURE 16-15

A length of 100 is more than adequate for your needs. The variable that you have added here is automatically updated from the data entered into the control by the DDX mechanism. You can click Finish to create the variable in the `CTextDialog` class, and close the Add Member Variable wizard.

NOTE As I said earlier, the DDX mechanism does not support strings of type `std::string` so you must use type `CString` here.

Adding the Text Menu Item

Adding a new menu item should be easy by now. You just need to open the menu resource with the ID `IDR_SketchTYPE` in Resource View by double-clicking it, and add a new menu item, Text, to the Element menu. The default ID, `ID_ELEMENT_TEXT`, that appears in the Properties window for the item is fine, so you can leave that as it is. You can add a prompt to be displayed on the status bar corresponding to the menu item, and because you'll also want to add an additional toolbar button corresponding to this menu item, you can add a tooltip to the end of the prompt line, using `\n` to separate the prompt and the tooltip.

Don't forget the context menu. You can copy the menu item from `IDR_SketchTYPE`. Right-click the Text menu item and select Copy from the pop-up. Open the menu `IDR_CONTEXT_MENU`, right-click the empty item at the bottom of the no element menu, and select Paste. All you need to do then is drag the item to the appropriate position — above the separator — and save the resource file.

Add the toolbar button to the `IDR_MAINFRAME` toolbar and set its ID to the same as that for the menu item, `ID_ELEMENT_TEXT`. You can drag the new button so that it's positioned at the end of the block defining the other types of elements. When you've saved the resources, you can add an event handler for the new menu item.

You need a new type for `CText` elements so add a `TEXT` enumerator to the `ElementType` enum:

```
enum class ElementType{LINE, RECTANGLE, CIRCLE, CURVE, TEXT};
```

In the Class View pane, right-click `CSketcherDoc` and display its Properties window. Add a `COMMAND` handler for the event corresponding to the `ID_ELEMENT_TEXT` ID and add code to it as follows:

```
void CSketcherDoc::OnElementText()
{
    m_Element = ElementType::TEXT;
}
```

Only one line of code is necessary to set the element type in the document to `ElementType::TEXT`.

You also need to add a function to check the menu item if it is the current mode, so add an UPDATE_COMMAND_UI handler corresponding to the event for the ID_ELEMENT_TEXT ID, and implement the code for it as follows:

```
void CSketcherDoc::OnUpdateElementText (CCmdUI* pCmdUI)
{
    // Set checked if the current element is text
    pCmdUI->SetCheck(m_Element == ElementType::TEXT);
}
```

This operates in the same way as the other Element menu items. Of course, you could also have added both of these handlers through the Class Wizard dialog that you display by selecting Class Wizard from the context menu in Class View.

Don't forget that the context menu needs updating too. Add code to the OnContextMenu() member of CSketcherView to check the Text menu item. The next step is to define the CText class for an element of type TEXT.

Defining a Text Element

You can derive the CText class from the CElement class as follows:

```
#pragma once
#include <memory>
#include "Element.h"

// Class defining a text element
class CText: public CEElement
{
public:
    // Constructor for a text element
    CText(const CPoint& start, const CPoint& end,
          const CString& aString, COLORREF color);

    virtual void Draw(CDC* pDC,
                      std::shared_ptr<CElement> pElement=nullptr) override;
    virtual void Move(const CSize& aSize) override; // Move a text element
    virtual ~CText(void) {}

protected:
    CString m_String;                                // Text to be displayed
    CText(void){}
};
```

I added this manually but I'll leave it to you to decide how you want to do it. This class definition declares the virtual Draw() and Move() functions, as the other element classes do. The data member m_String of type CString stores the text to be displayed.

The CText constructor declaration defines four parameters: the two points defining the rectangle in which the text is to be displayed, the string to be displayed, and the color. The pen width doesn't apply to text, because the appearance is determined by the font.

Implementing the CText Class

You have three functions to implement for the CText class:

- The constructor for a CText object
- The virtual `Draw()` function to display it
- The virtual `Move()` function to support moving a text object by dragging it with the mouse

I added these directly to the `Text.cpp` file.

The CText Constructor

The constructor for a CText object needs to initialize the class and base class data members:

```
// CText constructor
CText::CText(const CPoint& start, const CPoint& end,
             const CString& aString, COLORREF color) :
    CElement(start, color)
{
    m_String = aString; // Store the string

    m_EnclosingRect = CRect(start, end);
    m_EnclosingRect.NormalizeRect();
    m_EnclosingRect.InflateRect(m_PenWidth, m_PenWidth);
}
```

The base class constructor call stores the `start` point and the color and initializes the pen width to 1 by default. You calculate the rectangle that will enclose the string when it is displayed from the `start` and `end` points.

Creating a Text Element

If the element type has been set to `ElementType::TEXT`, a text object should be created at the cursor position whenever you click the left mouse button and enter the text you want to display. You therefore need to display the dialog that permits text to be entered in the `OnLButtonDown()` handler, but only when the element type is `ElementType::TEXT`. Add the following code to this handler in the `CSketcherView` class:

```
void CSketcherView::OnLButtonDown(UINT nFlags, CPoint point)
{
    CClientDC aDC(this); // Create a device context
    OnPrepareDC(&aDC); // Get origin adjusted
    aDC.DPtoLP(&point); // convert point to Logical
    CSketcherDoc* pDoc = GetDocument(); // Get a document pointer

    if(m_MoveMode)
    { // In moving mode, so drop the element
        m_MoveMode = false; // Kill move mode
        auto pElement(m_pSelected); // Store selected address
        m_pSelected.reset(); // De-select the element
    }
}
```

```
pDoc->UpdateAllViews(nullptr, 0, pElement.get()); // Redraw all the views
}
else if(pDoc->GetElementType() == ElementType::TEXT)
{
    CTextDialog aDlg;
    if(aDlg.DoModal() == IDOK)
    { // Exit OK so create a text element
        CSize textExtent = aDC.GetOutputTextExtent(aDlg.m_TextString);
        textExtent.cx *= m_Scale;
        textExtent.cy *= m_Scale;
        std::shared_ptr<CElement> pTextElement =
            std::make_shared<CText>(point, point + textExtent, aDlg.m_TextString,
                                   static_cast<COLORREF>(pDoc->GetElementColor()));

        pDoc->AddElement(pTextElement); // Add the element to the document
        pDoc->UpdateAllViews(nullptr, 0, pTextElement.get()); // Update all views
    }
}
else
{
    m_FirstPoint = point; // Record the cursor position
    SetCapture(); // Capture subsequent mouse messages
}
}
```

The code to be added is bolded. It creates a `CTextDialog` object and then opens the dialog using the `DoModal()` function call. The `m_TextString` member of `aDlg` is automatically set to the string entered in the edit box via the DDX mechanism, so you can use this data member to pass the string entered back to the `CText` constructor if the OK button was used to close the dialog. The color is obtained from the document using the `GetElementColor()` member that you have used previously.

You need to determine the corners of the rectangle that bounds the text in the client area of the view and this is a bit more complicated than with the geometric elements. The size of the rectangle that will enclose a string when you display it depends on the font used in the device context, as well as the number of characters in the string. You need the help of the device context object to figure this out. The `GetOutputTextExtent()` member of the `CCClientDC` object, `aDC`, returns a `CSize` object that defines what the width and height of the string you pass as the argument will be. This is calculated using characters from the current font for the device context. The dimensions are in logical coordinates, which is just what you need. You store the `CSize` object that is returned in `textExtent`.

The drawing scale adds a further complication. The text will be drawn at a given font size that is not affected by the scale. If the current drawing scale is greater than one, you must adjust `textExtent` in the same proportion, otherwise the enclosing rectangle for the text will not be large enough at lower scales. You do this by multiplying the `cx` and `cy` members of `textExtent` by the scale.

The left-top corner of the rectangle enclosing the string will be `point`, which is already in logical coordinates. You get the right-bottom corner by adding the dimensions in `textExtent` to `point`.

The CText object is created using the `make_shared<T>()` function because the list in the document stores `shared_ptr<CElement>` pointers to the elements. You can store a pointer of type `shared_ptr<CText>` in a `shared_ptr<CElement>` variable because CText is derived from CElement. You add the new element to the document by calling the `AddElement()` member of CSketcherDoc, with the pointer to the new text element as an argument. Finally, `UpdateAllViews()` is called with the first argument `nullptr`, which specifies that all views are to be updated. Don't forget that you need `#include` directives for `TextDialog.h` and `Text.h` in `SketcherView.cpp`.

Drawing a CText Object

Drawing text in a device context is different from drawing a geometric figure. The implementation of the `Draw()` function for a CText object is:

```
void CText::Draw(CDC* pDC, std::shared_ptr<CElement> pElement)
{
    // Set the text color and output the text
    pDC->SetTextColor(this == pElement.get() ? SELECT_COLOR : m_Color);
    pDC->SetBkMode(TRANSPARENT);           // Transparent background for text
    pDC->ExtTextOut(m_StartPoint.x, m_StartPoint.y, 0,
                     nullptr, m_String, nullptr);
}
```

You don't need a pen to display text. You have a choice of several functions in the CDC class that output text and in our case the simplest to use is `ExtTextOut()`. With this function you can specify a rectangle in which the text is to be displayed as well as other options that affect character spacing and the way it which the text is displayed in the rectangle. These are the parameters in sequence for one of the two versions of this function:

PARAMETER	DESCRIPTION
<code>int x</code>	Logical x-coordinate of the first character in the string.
<code>int y</code>	Logical y-coordinate of the first character in the string.
<code>UINT options</code>	<p>Either, neither, or both of the flags:</p> <p><code>ETO_CLIPPED</code>: string is clipped to <code>pRect</code>.</p> <p><code>ETO_OPAQUE</code>: current background color fills <code>pRect</code>.</p>
<code>LPCRECT pRect</code>	Rectangle that determines the dimensions of the rectangle in which the text is displayed (It's location is specified by x and y). This can be <code>nullptr</code> .
<code>const CString& str</code>	The string to be displayed.
<code>LPINT widths</code>	Pointer to an array of integers specifying distances between characters in the string. <code>nullptr</code> will select default spacing.

We have ignored all these options and just supplied the coordinates of where the text is to be displayed and the `CString` object that contains the text.

Before calling `ExtTextOut()`, you specify the text color using the `SetTextColor()` function member of the `CDC` object. You also call `SetBkMode()` to ensure the background to the string is transparent. An `OPAQUE` argument value would make the background opaque.

Moving a CText Object

The `Move()` function for a `CText` object is simple:

```
void CText::Move(const CSize& size)
{
    m_EnclosingRect += size;           // Move the rectangle
    m_StartPoint += size;             // Move the reference point
}
```

All you need to do is alter the enclosing rectangle by the distance specified in the `size` parameter and adjust the `m_StartPoint` member by the same amount.

Because the `ExtTextOut()` function for a `CDC` object doesn't use a pen, it isn't affected by setting the drawing mode of the device context. This means that the raster operations (ROP) method that you use to move geometric elements leaves trails behind when applied to text. You used the `SetROP2()` function to specify the way in which the pen would logically combine with the background. By choosing `R2_NOTXORPEN` as the drawing mode, you could cause a previously drawn element to disappear by redrawing it. Fonts aren't drawn with a pen, so it won't work properly with the text elements.

To fix the trails problem when moving a text element, you can treat it as a special case in the `MoveElement()` function in `CSketcherView`. Providing an alternative move mechanism for text elements requires that you can discover when the `m_pSelected` pointer contains the address of a `CText` object. The `typeid` operator that you met back in Chapter 2 can help with this.

By comparing the expression `typeid(*m_pSelected.get())` with `typeid(CText)`, you can determine whether or not `m_pSelected` points to a `CText` object. Here's how you can update `MoveElement()` to eliminate the trails when moving text:

```
void CSketcherView::MoveElement(CClientDC& aDC, const CPoint& point)
{
    CSize distance = point - m_CursorPos;           // Get move distance
    m_CursorPos = point;                            // Set current point as 1st for next time

    // If there is an element selected, move it
    if(m_pSelected)
    {
        CSketcherDoc* pDoc = GetDocument();           // Get the document pointer
        pDoc->UpdateAllViews(this, 0, m_pSelected.get());

        if (typeid(*m_pSelected.get()) == typeid(CText))
        { // The element is text so use this method...
            CRect oldRect = m_pSelected->GetEnclosingRect(); // Get old bound rect
```

```

    aDC.LPtToDP(oldRect);                                // Convert to client coords
    m_pSelected->Move(distance);                      // Move the element
    InvalidateRect(&oldRect);

    UpdateWindow();                                     // Redraw immediately
    m_pSelected->Draw(&aDC,m_pSelected);             // Draw highlighted
}

else
{ // ...it is not text so use the ROP method
    aDC.SetROP2(R2_NOTXORPEN);
    m_pSelected->Draw(&aDC, m_pSelected);           // Draw the element to erase it
    m_pSelected->Move(distance);                     // Now move the element
    m_pSelected->Draw(&aDC, m_pSelected);           // Draw the moved element
}

pDoc->UpdateAllViews(this, 0 , m_pSelected.get());
}

```

You use the `typeid` operator to check whether or not `m_pSelected` points to a `CText` element. If `m_pSelected` does not point to a `CText` element, the code proceeds as before. When `m_pSelected` does point to a `CText` element, you obtain the bounding rectangle in the current view for the position of the element before moving it to its new position. You convert the rectangle to client coordinates because that's what `InvalidateRect()` expects as an argument. You call `InvalidateRect()` and `UpdateWindow()` after the move to erase the element from its old position. Finally, you call `Draw()` for the text element to draw the element in its new position. The other views are taken care of by the calls to `UpdateAllViews()` for the document object, as before. You should now be able to produce annotated sketches using multiple scaled and scrolled views, such as the ones shown in Figure 16-16.




FIGURE 16-16

You can see that the text does not scale along with the shapes. You could scale the text by adjusting the font size in the device context based on the scale. This would involve creating a font of the appropriate point size based on the scale, and doing this whenever a `CText` element was drawn or redrawn. However, it's probably better to leave text elements at the font size with which they were created.

SUMMARY

In this chapter you've seen several different dialogs using a variety of controls. Although you haven't created dialogs involving several different controls at once, the mechanism for handling them is the same as what you have seen, because each control can operate independently of the others. Dialogs are a fundamental tool for managing user input in an application. They provide a way for you to manage the input of multiple related items of data. You can easily ensure that an application only receives valid data. Judicious choice of the controls in a dialog can force the user to choose from a specific set of options. You can also check the data after it has been entered in a dialog and prompt the user when it is not valid.

EXERCISES

1. Implement the scale dialog in Sketcher using radio buttons.
2. Implement the pen width dialog in Sketcher using a list box.
3. Implement the pen width dialog in Sketcher as a combo box with the drop list type selected as the `Type` property. (The drop list type allows the user to select from a drop-down list but not to enter alternative entries in the list.)

► WHAT YOU LEARNED IN THIS CHAPTER

TOPIC	CONCEPT
Status bars	The <code>CStatusBar</code> class encapsulates a status bar that can have multiple panes. You add a status bar to a window by adding it to the frame.
Dialogs	A dialog involves two components: a resource defining the dialog window and its controls, and a class that is used to display and manage the dialog. Dialog classes are typically derived from <code>CDialogEx</code> .
Extracting data from a dialog	Information can be extracted from controls in a dialog by means of the DDX mechanism. The data can also be validated with the DDV mechanism. To use DDX/DDV you need only to select the Control Variable option for the Add Member Variable wizard to define a variable in the dialog class that is associated with a control. The associated control is identified by its ID.
Modal dialogs	A modal dialog retains the focus in the application until the dialog is closed. As long as a modal dialog is displayed, all other windows in an application are inactive.
Modeless dialogs	A modeless dialog allows the focus to switch from the dialog to other windows in the application and back again. A modeless dialog can remain displayed as long as the application is executing, if required.
Common controls	Common controls are a set of standard Windows controls supported by MFC and the resource editing capabilities of Visual Studio.
Adding controls	Although controls are usually associated with a dialog, you can add controls to any window.
Displaying a dialog	You can display a dialog as modal by calling its <code>DoModal()</code> function.
Edit boxes	An edit box control allows entry of one or more lines of text. The text can be optionally scrolled vertically and/or horizontally.



Storing and Printing Documents

WHAT YOU WILL LEARN IN THIS CHAPTER:

- How serialization works
- How to make objects of a class serializable
- The role of a `CArchive` object in serialization
- How to implement serialization in your own classes
- How to implement serialization in the Sketcher application
- How printing works with MFC
- Which view class functions support printing
- What a `CPrintInfo` object contains and how it's used in the printing process
- How to implement multipage printing in Sketcher

WROX.COM CODE DOWNLOADS FOR THIS CHAPTER

You can find the wrox.com code downloads for this chapter on the Download Code tab at www.wrox.com/remtitle.cgi?isbn=9781118368084. The code is in the Chapter 17 download and individually named according to the names throughout the chapter.

UNDERSTANDING SERIALIZATION

A document in an MFC-based program is not a simple entity — it's a class object that can be very complicated. It typically contains a variety of objects, each of which may contain other objects, each of which may contain still more objects and that structure may continue for a number of levels.

You want to be able to save a document in a file, but writing a class object to a file represents something of a problem because it isn't the same as a basic data item like an integer or a character string. A basic data item consists of a known number of bytes, so to write it to a file only requires that the appropriate number of bytes be written. Conversely, if you know a value of type `int` was written to a file, to get it back, you just read the appropriate number of bytes.

Writing objects to a file is different. Even if you write all the data members of an object to a file, that's not enough to be able to get the original object back. Class objects contain function members as well as data members, and all the members, both data and functions, have access specifiers; therefore, to record an object in an external file, the information that is written to the file must contain complete specifications of all the class structures involved. The read process must also be clever enough to synthesize the original objects completely from the data in the file. MFC supports a mechanism called *serialization* to help you to implement input and output of your class objects with a minimum of time and effort.

The basic idea behind serialization is that any class that's serializable should take care of storing and retrieving itself. This means that for your classes to be serializable — in the case of the Sketcher application, this will include the `CElement` class and the element classes you have derived from it — they must be able to write themselves to a file. This implies that for a class to be serializable, all the class types that are used to declare data members of the class must be serializable too.

SERIALIZING A DOCUMENT

This all sounds rather tricky, but the basic capability for serializing your document was built into the application by the Application Wizard right at the outset. The handlers for the File \leftrightarrow Save, File \leftrightarrow Save As, and File \leftrightarrow Open menu items all assume that you want serialization implemented for your document, and already contain the code to support it. Take a look at the parts of the definition and implementation of `CSketcherDoc` that relate to creating a document using serialization.

Serialization in the Document Class Definition

The code in the definition of `CSketcherDoc` that enables serialization of a document object is shown shaded in the following fragment:

```
class CSketcherDoc : public CDocument
{
protected: // create from serialization only
    CSketcherDoc();
    DECLARE_DYNCREATE(CSketcherDoc)

    // Rest of the class...

    // Overrides
    public:
        virtual BOOL OnNewDocument();
        virtual void Serialize(CArchive& ar);

    // Rest of the class...
};
```

There are three things here that relate to serializing a document object:

- 1.** The `DECLARE_DYNCREATE()` macro.
- 2.** The `Serialize()` member function.
- 3.** The default class constructor.

`DECLARE_DYNCREATE()` is a macro that enables objects of the `CSketcherDoc` class to be created dynamically by the application framework during the serialization input process. It's matched by a complementary macro, `IMPLEMENT_DYNCREATE()`, in the class implementation. These macros apply only to classes derived from `CObject`, but as you will see shortly, they aren't the only pair of macros that can be used in this context. For any class that you want to serialize, `CObject` must be a direct or indirect base because it adds the functionality that enables serialization to work. This is why the `CElement` class was derived from `CObject`. Almost all MFC classes are derived from `CObject` and are serializable.

NOTE *The Hierarchy Chart in the Microsoft Foundation Class Reference for Visual C++ shows those classes, that are not derived from CObject. Note that CArcive is in this list.*

The `CSketcherDoc` class definition also includes a declaration for a virtual function `Serialize()`. Every class that's serializable must include this function. It's called to perform both input and output serialization operations on the data members of the class. The object of type `CArchive` that's passed as an argument determines whether the operation that is to occur is input or output. You'll explore this in more detail when considering the implementation of serialization for the document class.

Note that the class explicitly defines a default constructor. This is also essential for serialization to work because the default constructor is used by the framework to synthesize an object when reading it from a file. The synthesized object produced by the no-arg constructor is filled out with the data from the file to set the values of the data members of the object.

Serialization in the Document Class Implementation

There are two bits of the `SketcherDoc.cpp` file that relate to serialization. The first is the `IMPLEMENT_DYNCREATE()` macro that complements the `DECLARE_DYNCREATE()` macro:

```
// SketcherDoc.cpp : implementation of the CSketcherDoc class
//

#include "stdafx.h"
// SHARED_HANDLERS can be defined in an ATL project implementing preview,
// thumbnail and search filter handlers and allows sharing of document code
// with that project.
#ifndef SHARED_HANDLERS
#include "Sketcher.h"
#endif
```

```
#include "SketcherDoc.h"
#include "PenDialog.h"

#include <propkey.h>

#ifndef _DEBUG
#define new DEBUG_NEW
#endif

// CSketcherDoc

IMPLEMENT_DYNCREATE(CSketcherDoc, CDocument)

// Message maps and the rest of the file...
```

This macro defines the base class for `CSketcherDoc` as `CDocument`. This is required for the proper dynamic creation of a `CSketcherDoc` object, including members that are inherited.

The Serialize() Function

The class implementation includes the definition of the `Serialize()` function:

```
void CSketcherDoc::Serialize(CArchive& ar)
{
    if (ar.IsStoring())
    {
        // TODO: add storing code here
    }
    else
    {
        // TODO: add loading code here
    }
}
```

This function serializes the data members of the class. The argument to the function, `ar`, is a reference to an object of the `CArchive` class. The `IsStoring()` member of this class object returns `TRUE` if the operation is to store data members in a file, and `FALSE` if the operation is to read back data members from a previously stored document.

Because the Application Wizard has no knowledge of what data your document contains, the process of writing and reading this information is up to you, as indicated by the comments. To understand how you do this, let's look a little more closely at the `CArchive` class.

The CArchive Class

The `CArchive` class is the engine that drives the serialization mechanism. It provides an MFC-based equivalent of the stream operations in C++ that you used for reading from the keyboard and writing to the screen in the console program examples. A `CArchive` object provides a mechanism for streaming your objects to a file, or recovering them as an input stream, automatically reconstituting the objects of your class in the process.

A `CArchive` object has a `CFile` object associated with it that provides disk input/output capability for binary files, and provides the connection to the physical file. Within the serialization process, the `CFile` object takes care of all the specifics of the file input and output operations, and the `CArchive` object deals with the logic of structuring the object data to be written, or reconstructing the objects from the information read. You need to worry about the details of the associated `CFile` object only if you are constructing your own `CArchive` object. With the document in Sketcher, the framework has already taken care of it and passes the `CArchive` object that it constructs, `ar`, to the `Serialize()` function in `CSketcherDoc`. You'll be able to use the same object in each of the `Serialize()` functions you add to the element classes when you implement serialization for them.

The `CArchive` class overloads the extraction and insertion operators (`>>` and `<<`) for input and output operations, respectively, on objects of classes derived from `CObject`, plus a range of basic data types. These overloaded operators work with the object types and primitive types shown in the following table.

TYPE	DEFINITION
<code>bool</code>	Boolean value, <code>true</code> or <code>false</code>
<code>float</code>	Standard single precision floating point
<code>double</code>	Standard double precision floating point
<code>BYTE</code>	8-bit unsigned integer
<code>char</code>	8-bit character
<code>wchar_t</code>	16-bit character
<code>short</code>	16-bit signed integer
<code>int</code>	32-bit signed integer
<code>LONG</code> and <code>long</code>	32-bit signed integer
<code>LONGLONG</code>	64-bit signed integer
<code>ULONGLONG</code>	64-bit unsigned integer
<code>WORD</code>	16-bit unsigned integer
<code>DWORD</code> and <code>unsigned int</code>	32-bit unsigned integer
<code>CString</code>	A <code>CString</code> object defining a string
<code>SIZE</code> and <code>CSize</code>	An object defining a size as a <code>cx, cy</code> pair
<code>POINT</code> and <code>CPoint</code>	An object defining a point as an <code>x, y</code> pair
<code>RECT</code> and <code>CRect</code>	An object defining a rectangle by its upper-left and lower-right corners
<code>CObject*</code>	Pointer to <code>CObject</code>

For basic data types in your objects, you use the insertion and extraction operators to serialize the data. To read or write an object of a serializable class that you have derived from `CObject`, you can either call the `Serialize()` function for the object, or use the extraction or insertion operator. Whichever way you choose must be used consistently for both input and output, so you should not output an object using the insertion operator and then read it back using the `Serialize()` function, or vice versa.

Where you don't know the type of an object when you read it, as in the case of the pointers in the list of elements in our document, for example, you must *only* use the `Serialize()` function. This brings the virtual function mechanism into play, so the appropriate `Serialize()` function for the type of object pointed to is determined at run time.

A `CArchive` object is constructed either for storing objects or for retrieving objects. The `CArchive` function `IsStoring()` returns `TRUE` if the object is for output, and `FALSE` if the object is for input. You saw this used in the `Serialize()` member of `CSketcherDoc`.

There are many other member functions of the `CArchive` class that are concerned with the detailed mechanics of the serialization process, but you don't usually need to know about them to use serialization.

Functionality of CObject-Based Classes

There are three levels of functionality available in your classes when they're derived from the MFC class `CObject`. The level you get in your class is determined by which of three different macros you use in the definition of your class:

MACRO	FUNCTIONALITY
<code>DECLARE_DYNAMIC()</code>	Support for runtime class information
<code>DECLARE_DYNCREATE()</code>	Support for runtime class information and dynamic object creation
<code>DECLARE_SERIAL()</code>	Support for runtime class information, dynamic object creation, and serialization of objects

Each of these macros requires that a complementary macro, named with the prefix `IMPLEMENT_` instead of `DECLARE_`, be placed in the file containing the class implementation. As the table indicates, the macros provide progressively more functionality, so I'll concentrate on the third macro, `DECLARE_SERIAL()`, because it provides everything that the preceding macros do and more. This is the macro you should use to enable serialization in your own classes. It requires that the macro `IMPLEMENT_SERIAL()` be added to the file containing the class implementation.

You may be wondering why the document class uses `DECLARE_DYNCREATE()` and not `DECLARE_SERIAL()`. The `DECLARE_DYNCREATE()` macro provides the capability for dynamic creation of the objects of the class in which it appears. The `DECLARE_SERIAL()` macro provides the capability for serialization of the class, plus the dynamic creation of objects of the class, so it incorporates the effects of `DECLARE_DYNCREATE()`. Your document class doesn't need serialization because the

framework only has to synthesize the document object and then restore the values of its data members; however, the data members of a document *do* need to be serializable, because this is the process used to store and retrieve them.

The Macros that Add Serialization to a Class

With the `DECLARE_SERIAL()` macro in the definition of your `CObject`-based class, you get access to the serialization support provided by `CObject`. This includes special new and delete operators that incorporate memory leak detection in debug mode. You don't need to do anything to use this because it works automatically. The macro requires the class name to be specified as an argument, so for serialization of the `CElement` class, you would add the following line to the class definition:

```
DECLARE_SERIAL(CElement)
```

NOTE *There's no semicolon required here because this is a macro, not a C++ statement.*

It doesn't matter where you put the macro within the class definition, but if you always put it as the first line, you'll always be able to verify that it's there, even when the class definition involves a lot of lines of code.

The `IMPLEMENT_SERIAL()` macro that you place in the implementation file for the class requires three arguments. The first argument is the class name, the second is the name of the direct base class, and the third argument is an unsigned 32-bit integer identifying a *schema number*, or version number, for your program. This schema number allows the serialization process to guard against problems that can arise if you write objects with one version of a program and read them with another, in which the classes may be different.

For example, you could add the following line to the source file containing the implementation of the `CElement` class:


```
IMPLEMENT_SERIAL(CElement, CObject, 1001)
```

If you subsequently modify the class definition, you would change the schema number to something different, such as 1002. If the program attempts to read data that was written with a different schema number from that in the currently active program, an exception is thrown. The best place for this macro is as the first line following the `#include` directives and any initial comments in the `.cpp` file.

Where `CObject` is an indirect base class, as in the case of the `CLine` class for example, each class in the hierarchy must have the serialization macros added for serialization to work in the top-level class. For serialization in `CLine` to work, the macros must also be added to `CElement`.

How Serialization Works

The overall process of serializing a document is illustrated in a simplified form in Figure 17-1.

**FIGURE 17-1**

The `Serialize()` function in the document object calls the `Serialize()` function (or uses an overloaded insertion operator) for each of its data members. Where a member is a class object, the `Serialize()` function for that object serializes each of its data members in turn until eventually, basic data types are written to the file. Because most classes in MFC ultimately derive from `CObject`, they contain serialization support, so you can almost always serialize MFC class objects.

The data that you'll deal with in the `Serialize()` member functions of your classes and the application document object are just the data members. The structure of the classes that are involved and any other data necessary to reconstitute your original objects are automatically taken care of by the `CArchive` object.

Where you derive multiple levels of classes from `CObject`, the `Serialize()` function in a class must call the `Serialize()` member of its direct base class to ensure that the direct base class data members are serialized. Note that serialization doesn't support multiple inheritance, so there can only be one base class for each class defined in a hierarchy.

How to Implement Serialization for a Class

From the previous discussion, I can summarize the steps that you need to take to add serialization to a class:

1. Make sure that the class is derived directly or indirectly from `CObject`.
2. Add the `DECLARE_SERIAL()` macro to the class definition (and to the direct base class if the direct base is not `CObject` or another standard MFC class).
3. Declare the `Serialize()` function as a member function of your class.
4. Add the `IMPLEMENT_SERIAL()` macro to the file containing the class implementation.
5. Implement the `Serialize()` function for your class.

Now let's look at how you can implement serialization for documents in Sketcher.

APPLYING SERIALIZATION

To implement serialization in Sketcher, you must implement the `Serialize()` function in `CSketcherDoc` so that it deals with all of the data members of that class. You need to add serialization to each of the classes that define objects that may be included in a document. Before you start adding serialization to your classes, you should make some small changes to the program to record when a user changes a sketch document. This isn't essential, but it is highly desirable because it enables the program to guard against the document being closed without saving changes.

Recording Document Changes

There's already a mechanism for noting when a document changes. It uses an inherited member of the `CSketcherDoc` class, `SetModifiedFlag()`. By calling this function consistently whenever the document changes, you can record the fact that the document has been altered in a data member of the document class object. This causes a prompt to be automatically displayed when you try to exit the application without saving the modified document. The argument to the `SetModifiedFlag()` function is a value of type `BOOL`, and the default value is `TRUE`. When you have occasion to specify that the document was unchanged, you can call this function with the argument `FALSE`.

At present, there are four occasions when you alter a sketch in the document object:

- When you call the `AddElement()` member of `CSketcherDoc` to add a new element.
- When you call the `DeleteElement()` member of `CSketcherDoc` to delete an element.
- When you call `SendToBack()` for the document object.
- When you move an element.

You can handle these situations easily. All you need to do is add a call to `SetModifiedFlag()` to each of the functions involved in these operations. The definition of `AddElement()` appears in the `CSketcherDoc` class definition. You can extend this to:

```

void AddElement(std::shared_ptr<CElement>& pElement) // Add an element to the list
{
    m_Sketch.push_back(pElement);
    UpdateAllViews(nullptr, 0, pElement.get());           // Tell all the views
    SetModifiedFlag();                                    // Set the modified flag
}

```

The definition of `DeleteElement()` is also in the `CSketcherDoc` definition. You should add one line to it, as follows:

```

void DeleteElement(std::shared_ptr<CElement>& pElement)
{
    m_Sketch.remove(pElement);
    UpdateAllViews(nullptr, 0, pElement.get());           // Tell all the views
    SetModifiedFlag();                                    // Set the modified flag
}

```

The `SendToBack()` function needs to have the same line added:

```

void SendToBack(std::shared_ptr<CElement>& pElement)
{
    if(pElement)
    {
        m_Sketch.remove(pElement);                         // Remove the element from the list
        m_Sketch.push_back(pElement);                     // Put a copy at the end of the list
        SetModifiedFlag();                                // Set the modified flag
    }
}

```

Moving an element occurs in the `MoveElement()` member of a view object that is called by the handler for the `WM_MOUSEMOVE` message, but you only change the document when the left mouse button is pressed. If there's a right-button click, the element is put back to its original position, so you only need to call the `SetModifiedFlag()` function for the document in the `OnLButtonDown()` function:

```

void CSketcherView::OnLButtonDown(UINT nFlags, CPoint point)
{
    CClientDC aDC(this);                                // Create a device context
    OnPrepareDC(&aDC);                                 // Get origin adjusted
    aDC.DPtoLP(&point);                               // convert point to Logical
    CSketcherDoc* pDoc = GetDocument();                // Get a document pointer

    if(m_MoveMode)
    { // In moving mode, so drop the element
        m_MoveMode = false;                            // Kill move mode
        auto pElement(m_pSelected);                  // Store selected address
        m_pSelected = nullptr;                        // De-select the element
        pDoc->UpdateAllViews(nullptr, 0, pElement.get()); // Redraw all the views
        pDoc->SetModifiedFlag();                      // Set the modified flag
    }
    // Rest of the function as before...
}

```

You call the inherited `GetDocument()` member of the view class to get access to a pointer to the document object and then use this pointer to call the `SetModifiedFlag()` function.

You now have all the places where you change the sketch. The document object also stores the element type, the element color and the pen width, so you need to track when they change too. Here's how you can update `OnColorBlack()` for example:

```
void CSketcherDoc::OnColorBlack()
{
    m_Color = ElementColor::BLACK;           // Set the drawing color to black
    SetModifiedFlag();                      // Set the modified flag
}
```

Add the same statement to each of the handlers for the other colors and the element types. The handler for setting the pen width needs to be updated like this:

```
void CSketcherDoc::OnPenWidth()
{
    CPenDialog aDlg;                     // Create a local dialog object
    aDlg.m_PenWidth = m_PenWidth;        // Set pen width as that in the document

    if(aDlg.DoModal() == IDOK)           // Display the dialog as modal
    {
        m_PenWidth = aDlg.m_PenWidth;   // When closed with OK, get the pen width
        SetModifiedFlag();             // Set the modified flag
    }
}
```

If you build and run Sketcher, and modify a document or add elements to it, you'll now get a prompt to save the document when you exit the program. Of course, the File \leftrightarrow Save menu option doesn't do anything yet except clear the modified flag and save an empty file to disk. You must implement serialization to get the document written to disk, and that's the next step.

Serializing the Document

The first step is to implement the `Serialize()` function for the `CSketcherDoc` class. Within this function, you must add code to serialize the data members of `CSketcherDoc`. The data members that you have declared in the class are as follows:

```
protected:
    ElementType m_Element;                // Current element type
    ElementColor m_Color;                 // Current drawing color
    std::list<std::shared_ptr<CElement>> m_Sketch; // A list containing the sketch
    int m_PenWidth;                      // Current pen width
    CSize m_DocSize;                     // Document size
```

These have to be serialized to allow a `CSketcherDoc` object to be deserialized. You need to insert the statements to store and retrieve these data members in the `Serialize()` member of the class. However, there is a slight problem. The `list< std::shared_ptr<CElement>>` object is not serializable because the template is not derived from `cobject`. In fact, *none* of the STL containers are serializeable, so you always have to take care of serializing STL containers yourself.

All is not lost, however. If you can serialize the objects that the pointers in the container point to, you will be able to reconstruct the container when you read it back.

NOTE *The MFC defines container classes such as CList that are serializable. However, if you used these in Sketcher, you would not learn about how you can make a class serializable.*

You can implement serialization for the document object with the following code:

```
void CSketcherDoc::Serialize(CArchive& ar)
{
    if (ar.IsStoring())
    {
        ar << static_cast<COLORREF>(m_Color)           // Store the current color
            << static_cast<int>(m_Element)             // the element type as an integer
            << m_PenWidth                            // and the current pen width
            << m_DocSize                             // and the current document size

        ar << m_Sketch.size();                      // Store the number of elements in the list

        // Now store the elements from the list
        for(auto& pElement : m_Sketch)

            ar << pElement.get();                  // Store the element pointer
    }
    else
    {
        COLORREF color(0);
        int elementType(0);
        ar >> color                           // Retrieve the current color
            >> elementType                     // the element type as an integer
            >> m_PenWidth                    // and the current pen width
            >> m_DocSize                     // and the current document size

        m_Color = static_cast<ElementColor>(color);
        m_Element = static_cast<ElementType>(elementType);

        // Now retrieve all the elements and store in the list
        size_t elementCount(0);                 // Count of number of elements
        ar >> elementCount;                   // retrieve the element count
        CELEMENT* pElement;
        for(size_t i = 0 ; i < elementCount ; ++i)
        {
            ar >> pElement;
            m_Sketch.push_back(std::shared_ptr<CELEMENT>(pElement));
        }
    }
}
```

For four of the data members, you just use the extraction and insertion operators that are overloaded in the `CArchive` class. This won't work for `m_Color` because the `ElementColor` type is not

serializable. However, you can cast it to type COLORREF, which is serializable because type COLORREF is the same as type long. The `m_Element` member is of type `ElementType`, and the serialization process won't handle this directly either. However, you can cast it to an integer for serialization, and then just deserialize it as an integer before casting the value back to `ElementType`.

For the list of elements, `m_Sketch`, you first store the count of the number of elements in the list because you will need this to be able to read the elements back. You then write the element pointers that are contained in the `shared_ptr` objects from the list to the archive in the `for` loop. Something remarkable happens as a result. The serialization mechanism recognizes that the objects pointed to will be required to reconstruct the document, and will take care of writing those to the archive.

The `else` clause for the `if` deals with reading the document object back from the archive. You use the extraction operator to retrieve the first four members from the archive in the same sequence that they were written. The color and element types are read into the local integer variables, `color` and `elementType`, and then stored in the `m_Color` and `m_Element` members as the correct type.

You read the number of elements recorded in the archive and store it locally in `elementCount`. Finally, you use `elementCount` to control the `for` loop that reads the elements back from the archive and stores them in the list. Note that you don't need to do anything special to take account of the fact that the elements were originally created on the heap. The serialization mechanism takes care of restoring the elements on the heap automatically; all you need to do is pass the pointer for each element to the `shared_ptr<CElement>` constructor.

In case you are wondering where the `list<shared_ptr<CElement>>` object comes from when you are deserializing an object, it will be created by the serialization process using the default constructor for the `CSketcherDoc` class. This is how the basic document object and its uninitialized data members get created. Like magic, isn't it?

That's all you need for serializing the document class data members, but serializing elements from the list causes the `Serialize()` functions for the element classes to be called to store and retrieve the elements themselves, so you also need to implement serialization for those classes.

Serializing the Element Classes

All the element classes are serializable in principle because their base class, `CElement`, is derived from `CObject`. You specified `CObject` as the base for `CElement` solely to get support for serialization. Make sure that the default constructor is defined for each of the element classes. The deserialization process requires that this constructor be defined.

You can add support for serialization to each of the element classes by adding the appropriate macros to the class definitions and implementations, and adding the code to the `Serialize()` function member of each class to serialize its data members. You can start with the base class, `CElement`, where you need to modify the class definition as follows:

```
class CElement: public CObject
{
    #include "Serialize.h"
    DECLARE_SERIAL(CElement)
protected:
    CPoint m_StartPoint;                      // Element position
    int m_PenWidth;                           // Pen width
```

```

COLORREF m_Color;                                // Color of an element
CRect m_EnclosingRect;                          // Rectangle enclosing an element

public:
    virtual ~CElement();
    virtual void Draw(CDC* pDC, std::shared_ptr<CElement> pElement=nullptr) {}
    virtual void Move(const CSize& aSize){}          // Move an element
virtual void Serialize(CArchive& ar) override; // Serialize object

    // Get the element enclosing rectangle
    const CRect GetEnclosingRect() const
    {
        return m_EnclosingRect;
    }

protected:
    // Constructors protected so they cannot be called outside the class
    CElement();
    CElement(const CPoint& start, COLORREF color, int penWidth = 1);

    // Create a pen
    void CreatePen(CPen& aPen, std::shared_ptr<CElement> pElement)
    {
        if(!aPen.CreatePen(PS_SOLID, m_PenWidth,
                           (this == pElement.get()) ? SELECT_COLOR : m_Color))
        {
            // Pen creation failed
            AfxMessageBox(_T("Pen creation failed."), MB_OK);
            AfxAbort();
        }
    }
};

```

You add the `DECLARE_SERIAL()` macro and a declaration for the virtual function `Serialize()`. You already have the default constructor that was created by the Application Wizard. You changed it to `protected` in the class, although it doesn't matter what its access specification is as long as it appears explicitly in the class definition. It can be `public`, `protected`, or `private`, and serialization still works. If you forget to include a default constructor in a class, though, you'll get an error message when the `IMPLEMENT_SERIAL()` macro is compiled.

You should add the `DECLARE_SERIAL()` macro to each of the derived classes `CLine`, `CRectangle`, `CCircle`, `CCurve`, and `CText`, with the relevant class name as the argument. You should also add an override declaration for the `Serialize()` function as a `public` member of each class.

In the file `Element.cpp`, you must add the following macro at the beginning:

~~IMPLEMENT SERIAL(CElement, CObject, VERSION NUMBER)~~

You can define the static constant `VERSION_NUMBER` in the `Element.h` file by adding the definition after the other static constant:

```
static const uint VERSION_NUMBER = 1001; // Version number for serialization
```

You can then use the same constant when you add the macro to the .cpp file for each of the other element classes. For instance, for the `CLine` class you should add the line,

```
IMPLEMENT_SERIAL(CLine, CElement, VERSION_NUMBER)
```

and similarly for the other element classes. When you modify any of the classes relating to the document, all you need to do is change the definition of `VERSION_NUMBER` in the `Element.h` file, and the new version number applies in all your `Serialize()` functions.

The `Serialize()` Functions for the Element Classes

You can now implement the `Serialize()` member function for each of the element classes. Start with the `CElement` class and add the following definition to `Element.cpp`:

```
void CElement::Serialize(CArchive& ar)
{
    CObject::Serialize(ar); // Call the base class function

    if (ar.IsStoring())
    { // Writing to the file
        ar << m_StartPoint // Element position
        << m_PenWidth // The pen width
        << m_Color // The element color
        << m_EnclosingRect; // The enclosing rectangle
    }
    else
    { // Reading from the file
        ar >> m_StartPoint // Element position
        >> m_PenWidth // The pen width
        >> m_Color // The element color
        >> m_EnclosingRect; // The enclosing rectangle
    }
}
```

This function is of the same form as the one supplied for you in the `CSketcherDoc` class. All of the data members defined in `CElement` are supported by the overloaded extraction and insertion operators and so everything is done using those operators. Note that you must call the `Serialize()` member for the `CObject` class to ensure that the inherited data members are serialized.

For the `CLine` class, you can code the function as:

```
void CLine::Serialize(CArchive& ar)
{
    CElement::Serialize(ar); // Call the base class function

    if (ar.IsStoring())
    { // Writing to the file
        ar << m_EndPoint; // The end point
    }
    else
    { // Reading from the file
        ar >> m_EndPoint; // The end point
    }
}
```

The data member is supported by the extraction and insertion operators of the `CArchive` object `ar`. You call the `Serialize()` member of the base class `CElement` to serialize its data members, and this calls the `Serialize()` member of `CObject`. You can see how serialization cascades through the class hierarchy.

The `Serialize()` member of the `CRectangle` class is simple:

```
void CRectangle::Serialize(CArchive& ar)
{
    CElement::Serialize(ar);           // Call the base class function
    if (ar.IsStoring())
    { // Writing to the file
        ar << m_BottomRight;          // Bottom-right point for the rectangle
    }
    else
    { // Reading from the file
        ar >> m_BottomRight;
    }
}
```

This calls the direct base class `Serialize()` function and serializes the bottom-right point for the rectangle.

The function implementation for the `CCircle` class is identical to that for the `CRectangle` class:

```
void CCircle::Serialize(CArchive& ar)
{
    CElement::Serialize(ar);           // Call the base class function
    if (ar.IsStoring())
    { // Writing to the file
        ar << m_BottomRight;          // Bottom-right point for the circle
    }
    else
    { // Reading from the file
        ar >> m_BottomRight;
    }
}
```

For the `CCurve` class, you have rather more work to do. The `CCurve` class uses a `vector<CPoint>` container to store the defining points, and because this is not directly serializable, you must take care of it yourself. Having serialized the document, this is not going to be terribly difficult. You can code the `Serialize()` function as follows:

```
void CCurve::Serialize(CArchive& ar)
{
    CElement::Serialize(ar);           // Call the base class function
    // Serialize the vector of points
    if (ar.IsStoring())
    {
        ar << m_Points.size();          // Store the point count
        // Now store the points
        for(size_t i = 0 ; i < m_Points.size() ; ++i)
            ar << m_Points[i];
    }
}
```

```

    else
    {
        size_t nPoints(0);           // Stores number of points
        ar >> nPoints;             // Retrieve the number of points
        // Now retrieve the points
        CPoint point;
        for(size_t i = 0 ; i < nPoints ; ++i)
        {
            ar >> point;
            m_Points.push_back(point);
        }
    }
}

```

You first call the base class `Serialize()` function to deal with serializing the inherited members of the class. The technique for storing the contents of the vector is basically the same as you used for serializing the list for the document. You first write the number of elements in the container to the archive, then the elements themselves. The `CPoint` class is serializable, so it takes care of itself. Reading the points back is equally straightforward. You just store each object read from the archive in the vector, `m_Points`, in the `for` loop. The serialization process uses the no-arg constructor for the `CCurve` class to create the basic class object, so the `vector<CPoint>` member is created within this process.

The last class for which you need to add a `Serialize()` implementation is `CText`:

```

void CText::Serialize(CArchive& ar)
{
    CElement::Serialize(ar);           // Call the base class function

    if (ar.IsStoring())
    {
        ar << m_String;             // Store the text string
    }
    else
    {
        ar >> m_String;             // Retrieve the text string
    }
}

```

After calling the base class function, you serialize the `m_String` data member using the insertion and extraction operators for `ar`. Although `CString` is not derived from `CObject`, the `CString` class is still fully supported by `CArchive` with these overloaded operators.

EXERCISING SERIALIZATION

That's all you have to do to implement the storing and retrieving of documents in the Sketcher program! The Save and Open menu options in the file menu are now fully operational without adding any more code. If you build and run Sketcher after incorporating the changes I've discussed in this chapter, you'll be able to save and restore files and be automatically prompted to save a modified document when you try to close it or exit from the program without saving, as shown in Figure 17-2.




FIGURE 17-2

The prompting works because of the `SetModifiedFlag()` calls that you added everywhere you updated the document. Assuming you have not saved the file previously, if you click the Yes button in the screen shown in Figure 17-2, you'll see the File \Rightarrow Save As dialog shown in Figure 17-3.




FIGURE 17-3

This is the standard Windows dialog for this menu item. The dialog is fully working, supported by code supplied by the framework. The filename for the document has been generated from that assigned when the document was first opened, and the file extension is automatically defined as .ske. The application now has full support for file operations on documents. Easy, wasn't it?

PRINTING A DOCUMENT

It's time to take a look at how you can print a sketch. You already have a basic printing capability implemented in Sketcher, courtesy of the Application Wizard and the framework. The File ⇔ Print, File ⇔ Print Setup, and File ⇔ Print Preview menu items all work. Selecting the File ⇔ Print Preview menu item displays a window showing the current Sketcher document on a page, as shown in Figure 17-4.




FIGURE 17-4

Whatever is in the current document is placed on a single sheet of paper at the current view scale. If the document's extent is beyond the boundary of the paper, the section of the document off the paper won't be printed. If you select the Print button, this page is sent to your printer.

As a basic capability that you get for free, it's quite impressive, but it's not adequate for our purposes. A typical document in Sketcher may well extend beyond a page, so you would either want to scale the document to fit, or, perhaps more conveniently, print the whole document over as many pages as necessary. You can add your own print processing code to extend the capability of the facilities provided by the framework, but to implement this you first need to understand how printing has been implemented in MFC.

The Printing Process

Printing a document is controlled by the current view. The process is inevitably a bit messy because printing is inherently a messy business, and it potentially involves you in overriding quite a number of inherited functions in your view class. Figure 17-5 shows the logic of the process and

the functions involved. It also shows how the sequence of events is controlled by the framework and how printing a document involves calling five inherited members of your view class, which you may need to override. The `CDC` member functions shown on the left side of the diagram communicate with the printer device driver and are called automatically by the framework.




FIGURE 17-5

The typical role of each of the functions in the current view during a print operation is specified in the notes alongside it. The sequence in which they are called is indicated by the numbers on the arrows. In practice, you don't need to implement all of these functions, only those that you want to for your particular printing requirements. Typically, you'll want at least to implement your own versions of `OnPreparePrinting()`, `OnPrepareDC()`, and `OnPrint()`. You'll see an example of how these functions can be implemented in the context of Sketcher a little later in this chapter.

You write data to a printer in the same way as you write data to the display — through a device context. The GDI calls that you use to output text or graphics are device-independent, so they work just as well for a printer as they do for a display. The only difference is the physical output device to which the `CDC` object applies.

The CDC functions in Figure 17-5 communicate with the device driver for the printer. If the document to be printed requires more than one printed page, the process loops back to call the `OnPrepareDC()` function for each successive new page, as determined by the `EndPage()` function. All the functions in your view class that are involved in the printing process are passed a pointer to a `CPrintInfo` object that provides a link between all the functions that manage the printing process, so let's take a look at the `CPrintInfo` class in more detail.

The `CPrintInfo` Class

A `CPrintInfo` object has a fundamental role in the printing process because it stores information about the print job being executed and details of its status at any time. It also provides functions for accessing and manipulating this data. This object is the means by which information is passed from one view function to another during printing, and between the framework and your view functions.

A `CPrintInfo` object is created whenever you select the File \Rightarrow Print or File \Rightarrow Print Preview menu options. It will be used by each of the functions in the current view that are involved in the printing process, and it is automatically deleted when the print operation ends.

All the data members of `CPrintInfo` are `public`. The ones we are interested in for printing sketches are shown in the following table.

MEMBER	USAGE
<code>m_pPD</code>	A pointer to the <code>CPrintDialog</code> object that displays the Print dialog.
<code>m_bDirect</code>	This is set to <code>TRUE</code> by the framework if the print operation is to bypass the Print dialog; otherwise, <code>FALSE</code> .
<code>m_bPreview</code>	A member of type <code>BOOL</code> that has the value <code>TRUE</code> if File \Rightarrow Print Preview was selected; otherwise, <code>FALSE</code> .
<code>m_bContinuePrinting</code>	A member of type <code>BOOL</code> . If it is <code>TRUE</code> , the framework continues the printing loop shown in the diagram. If it's <code>FALSE</code> , the printing loop ends. You only need to set this variable if you don't pass a page count for the print operation to the <code>CPrintInfo</code> object (using the <code>SetMaxPage()</code> member). In this case, you'll be responsible for signaling when you are finished by setting this variable to <code>FALSE</code> .
<code>m_nCurPage</code>	A value of type <code>UINT</code> that stores the page number of the current page. Pages are usually numbered starting from 1.
<code>m_nNumPreviewPages</code>	A value of type <code>UINT</code> that specifies the number of pages displayed in the Print Preview window. This can be 1 or 2.
<code>m_lpUserData</code>	This is of type <code>LPVOID</code> and stores a pointer to an object that you create. This allows you to create an object to store additional information about the printing operation and associate it with the <code>CPrintInfo</code> object.

continues

(continued)

MEMBER	USAGE
<code>m_rectDraw</code>	A <code>CRect</code> object that defines the usable area of the page in logical coordinates.
<code>m_strPageDesc</code>	A <code>cstring</code> object containing a format string used by the framework to display page numbers during print preview.

A `CPrintInfo` object has the public member functions shown in the following table.

FUNCTION	DESCRIPTION
<code>SetMinPage(</code> <code>UINT nMinPage)</code>	The argument specifies the number of the first page of the document. There is no return value.
<code>SetMaxPage(</code> <code>UINT nMaxPage)</code>	The argument specifies the number of the last page of the document. There is no return value.
<code>GetMinPage() const</code>	Returns the number of the first page of the document as type <code>UINT</code> .
<code>GetMaxPage() const</code>	Returns the number of the last page of the document as type <code>UINT</code> .
<code>GetFromPage() const</code>	Returns the number of the first page of the document to be printed as type <code>UINT</code> . This value is set through the print dialog.
<code>GetToPage() const</code>	Returns the number of the last page of the document to be printed as type <code>UINT</code> . This value is set through the print dialog.

When you're printing a document consisting of several pages, you need to figure out how many printed pages the document will occupy, and store this information in the `CPrintInfo` object to make it available to the framework. You do this in your version of the `OnPreparePrinting()` member of the current view.

Page numbers are stored as type `UINT`. To set the number of the first page in the document, you call the `SetMinPage()` function for the `CPrintInfo` object, which accepts the page number as the argument. There's no return value. To set the number of the last page, you call `SetMaxPage()`. If you later want to retrieve these values, you call the `GetMinPage()` and `GetMaxPage()` functions for the `CPrintInfo` object.

The page numbers that you supply are stored in the `CPrintDialog` object pointed to by the `m_pPD` member of the `CPrintInfo` object and displayed in the dialog that pops up when you select File \Rightarrow Print... from the menu. The user can then specify the numbers of the first and last pages that are to be printed. You can retrieve the page numbers entered by the user by calling the `GetFromPage()` and `GetToPage()` members of the `CPrintInfo` object. In each case, the value returned is of type `UINT`. The dialog automatically verifies that the numbers of the first and last pages to be printed are within the range you supplied by specifying the minimum and maximum pages of the document.

You now know what functions you can implement in the view class to manage printing for yourself, with the framework doing most of the work. You also know what information is available through the `CPrintInfo` object that is passed to the functions concerned with printing. You'll get a much clearer understanding of the detailed mechanics of printing by implementing a basic multipage print capability for Sketcher documents.

IMPLEMENTING MULTIPAGE PRINTING

With the mapping mode in Sketcher set to `MM_ANISOTROPIC`, the unit of measure for the elements and the view extent is one hundredth of an inch. With the unit of size being a fixed physical measure, ideally you want to print objects at their actual size.

With the document size specified as 3000×3000 units, you can create documents up to 30 inches square, which spreads over quite a few sheets of paper if you fill the whole area. It requires a little more effort to work out the number of pages necessary to print a sketch than with a typical text document because in most instances you'll need a two-dimensional array of pages to print a complete sketch document.

To avoid overcomplicating the problem, we will assume that you're printing on a normal sheet of paper (either A4 size or $8\frac{1}{2} \times 11$ inches) and that you are printing in portrait orientation (which means the long edge is vertical). With either paper size, you'll print the document in a central portion of the paper measuring 7.5 inches \times 10 inches. With these assumptions, you don't need to worry about the actual paper size; you just need to chop the document into 750×1000 -unit chunks, where a unit is 0.01 inches. For a document larger than one page, you'll divide up the document as illustrated in the example in Figure 17-6.




FIGURE 17-6

As you can see, you'll be numbering the pages row-wise, so in this case, pages 1 to 4 are in the first row and pages 5 to 8 are in the second. A sketch occupying the maximum size of 30×30 inches will print on 12 pages.

Getting the Overall Document Size

To figure out how many pages a particular document occupies, you need to know how big the sketch is, and for this, you want the rectangle that encloses everything in the document. You can do this easily by adding a function `GetDocExtent()` to the document class, `CSketcherDoc`. Add the following declaration to the public interface for `CSketcherDoc`:

```
CRect GetDocExtent() const; // Get the bounding rectangle for the whole document
```

The implementation is no great problem. The code for it is:

```
// Get the rectangle enclosing the entire document
CRect CSketcherDoc::GetDocExtent() const
{
    if(m_Sketch.empty()) // Check for empty sketch
        return CRect(0,0,1,1);
    CRect docExtent(m_Sketch.front()->GetEnclosingRect()); // Initial doc extent
    for(auto& pElement : m_Sketch)
        docExtent.UnionRect(docExtent, pElement->GetEnclosingRect());

    docExtent.NormalizeRect();
    return docExtent;
}
```

You can add this function definition to the `SketcherDoc.cpp` file.

If the sketch is empty, you return a very small `CRect` object. The initial size of the document extent is the rectangle enclosing the first element in the list. The process then loops through every element in the document, getting the bounding rectangle for each element and combining it with `docExtent`. The `UnionRect()` member of the `CRect` class calculates the smallest rectangle that contains the two rectangles you pass as arguments, and stores that value in the `CRect` object for which the function is called. Therefore, `docExtent` keeps increasing in size until all the elements are contained within it.

Storing Print Data

The `OnPreparePrinting()` function in the view class is called by the application framework to enable you to initialize the printing process for your document. The basic initialization that's required is to provide information about how many pages are in the document, which is information that the print dialog will display. You should also store information about the pages that your document requires, so you can use it later in the other view functions involved in the printing process. You can create an object of your own class type in the `OnPreparePrinting()` member of the view class to store this information and store a pointer to the object in the `CPrintInfo` object that the framework makes available. I adopted this approach primarily to show you how this mechanism works; in many cases you'll find it easier just to store the data in your view object.

You'll need to store the number of pages running the width of the document, `m_nWidths`, and the number of rows of pages down the length of the document, `m_nLengths`. You'll also store the upper-left corner of the rectangle enclosing the document data as a `CPoint` object, `m_DocRefPoint`, because you'll need this when you work out the position of a page to be printed from its page number. You can store the filename for the document in a `CString` object, `m_DocTitle`, so that you can add it as a title to each page. It will also be useful to record the size of the printable area within the page. The definition of the class to accommodate these is:

```
#pragma once

class CPrintData
{
public:
    UINT printWidth;           // Printable page width - units 0.01 inches
    UINT printLength;          // Printable page length - units 0.01 inches
    UINT m_nWidths;            // Page count for the width of the document
    UINT m_nLengths;           // Page count for the length of the document
    CPoint m_DocRefPoint;      // Top-left corner of the document contents
    CString m_DocTitle;        // The name of the document

    // Constructor
    CPrintData():
        printWidth(750),       // 7.5 inches
        printLength(1000)       // 10 inches
    {}
};


```

The constructor sets default values for the printable area that corresponds to an A4 page with half-inch margins all round. You can change this to suit your environment, and, of course, you can change the values programmatically in a `CPrintData` object.

You can add a new header file with the name `PrintData.h` to the project by right-clicking the Header Files folder in the Solution Explorer pane and then selecting Add \Rightarrow New Item from the pop-up. You can now enter the class definition in the new file. You don't need an implementation file for this class. Because an object of this class is only going to be used transiently, you don't need to use `COobject` as a base or to consider any other complication.

The printing process starts with a call to `OnPreparePrinting()` so I'll explore how you should implement that next.

Preparing to Print

The Application Wizard has already added versions of `OnPreparePrinting()`, `OnBeginPrinting()`, and `OnEndPrinting()` to `CSketcherView`. The base code provided for `OnPreparePrinting()` calls `DoPreparePrinting()` in the return statement, as you can see:

```
BOOL CSketcherView::OnPreparePrinting(CPrintInfo* pInfo)
{
    // default preparation
    return DoPreparePrinting(pInfo);
}
```

The `DoPreparePrinting()` function displays the Print dialog using information about the number of pages to be printed that is defined in the `CPrintInfo` object. Whenever possible, you should calculate the number of pages to be printed and store it in the `CPrintInfo` object before this call occurs. Of course, in many circumstances, you may need information from the device context for the printer before you can do this — when you’re printing a document where the number of pages is going to be affected by the size of the font to be used for example — in which case it won’t be possible to get the page count before you call `DoPreparePrinting()`. In these circumstances you can compute the number of pages in the `OnBeginPrinting()` member, which receives a pointer to the device context as an argument. This function is called by the framework after `OnPreparePrinting()`, so the information entered in the Print dialog is available. This means that you can also take account of the paper size selected by the user in the Print dialog.

Assuming that the page size is large enough to accommodate a 7.5-inch × 10-inch area to draw the document data, you can calculate the number of pages in `OnPreparePrinting()`. The code to do this is:

```
BOOL CSketcherView::OnPreparePrinting(CPrintInfo* pInfo)
{
    CPrintData* printData(new CPrintData);      // Create a print data object
    CSketcherDoc* pDoc = GetDocument();          // Get a document pointer
    CRect docExtent = pDoc->GetDocExtent();      // Get the whole document area

    printData->m_DocRefPoint = docExtent.TopLeft(); // Save document reference point
    printData->m_DocTitle = pDoc->GetTitle();        // Save the document filename

    // Calculate how many printed page widths are required
    // to accommodate the width of the document
    printData->m_nWidths = static_cast<UINT>(ceil(
        static_cast<double>(docExtent.Width()) / printData->printWidth));

    // Calculate how many printed page lengths are required
    // to accommodate the document length
    printData->m_nLengths = static_cast<UINT>(
        ceil(static_cast<double>(docExtent.Height()) / printData->printLength));

    // Set the first page number as 1 and
    // set the last page number as the total number of pages
    pInfo->SetMinPage(1);
    pInfo->SetMaxPage(printData->m_nWidths * printData->m_nLengths);
    pInfo->m_lpUserData = printData;             // Store address of PrintData object
    return DoPreparePrinting(pInfo);
}
```

You first create a `CPrintData` object on the heap and store its address locally in the pointer. After getting a pointer to the document, you get the rectangle enclosing all of the elements in the document by calling the function `GetDocExtent()` that you added to the document class earlier in this chapter. You then store the corner of this rectangle in the `m_DocRefPoint` member of the `CPrintData` object, and put the name of the file that contains the document in `m_DocTitle`.

The next two lines of code calculate the number of pages across the width of the document, and the number of pages required to cover the length. The number of pages to cover the width is computed by dividing the document width by the width of the print area on a page and rounding up to the

next highest integer using the `ceil()` function that is declared in the `cmath` header. For example, `ceil(2.1)` returns `3.0`, `ceil(2.9)` also returns `3.0`, and `ceil(-2.1)` returns `-2.0`. A similar calculation to that for the number of pages across the width of a document produces the number to cover the length. The product of these two values is the total number of pages to be printed, and this is the value that you'll supply for the maximum page number. The last step is to store the address of the `CPrintData` object in the `m_lpUserData` member of the `pInfo` object.

Don't forget to add an `#include` directive for `PrintData.h` to the `SketcherView.cpp` file.

Cleaning Up after Printing

Because you created the `CPrintData` object on the heap, you must ensure that it's deleted when you're done with it. You do this by adding code to the `OnEndPrinting()` function:

```
void CSketcherView::OnEndPrinting(CDC* /*pDC*/, CPrintInfo* pInfo)
{
    // Delete our print data object
    delete static_cast<CPrintData*>(pInfo->m_lpUserData);
}
```

That's all that's necessary for this function in the Sketcher program, but in some cases, you'll need to do more. Your one-time final cleanup should be done here. Make sure that you remove the comment delimiters (`/* */`) from the second parameter name; otherwise, your function won't compile. The default implementation comments out the parameter names because you may not need to refer to them in your code. Because you use the `pInfo` parameter, you must uncomment it; otherwise, the compiler reports it as undefined. You don't need to add anything to the `OnBeginPrinting()` function in the Sketcher program, but you'd need to add code to allocate any GDI resources, such as pens, if they were required throughout the printing process. You would then delete these as part of the clean-up process in `OnEndPrinting()`.

Preparing the Device Context

At the moment, Sketcher calls `OnPrepareDC()` for the view object which sets up the mapping mode as `MM_ANISOTROPIC` to take account of the scaling factor. You must make some additional changes so that the device context is properly prepared in the case of printing:

```
void CSketcherView::OnPrepareDC(CDC* pDC, CPrintInfo* pInfo)
{
    CScrollView::OnPrepareDC(pDC, pInfo);
    CSketcherDoc* pDoc = GetDocument();
    pDC->SetMapMode(MM_ANISOTROPIC);           // Set the map mode
    CSize DocSize = pDoc->GetDocSize();          // Get the document size
    pDC->SetWindowExt(DocSize);                 // Now set the window extent

    // Get the number of pixels per inch in x and y
    int xLogPixels = pDC->GetDeviceCaps(LOGPIXELSX);
    int yLogPixels = pDC->GetDeviceCaps(LOGPIXELSY);

    // Calculate the viewport extent in x and y
    int scale(pDC->IsPrinting() ? 1 : m_Scale); // If we are printing, use scale 1
    int xExtent = (DocSize.cx*scale*xLogPixels)/100;
```

```

int yExtent = (DocSize.cy*scale*yLogPixels)/100;

pDC->SetViewportExt(xExtent, yExtent); // Set viewport extent
}

```

This function is called by the framework for output to the printer as well as to the screen. You should make sure that a scale of 1 is used to set the mapping from logical coordinates to device coordinates when you're printing. If you left everything as it was, the output would be at the current view scale, but you'd need to take account of the scale when calculating how many pages were required, and how you set the origin for each page.

You determine whether or not you have a printer device context by calling the `IsPrinting()` member of the current `CDC` object, which returns `TRUE` if you are printing. When you have a printer device context you set the scale to 1. Of course, you must change the statements calculating the viewport extent to use the local variable `scale` rather than the `m_Scale` member of the view.

Printing the Document

You write the data to the printer device context in the `OnPrint()` function. This is called once for each page. You need to add an override for this function to `CSketcherView`, using the Properties window for the class. Select `OnPrint` from the list of overrides and then click `<Add>` `OnPrint` in the right column.

You can obtain the page number of the page to be printed from the `m_nCurPage` member of the `CPrintInfo` object that is passed to the function. You can then use this value to work out the coordinates of the point in the document that corresponds to the upper-left corner of the current page. The way to do this is best understood using an example, so imagine that you are printing page 7 of an 8-page document, as illustrated in Figure 17-7.




FIGURE 17-7

Remember that these are in logical coordinates and x is positive from left to right and y is increasingly negative from top to bottom. You can get an index to the horizontal position of the page by decrementing the page number by 1 and taking the remainder after dividing by the number of page widths required for the width of the document. Multiplying the result by `printWidth` produces the x -coordinate of the upper-left corner of the page, relative to the upper-left corner of the rectangle enclosing the elements in the document. Similarly, you can determine the index to the vertical position of the document by dividing the current page number reduced by 1 by the number of page widths required for the horizontal width of the document. By multiplying the result by `printLength`, you get the relative y -coordinate of the upper-left corner of the page. You can express this in the following statements:

```
CPrintData* p(static_cast<CPrintData*>( pInfo->m_lpUserData));
int xOrg = p->m_DocRefPoint.x + p->printWidth*
           ((pInfo->m_nCurPage - 1)%(p->m_nWidths));
int yOrg = p->m_DocRefPoint.y + p->printLength*
           ((pInfo->m_nCurPage - 1)/(p->m_nWidths));
```

It would be nice to print the filename of the document at the top of each page and, perhaps, a page number at the bottom, but you want to be sure you don't print the document data over the filename and page number. You also want to center the printed area on the page. You can do this by moving the origin of the coordinate system in the printer device context *after* you have printed the filename. This is illustrated in Figure 17-8.




FIGURE 17-8

Figure 17-8 illustrates the correspondence between the printed page area in the device context and the page to be printed in the reference frame of the document data. The diagram shows the expressions for the offsets from the page origin for the printWidth by printLength area where you are going to print the page. You want to print the information from the document in the dashed area shown on the printed page in Figure 17-8, so you need to map the xOrg, yOrg point in the document to the position shown in the printed page, which is displaced from the page origin by the offset values xOffset and yOffset.

By default, the origin in the coordinate system that you use to define elements in the document is mapped to the origin of the device context, but you can change this. The CDC object provides a SetWindowOrg() function for this purpose. This enables you to define a point in the document's logical coordinate system that you want to correspond to the origin in the device context, in this case the point where (0,0) for the printer output will be. It's important to save the old origin that's returned from the SetWindowOrg() function. You must restore the old origin when you've finished drawing the current page; otherwise the m_rectDraw member of the CPrintInfo object is not set up correctly when you print the next page.

The point in the document that you want to map to the origin of the page has the coordinates xOrg-xOffset,yOrg-yOffset. This may not be easy to visualize, but remember that by setting the window origin, you're defining the point that maps to the viewport origin. If you think about it, you should see that the xOrg, yOrg point in the document is where you want it on the page.

The complete code for printing a page of the document is:

```
// Print a page of the document
void CSketcherView::OnPrint(CDC* pDC, CPrintInfo* pInfo)
{
    CPrintData* p(static_cast<CPrintData*>(pInfo->m_lpUserData));

    // Output the document filename
    pDC->SetTextAlign(TA_CENTER);           // Center the following text
    pDC->TextOut(pInfo->m_rectDraw.right/2, 20, p->m_DocTitle);
    CString str; str.Format(_T("Page %u"), pInfo->m_nCurPage);
    pDC->TextOut(pInfo->m_rectDraw.right/2, pInfo->m_rectDraw.bottom-20, str);
    pDC->SetTextAlign(TA_LEFT);             // Left justify text

    // Calculate the origin point for the current page
    int xOrg = p->m_DocRefPoint.x +
               p->printWidth*((pInfo->m_nCurPage - 1)%(p->m_nWidths));
    int yOrg = p->m_DocRefPoint.y +
               p->printLength*((pInfo->m_nCurPage - 1)/(p->m_nWidths));

    // Calculate offsets to center drawing area on page as positive values
    int xOffset = (pInfo->m_rectDraw.right - p->printWidth)/2;
    int yOffset = (pInfo->m_rectDraw.bottom - p->printLength)/2;

    // Change window origin to correspond to current page & save old origin
    CPoint OldOrg = pDC->SetWindowOrg(xOrg - xOffset, yOrg - yOffset);

    // Define a clip rectangle the size of the printed area
    pDC->IntersectClipRect(xOrg, yOrg, xOrg + p->printWidth, yOrg + p->printLength);
}
```

```

    OnDraw(pDC);                      // Draw the whole document
    pDC->SelectClipRgn(nullptr);      // Remove the clip rectangle
    pDC->SetWindowOrg(OldOrg);       // Restore old window origin
}

```

The first step is to initialize the local pointer, `p`, with the address of the `CPrintData` object that is stored in the `m_lpUserData` member of the object to which `pInfo` points. You then output the filename that you squirreled away in the `CPrintData` object. The `SetTextAlign()` function member of the `CDC` object allows you to define the alignment of subsequent text output in relation to the reference point you supply for the text string in the `TextOut()` function. The alignment is determined by the constant passed as an argument to the function. You have three possibilities for specifying the horizontal alignment of the text, as shown in the following table.

CONSTANT	ALIGNMENT
TA_LEFT	The point is at the left of the bounding rectangle for the text, so the text is to the right of the point specified. This is the default alignment.
TA_RIGHT	The point is at the right of the bounding rectangle for the text, so the text is to the left of the point specified.
TA_CENTER	The point is at the center of the bounding rectangle for the text.

You define the x-coordinate of the filename on the page as half the page width, and the y-coordinate as 20 units, which is 0.2 inches, from the top of the page.

After outputting the name of the document file as centered text, you output the page number centered at the bottom of the page. You use the `Format()` member of the `CString` class to format the page number stored in the `m_nCurPage` member of the `CPrintInfo` object. This is positioned 20 units up from the bottom of the page. You then reset the text alignment to the default setting, `TA_LEFT`.

The `SetTextAlign()` function also allows you to change the position of the text vertically by OR-ing a second flag with the justification flag. The second flag can be any of those shown in the following table.

CONSTANT	ALIGNMENT
TA_TOP	Aligns the top of the rectangle bounding the text with the point defining the position of the text. This is the default.
TA_BOTTOM	Aligns the bottom of the rectangle bounding the text with the point defining the position of the text.
TA_BASELINE	Aligns the baseline of the font used for the text with the point defining the position of the text.

The next action in `OnPrint()` uses the method that I discussed for mapping an area of the document to the current page. You get the document drawn on the page by calling the `OnDraw()` function that is used to display the document in the view. This potentially draws the entire document, but you can restrict what appears on the page by defining a *clip rectangle*. A clip rectangle encloses a rectangular area in the device context within which output appears. Output is suppressed outside of the clip rectangle. It's also possible to define irregularly shaped areas for clipping, called *regions*.

The initial default clipping area defined in the print device context is the page boundary. You define a clip rectangle that corresponds to the `printWidth` by `printLength` area centered in the page. This ensures that you draw only in this area and the filename and page number will not be overwritten.

After the current page has been drawn by the `OnDraw()` function call, you call `SelectClipRgn()` with a `nullptr` argument to remove the clip rectangle. If you don't do this, output of the document title is suppressed on all pages after the first, because it lies outside the clip rectangle that would otherwise remain in effect in the print process until the next time `IntersectClipRect()` gets called.

Your final action is to call `SetWindowOrg()` again to restore the window origin to its original location, as discussed earlier in this chapter.

Getting a Printout of the Document

To get your first printed Sketcher document, you just need to build the project and execute the program (once you've fixed any typos). If you try File \Rightarrow Print Preview and click on the Two Page button, you should get something similar to the window shown in Figure 17-9.




FIGURE 17-9

You get print preview functionality completely for free. The framework uses the code that you've supplied for the normal multipage printing operation to produce page images in the Print Preview window. What you see in the Print Preview window should be exactly the same as appears on the printed page.

SUMMARY

In this chapter, you have implemented the capability to store a document on disk in a form that allows you to read it back and reconstruct its constituent objects using the serialization processes supported by MFC. You have also implemented the capability to print sketches in the Sketcher application. If you are comfortable with how serialization and printing work in Sketcher, you should have little difficulty with implementing serialization and printing in any MFC application.

EXERCISES

1. Update the code in the `OnPrint()` function in Sketcher so that the page number is printed at the bottom of each page of the document in the form "Page *n* of *m*," where *n* is the current page number and *m* is the total number of pages.
2. As a further enhancement to the `CText` class in Sketcher, change the implementation so that scaling works properly with text. (*Hint:* Look up the `CreatePointFont()` function in the online help.)

► WHAT YOU LEARNED IN THIS CHAPTER

TOPIC	CONCEPT
Serialization	Serialization is the process of transferring objects to a file. Deserialization reconstructs object from data in a file.
MFC Serialization	To serialize objects in an MFC application, you must identify the class as serializable. To do this you use the <code>DECLARE_SERIAL()</code> macro in the class definition and the <code>IMPLEMENT_SERIAL()</code> macro in the file containing the class implementation.
Serializable classes in an MFC application	For a class to be serializable in an MFC application, it must have <code>CObject</code> as a direct or indirect base class, it must implement a no-arg constructor and implement the <code>Serialize()</code> function as a class member.
Printing with the MFC	To provide the ability to print a document in an MFC application, you must implement your versions of the <code>OnPreparePrinting()</code> , <code>OnBeginPrinting()</code> , <code>OnPrepareDC()</code> , <code>OnPrint()</code> , and <code>OnEndPrinting()</code> functions in the document view class.
The <code>CPrintInfo</code> object	A <code>CPrintInfo</code> object is created by the MFC framework to store information about the printing process. You can store the address of your own class object that contains print information in a pointer in the <code>CPrintInfo</code> object.

18

Programming Windows 8 Apps

WHAT YOU WILL LEARN IN THIS CHAPTER:

- How Windows 8 apps differ from desktop applications
- What XAML is and how you use it
- How you create the user interface for a Windows 8 app
- The characteristics of the interface to the operating system for Windows 8 apps
- How to create a project for a Windows 8 app
- How to create the user interface for an application graphically and modify UI elements in C++ code
- How to implement event handling
- How you can animate user interface elements

WROX.COM CODE DOWNLOADS FOR THIS CHAPTER

You can find the wrox.com code downloads for this chapter on the Download Code tab at www.wrox.com/remtitle.cgi?isbn=9781118368084. The code is in the Chapter 18 download and individually named according to the names throughout the chapter.

UNDERSTANDING WINDOWS 8 APPS

This chapter introduces the fundamentals of how you develop Windows 8 Apps with Visual C++. There is a great deal of detail involved in a comprehensive explanation of how you program for Windows 8 in C++, certainly more than enough to fill an entire book. Consequently this chapter will just provide you with a start down the path, a toe in the water. After a brief outline of the basics, most of the chapter is devoted to walking you through the development of an application, so it's learning by doing.

Writing a Windows 8 app is very different from writing a regular Windows desktop application such as Sketcher. The application context is different, the structure of the code is different, and the way the user interacts with the application is different. This is because Windows 8 apps are primarily aimed at computers with touch screens, such as tablets, and would typically be distributed through the Microsoft application store. This is similar to the Apple store for iPad and iPhone applications and the Google Play store for applications aimed at Android phones and tablets. Because of the nature of the target platform, Windows 8 apps run in a sandbox that insulates the application from the environment in which it is executing and limits what it can do with the resources in the environment in which it is running. Access to files, network connections, and the hardware are all constrained. You interact with a desktop application through the mouse and the keyboard, whereas you interact with a Windows 8 app using gestures through the touch-sensitive screen. When you run a Windows 8 app on your PC, mouse operations result in Windows 8 app tap events.

NOTE *I have found that Windows 8 provides a much more user-friendly interface if you have two displays installed. If your graphics card allows it I recommend that you install a second display. One display will always show the familiar Windows desktop, and both can show it when you have multiple desktop applications running. It is also very easy to switch between the Windows 8 Start screen and the desktop style. You can have the taskbar displayed on both displays too.*

You must have Visual Studio 2012 installed under Windows 8 in order to enable its Windows 8 development capabilities. You cannot develop Windows 8 apps in the Windows 7 environment. The operating system interface for Windows desktop applications under Windows 8 is still the Win32 API. For Windows 8 apps the interface is the *Windows Runtime (WinRT)*, which provides a relatively language-independent sandbox for creating and executing them.

NOTE *If you want to stick to standard C++, you can still program Windows 8 apps using the WinRT C++ Template Library (WRL). This involves relatively low-level programming with the API and WinRT objects and is beyond the scope of this book.*

The appearance of a Windows 8 app and its behavior are defined separately. You define what the application does in C++. You define the user interface (UI) in the *eXtensible Application Markup Language (XAML)*. You don't need to be an expert in XAML to create the UI for an application although a basic understanding of XAML will help a lot. There are UI design capabilities in Visual C++ in the form of the Design pane that allow you to create the UI in a similar manner to the way you created a dialog in the Sketcher. Creating the UI graphically in this way causes the required XAML and related C++ code to be generated automatically. You also get a lot of help from IntelliSense when you need to modify the XAML. You'll get experience with doing both through the example in this chapter.

Since the UI definition and the operation of a Windows 8 app are separate, in principle the UI development in XAML and the coding of the operation of the application in C++ can be separate activities. I say "in principle" because the separation cannot be total. How the C++ code needs to be implemented is very dependent on how the UI is defined in XAML. You can still synthesize UI components in code, so in many instances you have a choice as to how a component is created.

DEVELOPING WINDOWS 8 APPS

Visual C++ provides specialized facilities for developing Windows 8 apps that differ in many respects from what you have used up to now. To get an understanding of the development environment for them you should now create a project for a Windows 8 app. You'll be exploring and working with this project throughout this chapter.

Create a new C++ project by pressing Ctrl+Shift+N. Select the Windows 8 style option for Visual C++ in the left pane and click on the Blank App (XAML) template. This template creates a project with no UI controls predefined, just a Grid layout element covering the entire page, so you will create everything else from scratch later in this chapter. You can give the project the name `MemoryTest` and choose a folder for the solution if you don't like the default. Click OK to create the project.

Display the Solution Explorer pane. The first thing to note is that there are two `.xaml` files in the list. `App.xaml` defines the application and `MainPage.xaml` defines the UI page. A Windows 8 app always has one or more pages that define the UI, and each one will be defined by a separate `.xaml` file. Double-click on `MainPage.xaml` to display it. You'll see two editing panes. One is the *Design pane* where you can extend and modify the UI page graphically, and the other shows the listing of the XAML for the UI page. The XAML defines what is displayed in the Design pane. You can work with either of these, and changes you make in one pane will be automatically reflected in the other. Keep this project open because I'll be referring to it throughout the chapter.

I'll discuss three topics in a little more detail before getting into the specifics of developing the `MemoryTest` project:

- The basics of the Windows Runtime.
- The C++/CX extensions to Standard C++ and how they relate to the WinRT.
- The nature of XAML and how it is used to define UI components.

WINDOWS RUNTIME CONCEPTS

WinRT is an object-oriented API that is specifically for Windows 8 apps. For desktop applications under Windows 8 you would still use the Win32 API and the other application development aid, such as the MFC that apply equally well to Windows 7. WinRT is designed to be language neutral, so it can be used with JavaScript and C# as well as C++. WinRT provides a sandbox in which Windows 8 apps execute those controls and limit the extent to which an application can access the operating system and hardware resources.

Some different terminology from what you have seen so far is used in the context of WinRT applications. A *method* is the equivalent of a function in C++ parlance so these terms are interchangeable. You have learned about message handler functions that are called when a Windows message or event occurs in a desktop application. In a Windows 8 app, a *delegate* is essentially a function object that can encapsulate a method that is to be called to handle a particular type of event.

WinRT Namespaces

The classes that define WinRT objects are distributed within a large number of namespaces. To give you an idea of the extent of WinRT, there are well over 100 namespaces, each of which contains several, and in some cases many, class definitions. Classes that represent a particular set of UI components are all in the same namespace and generally the namespace name gives you an idea of what it contains. The `Windows::UI::Xaml::Controls` namespace, for example, contains classes that define controls such as buttons, check boxes and list boxes. In general, namespaces that relate to the definition or operation of the UI for an application have names that start with `Windows::UI`, and those that start with `Windows::UI::Xaml` relate to XAML types that you use to specify a UI.

You can define your own class types in a Windows 8 app. If you define your own class types that are to be passed to a WinRT component, the class definition must appear within a namespace and must be defined in a different way from what you have seen in standard C++. I'll explain how shortly.

TIP You will find it useful to have the reference documentation for the WinRT namespaces displayed in your browser while reading this chapter or when you are developing your own Windows 8 apps. At the moment, you can find it at <http://msdn.microsoft.com/en-us/library/windows/apps/br211377.aspx>.

WinRT Objects

WinRT is an object-oriented API where the objects are similar to *Component Object Model* (COM) objects. COM provides a mechanism for defining objects that can be accessed and operated on in different programming languages. A COM object is a rather different entity from the C++ class objects you have been using up to now. You cannot store a COM object in a variable; you can only store a reference to it. COM objects are reference counted, which means that a record of the number of separate references to an object is maintained. When the reference count for a COM object reaches zero, it will be destroyed and any resources the object owns will be released. If you use

naked COM object references, you are responsible to call functions at the appropriate times to keep the reference count correct. However, in WinRT, you are not using naked COM objects; WinRT objects have the management of their reference counts built-in. This means that while WinRT objects are created on the heap, you don't have to worry about deleting them because they take care of their own destruction automatically.

Because they are essentially COM objects, WinRT objects can be quite complicated to work with using standard C++. To write applications that work with COM objects you must understand the interfaces involved and stick to the rules for using them. For this reason, Visual C++ includes a set of Microsoft-specific C++ language extensions that hide the complexity of working with WinRT objects, thus making your application code much easier to write. These language extensions are referred to as *C++/CX*, from *C++ Component Extensions*. When you use C++/CX to work with WinRT objects, you can still use all of the C++ standard language and library facilities, including the STL. Any data passed to or received from the WinRT is always in terms of WinRT objects though, and you must always use C++/CX class types to reference WinRT objects.

C++ COMPONENT EXTENSIONS (C++/CX)

All data that you pass to, or receive from, the WinRT must be WinRT objects. Data of any of the fundamental C++ types will be converted to the equivalent WinRT type automatically, so you can always use C++ fundamental types in your Windows 8 apps. The WinRT types corresponding to C++ fundamental types are referred to as *value types* because they have pass-by-value semantics. You cannot pass objects of standard C++ class types to WinRT components. You must use WinRT object types. These are referred to as *ref class* or *ref struct* types, which are the WinRT equivalents of the standard C++ class and struct types. C++/CX provides additional language syntax for defining WinRT types and for working with WinRT objects.

C++/CX Namespaces

There are three C++/CX namespaces that contain things you should know about. These are the default namespaces that contain the WinRT types that correspond to the fundamental types in standard C++: the `Platform` namespace, the `Platform::Collections` namespace, and the `Windows::Foundation::Collections` namespace. You don't generally need to concern yourself with defining variables of the types in the default namespace. You can just use the C++ fundamental types in your code and they will be automatically converted to the corresponding value class type from the default namespace.

The `Platform` namespace contains, among others, the following built-in WinRT types:

TYPE	USE
<code>Object</code>	The base class for all WinRT types so it can represent any WinRT type.
<code>String</code>	An immutable Unicode character string. You must use this string type to pass strings to WinRT components.

continues

(continued)

TYPE	USE
Boolean	A value that is the equivalent of type <code>bool</code> .
SizeT	An unsigned data type that represents the size of an object.
IntPtr	A signed pointer value.
UIntPtr	A unsigned pointer value
Guid	A 16-byte value that represents a globally unique identifier.

Note that `Boolean`, `Guid`, `IntPtr`, and `UIntPtr` are value types and `Object` and `String` are ref class types. The one that you are likely to use most often is the `String` class that you use to represent text. The `Object` class is the ultimate base class for all WinRT class types.

The `Platform` namespace also includes the `Array` class that defines a one-dimensional array of object references. You cannot use standard C++ arrays to hold ref class references. You have no way to define multidimensional arrays or arrays of arrays with C++/CX.

The `Platform::Collections` namespace contains collection classes that store object references. It provides `Map` and `Vector` collection class types as well as `MapView` and `VectorView` types that provide read-only collections. You'll be using a `Vector` in the `MemoryTest` example.

The `Windows::Foundation::Collections` namespace defines `begin()` and `end()` functions that return iterators for the collection class reference that you pass as the argument. You can use these iterators to enable the functions defined in the STL algorithm header to be applied to a `Vector` collection. You will use these in the `MemoryTest` example. The namespace also defines a `back_inserter()` function that returns an iterator you use to insert a value at the end of a collection, and a `to_vector()` function that returns the contents of a `Vector` you pass to the function as an STL `std::vector` type.

Defining WinRT Class Types

You cannot use regular C++ class type definitions to define objects that you intend to use with the WinRT. The C++/CX language extensions provide an easy way to create ref class types and work with WinRT class objects. You define a WinRT class type using the `ref class` keyword, which indicates that the class is a WinRT type. The class definition in the `MainPage.xaml.h` file for the `MemoryTest` application looks like this:

```
public ref class MainPage sealed
{
public:
    MainPage();

protected:
    virtual void OnNavigatedTo(
        Windows::UI::Xaml::Navigation::NavigationEventArgs^ e) override;
};
```

MainPage is defined as a `ref class` so it will be a type that can be passed to or received from a WinRT method. The `sealed` keyword prevents this class from being used as a base class.

Here's how you might define your own `ref class` type:

```
public ref class Card sealed
{
public:
    // Public members...

private:
    // Private members...

protected:
    // Protected members...
internal:
    // Internal members...
};
```

You can mix standard C++ and `ref class` types as members of a `ref class` but standard C++ types can only appear in the `internal` and `private` sections of the class.

When a Windows 8 app is compiled, information about the `ref class` types it includes is stored in a `.winmd` file as metadata. If you compile the `MemoryTest` debug configuration, you'll see the `MemoryTest.winmd` file in the `MemoryTest\Debug\MemoryTest` folder for the project. The `.winmd` file specifies the public interface to the `ref class` types defined in the application that can be accessed by other Windows 8 development languages such as C# and JavaScript. Only `public` `ref classes` defined in a namespace will appear in metadata. You can use non-public `ref class` types in your application if you don't want the class interface to appear in the metadata. `ref class` members in the `internal` and `private` sections of a class are not published in metadata.

All public data members of a `ref class` type must be declared as properties. They cannot be ordinary data members. A *property* is a data member that has a privately stored value that you access through `get()` and `set()` methods. You define a property using the `property` keyword. Here's the `Card` class with a property defined:

```
public ref class Card sealed
{
public:
    property Platform::String^ type;
    property Windows::UI::Xaml::Media::SolidColorBrush^ color;
};
```

The `type` and `color` properties are *trivial properties*, for which the `get()` and `set()` method calls are inserted automatically by the compiler when you retrieve or store a value. Thus you can access data members that are trivial properties as though they were ordinary public data members. The compiler supplies default implementations of the `get()` and `set()` methods for a property that simply retrieve or assign the value of the property. You can define the `get()` and `set()` methods for a property

explicitly when you need something more than the default behavior. Here's how you could define the `type` property in the `Card` class with `get()` and `set()` methods:

```
property Platform::String^ type
{
    Platform::String^ get() { return m_type; }
    void set(Platform::String^ newType) { m_type = newType; }
}
private:
Platform::String^ m_type;
```

I'll explain the notation for specifying ref class variable types in the next section. The `get()` and `set()` methods here are defined to be the same as the defaults that are created by the compiler but they could be more complicated. You can omit the `set()` method definition and just define a `get()` method, in which case the property will be read-only.

The C++/CX syntax for defining a class includes the `partial` keyword. This is used to specify that a class definition is not complete and there is an additional part of the class definition that will come from elsewhere. The `MainPage` class definition that you have seen in the `MemoryTestexample` is not the whole story. The definition you saw earlier in the chapter complements a partial definition of the same class type. You can see the partial definition if you switch to Class View, extend `MainPage` and then `Partial Definitions` in the pane by clicking the arrows at the left, then double-click `MainPage`. The class definition looks like this:

```
partial ref class MainPage :
    public Windows::UI::Xaml::Controls::Page,
    public Windows::UI::Xaml::Markup::IComponentConnector
{
public:
    void InitializeComponent();
    virtual void Connect(int connectionId, Platform::Object^ target);

private:
    bool _contentLoaded;
};
```

The pane tab showing this code appears in a pane at the extreme right with the tab shaded mauve. The Mauve tab is a “preview” tab (hover the mouse over the tab to see the Preview tooltip). Once you start typing into the document, then the Mauve tab becomes blue and moves to the left. When you change the XAML, the class will be updated. The class here is defined using the `partial` keyword, and the previous definition that you saw is combined with this to form the complete `MainPage` class. UI elements that you create using XAML will have corresponding members defined in this class that reference WinRT component objects.

Variables of Ref Class Types

A variable of a ref class type is called a *handle* because it stores a reference to an object, not the object itself. A handle is like a smart pointer in standard C++. When you assign the value of one ref class variable to another, the handle is copied, not the object. The only way you can get two identical ref class objects is to create them explicitly. You specify the type for a variable of a ref class type using the class type name followed by ^, which is referred to as a *hat* symbol. Here's an example:

```
SolidColorBrush^ redBrush = ref new SolidColorBrush(Windows::UI::Colors::Red);
```

This defines the `redBrush` variable as a handle to a `SolidColorBrush` object, which is a WinRT type that defines a brush that fills an area with a particular color. The ref class definition is in the `Windows::UI::Xaml::Media` namespace. A WinRT object is created on the heap using `ref new`, and is destroyed automatically when no reference to it exists. If you create a ref class in a function and the only reference is stored in a local variable, the object will be destroyed when the function returns. The argument to the `SolidColorBrush` constructor is a constant member of the `Colors` class. This class defines a large number of members that represent standard colors.

You can use the `auto` keyword when creating ref class objects:

```
auto redBrush = ref new SolidColorBrush(Windows::UI::Colors::Red);
```

This does the same as the previous statement, but with fewer keystrokes.

You could create an array that holds handles to ref class objects like this:

```
auto brushes = ref new Platform::Array<SolidColorBrush^>(10);
```

The `brushes` array can store 10 handles to `SolidColorBrush` objects. You just specify the handle type to be stored between the angle brackets following the `Array` class name.

You can also create an array of handles with a set of initializers:

```
Platform::Array<SolidColorBrush^>^ colors =
    {redBrush, greenBrush, blueBrush, yellowBrush};
```

The `colors` array will contain four elements initialized with the `SolidColorBrush` handles that appear between the braces.

Accessing Members of a Ref Class Object

You use the `->` operator with an object reference to access a member of the object. Here's an example:

```
auto brush = ref new Windows::UI::Xaml::Media::SolidColorBrush();
brush->Color = Windows::UI::Colors::White;
```

This creates the reference `brush` and then sets the `Color` property for the object to `Colors::White`. The notation for calling a method for the object is exactly the same.

Event Handler Functions

A function that handles events that originate from a UI element is a regular C++ function with a particular signature that will depend on the UI element type. A typical event handler declaration in a class looks like this:

```
void Button_Tapped_1(  
    Platform::Object^ sender, Windows::UI::Xaml::Input::TappedRoutedEventArgs^ e);
```

This handler declaration for a button event was created automatically. It executes when the button is tapped on a tablet or when it is clicked with the mouse. The first parameter is the handle to the UI object that originated the event. You need to cast this to the appropriate type before you use it. The second argument provides additional information about the event. By convention event handlers for UI elements generally have two parameters, as shown here, with the first parameter type as `Platform::Object^` and a `void` return type. The type of the second parameter varies. The address of an event handler is recorded in a *delegate*, which is an object that has similarities to a function pointer in standard C++.

The delegate type for button tapped events is defined as:

```
public delegate void RoutedEventHandler(  
    Platform::Object^ sender, Windows::UI::Xaml::RoutedEventArgs^ e);
```

Any function that has the signature of this delegate can be added to a delegate of this type. The `TappedRoutedEventArgs` class is derived from `RoutedEventArgs`, so the `Button_Tapped_1()` handler function is consistent with this. You won't need to worry about the intricacies of delegates and event handler functions in this chapter because handler functions for UI component events are defined and registered automatically. All you have to worry about is what the handler function is going to do when it is called.

Casting Ref Class References

In the previous section you learned that you receive a reference to the object causing an event as type `Object^` and you must cast this in order to call methods for the type of object it actually is. You can use `static_cast` with references to WinRT objects, but it is better to use `safe_cast<T>` where `T` is the destination type. `safe_cast<T>` will throw a WinRT compatible exception if the cast fails.

Here's an example:

```
void Button_Tapped_1(Object^ sender, TappedRoutedEventArgs^ e)  
{  
    Button^ button = safe_cast<Button^>(sender);  
    button->Background = redBrush;  
}
```

The `Button` class is in the `Windows::UI::Xaml::Controls` namespace. The first statement in the handler function casts `sender` to type `Button^`. The next statement sets the value of the `Background` property to `redBrush`.

THE EXTENSIBLE APPLICATION MARKUP LANGUAGE (XAML)

XAML is a language that is defined in the eXtensible Markup Language (XML). XML is a meta-language that is used for defining a wide range of application-specific languages. XAML looks a bit like HTML in that it consists of tags and attributes with embedded text, but don't be fooled — XAML is quite different, with rigid rules for correctly writing XAML and none of the flexibility you have when writing HTML. You use XAML to define a set of elements in a hierarchy that specify the UI for a Windows 8 app. The UI for an application consists of one or more *pages*, and each page is defined by a separate XAML file with the extension .xaml.

The XAML definition for a page includes the controls and their layout. It also associates C++ functions with events that originate from user interaction with the controls in the UI. The XAML definition of a UI component will have an associated C++ class that encapsulates the component and its characteristics. A UI page defined by a .xaml file will have an associated .h file that contains the definition of a C++ class that encapsulates the page. It will also have an associated .cpp file that contains the class implementation.

XAML Elements

A XAML file always contains *XAML elements* that are arranged in a hierarchy. A XAML element has a type name that is case sensitive. You can define a XAML element by a *start tag*, for example <Grid>, followed by some optional element content, followed by an *end tag*, for example </Grid>. You can also define an element by a single tag called a *start-end tag*, for example <Grid/>. A tag is always delimited by a pair of angle brackets, <>. All tags contain an element type name, which is Grid in the preceding examples, and the name of each element type is unique.

In general, an element can contain other elements, and the elements that are contained are called *child elements* of the enclosing element. The enclosing element is the *parent* for its child elements. Elements in a XAML file must not overlap, so an end tag must always have the same element name as the immediately preceding start tag. There is always just one root element in a XAML file that encloses all the other elements; having more than one root element is not legal XAML.

A XAML element typically has *attributes* that specify *properties* for whatever is being defined; the color, dimensions, and orientation of a control, for example.

Here's a XAML element that defines a button control:

```
<Button x:Name="okButton" Background="Blue" Width="150" Click="HandleOK">  
    OK  
</Button>
```

The element name is Button. This defines a button control that is labeled OK. The label specification appears between the start tag on the first line, and the end tag, </Button>. The items following the element name, Button, in the start tag are attributes that define values for properties for the button control; each attribute definition is separated from the next by a space. The x:Name property

value specifies a name that you can use to reference the object that represents the button in code. This name must be different from any other names you assign in this way in a XAML file. The `Background` property value specifies the background color for the button. `Width` defines the width in pixels. The `Click` property value specifies the name of the function in the C++ class associated with the UI page that will be called when the button is clicked. Property values are always specified by a string in XAML.

NOTE *The name for a control that is specified in the XAML for a UI page will not exist in the C++ code in your project until you save the XAML file, so always save the file before you add code that references a control that is defined in XAML. Once the name for a control is defined in the code, IntelliSense will help you choose the function you want to call in C++ for the control object.*

You could define the same button with a single tag:

```
<Button x:Name="okButton"
        Background="Blue" Width="150" Click="HandleOK" Content="OK" />
```

This defines the same button control as the preceding example but using a start-end tag. The forward slash preceding the closing angle bracket indicates the end of the start-end tag. The button label is now defined by the value of the `Content` property. The slash preceding the closing angled bracket indicates that this is both a start and an end tag.

Here's an example of an element with child elements:

```
<StackPanel Height="400" Width="900"
            HorizontalAlignment="Left" VerticalAlignment="Top">
    <Button x:Name="okButton" Background="Blue" Width="150"
            Click="HandleOK" Content="OK"/>
    <Button x:Name="cancelButton" Background="Blue" Width="150"
            Click="HandleCancel" Content="Cancel"/>
</StackPanel>
```

The `StackPanel` element has two child elements that are buttons. Note how the child elements are indented with respect to the parent. Child elements are indented in this way to make the structure of the XAML easier to see.

When necessary, you can add comments in XAML. A XAML comment looks like this:

```
<!-- This is a comment. -->
```

A XAML comment starts with `<!--` and ends with `-->`. You can define a comment spanning several lines:

```
<!--
    This is a comment that is spread
    over two lines.
-->
```

The root element for a page looks like this:

```
<Page
    x:Class="MemoryTest.MainPage"
    IsTabStop="false"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    xmlns:local="using:MemoryTest"
    xmlns:d="http://schemas.microsoft.com/expression/blend/2008"
    xmlns:mc="http://schemas.openxmlformats.org/markup-compatibility/2006"
    mc:Ignorable="d">
</Page>
```

This is the root element for the `MainPage` in the `MemoryTest` example. The stuff following `Page` between the angle brackets in the start tag are properties that identify the page and the set of rules for the XAML in the file. The value for the `xmlns` property, for example, identifies the namespace name for the XAML specification. This is just a unique identifier and does not necessarily relate to a real web page. All the elements that define the page must appear between the `Page` start and end tags.

UI Elements in XAML

The entities that you can add using the Design pane are shown in Figure 18-1, which displays the Toolbox pane. You have a wide range of elements available in the Toolbox including those that define controls, elements that define a layout for a number of controls, and elements that define shapes such as an ellipse. As you'll see, when you add a control from the Toolbox to the Design pane, the XAML that defines the control is added to the `.xaml` file for the page immediately. You can then amend the dimensions and location of the control by interacting with the graphic in the Design pane. This will cause the property values in the XAML for an element to be updated.

You can also change the properties of the element through the Properties pane for the control. You can see this if you click on the `Grid` element in the listing for `MainPage.xaml` in the `MemoryTest` project and display the Properties pane. It will look like Figure 18-2, where I have extended the Layout and Appearance properties for the element. If Properties is not showing on the right side of your Visual Studio window for you to click, just select the element in the Design pane and press `Alt+Enter` or select from the `View` \leftrightarrow Other Windows menu to display the pane.




FIGURE 18-1




FIGURE 18-2

The Properties pane does not necessarily display all the properties that an element has.

Every XAML element has a corresponding WinRT class type. A `Button` element in XAML is defined by a `Button` class in the WinRT. For each element in the XAML for a page, there will be a WinRT object created in the application. If you define a value for the `x:Name` property for a XAML element, there will be a member of the page class that has that name. The member is a handle for the WinRT object.

A WinRT object that defines a UI component typically will be of a derived type. For example, the `Ellipse` class that is defined in the `Windows::UI::Xaml::Shapes` namespace has the inheritance hierarchy shown in Figure 18-3. The Properties pane will show all the properties that are relevant

to the definition of an `Ellipse` element, and many of these will be inherited. This does not mean that it shows all the inherited properties.

Knowing which properties are inherited is important when you want to store UI object references of different types in an array. For example, you might want to store shape elements such as `Rectangle` and `Ellipse` in an array, and you could declare the array element type as the base class type, `Shape`¹. The elements inherit many properties such as `Fill`, `Height`, and `Width` from the `Shape` class, so you modify the values of the inherited properties of an element without casting the reference stored in the array to its actual type.

As I said earlier, you can amend the XAML file directly and this will be reflected in the Design pane. Modifying XAML is not as daunting as it may sound, even if you are not an expert in XAML, because you get a lot of help to get it right from IntelliSense.

The controls in the Toolbox pane do not represent everything that you can define in XAML. There are additional element types such as `Polygon`, which defines a polygonal shape, and many element properties can be defined by other XAML elements. Clearly, you can only create such elements by adding the XAML for them. Here's an example:

```
<Polygon x:Name="triangle" Fill="Red" Points="0,70 70,70 35,0"
         HorizontalAlignment="Center"
         VerticalAlignment="Center"
         Height="70" Width="70" />
```




FIGURE 18-3

This defines a `Polygon` element that defines a triangle that is filled in red.

The vertices are defined by the value of the `Points` property. It has a name specified by the `x:Name` property value so you reference the object for this UI element with `triangle` in your C++ code. A `Polygon` element cannot have any content, so you can only use a start-end tag to define it. You don't have to remember this. You will see a warning when you try to insert an element with content that is not permitted.

Elements that can have content can be defined with a start tag and an end tag when you need to specify content. Elements that cannot have content must be defined with a single start-end tag. Look at this:

```
<Ellipse x:Name="circle" Height="100" Margin="10" Width="100"
         HorizontalAlignment="Center" VerticalAlignment="Center">
    <Ellipse.Fill>
        <SolidColorBrush x:Name="blueBrush" Color="Blue" />
    </Ellipse.Fill>
</Ellipse>
```

This defines an `Ellipse` element with the name `circle`, so you can use `circle` to reference the shape in C++. It will display as a circle with a diameter of 100 that is filled in blue. The color fill for the interior of the shape is specified by a nested `Ellipse.Fill` element that defines the value of the `Fill` property for the `Ellipse` element. An `Ellipse` element cannot have independent content, but it can have elements that define its property values. The color value for the `Fill` property for the `Ellipse` element is specified by a further nested XAML element of type `SolidColorBrush`.

The `Color` property value for the `SolidColorBrush` object is `Blue`, which is a standard color. The `SolidColorBrush` element has a name assigned as the value for `x:Name` so you could reference the brush object in code as `blueBrush`. Here's an example:

```
if(circle->Fill == blueBrush)
    circle->Fill = redBrush;
```

This statement compares the `Fill` attribute for the `circle` object to `blueBrush`. If they match, the `Fill` property value is changed to another `SolidColorBrush` object: `redBrush`. I'll explain the syntax for the C++ I use here a little later.

You could try entering the XAML for the ellipse in the `MemoryTest` project. Type the XAML immediately before the `</Grid>` end tag in the `MainPage.xaml` file. You'll see the blue circle displayed in the Design pane. You can delete the XAML afterwards and the circle will disappear from the Design pane.

Attached Properties

When you set property values in XAML, you are setting values for the property members of the WinRT object that defines the element. A XAML element can also have *attached properties*. An attached property allows a child element to set a value for a property belonging to a parent. A child element references a property belonging to a parent element by qualifying the property name with the type name for the parent element. The value for an attached property can be specified as a property in a child element or as an explicit child element. Here's an example of using an attached property:

```
<Grid Margin="0,0,10,0">
    <Grid.RowDefinitions>
        <RowDefinition Height="100*" />
        <RowDefinition Height="100*" />
    </Grid.RowDefinitions>

    <Grid.ColumnDefinitions>
        <ColumnDefinition Width="75*" />
        <ColumnDefinition Width="75*" />
    </Grid.ColumnDefinitions>

    <Rectangle Height="70" Width="70" Grid.Row="0" Grid.Column="0"/>
    <Rectangle Height="70" Width="70" Grid.Row="0" Grid.Column="1"/>
</Grid>
```

The `Grid.Row` and `Grid.Column` specifications in the `Rectangle` elements are attached properties. They specify values for the `Row` and `Column` properties in the parent `Grid` element and define where the `Rectangle` elements are to be located in the grid.

A code snippet in the previous section shows an attached property specified by a child element:

```
<Ellipse Height="100" Margin="10" Width="100"
            HorizontalAlignment="Center" VerticalAlignment="Center">
    <Ellipse.Fill>
        <SolidColorBrush x:Name="blueBrush" Color="Blue"/>
    </Ellipse.Fill>
</Ellipse>
```

The `Ellipse.Fill` child element specifies the `Fill` property for the parent `Ellipse` element.

Parents and Children

A parent element knows its own children and a child knows its parent. Elements that have `Windows::UI::Xaml::FrameworkElement` as a base inherit the `Parent` property, which has a value that is a reference to the parent object. The parent reference is of type `DependencyObject`¹, which is a base class for the `UIElement` class that is defined in the `Windows::UI::Xaml` namespace. Thus you will need a way to figure out what the actual parent type is when you want to work with it in your code.

Elements that can have children have `Windows::UI::Xaml::Controls::Panel` as a base, from which they inherit the `Children` property. `Children` has a value that defines a collection of child elements. The value is a reference to an object of type `UIElementCollection` that is contained in the `Windows::UI::Xaml::Controls` namespace. The references to the child elements are stored in the collection as type `UIElement`. You can use the value of the `Children` property to access the child elements in your code without having to specify individual names in XAML. You'll see how you can access and use a collection of child elements in the `MemoryTest` example.

Control Elements

There are many control elements, as you will have seen in the Tool box pane that is shown in Figure 18-1. Most of these are contained in the `Windows::UI::Xaml::Controls` namespace, but types that define shapes are in the `Windows::UI::Xaml::Shapes` namespace. As you might expect, several of these are functionally very similar to controls you have available for a desktop application, and these include `Button`, `CheckBox`, `ComboBox`, `ListBox`, and `TextBox` elements. The `Rectangle` element defines a rectangle that can be optionally filled and the element has a similar set of properties as an `Ellipse` element; a `Rectangle` element also has additional properties over an `Ellipse` such as `RadiusX` and `RadiusY` that specify how the corners are to be rounded.

The `FlipView` control is interesting. It can flip sequentially through the items in a collection under the control of your code. The items can be anything; text or images, for example. The collection of items can be a static set, or items can be added programmatically. This control also has built-in animation capability.

Layout Elements

The principle layout elements that you use to control how control elements are arranged on a UI page are `Grid` and `StackPanel` from the `Windows::UI::Xaml::Controls` namespace. They arrange elements in different ways. A `Grid` provides a rectangular grid of cells in which you can place elements, whereas the `StackPanel` provides a linear stack of elements that can be horizontal or vertical. The `Grid` element is perhaps the most frequently used layout control. You would typically have at least one `Grid` in a UI page covering the entire page area, as in the case of the default blank page in the `MemoryTest` project. This provides a primary arrangement to which you add other elements. A `Grid` element can have one or more rows and columns, and you can reference individual rows or columns with an index value, where index values start from zero. You can identify a particular `Grid` cell by a row index plus a column index, and you can locate a control in a grid cell by specifying a row index and a column index for it. `Grid` cells can contain elements of any type, including `Grid` and `StackPanel` elements, and you can place more than one element in a cell so they are displayed one over the other. Child elements in a grid can also span several grid cells. You'll be working with a grid in the `MemoryTest` example.

A Canvas element can contain multiple UI elements as children that are located relative to the left side and top of the Canvas element. This means that you have complete freedom as to how the child elements are arranged. Here's an example:

```
<Canvas Background="Azure" Height="200" Width="200">
    <Rectangle Fill="Blue" Canvas.Left="20" Canvas.Top="5" Height="70" Width="70"/>
    <Ellipse Fill="Red" Canvas.Left="100" Canvas.Top="100" Height="30" Width="70"/>
</Canvas>
```

Left and Top are attached properties so they are qualified by the parent name in the child elements. The values are in pixels.

Handling Events for UI Elements

A UI element has properties that identify the event handler function for events. Each type of event will have a unique property. For example, the Tapped property value defines the handler function for the event that arises when an element is tapped on a touch screen or clicked in the desktop environment with the mouse. The majority of event properties for an element are inherited. Most UI elements have the `UIElement` class that is in the `Windows::UI::Xaml` namespace as a base class. `UIElement` has many properties for events, including the following:

PointerEntered	PointerExited	PointerMoved	PointerPressed
Tapped	DoubledTapped	RightTapped	

This is a subset of the event properties in `UIElement`. All elements derived from this class will inherit all the event properties it defines. The names are self-explanatory. When you want to handle an event, you assign the name of the event handler function as the property value. Here's an example:

```
<Rectangle Tapped="Rectangle_Tapped_1" Fill="Blue" Height="50" Width="100"/>
```

When the rectangle defined by this element is tapped or clicked, the `Rectangle_Tapped_1()` function will be called. Typically you would use the Properties pane to define an event handler rather than modify the XAML directly. This will set the value for the selected property and create the definition for the handler in the class that defines the page containing the UI element. The name for the handler function is created automatically. If you want to make the name more concise, you must change the property value and change the handler function name in the .h and .cpp files for the page. You'll see how this works in the context of the `MemoryTest` example.

If you write the name for a handler as a property value directly in an XAML element, you can right-click the name and select Navigate to event handler. If the event handler doesn't exist yet, Visual Studio will create it for you and navigate to the code it has created.

Elements also have properties that control whether or not particular events are enabled for an element. This allows you to define a handler for a particular event and then control whether or not the events actually occur by setting a property value. The `IsTapEnabled` and `IsDoubleTapEnabled` properties can have values "true" or "false" that determine whether the `Tapped` or `DoubleTapped` events are enabled.

Whether or not an element is visible is determined by the value of its `Visibility` property. The value can be "Visible" or "Collapsed" in the XAML, the latter being invisible. The values for the `Visibility` property are defined by the `Visibility` enum class that is in the `Windows::UI::Xaml` namespace. You need to know this when you are controlling the visibility of an element in code.

You can also control the transparency of an element by setting a value for the `Opacity` property. The value for the property can be from 0 to 1.0, where 0 is completely transparent and 1.0 is completely opaque.

CREATING A WINDOWS 8 APP

You are now going to develop the `MemoryTest` project into a working program. You will use a diverse range of controls just for the experience rather than for implementing the application in the most elegant way. Of course, this means that the example will not be as consistent in its design as it should be, and it will not demonstrate the many UI embellishments that are possible, but it will show you how to work with several of the controls you have available. The approach I will describe will give you experience of using the UI Designer pane to create the UI for the example as well as extending and modifying the XAML that specifies the UI to expand it. Again, this will not be the ideal approach in practice, but it is a good way to try out the various possibilities you have available to you.

The application will implement a memory testing game. It will display a set of 24 cards that are face down initially. The 24 cards consist of 12 matching pairs. The face of each card will be a circle, a square, or a triangle, colored red, green, blue, or yellow, so there are 12 different cards. To play the game you turn up successive pairs of cards. If the pair match in shape and color they remain turned up. You win the game when you have found all the matching pairs.


Application Files

If you look at the Solution Explorer pane, you'll see two `.xaml` files. `App.xaml` defines the application object and `MainPage.xaml` defines the main page of the UI. In general, there will be a `.xaml` file for each UI page in an application. The `MemoryTest` game will have just one.

If you extend the `MainPage.xaml` entry by clicking the arrow that appears on the left, you'll see there are two source files, `MainPage.xaml.h` that contains the `MainPage` class definition for the main page, and `MainPage.xaml.cpp` that contains the class implementation. Your modifications to the code can be in either of these files. You will be adding to both files in the example. The `MainPage` class is a ref class so it defines a WinRT object. The class is specified with the `sealed` keyword, so you cannot derive another class from it.

The `MainPage` class definition in `MainPage.xaml.h` is not complete. None of the details of the UI are defined in `MainPage.xaml.h`. There is another file, `MainPage.g.h`, that defines the rest of the class. This file does not appear in the Solution Explorer pane because you must not modify it. The contents are created for you from the XAML for the main page.

The `Package.appxmanifest` file defines properties that apply when the application is deployed. If you double-click the filename in the Solution Explorer pane you'll see the pane shown in Figure 18-4.

**FIGURE 18-4**


Here you can set the path for the logo for the application and specify its orientation as well as other characteristics. The default images for the application are shown in the Assets list in the Solution Explorer pane. You can set permissions for the application on the Capabilities tab that determines what hardware and other resources the application is able to access. I won't be going into details of how you modify any of the settings in this file.

The first development task for the application is to design and specify the UI for the game in XAML.

Defining the User Interface

First you must decide the broad layout of the application page — what goes where. You have complete flexibility here, so my choice is arbitrary and undoubtedly not the best. I decided on the arrangement shown in Figure 18-5.

Along the top and the full width is the application title, the 4×6 arrangement of

**FIGURE 18-5**

cards will be in the rectangular area below the title and to the right. Controls for the game will be in a column at the left, and an information or message area will be at the bottom. You can now add rows and columns to the page grid to provide for this arrangement.

Double-click on `MainPage.xaml` to display the XAML and the Design pane. You can select any element to be current so that its properties are displayed in the Properties pane by clicking it in the Design pane or clicking the XAML that defines it, so select the main page grid. If you move the cursor just above the upper edge of the grid you will see a vertical orange line appear that divides the grid into two columns. The line follows the cursor as you move it and you select a position by clicking it. You can add horizontal lines that divide the grid into rows with the same procedure with the mouse cursor on the vertical grid boundaries. You can add two horizontal dividers and one vertical divider so the grid has the three rows and two columns shown in Figure 18-6.




FIGURE 18-6

You can specify the way in which the dimensions of a row or column are measured. If you hover the cursor over any of the column dimensions that are along the top of the grid, you'll see a popup appear. When you click the down arrow in the popup you'll see the menu in Figure 18-7.

The top three menu items set the way the dimensions are measured and have the following meanings:

Star: Selecting this means that measurements are relative. If your grid has two columns with widths specified as "4*" and "6*", the first column will occupy 40% of the overall width and the second column 60%. Three columns with widths, "2*", "3*", and "5*" will occupy 20%, 30%, and 50% of the total grid width. With this specification of dimensions for grid rows and columns, the dimensions of the columns and rows will resize proportionately when you resize the grid.




FIGURE 18-7

Pixel: This means measurements are absolute in pixels.

Auto: You can use this to make a dimension occupy the available space, whatever it is. For example, with two columns you could specify the first in pixels: "150" for example. If you specify the second column width as "Auto", the second column width will take up the remaining grid width.

You can modify the option for the dimension for each row and column either by selecting from the pop-up menu for each dimension, or you can just use appropriate values for the Height and Width properties for the rows and columns in the XAML, as you'll see. You should not hard code fixed dimensions for your UI elements. By using Star or Auto specifications for dimensions, you allow your application to adapt to the screen size on which it is executing.

The grid rows are defined in the XAML by a Grid.RowDefinitions element that has a nested RowDefinition element for each row, and the grid columns are defined in a similar way. You can amend the row heights and column widths in the grid by modifying the Height and Width property values for the RowDefinition and ColumnDefinition elements in the XAML. I changed the widths of the columns and the heights of the rows to the values shown in Figure 18-6 so you should try that too. The XAML for my grid now looks like this:

```
<Grid Background="{StaticResource ApplicationPageBackgroundThemeBrush}">
    <Grid.RowDefinitions>
        <RowDefinition Height="160"/>
        <RowDefinition Height="*"/>
        <RowDefinition Height="170"/>
    </Grid.RowDefinitions>
    <Grid.ColumnDefinitions>
        <ColumnDefinition Width="350"/>
        <ColumnDefinition Width="*"/>
    </Grid.ColumnDefinitions>
</Grid>
```

You can add a UI element to any cell of a grid and that includes another grid. An element can also occupy several cells in a row or column. When you add an element in the Design pane, the element is added as a child of the currently selected element. You must always make sure that the correct element is selected for the parent of a new element. You can make an element selected by clicking it in the Design pane, or by clicking the element type name in the XAML.

The element you will add to display the title will occupy the whole of the top row. You can reference grid rows and columns by index values starting from 0 and I'll refer to a particular grid cell in the text as (row_Index, column_Index), so cell (2,1) is the second cell in the third row.

Creating the Title

You could use a child Grid element to the existing grid to provide a background for the application title. Click the Toolbox on the right of the Visual Studio application window to display it. If it is not shown there, you can display it by pressing Ctrl+Alt+X. Click Grid in the list. Click on the boundary between cells in the top row of the current grid to add the new Grid element to that row, move it so it lies within the top row of the original grid and drag the sides so it is the full width. You can now edit the XAML for the new grid by deleting all the properties except for Grid.ColumnSpan="2".

Place the cursor immediately before the `>` at the end of the new grid element and enter a space followed by `Background`. IntelliSense will prompt with a list so you can select from the list instead of entering the entire property name. Type `B` between the double quotes to see the list of colors — I chose `Bisque` because it sounds rather nice. The new property value, `Background="Bisque"`, sets the background color for the grid. The XAML for the new grid element should be:

```
<!-- The title for the game -->
<Grid Grid.ColumnSpan="2" Background="Bisque" />
```

The first line is a comment that I added. The new grid should now fill the top row of the original grid and have a nice background color. The value for the `Grid.ColumnSpan` attached property specifies that the grid covers two columns of the parent grid. There are no dimensions determined by the size of the top row of the parent grid.

When you want to enter a new property value in the XAML for an element, just enter a space in the element where you want to position the property and type the first few letters of the property name. IntelliSense will display a list of property names that you can select from by using the arrow keys, as Figure 18-8 shows.




FIGURE 18-8

Pressing Enter with a selection highlighted will create the property so that you just have to enter the value. When the value is from a predefined set, IntelliSense will prompt for that too.

To display the title text you will use a `RichTextBlock` element, just to introduce you to it. This is a very powerful element for presenting text, but you will use it in a simple way. It can display several separate blocks of text defined by `Paragraph` child elements, each of which can have its own font specification and alignment. Make sure the new grid is selected by clicking the

XAML element for it. Click `RichTextBlock` in the Toolbox pane, then click inside the `Grid` element. Remove all properties from the XAML for the `RichTextBlock` element except for `VerticalAlignment="Center"`. The Toolbox list doesn't contain the `Paragraph` element but you can add it manually. Place the cursor just before the closing `/` in the `RichTextBlock` element and enter `>`. You should see the end tag inserted but you may have to delete an extra `>` at the end. Now enter a `Paragraph` element as a child of the `RichTextBlock` element. Edit the `RichTextBlock` XAML and its child element so that it looks like this:

```
<RichTextBlock FontFamily="Freestyle Script" FontWeight="Bold" FontSize="90"
    TextAlignment="Center" Foreground="Red" VerticalAlignment="Center">
    <Paragraph>
        <Run Text="Test Your Memory!" />
    </Paragraph>
</RichTextBlock>
```

The `FontFamily` property value identifies the font. I chose "Freestyle Script" as a fun font for the application tile. I also set the `FontWeight` property value to "Bold". The `FontSize` property value is "90" so you have a sizeable title. The `TextAlignment` property value is "Center" and the `Foreground` property value is "Red" so the text will be centered and in red. The `VerticalAlignment` property value determines how the `RichTextBlock` element is aligned in its parent. The `Run` child element for the `Paragraph` element defines a block of formatted or unformatted text. You could write the `Run` element as:

```
<Run>Test Your Memory!</Run>
```

The complete XAML for the title should now look something like:

```
<!-- The title for the game -->
<Grid Grid.ColumnSpan="2" Background="Bisque">
    <RichTextBlock FontFamily="Freestyle Script" FontWeight="Bold" FontSize="90"
        TextAlignment="Center" Foreground="Red" VerticalAlignment="Center">
        <Paragraph>
            <Run Text="Test Your Memory!" />
        </Paragraph>
    </RichTextBlock>
</Grid>
```

I added a comment at the beginning of the block of XAML to identify it. You'll add something to cells (1,0) and (2,0) of the base grid next.

Adding Game Controls

You will add just two game control buttons. There's space for more if you want to develop the game further. One button will be a `Start` button to reset the game with a new random deal of the cards and the other will display instructions on how to play the game. You'll add the functionality for these later.

First select the base grid and add a child `Grid` element from the Toolbox to cell (1,0) and drag the sides of the new grid so it occupies cells (1,0) and (2,0). Add a horizontal divider so the grid has two equal height rows and a single column. Adjust the properties so the XAML is:

```
<Grid Grid.Row="1" Grid.RowSpan="2" Background="Bisque" Margin="0,10,0,0">
    <Grid.RowDefinitions>
        <RowDefinition Height="1*" />
        <RowDefinition Height="1*" />
    </Grid.RowDefinitions>
```

The grid background color is the same as that for the grid holding the title. With the grid row height property values as "1*", the rows will be of equal height and will adjust automatically to fit the space in the parent grid.

Now add a button in the top cell of the `Grid` element, with the `Content` value as "Start". Adjust the properties in the XAML for the button so it is:

```
<Button Grid.Row="0" Content="Start" FontSize="32" Foreground="Red"
    Background="Gray" BorderBrush="Black" Height="90" Width="150"
    HorizontalAlignment="Center" VerticalAlignment="Center" />
```

The background is gray and the border is drawn in black. The button height and width are as you see. The `HorizontalAlignment` and `VerticalAlignment` property values determine how the button is positioned in relation to its container, the top row of the grid.

You are going to implement more UI function with the second button and to allow for this to be added later, you can place the button in a `StackPanel` element that sits in the second row of the grid. After making sure the grid that holds the game controls is selected, click on `StackPanel` in the Toolbox pane and click cell (1,0) of the grid. Edit the XAML for the `StackPanel` to:

```
<StackPanel x:Name="ButtonPanel" Grid.Row="1" />
```

The `x:Name` property value specifies the name by which you can refer to the `StackPanel` object in code.

Add the button in the bottom cell with the `Content` value "How to Play". Make it the same height and width as the Start button. You can make the value of the `Background` property for both "Gray", and the `BorderBrush` property value "Black". The `FontSize` property value for the bottom button can be "20". My XAML for the game controls now looks like this:

```
<!-- Game controls-->
<Grid Grid.Row="1" Grid.RowSpan="2" Background="Bisque" Margin="0,10,0,0">
    <Grid.RowDefinitions>
        <RowDefinition Height="1*" />
        <RowDefinition Height="1*" />
    </Grid.RowDefinitions>
    <Button Grid.Row="0" Content="Start" FontSize="32" Foreground="Red"
        Background="Gray" BorderBrush="Black" Height="90" Width="150"
        HorizontalAlignment="Center" VerticalAlignment="Center" />
    <StackPanel x:Name="ButtonPanel" Grid.Row="1">
        <Button Content="How to Play" FontSize="20" Foreground="Red"
            Background="Gray" BorderBrush="Black" Height="90" Width="150"
            HorizontalAlignment="Center" VerticalAlignment="Center" />
    </StackPanel>
</Grid>
```

To the left of the XAML, you'll see a vertical line with a minus sign on the same line as a parent element. Clicking the minus sign will collapse the XAML into a single line. Clicking the plus sign for a collapsed parent element restores it. This is very helpful when you are working with a lot of XAML, as you'll see later.

You can add another `Grid` element with the name "messageArea" to cover grid cell (2,1) and make the `Background` property value "Bisque". My XAML for this is:

```
<!-- Message area -->
<Grid x:Name="messageArea" Grid.Column="1" Grid.Row="2" Margin="10,0,0,0"
      Background="Bisque"/>
```

You'll place some elements in this grid later. You'll be able to access the grid in code through the handle with the name `messageArea`. The `Margin` property value here specifies four values separated by spaces that are the margins for left, top, right, and bottom edges of the grid. These specify the distances of the boundaries of the grid to its parent child so the distance between the left edge of the parent cell and the left edge of this grid will be 10 pixels. With two values in the `Margin` property value, the first applies to the left and right margins and the second is the top and bottom margins. With one value it applies to all four edges.

Creating a Grid to Contain the Cards

You are going to place another grid inside cell (1,1) of the existing grid that will contain the cards. Click `Grid` in the list in the Toolbox pane and then click cell (1,1) of the existing grid. This will display the grid element in the Design pane and add its definition to `MainPage.xaml`. Add five column dividers and three row dividers evenly spaced so the grid has four rows of six cells. You can then edit the XAML for the new grid in `MainPage.xaml` to the following:

```
<!-- Grid holding the cards -->
<Grid x:Name="cardGrid" Grid.Row="1" Grid.Column="1" Margin="32">
  <Grid.RowDefinitions>
    <RowDefinition Height="4*"/>
    <RowDefinition Height="4*"/>
    <RowDefinition Height="4*"/>
    <RowDefinition Height="4*"/>
  </Grid.RowDefinitions>
  <Grid.ColumnDefinitions>
    <ColumnDefinition Width="6*"/>
    <ColumnDefinition Width="6*"/>
    <ColumnDefinition Width="6*"/>
    <ColumnDefinition Width="6*"/>
    <ColumnDefinition Width="6*"/>
    <ColumnDefinition Width="6*"/>
  </Grid.ColumnDefinitions>
</Grid>
```

Now you have a grid defined to hold the cards; the next step is to decide how a card will be represented.

Defining a Card

A card has two sides. The front will have one of three shapes on it that is filled in one of four colors. The back will just show the string "???". There are many ways you could represent a card using XAML. For example, you could define the front and back of each card as separate elements with a suitable child element. This would mean 48 elements for the complete pack of cards. Alternatively, you could define the front of a card as an element containing the three possible shapes, and the back as another element with a child to display the string. I decided on yet another approach. I'll explain where we are headed. This will make it easier for you to understand the steps that follow.

Each grid cell needs to display either the front or the back of a card. As I said, the front of a card can contain a circle, a square, or a triangle in any of four colors: red, green, blue, or yellow. A card back will just be the string "???". To make this possible, you can locate instances of all three shape elements — `Ellipse`, `Rectangle`, and `Polygon` — plus a `TextBlock` for the card back inside a `Grid` element that will determine their sizes. This `Grid` element will be placed in another `Grid` element that sits in a cell of the card grid and that will provide the background color for the cards. The `Grid` element holding the shapes and the `TextBlock` element will represent the background of both the card front and the card back. Thus a single card is a `Grid` element containing a `Grid` element containing the shapes and the `TextBlock`. If you place one of these nested `Grid` elements with its children in each cell of `cardGrid`, you can display any of the card fronts or the card backs by judiciously setting the `Visibility` property for the child elements of the inner grid. You can start by creating the elements that define the card for cell (0,0) of `cardGrid`.

Creating a Card

Create the `Grid` element in `cardGrid` cell (0,0) by selecting `cardGrid`, clicking the `Grid` control in the Toolbox pane list then clicking the `cardGrid` cell (0,0). Edit the XAML to the following:

```
<Grid Grid.Row="0" Grid.Column="0" Background="Azure" Margin="5" />
```

The value of the `Background` property is "Azure", which will be the color of the background for the front and back of a card. The `Margin` property value will create a boundary of 5 pixels between the edge of each card and the `cardGrid` cell it occupies. This element will be visible at all times because it represents the background for both the front and the back of a card.

Make sure the grid that you just added is selected and place another `Grid` element from the Toolbox in it. This will contain the shapes and the `TextBlock` element and determine the size of them. Edit its properties to the following:

```
<Grid Margin="10" Width="50" Height="50" />
```

This has margins of 10 pixels all round and has a height and width of 50 which will determine that the child elements will have a height and width of 50 pixels.

Now you can add the shapes that define the front of a card and the `TextBlock` that defines the back to this inner `Grid` element.

Creating a Square

You can define a square with the `Rectangle` XAML element. The corresponding WinRT `Rectangle` class is defined along with other shapes in the `Windows::UI::Xaml::Shapes` namespace. Add a

Rectangle element from the Toolbox pane to the interior of the Grid element that you just added in the Design pane. You'll see that the XAML defining the Grid element now has a start and end tag and the Rectangle element appears between them. Edit the XAML for the Rectangle element to the following:

```
<Rectangle Fill="Blue" Stroke="Black" Tapped="Shape_Tapped" />
```

This will define a square because the parent Grid element forces the dimensions of the Rectangle element to be 50. The border is black and the fill color is blue. It doesn't matter what color you set here because you will change it programmatically when you decide which card will be placed in each cell of cardGrid. The value for the Tapped property is the name of the handler function to be called for Tapped events on the rectangle. It does not exist yet but you will create it a bit later in this chapter. A Tapped event occurs when an element is tapped on a touch screen or clicked with the mouse. You are entering the handler name here because the same handler will service Tapped events for all elements that appear on the fronts of all the cards.

Creating a Circle

The XAML for the element that defines a circle will be almost identical to that for a square so I think you can add the XAML for that directly, immediately after the XAML for the rectangle:

```
<Ellipse Fill="Red" Stroke="Black" Tapped="Shape_Tapped" />
```

The only differences are the element name and the fill color. The Ellipse element will define a circle because the size will be determined by the parent Grid element to be 50 × 50 pixels.

Creating a Triangle

There is no control in the Toolbox list that defines a triangle. You have to enter XAML to create a triangle. You'll use a Polygon element type, which allows you to define a closed polygon by a series of points with as many vertices as you like. A triangle is defined by three points, and you define the coordinates of the points in the value for the Points property. The points are defined by a string containing a series of integer coordinates separated by spaces or commas. Obviously there must be an even number of coordinates in the string because each point is defined by an x,y pair. The coordinate system has its origin at the top left of the element area with positive x running from left to right and positive y from top to bottom. Add a Polygon element to the Grid element, following the Ellipse element. The XAML should be like this:

```
<Polygon Fill="Green" Points="0,50 50,50 25,0" HorizontalAlignment="Center"
VerticalAlignment="Center" Stroke="Black" Tapped="Shape_Tapped" />
```

The HorizontalAlignment and VerticalAlignment property values center the triangle in its parent. The element properties can be in any order, so if yours are in a different sequence it doesn't matter. I have used commas to separate x and y in a pair and spaces between coordinate pairs for the Polygon element. You could use all spaces or all commas as separators if you wish. If you want an inverted triangle you could define the value of the Points property as "0,0 50,0 25,50". The Stroke property value specifies the color for the outline of the polygon.

Creating the Card Back

The back of a card will be represented by a `TextBlock` element so select it in the Toolbox pane and place it in the `Grid` element in the Design pane that contains the shapes. You can then edit the `TextBlock` XAML element to the following:

```
<TextBlock TextWrapping="Wrap" Text="???" Foreground="Black" FontSize="32"
FontWeight="Bold" VerticalAlignment="Center" Tapped="Cardback_Tapped"/>
```

The text that will be displayed is specified by the `Text` property value. The value for the `Foreground` property determines the color for the text. The font size and weight are defined by the `FontSize` and `FontWeight` property values. There are other `TextBlock` properties that define the font characteristics such as `FontStyle` and `FontFamily`, but I'll leave you to explore those possibilities.

The complete XAML for the card in cell (0,0) in `cardGrid` should be like this:

```
<Grid Grid.Row="0" Grid.Column="0" Background="Azure" Margin="5">
<Grid Margin="10" Width="50" Height="50">
<Rectangle Fill="Blue" Stroke="Black" Tapped="Shape_Tapped" />
<Ellipse Fill="Red" Stroke="Black" Tapped="Shape_Tapped" />
<Polygon Fill="Green" Points="0,50 50,50 25,0"
HorizontalAlignment="Center" VerticalAlignment="Center"
Stroke="Black" Tapped="Shape_Tapped" />
<TextBlock TextWrapping="Wrap" Text="???" Foreground="Black"
FontSize="32" FontWeight="Bold" VerticalAlignment="Center"
Tapped="Cardback_Tapped" />
</Grid>
</Grid>
```

With the UI for one card created, the rest of the cards will be a piece of cake.

Adding Event Handling

You haven't finished the UI yet so it may seem premature to start talking about event handlers, but since there are only two that will be the same for every card location you might as well add them now. You will want to respond to `Tapped` events from each of the shape elements and the `TextBlock` element that represents the card back. You won't respond to events on the `Grid` elements in the `cardGrid` cells, so they are essentially inert.

Let's start with the square on a card. In the XAML for the `Rectangle` element, right-click the value of the `Tapped` property and select `Navigate to Event Handler` from the context menu. The `MainPage.xaml.cpp` file contents will be displayed and you'll see that an implementation for the `Shape_Tapped()` handler has been added. Return to the XAML and repeat the process for the `TextBlock` element that represents the card back. You have added all the handlers you need for the cards and you'll add the code for these later. Easy, wasn't it?

It would be nice to highlight the card that is under the mouse cursor when the game is played. One way to do this is to implement handlers for the `PointerEntered` and `PointerExited` events for the outer `Grid` element in a `cardGrid` cell that defines the background color for the cards as azure. You'll be able to implement these so the background color changes as the mouse cursor enters and exits the grid area. You can do this via the Properties pane, just for the experience.

Click the Grid element with the azure color and display the Properties pane for it. Display the event handlers for the element by clicking the button at the top of the Properties pane. Enter Card_Entered as the value for the PointerEntered event and press Enter. This will create the handler implementation and display it. Return to the XAML and repeat the process for the PointerExited event. The value for the PointerExited event can be Card_Exited. Both handlers will deal with any card.

You can now deal with defining the other card positions in the UI.

Creating All the Cards

You have 23 more cards to create in the UI. When you have completed these you'll appreciate the ability to collapse the XAML for parent elements. Repeating the preceding process 23 times would be very tedious indeed, but fortunately there's a shortcut. The contents of cardGrid cell (1,0) will be exactly the same as that for grid cell (0,0) apart from the value of the Grid.Row attached property in the Grid element that defines the background color, which will be "1". Thus you can create the contents of cardGrid cell (1,0) by copying the Grid XAML element, including its child elements, and setting the value of Grid.Row to "1". The new Grid element will be:

```
<Grid Grid.Row="1" Grid.Column="0" Background="Azure" Margin="5"
    PointerEntered="Card_Entered" PointerExited="Card_Exited">
    <Grid Margin="10" Width="50" Height="50">
        <!-- ... Rectangle, Ellipse, Polygon and TextBlock elements as before...-->
    </Grid>
</Grid>
```

The child elements stay exactly the same. The Shape_Tapped() handler will be called for the Tapped event for all shapes, and Tapped events originating from any of the TextBlock elements representing card backs will be handled by the Cardback_Tapped() function. The Card_Entered() and Card_Exited() handler functions will process events from both Grid elements.

Of course, you can create the XAML for cardGrid cells (2,0) and (3,0) in exactly the same way; just change the values of the Grid.Row property for each to "2" and "3". When you have completed that you'll see the entire first column of the grid is populated with cards in the Design pane.

The XAML for the cards in column two of cardGrid will be the same as the XAML for column one, except that the Grid.Column attached property value in the Grid elements will be "1". Therefore, you can create the XAML for column two by duplicating the four Grid elements that define column one cards, and setting the Grid.Column attached property value for each Grid element in the new set to "1". I'm sure you'll be able to deduce how to fill the remaining columns of cardGrid. When you are done, there should be 24 Grid elements, each with the same children, and 24 identical cards in the Design pane. You should be able to compile and execute MemoryTest now and see how the UI looks. It's a good idea to execute the program with the Simulator Debugger because it will execute in a context that simulates a tablet. If you select the down arrow to the right of Local Debugger on the Debug toolbar, you can select Simulator Debugger from the drop-down list. The application window in the simulator should look like Figure 18-9.




FIGURE 18-9

NOTE Visual Studio has advanced features that allow you do define resources that you can use as templates in your XAML. This would allow you to define the nature of a card once in a resource and use the resource to define each card in the UI. This means that if you later needed to change the cards, you would only have to change the resource.

Implementing Game Operations

You need to put the framework in place in the `MainPage` class to make the game work as you want. You will need a few additional data members as well as a number of additional functions. You can do this manually or use the capabilities in Class View you are familiar with for adding members to a class. I'll assume in the text that you'll just add the code directly to the `.h` or `.cpp` file for the `MainPage` class, but you can use Class View facilities if you want.

First you must decide what you want to do and how it's going to work. You need to be able to set up the elements in each `cardGrid` cell so that they each represent a particular card. For this you need access to the `Grid` element in each cell, the `Grid` element that contains, and the child shape elements and `TextBlock` element that define the front and back of each card. You'll be referencing the elements that define a card often so you won't want to extract them every time. None of them have names, so you must find and store references to them somehow.

The route to finding the elements is through the value of the `Children` property for a parent element. The value of the `Children` property for `cardGrid` is a collection of its child elements, which are the `Grid` elements in the cells that provide the background color for the cards. You can extract references to these `Grid` objects from the collection, and extract the child elements of each in a similar way to obtain references to the `Grid` elements containing the shapes and the `TextBlock`.

You will obviously need to store the references that you extract, and arrays are probably the best choice because there will be 24 of each type.

You will need functions in `MainPage` to do the following:

- A `setUpUIState()` function that will set up the arrays that store the references to the elements in `cardGrid` and set their initial state.
- An `InitializeCardPack()` function to create a pack of 24 cards. It will be easiest to keep the definition of a pack of cards separate from the XAML elements that represent cards in the UI. This means you'll also need to define a `Card` class to represent a card.
- An `InitializeGame()` function that will set up a new game with cards randomly shuffled.
- There are several discrete operations you need in the `MainPage` class that each will require a function member.

You will probably also need some helper functions to keep the code for a function to a reasonable number of lines. The `MainPage` constructor will also have to be extended to initialize your own data members. You also have to implement all the handler functions. There's a way to go yet!

Before you start extending the `MainPage` class, let's get the definition of the `Card` class out of the way.

Defining the Card Class

A card is defined by the type and color of the shape on the front of the card plus the `TextBlock` object that defines the back. You can define this class as a ref class type for the experience. Add a header file to the `MemoryTest` project with the name `Card.h`. You can press **Ctrl+Shift+A** to open the dialog to do this. You can add the basic definition for the class as:

```
#pragma once
namespace MemoryTest
{
    ref class Card
    {
        // Members to be defined...
    };
}
```

The class must be defined within the project namespace, `MemoryTest`. You could define it as public to get it into the `.winmd` file but you don't need to.

You will use a `Card` object in two ways. First, it will be a specification for a particular card with a given type and color of shape. Second, you will use it to represent that card in a particular grid cell of `cardGrid`. Thus, an array of 24 `Card` objects can define the shuffled pack of cards and also identify the objects in the UI corresponding to those cards.

A `Card` object must be able to identify what the shape is and its color to represent a particular card. You can store the type of shape as a handle to a `String` object that is the name of the class type for the shape: "Ellipse", "Rectangle", or "Polygon". You can store the color as a handle to a `SolidColorBrush` object. This is a good choice because the value of the `Background` property for a shape is of type `Brush`, and `Brush` is the base class for `SolidColorBrush`. The reference to the

specific shape object in `cardGrid` can be any of the three types of shapes, so you'll store this as a handle to the base class type for shapes, which is type `Shape` in the `Windows::UI::Xaml::Shapes` namespace. The handle to the element that is the back of the card in `cardGrid` can be a handle to a `Windows::UI::Xaml::Controls::TextBlock` object. If you make these public properties of the class, they will be easy to access. Here's the complete `Card` class definition:

```
#pragma once
namespace MemoryTest
{
    public ref class Card sealed
    {
        public:
            Card() {}

        // Copy constructor
        Card(Card^ card)
        {
            type = card->type;
            color = card->color;
            shape = card->shape;
            back = card->back;
        }

        public:
            property Platform::String^ type;                                // Shape type
            property Windows::UI::Xaml::Media::SolidColorBrush^ color;    // Shape color
            property Windows::UI::Xaml::Shapes::Shape^ shape;              // Shape handle
            property Windows::UI::Xaml::Controls::TextBlock^ back;         // The card back
    };
}
```

The class must be specified as `sealed` because it defines public constructors. If you don't define it as `sealed`, the code will not compile. You don't need to define any function members beyond the default constructor and the copy constructor. You will need the copy constructor to create pairs of identical cards.

Adding Data Members to the `MainPage` Class

You can make all the members you add to the `MainPage` class `private`. The first data member to add to `MainPage` will store the number of cards:

```
size_t cardCount;                                         // The number of cards
```

You'll initialize this in the `MainPage` constructor. Next you can add arrays to store the handles to the shapes in `cardGrid` to the `MainPage` class definition:

```
Platform::Array<Windows::UI::Xaml::Controls::Grid^>^ grids;
Platform::Array<Windows::UI::Xaml::Shapes::Ellipse^>^ circles;
Platform::Array<Windows::UI::Xaml::Shapes::Rectangle^>^ squares;
Platform::Array<Windows::UI::Xaml::Shapes::Polygon^>^ triangles;
Platform::Array<Windows::UI::Xaml::Controls::TextBlock^>^ cardBacks;
```

These arrays will each have `cardCount` elements.

You will also need an array of Card objects:

```
Platform::Array<Card^>^ cardPack; // The pack of cards
```

This requires an #include directive for Card.h to be added to MainPage.xaml.h. You'll create the array in the MainPage constructor with cardCount elements, each storing a handle to a Card object. You'll be shuffling the handles in this array for a new game arrangement because this array is the deck of cards for the game.

You can add members that are handles to String objects that will store the type names for the child elements in cardGrid:

```
// Type names for card elements
Platform::String^ typeCircle;
Platform::String^ typeSquare;
Platform::String^ typeTriangle;
```

You will initialize these in the MainPage constructor. You will be able to obtain the type name for the object referenced by a handle of type Shape^ and compare it to these type name variables to determine the precise type of the Shape object referenced by the handle. There will be other data members added when you get to implement the event handlers, but that will suffice for now.

Adding Function Members

You can add the three functions identified earlier:

```
private:
    // Game functions
    void InitializeCardPack(); // Initializes cardPack to hold two of each card
    void SetUpUIState(); // Initializes the child elements of cardGrid

    void InitializeGame(); // Sets up a game with a shuffled cardPack
```

If you put outline definitions for these functions in MainPage.xaml.cpp, the application should be compilable:

```
// Initialize the pack of cards so it contains 12 different pairs
void MainPage::InitializeCardPack()
{
    // Code to be added here...
}

// Sets up the initial state of the UI and stores elements in grid cell order
void MainPage::SetUpUIState()

{
    // Code to be added here...
}
```

```
// Shuffle the cards and deal
void MainPage::InitializeGame()
{
    // Code to be added here...
}
```

The basic initialization for the game will be done in the `MainPage` constructor, so let's look at that next.

Initialize the MainPage Object

All the basic initialization for the game will be done in the `MainPage` class constructor. The default implementation includes a call to the `InitializeComponent()` function that sets up the UI components. Be sure to put any code that references UI component objects after this function call. You can amend the constructor definition to the following:

```
MainPage::MainPage()
{
    InitializeComponent();

    // cardCount is number of rows x number of columns in cardGrid
    cardCount = cardGrid->ColumnDefinitions->Size*cardGrid->RowDefinitions->Size;

    // Initialize type names for card elements
    typeCircle = Ellipse::typeid->FullName;
    typeSquare = Rectangle::typeid->FullName;
    typeTriangle = Polygon::typeid->FullName;

    // Create arrays that will store element handles for the cards
    // Each type is in a separate array and will be stored in sequence
    circles = ref new Array<Ellipse^>(cardCount);
    triangles = ref new Array<Polygon^>(cardCount);
    squares = ref new Array<Rectangle^>(cardCount);
    cardBacks = ref new Array<TextBlock^>(cardCount);
    grids = ref new Array<Grid^>(cardCount);

    InitializeCardPack();
    SetUpUIState();

    InitializeGame();
}
```

After initializing `cardCount` to the number of cells in `cardGrid`, you initialize the members that store the type names for the shapes. The expression `Ellipse::typeid` results in a handle to an object of type `Platform::Type` that identifies the `Ellipse` type. The value of the `FullName` property for a `Type` object is a `String` object containing the type name for the type. Every WinRT object inherits the `GetType()` function from the `Object` base class that returns a handle to the `Type` object for the object's type. Thus you can get the type name for the actual type for a shape object that is referenced through a `Shape^` handle by calling its inherited `GetType()` member.

The arrays that hold handles for the `Grid` objects in `cardGrid` and the child elements of the `Grid` objects each have `cardCount` elements. After the basic data initialization in the constructor, you call the three new function members of the class to initialize the card pack, set up the states of the UI elements, and initialize the game with a shuffled card pack.

To use the shape type names without qualifying them with the namespace name, you need to add the following using directive to the beginning of `MainPage.xaml.cpp`:

```
using namespace Windows::UI::Xaml::Shapes;
```

Initializing the Card Pack

You are going to create `cardCountCard` objects and store the handles in the `cardPack` array. The `Card` objects must consist of 12 pairs of identical objects. The 12 different cards comprise cards with three different shapes in each of four different colors. You can create this by iterating over the shape colors in a loop, and over the shape types in an inner loop. Here's how that looks:

```
void MainPage::InitializeCardPack()
{
    // Create arrays of the shape types and colors
    Array<String^>^ shapeTypes = {typeCircle, typeSquare, typeTriangle};
    Array<SolidColorBrush^>^ colors = {
        ref new SolidColorBrush(Windows::UI::Colors::Red),
        ref new SolidColorBrush(Windows::UI::Colors::Green),
        ref new SolidColorBrush(Windows::UI::Colors::Blue),
        ref new SolidColorBrush(Windows::UI::Colors::Yellow)
    };

    // Initialize the card pack
    cardPack = ref new Array<Card^>(cardCount);
    size_t packIndex(0);                                // Index to cardPack array
    Card^ card;
    for(auto color : colors)
    {
        for(auto shapeType : shapeTypes)
        {
            card = ref new Card();                      // Create a card...
            card->type = shapeType;                    // with the current type...
            card->color = color;                      // ... and color
            card->shape = nullptr;                     // we will find the shape...
            card->back = nullptr;                      // ...and back later.
            cardPack[packIndex++] = card;              // Store the card in the pack...
            cardPack[packIndex++] = ref new Card(card); // ...and a copy.
        }
    }
}
```

You first create arrays holding the possible colors and shape type. You initialize the elements in the `cardPack` array with two copies of each `Card` representing a card with a given shape of a particular color. After executing this function, the `cardPack` array will contain a representation of the pack of 24 cards arranged in sequence. They will need to be shuffled for a game.

Setting Up the Child Elements of `cardGrid`

The `SetUIState()` function will set the elements in each cell of `cardGrid` so only the back of the card is visible. This implies setting the child shape elements for each cell in `cardGrid` as not visible. Whether or not an element is visible is determined by the value of its `Visibility` property. This

can be one of two values, `Visible` or `Collapsed`, where these values are defined by the `Visibility` enum class in the `Windows::UI::Xaml` namespace.

The function will also store the handles to the `Grid` elements in the `grids` array, and store the handles to the shapes that are children of a `Grid` child to an element in the `shape` array of the appropriate type. You want all the elements in the arrays that store handles to shapes, card backs, and grids to be in the same order as their occurrence in `cardGrid`. Here's the code:

```
void MainPage::SetUpUIState()
{
    // Handle to the collection of grids in cardGrid
    auto elements = cardGrid->Children;

    UIElement^ element;           // Handle to a collection element
    Grid^ grid;                  // Grid^ handles in the grids array in sequence
    UIElementCollection^ shapes; // Handle to collection of shapes in child-grid
    UIElement^ shape;            // Handle to a shape in a child-grid

    int row(0);                 // Grid row location
    int column(0);               // Grid column location
    int index(0);                // Index to shape arrays
    unsigned int rowLength(cardGrid->ColumnDefinitions->Size); // Length of a grid row

    // Iterate over the child elements to cardGrid and store
    // the Grid^ handles in the grids array in sequence
    for(size_t i = 0 ; i < elements->Size ; ++i)
    {
        element = elements->GetAt(i);           // Get next grid child...
        String^ elementType = element->GetType()->FullName; // ...and get its type
        if(Grid::typeid->FullName == elementType) // Make sure it's a Grid
        {
            grid = safe_cast<Grid^>(element);
            row = cardGrid->GetRow(grid);          // Get the grid row
            column = cardGrid->GetColumn(grid);      // and column location.
            index = row*rowLength + column;           // Index for row/column
            grids[index] = grid;                     // Save the grid

            // A grid in each cell contains another grid as child.
            // We know that's always the case so get the child-grid:
            grid = safe_cast<Grid^>(grid->Children->GetAt(0));

            shapes = grid->Children;                // Get the child shapes
            // Iterate over the child elements to the current Grid and store
            // the shape element handles in the array for their type in sequence
            for(size_t j = 0 ; j < shapes->Size ; ++j)
            {
                element = shapes->GetAt(j);           // Get child shape handle
                elementType = element->GetType()->FullName; // and its type

                // Store a circle in circles array & do the same for the other elements
                // Only card backs will be visible - all other shapes collapsed.
                if(typeCircle == elementType)
                {
                    circles[index] = safe_cast<Ellipse^>(element);
                    element->Visibility = Windows::UI::Xaml::Visibility::Collapsed;
                }
            }
        }
    }
}
```

```
        }
        else if(typeSquare == elementType)
        {
            squares[index] = safe_cast<Rectangle^>(element);
            element->Visibility = Windows::UI::Xaml::Visibility::Collapsed;
        }
        else if(typeTriangle == elementType)
        {
            triangles[index] = safe_cast<Polygon^>(element);
            element->Visibility = Windows::UI::Xaml::Visibility::Collapsed;
        }
        else if(TextBlock::typeid->FullName == elementType)
        {
            cardBacks[index] = safe_cast<TextBlock^>(element);
            element->Visibility = Windows::UI::Xaml::Visibility::Visible;
        }
    }
}
}
```

Handles to child elements are stored as type `UIElement^` in a collection of type `UIElementCollection`. `UIElement` is the base type for all UI element types. The way you access the child elements of a parent is to obtain a handle to the collection of child elements from the value of its `Children` property. You then iterate over the elements in the collection and cast the `UIElement^` handles you get to the type of element actually stored. With child elements of `cardGrid` it's easy because the handles are all of type `Grid^` and each of these has a child element that is a `Grid`. With child elements of these `Grid` objects you have to do a little work to determine the type of handle you obtain from each collection.

The value of the `Size` property for a `UIElementCollection` object is the number of elements in the collection, so you can use this in a `for` loop to iterate over the entire collection. The `GetAt()` function for a `UIElementCollection` object returns a handle of type `UIElement^` that is the object handle stored at the index position specified by the argument to the function. The outer loop iterates over the collection of `Grid` child elements in `cardGrid`. The `GetRow()` and `GetColumn()` functions for a `Grid` object return the row and column index, respectively, for the child element referenced by the handle you pass as the argument. For each inner `Grid` element, you iterate over the collection of its child elements. By comparing the type name of each child element with the type names for the shape classes, you are able to determine the type of element referenced by the handle and store the handle in the appropriate array.

The conversion of child elements handles is done using `safe_cast`, which will throw an exception if the cast is not valid.

Initializing the Game

The game play involves turning up two cards to see if they match. You will need to record the two cards that are turned up, the count of pairs found, and the handles to the `Card` objects in the pairs that have been found. Add the following private members to the `MainPage` class:

```

// Game records
Card^ card1Up;                                // 1st card turned up
Card^ card2Up;                                // 2nd card turned up
int pairCount;                                 // Number of pairs found
Platform::Collections::Vector<Card^>^ pairsFound; // Pairs found in the game

```

`card1Up` and `card2Up` will store handles to the cards turned up. `pairCount` will record the number of pairs found, and when this reaches 12 the game is over. `pairsFound` will record handles to the `Card` objects in the pairs. You'll use this to manage what cards can cause events.

You can initialize these in the constructor:

```

 MainPage::MainPage() : card1Up(nullptr), card2Up(nullptr), pairCount(0)
{
    InitializeComponent();

    // cardCount is number of rows x number of columns in cardGrid
    cardCount = cardGrid->ColumnDefinitions->Size*cardGrid->RowDefinitions->Size;
    pairsFound = ref new Platform::Collections::Vector<Card^>(cardCount);

    // Code as before...
}

```

Initializing the game involves shuffling the cards, so you can add a `private` function member, `ShuffleCards()`, to the `MainPage` class definition:

```
void ShuffleCards();
```

You can add a content-free definition to `MainPage.xaml.cpp` that you'll complete in the next section:

```

void MainPage::ShuffleCards()
{
    // Code to be added later...
}

```

The `InitializeGame()` function must shuffle the cards in `cardPack`, then set up the elements in `cardGrid` to reflect the order of the cards in `cardPack`. It will also ensure that the UI elements just display the card backs. Here's the code to do that:

```

void MainPage::InitializeGame()
{
    card1Up = card2Up = nullptr;                                // No cards up
    pairCount = 0;                                              // No pairs found
    pairsFound->Clear();                                       // Clear pairs record

    // Null the handles to UI elements
    for(auto card : cardPack)
    {
        card->shape = nullptr;
        card->back = nullptr;
    }
}

```

```

        ShuffleCards();                                     // Shuffle cardPack

        // Set the shapes in the Grid elements to represent the cards dealt
        for(size_t i = 0 ; i < cardCount ; ++i)
        {
            cardPack[i]->back = cardBacks[i];

            if(cardPack[i]->type == typeCircle)
            {
                circles[i]->Fill = cardPack[i]->color;
                cardPack[i]->shape = circles[i];
            }
            else if(cardPack[i]->type == typeSquare)
            {
                squares[i]->Fill = cardPack[i]->color;
                cardPack[i]->shape = squares[i];
            }
            else if(cardPack[i]->type == typeTriangle)
            {
                triangles[i]->Fill = cardPack[i]->color;
                cardPack[i]->shape = triangles[i];
            }
            cardPack[i]->shape->IsTapEnabled = true;

            // Set up UI to show card backs & enable events
            cardBacks[i]->Visibility = Windows::UI::Xaml::Visibility::Visible;
            cardBacks[i]->IsTapEnabled = true;

            // Ensure background grids are hit test visible & opaque
            grids[i]->IsHitTestVisible = true;
            grids[i]->Opacity = 1;

            // Ensure all shapes are invisible & opaque
            circles[i]->Visibility = Windows::UI::Xaml::Visibility::Collapsed;
            squares[i]->Visibility = Windows::UI::Xaml::Visibility::Collapsed;
            triangles[i]->Visibility = Windows::UI::Xaml::Visibility::Collapsed;
            circles[i]->Opacity = 1;
            squares[i]->Opacity = 1;
            triangles[i]->Opacity = 1;
        }
    }
}

```

After the game records have been reset, the first loop nulls the handles to shapes and card backs in the Card objects. The second loop sets the shape property value of each Card object to a handle to the appropriate shape from one of the shapes arrays. It also sets the back property value to a handle for the corresponding card back element. The loop also resets grids, card backs, and shapes to their initial state. An Opacity property of 1 is completely opaque. Setting the IsHitTestVisible property value for an element to true allows hit testing to work in the area of the element. This means that the mouse cursor being over the element can be detected, for example. Setting the value to false would prevent the mouse cursor from causing events when it is in the area occupied by the element.

Shuffling the Cards

You can use the `random_shuffle()` function that is defined in the STL `algorithm` header with elements stored in a `Platform::Array` object. There are two versions of the function. The simple version takes two arguments that are iterators specifying the first and one-past-the-last items in the sequence to be shuffled. To get the begin and end iterators for the array of cards, you must use `begin()` and `end()` functions to which you pass the array reference. These are not STL functions but special versions of `begin()` and `end()` that are from the `Windows::Foundations::Collections` namespace.

The `random_shuffle()` function uses the `rand()` random number generator from `stdlib.h` seeded with a default value for the shuffle and thus the results are entirely repeatable so you will always get the same sequence of shuffled card decks. However, you can seed the random number generator with the current time to get random shuffles, like this:

```
 srand(static_cast<unsigned int>(time(nullptr)));
```

The `time()` function returns the current time as the number of seconds elapsed since midnight on 1st January 1970. The argument can be a pointer to a variable in which you want the time to be stored. The function returns -1 if something goes wrong. The time value is of type `time_t`, which is an integer type. You can add the preceding statement to the `MainPage()` constructor right after the call to `InitializeComponent()` because it has to be seeded before any call to `random_shuffle()`.

The implementation of the `ShuffleCards()` function to produce a shuffled deck is just one statement:

```
 void MainPage::ShuffleCards()
{
    std::random_shuffle(begin(cardPack), end(cardPack));
}
```

This uses the `begin()` and `end()` functions to create iterators for the `cardPack` array that you pass to the `random_shuffle()` function. This shuffles the `Card` object references in the array.

You need to add the following directives to the beginning of `MainPage.xaml.cpp`:

```
#include <algorithm>
#include <ctime>
```

The `algorithm` header is for the `random_shuffle()` function and the `ctime` header provides the `time()` function.

Highlighting the UI Cards

Highlighting a card when the mouse cursor is over it is implemented through the `Card_Entered()` and `Card_Exited()` handler functions. You could highlight a card simply by changing its color, which means changing the value of the `Background` property for the `Grid` object in the `Card_Entered()` handler:

```

void MemoryTest:: MainPage::Card_Entered(Platform::Object^ sender,
                                         Windows::UI::Xaml::Input::PointerRoutedEventArgs^ e)
{
    safe_cast<Grid^>(sender)->Background = steelBrush;
}

```

You know that `sender` is really a handle to an object of type `Grid` so you cast it to type `Grid^`. You set the value of the `Background` property to the color provided by a `SolidColorBrush` object that is referenced by `steelBrush`. You can add this handle and a handle to a `SolidColorBrush` of the original color as a class member to avoid creating an object each time the handler is called.

Add the following to the `MainPage` class as private members:

```

Windows::UI::Xaml::Media::SolidColorBrush^ steelBrush; // Card highlight color
Windows::UI::Xaml::Media::SolidColorBrush^ azureBrush; // Card normal color

```

You can initialize these in the `MainPage` constructor:

```

MainPage:: MainPage() : card1Up(nullptr), card2Up(nullptr), pairCount(0)
{
    InitializeComponent();

    // Brushes for card colors
    steelBrush = ref new SolidColorBrush(Windows::UI::Colors::SteelBlue);
    azureBrush = ref new SolidColorBrush(Windows::UI::Colors::Azure);

    // Rest of the code as before...
}

```

A card will be returned to its original color by the `Card_Exited()` handler:

```

void MemoryTest:: MainPage::Card_Exited(Platform::Object^ sender,
                                         Windows::UI::Xaml::Input::PointerRoutedEventArgs^ e)
{
    safe_cast<Grid^>(sender)->Background = azureBrush;
}

```

If you recompile and execute the application, you should be able to see card highlighting in action.

Handling Card Back Events

Clicking the back of a card turns over the card. This is handled by the `Cardback_Tapped()` member of `MainPage`. If it is the first card turned over, then the function is done.

If another card is already turned over, which is signaled by `card1Up` being non-null, then the card originating the current `Tapped` event is the second card. In this case the function must check if the two cards are the same. If they are the same, a pair has been found, so the function will update `pairCount` and disable events for the cards that are turned up. It will also store handles to the pair in the `pairsFound` vector. It will also fade the cards a bit to show they are no longer in the game.

If they are not the same, you want the player to click either upturned card to turn them both back over before trying for another pair. To ensure that this happens, the function should disable events for all the other cards, which will be showing the backs. When the front of one card of the pair is

clicked, the `Shape_Tapped()` handler will be called, which should turn over both cards to show the backs and restore events to all the other card backs.

Here's how the code for `Cardback_Tapped()` looks to do that:

```
void MemoryTest:: MainPage::Cardback_Tapped(Platform::Object^ sender,
                                            Windows::UI::Xaml::Input::TappedRoutedEventArgs^ e)
{
    // There may be 0 or 1 cards already turned over
    // If there is 1, the card handle will be in card1Up
    TextBlock^ cardBack = safe_cast<TextBlock^>(sender); // Always a card back handle
    cardBack->Visibility = Windows::UI::Xaml::Visibility::Collapsed; // Hide the back

    // Find the card for the back so the shape can be made visible
    Card^ theCard(nullptr);
    for(auto card : cardPack)
    {
        if(cardBack == card->back)
        { // We have found the card so show the front
            card->shape->Visibility = Windows::UI::Xaml::Visibility::Visible;
            theCard = card;
            break;
        }
    }
    if(card1Up == nullptr)
    {
        card1Up = theCard;
    }
    else
    {
        card2Up = theCard;
        if(card1Up->type == card2Up->type && card1Up->color == card2Up->color)
        { // We have a pair!
            pairsFound->Append(card1Up);
            pairsFound->Append(card2Up);
            DisableCardUp(card1Up);
            DisableCardUp(card2Up);
            card1Up = card2Up = nullptr;
            if(++pairCount == cardCount/2)
                GameOver();
        }
        else
        { // Two cards up but no pair so we now want a Tapped event on either
            // Disable Tapped event for card backs and PointerEntered
            // and PointerExited events for other cards
            for(size_t i = 0 ; i < cardBacks->Length ; ++i)
            {
                if(cardBacks[i] == card1Up->back || cardBacks[i] == card2Up->back)
                    continue;

                cardBacks[i]->IsTapEnabled = false;
                grids[i]->IsHitTestVisible = false;
            }
        }
    }
}
```

After hiding the card back that originated the event by setting its `Visibility` property to `Collapsed`, the function searches `cardPack` to find the `Card` object with this back. It is then able to show the front of the card by setting the `Visibility` property value for the shape to `Visible`. It then checks for one or two cards up and proceeds as I described at the beginning of this section. If the `pairCount` reaches half the number of cards in the pack, all pairs have been found, so the `GameOver()` function is called to end the game. Add this function as a `private` member of the `MainPage` class:

```
void GameOver();
```

Add a skeleton implementation to the `.cpp` file:

```
void MainPage::GameOver()
{
    // Code to be added later...
}
```

The `Cardback_Tapped()` function also calls a helper function, `DisableCardUp()`, so add the following as a `private` member of the `MainPage` class:

```
void DisableCardUp(Card^ card);
```

The implementation in `MainPage.xaml.cpp` will be:

```
void MainPage::DisableCardUp(Card^ card)
{
    card->shape->IsTapEnabled = false;           // Disable Tapped event...
    card->shape->Opacity = 0.5;

    // Get the parent Grid for shape
    auto grid = safe_cast<Grid^>(card->shape->Parent);
    grid = safe_cast<Grid^>(grid->Parent);

    grid->IsHitTestVisible = false;                // Disable hit test
    grid->Background = azureBrush;                 // Make sure of color
    grid->Opacity = 0.5;
}
```

This disables the `Tapped` event for the `Card` object referenced by the argument and sets the value of its `Opacity` property to 0.5, which will make it semi-transparent. The function also disables hit testing for the parent `Grid` object and sets its `Opacity` to 0.5. It is possible that the background color could be the highlight color so this is set to the normal color to make sure.

Handling Shape Events

When a `Tapped` event for a `Shape` object occurs, there must be at least one card face up since the event could not occur otherwise, and there may be two cards face up. If there's just one, the function should just turn the card face down. If there are two, they represent a failed pair selection so `Tapped` events from the backs of the other cards will be disabled. Thus for two cards up the function must turn the cards over, then enable `Tapped` events for all the backs that are not pairs.

Here's the code for Shape_Tapped():

```
void MemoryTest:: MainPage::Shape_Tapped(Platform::Object^ sender,
                                         Windows::UI::Xaml::Input::TappedRoutedEventArgs^ e)
{
    // With this event there is always at least one card up but could be two.
    // If only one card is up, the handle is in card1Up
    Shape^ shape = safe_cast<Shape^>(sender);
    if(card1Up != nullptr && card2Up != nullptr)
    { // Two cards up so turn over both cards
        card1Up->shape->Visibility = Windows::UI::Xaml::Visibility::Collapsed;
        card1Up->back->Visibility = Windows::UI::Xaml::Visibility::Visible;
        card2Up->shape->Visibility = Windows::UI::Xaml::Visibility::Collapsed;
        card2Up->back->Visibility = Windows::UI::Xaml::Visibility::Visible;

        // Enable events for all card backs and background grids
        for(size_t i = 0 ; i < cardBacks->Length ; ++i)
        {
            if(IsFound(cardBacks[i]))
                continue;

            cardBacks[i]->IsTapEnabled = true;
            grids[i]->IsHitTestVisible = true;
        }
        card1Up = card2Up = nullptr; // Reset both handles to cards up
    }
    else
    { // only one card up and it was clicked so turn over the card
        card1Up->shape->Visibility = Windows::UI::Xaml::Visibility::Collapsed;
        card1Up->back->Visibility = Windows::UI::Xaml::Visibility::Visible;
        card1Up = nullptr;
    }
}
```

This function also calls a helper function, `IsFound()`, that checks whether a card back belongs to a card in a previously found pair. Add the following to the `MainPage` class, in a private section as always:

```
bool IsFound(Windows::UI::Xaml::Controls::TextBlock^ back);
```

The implementation of the function is:

```
bool MainPage::IsFound(TextBlock^ back)
{
    for(auto cardFound : pairsFound)
    {
        if(cardFound && cardFound->back == back) return true;
    }

    return false;
}
```

This iterates over the cards in the `pairsFound` vector. When the `back` property value for a card in the vector is the same as the argument handle, the function returns `true`. If no card is found, `false` is returned.

At this point you should be able to try out the game. Nothing happens when you find all the pairs and you can't start a new game yet.

Recognizing a Win

The `GameOver()` function is called when all pairs have been found. The success should be acknowledged in some way. You could display a message in the message area that recognizes the win. Return to `MainPage.xaml`. Add a `RichTextBlock` control to the `messageAreaGrid` element at the bottom of the game grid. You can specify the text using a `Paragraph` element, as you did with the game title. The XAML for the `messageArea` element should now be:

```
<Grid x:Name="messageArea" Grid.Column="1" Grid.Row="2" Margin="10,0,0,0"
    Background="Bisque">
    <RichTextBlock x:Name="winMessage" Opacity="0" FontFamily="Freestyle Script"
        FontWeight="Bold" FontSize="90" TextAlignment="Center" Foreground="Red">
        <Paragraph>
            <Run Text="YOU WIN!!!" />
        </Paragraph>
    </RichTextBlock>
</Grid>
```

Note that the `Opacity` property value for the `RichTextBlock` element is 0, so the text will not be visible. The `GameOver()` function that is called when all pairs have been found can display the content for the `winMessage` element by setting the value for its `Opacity` property to 1.0:

```
void MainPage::GameOver()
{
    winMessage->Opacity = 1.0; // Show the win message
}
```

There may be other messages in the message area so it would be a good idea to provision for hiding any other messages that appear there. You could do this by adding a helper function to the `MainPage` class, which you could implement like this:

```
void MainPage::HideMessages()
{
    auto messageCollection = messageArea->Children;
    for(size_t i = 0 ; i < messageCollection->Size ; ++i)
    {
        safe_cast<FrameworkElement^>(messageCollection->GetAt(i))->Opacity = 0;
    }
}
```

This function obtains the collection of child elements for the `Grid` element, `messageArea`. The `GetAt()` function returns a handle to a child element in the collection as type `UIElement`. All the controls have `UIElement` as a base class but the `UIElement` class does not define the `Opacity`

property. This is defined in the `FrameworkElement` class that is derived from `UIElement`, which is also a base class for all control element classes. Thus by casting the handle to type `FrameworkElement^`, you can make the child control transparent by setting its `Opacity` property value to 0, regardless of the type of control.

You can call this helper function in the `GameOver()` function:

```
void MainPage::GameOver()
{
    HideMessages();                                     // Hide any other messages
    winMessage->Opacity = 1.0;                         // Show the win message
}
```

When you find all the pairs, the win message will magically appear.

Handling Game Control Button Events

There are just two `Button` elements in the `Grid` element at the left of the card grid that are game controls. Add `Tapped` event handlers for these with the names `Start_Tapped` and `Show_How_Tapped` through the Properties pane for each.

Let's implement the handler for the Start button first. When the Start button event occurs, the game should be reset to its initial state with all messages hidden and a new game started with the cards shuffled. This is not too taxing:

```
void MemoryTest::MainPage::Start_Tapped(Platform::Object^ sender,
Windows::UI::Xaml::Input::TappedRoutedEventArgs^ e)
{
    HideMessages();                                     // Clear the message area
    InitializeGame();                                  // Reset the game
}
```

You have already done the work necessary. Calling `HideMessages()` clears the message area and `InitializeGame()` sets up the cards and elements in `cardGrid` for a new game.

The `Show_How_Tapped()` handler just needs to display the instructions in the message area. The first step is to add another `RichTextBlock` element as a child of the `messageArea.grid`. You can do this in the Design pane. Be sure that you add the `RichTextBlock` element to the `Grid` element, and not as a child of the `RichTextBlock` element for the win message. You can specify the content with `Paragraph` elements, like this:

```
<RichTextBlock x:Name="playMessage" Opacity="0" FontFamily="Freestyle Script"
Margin="10 0 0 0">
<Paragraph FontFamily="Verdana" FontSize="30" FontWeight="Bold"
Foreground="Green">
<Run Text="How to Play:"/>
</Paragraph>
<Paragraph FontFamily="Verdana" FontSize="20" FontWeight="Normal"
Foreground="Black">
<Run Text="The idea is to find all the pairs of matching cards "/>
<Run Text="by turning up two at a time."/>
```

```

</Paragraph>
<Paragraph FontFamily="Verdana" FontSize="20" FontWeight="Normal"
           Foreground="Black">
    <Run Text="If you find a pair, they will fade "/>
    <Run Text="and you can try for another pair."/>
</Paragraph>
<Paragraph FontFamily="Verdana" FontSize="20" FontWeight="Normal"
           Foreground="Black">
    <Run Text="If two cards don't match, click either to turn them back over."/>
</Paragraph>
<Paragraph FontFamily="Verdana" FontSize="20" FontWeight="Normal"
           Foreground="Black">
    <Run Text="Click the Start button for a new game."/>
</Paragraph>
</RichTextBlock>

```

Of course, these elements appear just before the end tag for the `messageAreaGrid` element. The `Margin` property value inset the text in the `Paragraph` elements from the left edge of the grid. You can see from this that you can set individual text characteristics for each `Paragraph` element. The first has a `FontSize` property value of "30" while the other elements display the text in a 20-point font. You can set any of the text properties individually in each `Paragraph` element, including the text color. Each `Paragraph` element starts a new line. If the content for a `Paragraph` element does not fit on a single line within the width of the parent, the content will spill automatically. The `Opacity` property for the `RichTextBlock` element is "0", so it will not be visible initially.

NOTE You must not split the string for the value of a `Text` property in a `Run` element over two or more lines but you can put the text in several `Run` elements as in the preceding code.

All you need to do is display the `playMessage` element when the `Show_How_Tapped()` event handler is called:

```

void MemoryTest::MainPage::Show_How_Tapped(Platform::Object^ sender,
                                            Windows::UI::Xaml::Input::TappedRoutedEventArgs^ e)
{
    HideMessages();                                         // Clear the message area
    playMessage->Opacity = 1;                             // Show the instructions
}

```

You should now have a fully working game. Figure 18-10 shows the game in progress.




FIGURE 18-10

The game works but there is a limitation. The shapes on the front of the cards do not scale. They have fixed dimensions determined by the inner grid element that is their parent. Let's see how we can fix that.

SCALING UI ELEMENTS

We need to keep the height and width of the `Grid` element that is the parent of the shapes equal because that makes the `Rectangle` element a square and the `Ellipse` element a circle but we don't want it to be fixed. The outer `Grid` element that is the parent of the `Grid` element with a fixed size will vary its size according to the context and will automatically adjust if the application UI is resized. If we can define the height and width of the inner `Grid` in terms of the dimensions of the outer `Grid` element that defines the background for a card, that should do the trick.

You can implement this in a handler for the `Loaded` event for the `Page` root element for the UI. The handler for this event will be called when the complete page has been created so the UI element dimensions will have been determined. It is also called if the application is resized. Windows 8 apps cannot be resized easily but it will occur if you resize the simulator window. This means that you can define the inner `Grid` dimensions in terms of the outer `Grid` height in this handler and it will automatically adjust the sizes of the shapes so they fit.

Add the Loaded property to the XAML for the Page element with the value as "Page_Loaded", like this:

```
<Page
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    xmlns:local="using:MemoryTest"
    xmlns:d="http://schemas.microsoft.com/expression/blend/2008"
    xmlns:mc="http://schemas.openxmlformats.org/markup-compatibility/2006"
    x:Class="MemoryTest.MainPage"
    IsTabStop="false"
    mc:Ignorable="d"
    Loaded="Page_Loaded">

    <!-- All the UI elements -->

</Page>
```

Right-click the handler name and select Navigate to Event Handler. You can implement the handler like this:

```
void MemoryTest:: MainPage::Page_Loaded(Platform::Object^ sender,
                                         Windows::UI::Xaml::RoutedEventArgs^ e)
{
    // Scale all card shapes so they squarely fit their grid cells.

    // Iterate over all children of the cardGrid grid.
    for (unsigned int i = 0; i < cardGrid->Children->Size; ++i)
    {
        // Get the small grid in each cell.
        Grid^ grid = safe_cast<Grid^>(cardGrid->Children->GetAt(i));

        // Get the small grid inside the small grid.
        Grid^ childGrid = safe_cast<Grid^>(grid->Children->GetAt(0));

        // Calculate the scaling factor to keep everything square.
        auto scale = grid->ActualHeight / childGrid->ActualHeight * 0.7;

        // Apply scaling factor.
        auto scaleTransform = ref new ScaleTransform();
        scaleTransform->ScaleX = scale;
        scaleTransform->ScaleY = scale;
        childGrid->RenderTransformOrigin = Point(0.5, 0.5);
        childGrid->RenderTransform = scaleTransform;
    }
}
```

This iterates over all the children of cardGrid that are the outer Grid elements. You define the height and width of the inner Grid element that houses the shapes to be 70% of the least of the inner Grid height and width. This will accommodate cards in portrait or landscape orientation. Scaling is achieved using a ScaleTransform object. The ScaleTransform class is defined in the Windows::UI::Xaml::Media namespace. The ScaleX and ScaleY property values specify the scaling factor to be applied in the x and y dimensions. You apply the scaling transform by defining the

`RenderTransform` property value for `childGrid` to be the `ScaleTransform` object that you created. The `RenderTransform` property value specifies a transformation that is to be applied when `childGrid` is rendered along with its children. The `RenderTransform` property is inherited from `UIElement`, so you can define a transform for any element type that has `UIElement` as a base and the transform will be applied to the element as well as any child elements when it is rendered.

Of course there's huge potential for enhancing the game further. I'll finish by introducing one more thing you can do in a Windows 8 app.

TRANSITIONS

Transitions are elements that provide the capability for animation of UI elements. The WinRT types for transition elements are in the `Windows::UI::Xaml::Media::Animation` namespace. I'll just introduce you to a couple of animations in `MemoryTest`.

Application Startup Transitions

The `EntranceThemeTransition` element provides animation for controls when they are first displayed. When you apply it to a parent element with children such as `cardGrid`, the child elements will appear in sequence, rather than all together. This makes the initial presentation of the game window more pleasing. Here's how you can implement an `EntranceThemeTransition` for `cardGrid` child elements:

```
<Grid x:Name="cardGrid" Grid.Row="1" Grid.Column="1" Margin="32">

    <Grid.RowDefinitions>
        <!-- Elements defining the rows... -->
    </Grid.RowDefinitions>
    <Grid.ColumnDefinitions>
        <!-- Elements defining the columns... -->
    </Grid.ColumnDefinitions>

    <!-- Animate the display of the cards -->
    <Grid.ChildrenTransitions>
        <TransitionCollection>
            <EntranceThemeTransition/>
        </TransitionCollection>
    </Grid.ChildrenTransitions>

    <!-- Child elements defining the cards... -->
</Grid>
```

`Grid.ChildrenTransitions` is an attached property for a `Grid` element that is inherited from the `Panel` class. It has a property value of type `TransitionCollection` that represents a collection of one or more transitions. Transitions are objects that have `Transition` as a base class. The `Transition` class is in the `Windows::UI::Xaml::Media::Animation` namespace. There is just one element in the `TransitionCollection` for `cardGrid` and that is an `EntranceThemeTransition`. This transition does what you see for elements when they are first displayed. With these additional elements in `cardGrid`, the cards will animate into view in sequence when the application starts. You can apply this to any element or set of elements to get this behavior when the application is first displayed.

Storyboard Animations

I hope the second transition I'll introduce will open the door to you exploring more possibilities. I'll apply this transition to the button that shows how to play the game. This is much more complicated than the cardGrid transition because it introduces several elements involved in defining transitions, so this requires more concentration than the previous animation.

The transition you will use applies to a transform for the button that is in the StackPanel element in the game controls grid. The Button element with the Content value "How to Play" will have a child element that specifies the transform. The XAML for the button is now this:

```
<Button Content="How to Play" FontSize="20" Foreground="Red" Background="Gray"
       BorderBrush="Black" Height="90" Width="150" HorizontalAlignment="Center"
       Tapped="Show_How_Tapped">
    <!-- This defines a transform that applies to the button -->
    <Button.RenderTransform>
        <RotateTransform x:Name="buttonRotate" />
    </Button.RenderTransform>
</Button>
```

`Button.RenderTransform` is an attached property that has a value of type `RotateTransform` here. The content can be any element that has `Transform` as a base class, which includes `ScaleTransform`, `SkewTransform`, or `TranslateTransform`. A transform element can be subject to an animation that operates on a property of the transform. In the case of the `RotateTransform`, the property you are going to manipulate is `Angle`, which has a value that is the angle through which the element to which the transform applies — the button in this case — is rotated.

The mechanism for the manipulation of the `Angle` property value for the `RotateTransform` element that is applied to the button will be provided by a `StoryBoard` element that controls one or more animations specified by its child elements. The `StoryBoard` element will be defined as a resource for the `StackPanel` that is the parent for the button. You define it as a child of a `StackPanel.Resources` element, which is an attached property of the `StackPanel` element.

NOTE You can also define resources at a global level for your application.

A `StoryBoard` element has child elements that each define an animation. The `StoryBoard` element can control the start time and duration of the animations that are its children through its `Duration` and `BeginTime` property values, and the child elements can also specify these properties independently. You are going to keep it very simple and just apply one animation. This will be a `DoubleAnimation` element that can animate any value of any property as long as the value is of type `double`. The animation varies the value linearly between two values. You specify the range of the values with the `From` and `To` properties for the `DoubleAnimation` element. You can specify the time over which the variation will occur by the value of the `Duration` property for the element. The value for `Duration` is of the form "`hh:mm:ss[.fractional seconds]`" where `hh` is from 0 to 23 hours,

`mm` is from 0 to 59 minutes, and `ss` is from 0 to 59 seconds and you can optionally specify fractions of a second. You specify the `BeginTime` value in the same way. The value for `BeginTime` is the delay before the animation starts.

Here's the complete set of XAML for the `Grid` element that contains the buttons, including the animation:

```
<!-- Game controls-->
<Grid Grid.Row="1" Grid.RowSpan="2" Background="Bisque" Margin="0,10,0,0">
    <Grid.RowDefinitions>
        <RowDefinition Height="1*" />
        <RowDefinition Height="1*" />
    </Grid.RowDefinitions>
    <Button Grid.Row="0" Content="Start" FontSize="32" Foreground="Red"
        Background="Gray" BorderBrush="Black" Height="90" Width="150"
        HorizontalAlignment="Center" VerticalAlignment="Center" Tapped="Start_Tapped"/>

    <StackPanel x:Name="ButtonPanel" Grid.Row="1">
        <!-- This Child element contains resources that can be used in the panel -->
        <StackPanel.Resources>

            <!-- This defines one or more animations as a resource.
                The value for x:Name is the name you use in C++ to start
                the animation.
            -->
            <Storyboard x:Name="playButtonTurn">

                <!-- This defines an animation that will start 5 seconds after
                    the animation is initiated. The animation and its reverse
                    will each last 3 seconds.
                -->
                <DoubleAnimation From="1" To="90" Duration="00:00:3" BeginTime="00:00:5"
                    Storyboard.TargetName="buttonRotate"
                    Storyboard.TargetProperty="Angle"
                    AutoReverse="True">

                    <!-- The easing function determines how the animation operates.
                        This particular easing function defines an elastic animation
                        by its springiness and the number of oscillations.
                    -->
                    <DoubleAnimation.EasingFunction>
                        <!-- This function specifies how the Angle property value
                            changes.
                        -->
                        <ElasticEase Oscillations="5" Springiness="1"
                            EasingMode="EaseOut"/>
                    </DoubleAnimation.EasingFunction>
                </DoubleAnimation>
            </Storyboard>
        </StackPanel.Resources>

        <Button Content="How to Play" FontSize="20" Foreground="Red"
            Background="Gray" BorderBrush="Black" Height="90" Width="150"
            HorizontalAlignment="Center" Tapped="Show_How_Tapped">
    
```

```

<!-- This defines a transform that applies to the button -->
<Button.RenderTransform>
    <RotateTransform x:Name="buttonRotate" />
</Button.RenderTransform>
</Button>
</StackPanel>
</Grid>

```

You start the animation in C++ by calling the `Begin()` function for the `Storyboard` object that you can reference through the handle, `playButtonTurn`. The value of the `Storyboard.TargetName` attached property in the `DoubleAnimation` element identifies the transform to which the child animation applies. This is the name for the `RotateTransform` for the button. The `From` and `To` property values in the `DoubleAnimation` element specify the range over which the `Angle` property for the `RotateTransform` will be varied by the animation. Here it's from 0 to 90 degrees. The `Angle` property is identified by the value of the `Storyboard.TargetProperty` attached property. Specifying `AutoReverse` as "True" for the `DoubleAnimation` element causes the animation to execute forward, then in reverse. The value for the `Duration` property applies to both.

The algorithm that the `DoubleAnimation` applies to the property it is animating is defined by an *easing function*. There are several elements defining easing functions and the corresponding WinRT types are in the `Windows::UI::Xaml::Media::Animation` namespace. My choice is the `ElasticEase` function. This has a `Springiness` property that determines the springiness of the animation. The larger the value for this property, the more elastic the animation is. The `Oscillations` property value is the number of oscillations in the animation. Other easing function elements include `BounceEase`, `CubicEase`, `QuarticEase`, `QuinticEase`, and `SineEase`.

You can initiate the animation when the How to Play button is clicked:

```

void MemoryTest::MainPage::Show_How_Tapped(Platform::Object^ sender,
                                            Windows::UI::Xaml::Input::TappedRoutedEventArgs^
e)
{
    HideMessages();                                         // Clear the message area
    playButtonTurn->Begin();                                // Start the animation
    playMessage->Opacity = 1;                               // Show the instructions
}

```

If you have entered all the XAML and code correctly, you should see an interesting effect after 5 seconds when you click the button.

SUMMARY

As I said at the beginning, this chapter is a brief introduction to programming for Windows 8 apps. I have had to omit a lot of detail and just pick what I think are the features that you need to understand at the outset. My objective with this chapter has been to show that while developing a Windows 8 app is not trivial, it's not that difficult. There's a lot of code involved, but when you break it down it's easy to manage. I hope I have given you enough of an insight to delve deeper into writing Windows 8 app.

► WHAT YOU LEARNED IN THIS CHAPTER

TOPIC	CONCEPT
Windows 8 apps	A Windows 8 app is targeted at tablets or desktop PCs running Windows 8 and executes in a sandbox that limits access to resources in the environment in which it is running.
Windows Runtime (WinRT)	WinRT is the Windows API for Windows 8 apps. It is an object-oriented API that is language neutral, and WinRT objects are COM objects. WinRT objects are reference counted.
C++/CX	C++/CX is a set of Microsoft-specific extensions to standard C++ that make it easier to work with the WinRT. C++/CX includes the ability to define class types that are compatible with WinRT, and to define handle types that can store handles to ref class objects.
XAML	XAML is a language used for specifying the user interface in a Windows 8 app. When an application is compiled, code is generated that creates the UI elements defined by the XAML.
XAML elements	A XAML element is defined by a start tag and an end tag or by a start-end tag. A XAML element can contain other elements called child elements. Start and end tags for XAML elements must not overlap. An end tag must always apply to the immediately preceding start tag.
XAML files	A XAML file comprises a set of nested XAML elements with a single root element. Each page in the UI for a Windows 8 app is defined by a separate XAML file.

INDEX

Symbol

-- operator, 368–369
& (ampersand)
 address-of operator, 155
 bitwise operator, 71–72
 lvalues and rvalues and, 180, 182
 as menu shortcut, 672
&& (ampersands)
 AND operator, 107
 rvalue references and, 182
#include directive, 32–33
* (asterisks)
 declaring pointers and, 154–155, 236
 indirection operator, 156
/* and */, comments and, 31
// (slashes)
 comments and, 31
 start and end tags and, 864
:: (scope resolution operator), 82–84, 86
[] (square brackets)
 deleting arrays and, 176, 179
 function pointer array elements
 and, 241
 as subscript operator, 424
^ (hat symbol)
 ref class objects and, 861
^ operator (bitwise exclusive OR), 73–74
_ (underscore), variable names and, 39
{ } (curly braces)
 case statements and, 112
 if statements and, 100
 if-else statements and, 105
 initializing arrays and, 144, 152
| (bitwise OR operator), 72–73

|| (OR operator), 107–108
~ (bitwise NOT operator), 74
+ operator, concatenating strings with, 420,
 421
++ (increment operator), 62–63, 368–369
+= operator, concatenating strings
 with, 421
<!--, XAML comments and, 864–865
< > (angled brackets) header files and, 32
< operator
 CBox objects and, 399
 overloading, 350
<< operator (bitwise shift), 74–76
<= operator, CBox objects and, 399
= (assignment operator), 98
!= operator, CBox objects and, 399
== (equal to operator)
 basics of, 97–98
 CBox objects and, 399
 comparing variables and constants and,
 100
-> (indirect member selection operator),
 291, 350, 861
-->, XAML comments and, 864–865
> operator, comparing strings and, 431
>> operator (bitwise shift), 74–76
. (member selection operator), 283, 348
; (semicolons)
 assignment statements and, 55
 declarations and, 41, 153
 else keywords and, 104
 function prototypes and, 199
 if statements and, 99
 for loops and, 119
 macros and, 827

, (commas)
 initializing arrays and, 144, 152
 in numbers, 43
:: (colon)
 namespaces and, 33
 scope resolution operator, 197, 350
. . . (ellipses)
 exception declarations and, 246
 in function definitions, 218
() (parentheses)
 around dereferenced pointers, 290–291
 expressions between, 273–274
 extract() function and, 275–276
 overriding operator precedence and, 66
 sizeof operator and, 164
 std::min and std::max and, 724
 () operator, 505
! operator, 108

A

A<pair<K, T>> allocator type, 498
A<T> allocator type, 498
abstract classes, 478–481
access control
 in classes, basics of, 295
 inheritance and, 451–454, 461–462
accumulate() algorithm, 580
accumulate() template function, 533
Add Member Variable Wizard, 407, 678–682, 793–794, 810, 811
Add New Item dialog, 29
addition operators, overloading, 363–368
addresses
 pointer arithmetic and, 168
 returning from functions, 222–223
address-of operator
 & (ampersand), 155
AddSegment() function
 drawing curves and, 728–729
 implementing, 730
algorithms, 504–505, 588–591

alignment
 when creating triangles, 880
 when printing, 851
allocators, 498
AND operator (&&), 107
animate controls, 777
animation, transitions and, 903, 904–906
anonymous unions, 348–349
append() function, strings and, 425
application class
 MFC, 652–653
 Windows programming and, 632
Application Type option (MFC Application Wizard), 645–646
Application Wizards. *See also* MFC
 Application Wizard
 output, 644
 printing and, 839, 845
 serialization and, 822, 824
 A Simple Program (example) and, 27–31
 various, 610
applications
 basics of writing, 2
 console. *See* console applications
 desktop, 2–5
 MDI, creating, 659–661
 MFC, creating, 644–645
 SDI, creating, 645–649. *See also* MFC
 Application Wizard output
 Windows, creating and executing, 20–23
Arc() function, 700–701
Area() function, 286
arguments. *See also* functions, passing
 arguments to
 defined, 194
 function arguments, omitting, 242–243
 passed to WindowProc() function, 626
 pointers to functions as, 239–240
 type arguments, using containers and, 557–558
arithmetic expressions, in assignment statements, 35

arithmetic operations
 basics of, 55–56
 calculating results, 60
`const` keyword, 58
 constant expressions, 58
 displaying results, 60–61
Exercising Basic Arithmetic (example),
 56–57
 operators, 261
 with pointers, 168–169
 program input, 59

array containers
`array<T, N>` template, 506–508
`array<T, N>` template, 530
 basics of, 496, 530–533
 members of derived class objects, 531
Using Arrays (example), 531–533

arrays. *See also* multidimensional arrays
 allocating memory dynamically for, 176–179
Array Names as Pointers (example), 169–171
Arrays of Pointers (example), 161–163
 basics of, 139–141
 character arrays, strings and, 147–150
 declaring, 141–144
 defined, 44
 initializing, 144–146
 of objects, 324–325
 one-dimensional, defined, 150
 passing to functions, 206–210
 pointers and, 167
 of pointers to functions, 241–242
 range-based `for` loop, using with, 146
`sort<T>()` function template and, 525

Arrow Keys property, 792

ASCII codes
 character data types and, 44
`if` statements and, 101, 102

`ASSERT_VALID()` macro, 736

`assign()` function
 lists and, 542
 vectors and, 520

assignment operators, overloading, 358–363
 assignment statements, 35, 237
 assignments, type conversion and, 67–68
 associative containers
 basics of, 506, 565
 map containers. *See* map containers
 multimap containers, 578–579
 associativity, operator precedence and, 66
`at()` function
 accessing string characters and, 424
 containers and, 570
 vectors and, 516
 attached properties (XAML), 868

attributes
 defined (XAML), 863
 device contexts and, 693

`auto` keyword, 69–70, 146, 237, 861

automatic storage duration, 78
 automatic variables, 78–80
`average()` function template, lambda
 expressions and, 597

B

`back()` function
 queue containers and, 550
 vectors and, 517

`back_insert_iterator<T>`, 580–581

base classes
 access control and, 451–454
 basics of, 447–451
 constructors in, 454
 derived classes and, 447, 448–451, 457
 destructors and, 483, 485, 486
 direct and indirect, 447
 levels of, 481–483
 MFC, 648–649
 pointers to, 474–476

`basic_string<T>` class template, 183, 418

`begin()` member function, containers and, 510, 511, 570

bidirectional iterators, 500

binary operations, defined, 56, 506

- binding, early and late, 471
- bitwise operators
 - basics of, 70–71
 - bitwise AND (& $\&$), 71–72
 - bitwise exclusive OR (^), 73–74
 - bitwise NOT (~), 74
 - bitwise OR (|), 72–73
 - shift operators, 74–76
- block scope, automatic variables
 - and, 78
- body of functions, 195, 197
- Boolean variables, 46
- borders (windows), 607
- Box.h files
 - basics of, 405
 - class definitions and, 407, 415
 - creating, 405
 - `operator*()` and `operator/()` functions and, 411
- BoxSurface() function, 316
- brushes, 617, 704–706, 861
- buddy controls, 791, 792
- buffer arrays, 262
- building projects, defined, 22
- buttons. *See also* toolbar buttons
 - adding transitions to, 904–906
 - button-tapped events, 862
 - editing, 685–686
 - game control buttons, adding, 876–878
- C**
- `c_str()` function, converting strings objects with, 427
- C++ 11 standard, initializing arrays and, 146
- C++ program structure, 26–27
 - #include directive, 32–33
 - automatically generated console programs, 37–39
 - comments and, 31–32
 - console program structure, 26–27
 - declarations, using, 33–34
 - `main()` function, 34
- namespaces, 33–34
- Simple Program (example), 27–31
- statement blocks, 37
- whitespace, 37
- C++ programming basics, 1–24
 - C++ language, 3
 - desktop applications, 2–5
 - dockable toolbars, 9–10
 - IDE basics, 5–8
 - options, setting, 19–20
 - product documentation, 10
 - projects. *See* projects and solutions
 - toolbar options, 8–9
 - Windows applications, creating and executing, 20–23
 - Windows programming and, 3
 - writing applications, 2
- C++ standard library
 - headers, 93
 - namespaces and, 90, 342
- C++/CX
 - basics of, 857
 - event handler functions, 862
 - namespaces, 857–858
 - `ref` class object members, accessing, 861
 - `ref` class references, casting, 862
 - `ref` class types, variables of, 861
 - WinRT class types, defining, 858–860
- calculating, 55–66
 - arithmetic operations. *See* arithmetic operations
 - assignment statements, 55
 - Comma Operator (example), 64
 - enclosing rectangles for, 723
 - increment and decrement operators, 62–63
 - remainders, 61
 - sequence of, 65–66
 - variables, modifying, 61–62
- calculator program. *See* functions, creating program using
- calling conventions, 613
- capture clauses, lambda expressions and, 593–594

CArchive class, serialization and, 824–826
Card class, defining, 884–885
Cardback_Tapped() member of MainPage, 894–895, 896
cards. *See* game cards
case
 keywords and, 40
 variable names and, 39
case values and case labels
 Sharing a Case (example), 113–114
 switch statements and, 111–112
casting, 66–69, 467, 862
casts, explicit type conversion and, 68–69
catch blocks, 244–247, 249
catch keyword, 244, 246, 249
catching exceptions, 244–247
CBottle class, 466–468
CBox class. *See also* classes, using
 adding member function to (example), 298–300
 CBox objects, creating with Visual C++, 11, 309
 Constructor, Adding to (example), 303–304
 constructors and, 310, 456–457, 462–463
 defined, 293
 defining, 292, 478–479
 derived classes and, 448, 450–451
 nested classes and, 489–491
 operator overloading and, 350–354, 363–368
 virtual functions and, 468–469
CBox class, Multifile Project Using (example)
 constructor, adding, 407–408
 data members, adding, 407
 defining, 406–407
 function members, adding, 408–411
 global functions, adding, 411–413
 output, 415–416
 project creation, 404–405
 using, 413–415
CCan class, Volume() function and, 480
CCandyBox class
access control and, 451–454
constructors and, 457, 462–465
derived classes and, 448, 450–451
protected class members and, 458–460
CCircle class, 725–728, 836
CCClientDC class, 697
CCContainer class
 defining CBox class as subclass of, 478–479
 nested classes and, 489–491
ccctype header, functions provided by, 268–269
CCurve class, 728–730, 836
CDC class
 basics of color drawing, 701–703
 brushes and, 704–706
 circles, 699–701
 for drawing, 697
 drawing in color. *See* MFC drawing in color
 graphics, displaying, 697–699
 pens, using, 703–704
 __cdecl modifier, 613
CElement base class, 719–720
CGlassBox class
 inheritance and, 481–482, 483
 nested classes and, 489–491
 virtual keyword and, 471–473
char array, 147
char variables, declaring, 44
char* const pointer to characters, 167
char* pointers, 159
character arrays, strings and, 147–150
character data types, 44–45
Character Map utility, 45
character strings
 vs. null-terminated strings, 418
 string and wstring classes and, 418
CheckMenuItem() member (CMenu class), 757–758
child elements (XAML), 863
child windows, 607, 618
circles
 CCircle class, 725–728
 CCircle constructor, 788

circles (*continued*)
design of game cards and, 880
drawing, 699–701, 706–707, 727–728, 739
class constructors
 Adding Constructor to CBox class
 (example), 303–304
 basics of, 302–303
 default, 304–306
 default parameter values, 307–309
 initialization lists as, 309
 making explicit, 310–311
class context menu (MFC), 644
class destructors
 basics of, 338
 default destructors, 338–340
 dynamic memory allocation and,
 341–344
class keyword, 256, 292, 295
class templates, 382–392
 basics of, 382–383
 defined, 183
 defining, 383–386
 for function objects, 392
 with multiple parameters, 390–392
 objects, creating from, 386–389
 for sequence containers, 506–508
 template member functions, 385–386
class types, casting between, 467
Class View tab
 MFC, 651–652
 Windows programming, 12
Class Wizard, 717–718, 779–780, 812
classes
 arrays of objects, 324–325
 basics of, 291–293, 294–295, 445–447
 class constructors. *See* class constructors
 class derivation, preventing, 465–466
 class terminology, 294
 const objects, 321–324
 data members, accessing, 296
 declaring objects of, 295–296
 defining, 293, 295, 822–823, 856
 deriving from base classes, 448–451
 dialog classes, creating, 810–811
 element classes, defining, 715–718
 in examples, 481
 First Use of Classes (example), 296–298
 friend classes. *See* friends
 to handle menu messages, 676
 implementing, serialization and,
 823–826, 829
 inheritance in. *See* inheritance
 inline functions, 301–302
 macros that add serialization to, 827
 member function definitions, 300–301
 member functions of, 298–300
 MFC basic classes, 643–644
 MFC document template classes, 641–643
 nested, 487–491
 operations on, 293–294
 Pointers to Classes (example), 330–332
 pointers to objects, 329–330
 private members of. *See* private class
 members
 references to class objects, 329, 332–334
 serializing element classes, 833–837
 Sketcher program, 666–667
 static members, 326–329
 vs. structs, 295
 vs. structures, 292
 this pointer, 318–321
 unions in, 349
 viewing (MFC), 651–652
 windows vs. C++ classes, 617
classes, using, 396–416
 analyzing objects, 402–404
 class interfaces basics, 396–397
 combining objects, 400–402
 comparisons of objects, 399–400
 packaging objects, 397
 valid objects and, 397–399
cleanup after printing, 847
clear() function, 542, 571
client area (windows), 608, 619, 627–629,
 691–692, 714–715
client coordinates
 basics of, 750, 797–799
 dealing with, 751–753

CLine class
 drawing and, 720–723
 serialization and, 835
 clip rectangles, 852
 CMainFrame class, 654–655
 CMessage class
 assignment overloading and, 359
 copy constructor, 344
 destructor, 342–343
 named objects as lvalues and, 376–379
 object copying and, 371
 CMultiDocTemplate class (MFC), 642, 644
 CMyApp class (MFC), 643
 CMyDoc class (MFC), 643
 CMyView class (MFC), 643
 CMyWnd class (MFC), 643
 CObject-based classes, serialization and, 826–827
 code
 for chapters, 1
 object code, compiler and, 6
 program code, organizing, 416–418
 source code, example of modifying, 13–14
 collocation, 436–441
 colons (:) :)
 namespaces and, 33
 scope resolution operator, 82–84, 86
 color
 of brushes, 704, 861
 classes to handle Color menu messages and, 676
 Color menu message handlers, creating, 676–678
 Color menu message handlers, implementing, 678–682
 Color menus, 674, 755–756
 color type, defining, 680–681
 drawing in color. *See* MFC drawing in color
 highlighting keywords and, 30, 40
 initializing color type members, 681
 language elements and, 17
 of lines, 702–703
 of pens, 721, 731–733
 store color, adding members to, 678–679
 styling windows and, 617
 toolbar buttons and, 685, 686
 Comma Operator (example), 64
 command lines, output to, 50–51
 command messages
 classes to handle menu messages, 676–677
 defined, 667
 menu message handlers, implementing, 678–682
 processing, 670
 command update handlers, 683–684
 comments, 31–32
 common controls, 777
 comparators, 498–499
 Compare() function, 320, 322–323, 332
 comparison operators
 comparing strings and, 428–432
 expressions and, 391–392
 overloading, 354–358
 compiler, 6
 compiling, Simple Program example and, 31
 Component Object Model (COM), WinRT objects and, 856–857
 compound statements, 37
 concatenating strings, 420–423
 conditional operators, for comparing numeric values, 109–110
 console applications
 basics of, 4
 Empty Console Project, Creating (example), 16–19
 files created by building, 15
 vs. Windows programs, 4
 console programs
 automatically generated, 37–39
 structure. *See* C++ program structure
 const char* pointer, 167
 const function (), 321–324
 const keyword
 arithmetic operations and, 58
 member functions and, 322–323

const modifier, 212–214
const qualifier, 333
const variable types vs. literals, 58
`const_cast<>()`, 66–69
`const_pointer_cast`, 504
constant expressions, arithmetic operations and, 58
constant time, 517
constants
 hexadecimal constants, 45
 pointers to, 165–167
 windows displaying and, 614
 windows styling and, 615–617
constructors. *See also* class constructors; copy constructors
 adding, 407–408
 base classes vs. derived classes and, 457
 `CCircle`, 726–727, 788
 `CLine`, 721
 `Crectangle`, 724, 788
 `CText`, 813
 default, 382
 default parameters and, 307–309
 in derived classes, 454–458
 inheritance and, 447
 `MainPage`, 887
containers
 basics of, 496–499
 container adapters, 499
 range of, 506
 sequence containers. *See* sequence containers
context menus
 associating with view class, 756–757
 basics of implementing, 754–756
 Color menu and, 755–756
 elements under cursors and, 760
 items, checking, 757–758
continue statements, executing within loops, 122–124
control variables, 793
controls
 adding to dialog boxes, 777–779
 basics of, 776–777

control elements (XAML), 869
control menu (windows), defined, 607–608
control notification messages, 667
dialog controls, supporting, 783–786
edit box controls. *See* `CText` class; edit box controls
game controls, adding, 876–878
spin button controls. *See* spin button controls
tab sequence, 792–793
conversion, type, 59
cooperative multitasking, 622–623
`copy()` algorithm, 584, 586
copy constructors
 basics of, 317–318
 in derived classes, 462–465
 implementing, 333–334, 344–346
 rvalue reference parameters, applying, 375–376
copying. *See also* copy constructors
 buffer arrays, 262
 null-terminated strings, 185
 objects. *See* object copying
`_countof()` macro, 147, 164
`cout`. *See* `std::cout`
`CPoint` class, 837
.cpp extension, 22
.cpp files
 basics of, 22, 405, 407, 416–417
 console program files and, 415
 global functions and, 412, 413
.h files and, 412
`CPrintInfo` class, 841–843
`Create()` function
 status bar panes and, 805
 windows class and, 633–634
`CreateElement()` function, 735–736, 789–790
`CreatePen()` function, 701–702, 721, 722, 761–762
`CreateWindow()` function, 617–619
Creating a Project for a Win32 Console Application (example), 11–13

Creating an Empty Console Project (example), 16–19
C
 CRectangle class, 723–725, 836
 CS_HREDRAW, 616
 CScaleDialog class, 793–796
 CSingleDocTemplate class (MFC), 642
 CSketcherDoc class
 initializing color and element type
 members and, 681
 members, adding (color and element mode and), 679–680
 menu message handlers and, 676–677
 CSketcherView class, 695
 CStack class, 488–489
 CString class, 807–808
 cstring header
 basics of, 182–183
 functions and, 341–342
 functions of. *See* null-terminated strings
 C-style strings, 147
 CText class
 constructor, 813
 objects, drawing, 815–816
 objects, moving, 816–818
 serialization and, 837
 text elements, creating, 813–815
 CTextEditorApp class, 653–654
 CTextEditorDoc class, 655–656
 CTextEditorView class, 656, 657
 curly braces ({}). *See* {} (curly braces)
 current position, 697
 curves
 CCurve class, 728–730
 constructor, modifying, 788–789
 drawing, 708, 739
 CWinApp class, 632–633
 CWnd class, message handling and, 669

D

dangling pointers, 176
 data
 data elements, 139
 data exchanges, dialogs and, 794–795

print data, storing, 844–845
 putting into struct members, 283
 data() function, string contents and, 427
 data members
 accessing, 296
 adding, 407, 885–886
 CPrintInfo class, 841–842
 defined, 292, 294
 static, 326–329
 data types
 basics of, 42
 Boolean variables, 46
 character, 44–45
 classes and structs, 292, 294
 defining, structs in C++. *See* structs
 defining synonyms for, 49–50
 floating-point numbers, 47
 fundamental, 42, 47–48
 integer type modifiers, 45–46
 integer variables, 42–44
 Windows, 610–611
 debugging
 Debug versions, 31
 MFC applications and, 657
 programs, 15
 decimal fractional values, 126
 declarations
 in header files, 34
 incomplete class declaration, 357, 476–477
 using, 33
 variable, 41–42, 80
 DECLARE_DYNCREATE() macro, 823, 826
 DECLARE_MESSAGE_MAP() macro, 653
 DECLARE_MESSAGE_MAP() macro, 666–667
 DECLARE_SERIAL() macro, 826, 827
 declaring
 arrays, 141–144
 arrays of pointers, 161–163
 arrays of pointers to functions, 241–242
 lvalue references, 180–181
 namespaces, 91–92
 objects of classes, 295–296
 pointers, 154–155, 236–237

declaring (*continued*)
 protected class members, 458–460
 variables, 41

decltype operator, 258–260

decoding Windows messages, 626–629

decrement operators
 arithmetic operations and, 62–63
 overloading, 368–369

decrementing pointers, 168

default capture clauses, 593

default class destructors, 338–340

default class members, 381–382

default constructors
 arrays of objects and, 324–325
 constructors and, 382

default copy constructors
 vs. assignment operators, 358–359
 CMessage class, 344
 private class members, 317–318

defining
 Card class, 884–885
 class templates, 383–386
 classes, 293, 295, 447
 game cards, 879
 projects, 10
 structs, 282–283
 variables, 39–40

definition
 of class template member functions, 385
 of classes, serialization and, 822–823
 of member functions, 300–301
 of variables, 41

DefWindowProc() function, 609

delegates (Windows 8 apps), 856, 862

delete operator
 class destructors and, 338
 cleaning free store with, 480–481
 dynamic memory allocation and, 174–176

DeleteElement() function, 748

deleting
 arrays, 176, 179
 elements, 517–520, 748, 764
 exceptions, 249

deque<T> container template, 506–508

dereference operator, 156
 * (asterisks), 156

de-referencing pointers, 156

derived classes
 access control and, 451–454
 base classes and, 447, 448–449, 457
 constructor operation in, 454–458
 copy constructors in, 462–465
 defined, 447
 inherited members of, 461–462
 pointers to functions, 474–476
 preventing, 466–467
 Using (example), 449–451

Design pane (Solution Explorer), 855, 865–866

desktop applications
 basics of, 2
 programming, 3
 vs. Windows 8 apps, 854

destructors
 default, 338–340
 for derived class objects, 460
 dynamic memory allocation and, 341–344
 in example classes, 484–485
 inheritance and, 447
 virtual, 483–486

device contexts
 defined, 628
 document printing and, 849–850
 GDI and, 722
 preparing for printing, 847–848
 working with, 693

device coordinates, 751–753, 797–799

dialog data validation, 795

Dialog Editor toolbar, 779

dialogs
 basics of, 776
 closing, 782–783
 data exchanges and, 794–795
 dialog classes, adding, 779–780
 dialog classes, creating, 810–811
 dialog controls, supporting, 783–786
 dialog data exchange, 795
 dialog data validation, 795

dialog resources, creating, 776–779
 displaying, 781–782
 elements in views, creating, 789–790
 exercising, 790–791
 initializing, 795–796
 modal and modeless, 780
 pen, 790–791
 programming for, 779–783
 testing, 779

direct base classes, 447

direct member selection operator, 296

directives, 32

DirectX, defined, 606

`DispatchMessage()` call, 622, 623

display context, 628

`DisplayMessage()` function, 346

dockable toolbars (IDE), 9–10

document class (MFC), 654–655

document interfaces (MFC), 640

document templates (MFC), 641–643

documentation (C++), 10

documents. *See also* serialization
 adding pen widths to, 787–788
 basics of, 640
 linking to views, 641–643
 printing. *See* printing
 size, setting, 799

`DoDataExchange()` virtual function, 794–795

`DoModal()` function, 780, 782, 785

double-ended queue containers
 sequence containers, 533–536
 vs. vectors, 534

do-while loops, 128–129

downloading code for chapters, 1

`Draw()` function
 `CCircle` class, 727
 `CCurve` class, 729–730
 `CElement` base class, 735
 `CLine` class, 722
 for `CText` object, 815
 highlighting elements and, 760, 761–762
 text elements, defining and, 812

drawing
 client area and, 619, 627–629
 in color. *See* MFC drawing in color
 `CText` objects, 815–816
 `DrawText()` function, 628–629
 MFC drawing. *See* MFC drawing
 in practice, 706–708
 redrawing windows, 615–616
 using mouse for. *See* mouse, using for
 drawing; mouse programming for
 drawing; `WM_MOUSEMOVE` message
 handler

drawing in windows, 691–743
 circles, 706–707
 client area and, 691–692
 curves, 708
 drawing mode, setting, 731–733
 GDI and, 692–695
 graphics, 706–708
 introduced, 691
 lines, 706
 mouse message handlers and, 731–733
 rectangles, 707–708

Dynamic Link Library (DLL), MFC library and, 647

dynamic linkage, 472

dynamic memory allocation
 allocating space in the heap, 174
 for arrays, 176–179
 class destructors and, 341–344
 copy constructors and, 346
 `delete` operator and, 175–176
 of multidimensional arrays, 179–180
 `new` operator and, 175–176

`dynamic_cast` operator, 487

`dynamic_cast<>()`, 66–69

`dynamic_pointer_cast`, 504

E

early binding, 471
 easing functions, 906

edit box controls
 basics of, 808–809
 CText class. *See* CText class
 dialog classes, creating, 810–811
 resources, creating, 809–810
 text elements, defining, 812
 Text menu item, adding, 811–812

editing
 menu resources, 671–674
 toolbar button properties, 686–687

editor, 6

Editor window, 8

Element pop-up menu properties, 673–674

elements
 adding pen widths to, 787–789
 adding to forward_lists, 548–549
 array, 140
 child elements of cardGrid, 888–890
 classes to handle menu messages and, 676
 createElement() function, 735–736
 creating in views, 789–790
 data, 139
 element classes, defining, 715–718
 language elements, color and, 6, 17–18
 list, 537–539
 mouse message handlers and,
 735–736
 serializing classes, 833–837
 text elements, creating, 813–815
 text elements, defining, 812
 vector elements, accessing, 516–517
 vector elements, sorting, 526–527
 visibility of, 871

elements (XAML)
 basics of, 863–865
 control, 869
 layout, 869–870
 parent and child, 869
 UI, 865–868

elements for sketching
 dropping, 770–771
 masked, 771–772
 moving and deleting, 754, 768–769

elements under cursors, identifying
 basics of, 758–759
 context menus and, 760
 deleting, 764
 dropping, 770
 elements moving themselves,
 768–769
 highlighting and, 760–763
 moving, 764–767
 views, updating, 767

ElementType
 defining, 680–681
 initializing, 681

ellipses (...), in function definitions, 218

Ellipse() function, drawing circles with,
 699–701, 728

else keyword, indentation and, 104

emplace() and emplace_back() functions,
 518–519

emplace() function template, 568

empty() function, containers and, 512, 550,
 554, 559, 571

encapsulation, 292, 294

end() member function, containers and, 510,
 511, 570

endl. *See* std::endl

EntranceThemeTransition element, 900

enum keyword, declaring variables and, 86

enumerations
 defined, 85
 old, 85–87
 type-safe, 87–88

enumerators, 85

erase() function
 containers and, 569–570
 lists and, 542
 map containers and, 578
 vectors and, 519

errors, dealing with, 18–19

escape sequences, 16, 53–55

Euclid's method, 601

Event Handler Wizard, 675–678

event handlers
 adding, 881–882
 functions (C++/CX), 862

- event handling
- card back events, 894–896
 - game control button events, 899–901
 - shape events, 896–898
 - for UI elements (XAML), 870–871
- event-driven programs
- defined, 4
 - Windows programs as, 609
- events
- defined (Windows), 4
 - in Windows applications, 609
- examples, listed. *See also* functions, creating
- program using
 - Abstract Classes, 478–481
 - Addition Operator, Exercising, 365–368
 - Arithmetic, Exercising Basic, 56–57
 - Array Names as Pointers, 169–171
 - Arrays, Passing, 206–207
 - Arrays, Using, 141–144, 531–533
 - Arrays of Class Objects, 324–325
 - Arrays of Pointers, 161–163
 - Automatic Variables, 78–80
 - Calling Wrong Destructor, 483–486
 - Catching Exceptions Thrown by new Operator, 249–251
 - CGlassBox, Fixing, 471–473
 - Class Template, Using, 387–389
 - Classes, Using, 296–298
 - CMessage Class, Using, 343–344
 - Comma Operator, 64
 - Complete Overloading of Comparison Operators, 355–358
 - const, Passing, 213–214
 - Constructors, Calling, 454–458
 - Copy Constructors Derived Classes, 462–465
 - Counting Characters Revisited, 171–172
 - Counting Instances of Class Types, 327–329
 - Creeping Inefficiencies, 379–381
 - Default Values for Constructor Arguments, Supplying, 308–309
 - Derived Classes, Using, 449–451
 - Destructor, Simple, 339–340
 - Efficient Object Copy Operations, 375–376
 - Empty Console Project, Creating, 16–19
 - Enumerations, Using, 88–89
 - Escape Sequences, Using, 54–55
 - Explicit Use of this, 319–321
 - Free Store, Using, 177–179
 - friend, Using to Calculate Surface Area, 314–317
 - Function Arguments, Omitting, 242–243
 - Function Pointers, Passing, 240–241
 - Function Templates, Using, 257–258
 - Functions, Using, 199–202
 - Inheritance, More Than One Level of, 481–483
 - Inherited Functions, Using, 470–471
 - Input Stream Iterators, Using, 580–582
 - lambda expressions, Using, 595–599
 - Lists, Working with, 540–541
 - Lucky Stars with Pointers, 159–161
 - Manipulators, Using, 52–53
 - Map Containers, Using, 571–578
 - Minimal MFC Application, 632–636
 - Multidimensional Arrays, Passing, 209–210
 - Multiple Strings, Storing, 152–154
 - Nested Classes, Using, 489–491
 - Nested try Blocks, 247–248
 - Object Copy Operations, Tracing, 372–374
 - Objects in Vectors, Storing, 521–526
 - Operator Overloading, 352–353
 - Output to the Command Line, 51
 - Overloaded Functions, Using, 252–254
 - Overloading Assignment Operators, 361–363
 - Pass-by-Pointer, 205–206
 - Pass-by-Reference, 211–212
 - Passing-by-Value, 204
 - Perfect Forwarding, 393–396
 - Pointer Notation When Passing Arrays, 207–208
 - Pointers, Using, 157–159
 - Pointers in Vectors, Storing, 527–529

examples, listed (*continued*)

- Pointers to Base and Derived Classes, 474–476
 - Pointers to Classes, 330–332
 - Pointers to Functions, 237–239
 - Predicate for Filtering Lists, 544–548
 - Private Data Members, 312–314
 - Private Members of Base Classes, Accessing, 452–454
 - Program, Simple, 27–31
 - Project for a Win32 Console Application, Creating, 11–13
 - Protected Members, Using, 458–460
 - Queue Containers, Using, 551–553, 554–559
 - Receiving a Variable Number of Arguments, 218–220
 - Receiving Command-Line Arguments, 217–218
 - Recursion in Lambda Expressions, 600–602
 - Recursive Functions, 228–231
 - References Returning, 224–226
 - References with Virtual Functions, Using, 476–477
 - Returning Bad Pointers, 221–222
 - rvalue Reference Parameters, Using, 214–216
 - Scope Resolution Operator, 82–84
 - sizeof Operator, Using, 163–165
 - Sorting Words from Text, 436–441
 - Stack Containers, Using, 560–561
 - Static Variables, Using in Functions, 227–228
 - Strings, Comparing, 429–432
 - Strings, Creating and Joining, 421–423
 - structs, Using, 284–287
 - Throwing and Catching Exceptions, 244–245
 - Vector Size and Capacity, Exploring, 513–516
 - Windows API Program, Simple, 630–631
- exceptions
- basics of, 243–244
- catching, 244–247, 249–251
 - defined, 175
 - handling of in MFC, 248–249
 - memory allocation errors and, 249–251
 - Nested try Blocks (example), 247–248
 - rethrowing, 248
 - throwing, 244–246
 - .exe files, linker and, 6
 - executable modules, creating (MFC), 657
 - executing
 - continue statements within loops, 122–124
 - for loops, 117–118
 - MFC applications, 22–23
 - programs, 16
 - projects and solutions, 16
 - Exercising Basic Arithmetic (example), 56–57
 - explicit type conversion, 60, 68–69
 - expr() function, 264–267
 - expressions
 - comparison operators and, 391–392
 - decltype operator and, 258–260
 - evaluating, 264–267
 - explicit type conversion and, 68
 - lvalues and rvalues and, 76–77
 - old-style casts and, 69
 - types of, 70
 - extended if statements, 102–104
 - extending
 - calculator program, 273–275
 - menus for elements and colors, 672–674
 - eXtensible Markup Language (XML), 863
 - extract() function, substrings and, 275–277
 - ExtTextOut() function, 815–816

F

- FALSE value, numeric type variables and, 46
- file scope, 80–82
- files
 - application files (MemoryTest project), 871–872
 - created by building console applications, 15

object files, defined, 6
 viewing project files (MFC), 651

fill() algorithm, 588

filtering lists (example), 544–548

final modifier, 465–466

find() algorithm, 589

find() function

- map containers and, 578
- searching strings and, 432–433

find_first_not_of() function, 440

find_first_of() and **find_last_of()**

- member functions, 433–436

find_first_of() function, 440

FindElement() function, 759

floating-point numbers, 47

floating-point value loop counters, 126

folders, project folders basics, 10

font (MemoryTest project), 875–877

for loops

- concatenating strings and, 423
- executing, 117–118
- Indefinite **for** Loop (example), 120–122
- for** Loop, Using (example), 116–117
- for** loop statement, in Pointer Notation
 - When Passing Arrays (example), 208
- Multiple Counters, Using (example), 119–120
- range-based, 129, 146
- variations, 118–119
- vs. while loops, 126

formatting output, 51–53

forward declarations, operator overloading and, 357–358

forward iterators, 500

forward_list container template, 506–508, 548–550

frame windows (MFC)

- defined, 633, 641
- frame window class, 653–654

frames, adding status bars to. *See* status bars, adding to frames

free store

- basics of, 174
- Free Store, Using (example), 177–179

friends

- friend** classes, 468
- friend** functions of classes, 314–317
- members as, 466–468

front() function

- lists and, 548
- queue containers and, 550
- vectors and, 517

front_insert_iterator<T>, 580–581

function adapters, 506

function call operator, overloading, 369–370

function members

- adding, 408–411, 886–887
- defined, 294
- preventing overriding of, 473–474

function objects

- defined, 369
- in STL, 505–506, 586–588
- templates for, 392

function overloading

- basics of, 251–252
- overload selection, 254
- Overloaded Functions, Using (example), 252–254
- reason to use, 255

function templates

- basics of, 198
- class templates and, 382

functional header, 587, 588

functional notation

- defined, 41–42
- wchar_t** variables and, 45

functions. *See also* library functions for strings; virtual functions

- advantages of, 195
- in **algorithm** header, 588
- alternative syntax, 198
- basics of, 34, 193–195
- in C++ programs, 26
- CCmdUI** class, 683
- defined, 26
- easing functions, 906
- event handler functions (C++/CX), 862
- function body, 195, 197

functions (*continued*)

- function headers, 195–196
 - function prototypes, 198–199
 - function templates, 255–258
 - globals, 30
 - initializing function parameters, 242–243
 - list functions, 537–539, 542–544
 - in MainPage (MemoryTest project), 884, 886
 - member function definitions, 300–301
 - member functions of classes, 298–300
 - for preparing to print, 845
 - recursive function calls, 228–231
 - return statements, 197–198
 - returning pointers from, 220–222
 - returning references from, 223–226
 - returning values from, 220–223
 - static variables in, 226–228
 - template member functions, 385–386
 - Using Functions (example), 199–202
- functions, creating program using, 260–277
- basics of, 260–261
 - blanks from strings, eliminating, 264
 - calculator, implementing, 261–264
 - completing, 272–273
 - expressions, evaluating, 264–267
 - extending, 273–275
 - numbers, analyzing, 268–272
 - running, 277
 - substrings, extracting, 275–277
 - values of terms, 267–268
- functions, passing arguments to, 202–220.
- See also* pointers
- arguments to main() function, 216–218
 - arrays, passing to functions, 206–210
 - basics of, 202
 - const modifier, 212–214
 - copying and, 370
 - pass-by-value mechanism, 202–204
 - Receiving Command-Line Arguments (example), 217–218
 - references as arguments to functions, 210–212

rvalue reference parameters, 214–216

UpdateAllViews () function and, 746–747

variable numbers of function arguments and, 218–220

functors, 369, 505

fundamental data types, 42, 47–48

G**game cards**

back of, creating, 881

basics of creating, 879–880, 882–883

Card class, defining, 884–885

circles for design of, 880

defining, 879

event handler, adding, 881–882

grid to contain, creating, 878

highlighting, 893–894

shuffling, 893

triangles for design of, 880

GameOver () function, 898–899

GCD (greatest common divisor), 600

GDI (Graphical Device Interface)

drawing in windows and, 692–695

GDI objects, 722

GetClientRect () function, 628

GetCursorPos () function, 766

GetDocument () function

CSketcherView, 696

MFC Application Wizard, 656–657

GetEnclosingRect () function, 719

getline () function

comparing strings and, 431

in Sorting Words from Text (example), 439

string input and, 148

template, 419, 423

GetMessage () function, 620–623

global functions, adding, 411–413

global namespace scope, 80–82

global scope, 80–82

global variables

basics of, 30, 80–84

risk with, 226

- globals
- defined, 30
 - variables, 30, 80–84, 226
- goto statements, unconditional branching and, 115
- Graphical Device Interface (GDI)
- drawing in windows and, 692–695
 - objects, 722
- graphical user interface (GUI)
- defined, 3
 - programming desktop applications and, 3
- graphics. *See also* drawing
- displaying, 697–699
- greatest common divisor (GCD), 600
- Grid element
- cards, creating and, 879–881, 882
 - cards, defining and, 879
 - game controls and, 876–878
 - game operations and, 883
 - layout controls and, 869
 - scaling elements and, 901–902
 - titles, creating and, 874–875
- grids (MemoryTest project)
- child elements of cardGrid, 888–890
 - to contain game cards, creating, 878
 - creating cards and, 882
 - event handling and, 881–882
 - game controls and, 876–878
 - page grid, 873–874
 - title and, 874–876
- group boxes in dialogs, 778
- GUI (graphical user interface)
- defined, 3
 - programming desktop applications and, 3
- ## H
- .h files
- basics of, 22, 416–417
 - class definitions and, 405
 - console program files and, 415
 - .cpp files and, 412
 - data members adding and, 407
- global functions and, 412
- shortcut for viewing, 668
- handlers. *See* message handlers
- handles, 613, 861
- hatching style of brushes, 704
- header files
- < > (angled brackets) and, 32
 - basics of, 32
 - in console programs, 38
 - declarations in, 34
 - precompiled, 38
- headers, 578
- function headers, 195–196, 198
 - STL container adapters, 499
 - STL container classes, 496–497
- heap
- basics of, 174
 - example using, 177–179
- hexadecimal constants, integer variables and, 45
- highest common factor (HCF), 600
- highlighting
- elements for, 760–763
 - game cards, 893–894
 - highlighted elements, drawing, 763
 - highlights, exercising, 763
- hInstance argument, 613
- HorizontalAlignment property (MemoryTest project), 876–877, 880
- hPrevInstance argument, 614
- Hungarian notation, 612
- ## I
- .ico files, 22
- icons
- Class View documentation and, 651
 - class view tab (MFC), 651
 - .ico files and, 22
 - toolbar, 10, 608, 684
- ID_ELEMENT_DELETE, 755–756
- ID_ELEMENT_MOVE, 755–756
- ID_ELEMENT_SENDOBACK default ID, 772
- ID_ELEMENT_TEXT ID, 811–812

IDE (Integrated Development Environment)
 basics, 5–8
identifiers, 39
`if` statements
 basics of, 99–100
 extended, 102–104
 nested, 100–102
 numeric values and, 104
 to test expressions, 244
`if-else` statements, nested, 104–106
`IMPLEMENT_DYNCREATE()` macro, 823–824, 826
`IMPLEMENT_SERIAL()` macro, 827
implicit type conversion, 59, 69–70
inclusive OR operators, 72–73
increment operators
 arithmetic operations and, 62–63
 overloading, 368–369
incrementing pointers, 168
index values, arrays and, 140, 144
indirection operator, 156
indirect base classes, 447
`InflateRect()` function, 723
inheritance
 access controls under, 451–454
 access level of class members, 461–462
 base classes, 447–451
 basics of, 447
 class friendship and, 468
 constructor operation in derived classes, 454–458
 copy constructors in derived classes, 462–465
 derived classes and, 447
 deriving classes from base classes, 448–451
 inherited functions, 469–471
 inherited members of derived classes, 461–462
 levels of, 481–483
 protected class members, 458–460
initialization lists, as class constructors, 309
`InitializeComponent()` function, 887
`InitializeGame()` function, 891–892
initializing
 arrays, 144–146
 arrays of pointers to functions, 241
 card pack, 888
 color and element type members, 681
 dialog controls, 784–785
 dialogs, 795–796
 function parameters, 242–243
 lvalue references, 180–181
 `MainPage` object, 887–888
 members of derived class objects, 465
 members of unions, 348
 memory test game, 890–892
 pointers, 156–157
 pointers to functions, 237
 static data members, 327–329
 static variables within functions, 227
 string objects, 418–420
 structs, 283
 variables and, 41–42
Windows program windows, 619
`GetInstance()` function, 634, 658–659
inline functions, 301–302
input
 `getline()` function, string input and, 148
 from keyboards, 50, 59
 program input, arithmetic operations, 59
input stream iterators
 basics of, 579–582
 creating, 586
input/output operations
 escape sequences, 53–55
 input from keyboards, 50
 output, formatting, 51–53
 output to command lines, 50–51
 Using Manipulators (example), 52–53
`insert()` function
 elements, adding to lists and, 537–538
 inserting characters in strings with, 425–427
 map containers and, 567–568, 578
 parameters of, 426
 vectors and, 517–518
`insert_after()` function, lists and, 549
`insert_iterator<T>`, 580–581
inserter iterators, 579, 582–584

instances

- Copying Information Between Instances (example), 317–318
- defined, 294
- of templates, 382

instantiation

- defined, 256, 294
- templates and, 257, 382, 385

`int` keyword, 35, 42, 43**integer type modifiers**, 45–46**integer variables**, 42–44**IntelliSense**

- basics of, 6
- structs and, 287–288
- turning on and off, 288

interfaces. *See also user interfaces (UIs)*

- class interfaces, 312, 396–397
- graphical user interface. *See GUI (graphical user interface)*
- Multiple Document Interface (MDI), 640
- Single Document Interface (SDI), 640

InvalidateRect(), client area redrawing and, 714–715**iostream header files**, 32, 148**iterators**

- basics of, 499–501, 579
- input stream iterators, 579–582
- inserter iterators, 579, 582–584
- iterator categories, 499–501
- iterator header, 579
- output stream iterators, 584–586
- stream iterators, 579

J**joining**

- null-terminated strings, 183–185
- strings, 420–423

K**keyboards**

- arithmetic operations and, 59
- input from, 50

keywords

- basics of in C++, 40–41
- data types and, 42
- fundamental types and, 42
- highlighting color and, 30

L**L prefix**, 148**lambda expressions**

- basics of, 592–593
- capture clauses, 593–594
- function objects and, 506
- lambda expressions, Using (example), 595–599
- naming, 599–600
- Recursion in Lambda Expressions (example), 600–602
- specific variables, capturing, 594–595
- templates and, 595

lambda introducers, 592**lambda parameter lists**, 592**language extensions (C++)**, 857**languages (spoken)**, changing in menus, 671**late binding**, 472**length**

- of documents when printing, 845–847, 849–850
- of null-terminated strings, 183
- `rollLength const` variable, 58
- of strings, 183, 261

libraries

- basics of, 6
- locating library files, 33
- Visual C++, 7

library classes for strings. *See strings, library classes for***library functions for strings.** *See also*

- null-terminated strings
- `cstring` header, 182–183

linear time, 517**lines**

- calculating enclosing rectangles for, 723
- drawing, 698–699, 706, 720–723, 739

lines (*continued*)
 style of, 702
 thickness of, 721
LineTo() function, 698–699
linked lists, 290
linker, 6
linking, Simple Program example and, 31
list containers
 basics of, 537–539
 list functions, 537–539, 542–544
 list<T> template, 506–508, 537
 Predicate for Filtering Lists (example), 544–548
 Working with Lists (example), 540–541
listVector() function template, lambda expressions and, 598–599
literals
 basics of, 48–49
 vs. const variable types, 58
local scope, automatic variables and, 78
local smart pointers, 504
logical coordinates
 basics of, 750–751, 797–799
 printing and, 848, 849
logical operators
 basics of, 106–109
 combining with conditional expressions (example), 108–109
logical variables. *See* Boolean variables
long int, 43–44
loop_statements
 basics of, 117–118
 while loops and, 126
loops
 basics of, 116
 continue statements and, 122–124
 do-while loops, 128–129
 floating-point value loop counters, 126
 for Loops. *See* for Loops
 nested, 130–133
 Using Other Types in Loops (example), 124–125
 while loops, 126–128
lpCmdLine argument, 614

lvalue references
 declaring and initializing, 180–181
 rvalue references and, 216
lvalues, 76–77

M

m_PenWidth, 783–785
m_pTempElement, 734–735
macros
 basics of, 653
 CObject-based classes and, 826
 function arguments and, 218–220
 serialization and classes and, 827, 833
Magnification Tool editing button, 686
main() function
 arguments to, 216–218
 basics of, 14, 18, 25, 26, 34, 39
 calculator program and, 272–273
 names, 39
 vs. WinMain() function, 613
 MainPage class
 application files and, 871
 basics of, 855
 data members, adding, 885–886
 defining, 858–860
 function members, adding, 886–887
 functions, 884
 object, initializing, 887–888
make_pair() function, 567
make_shared<T>() function, 503
map containers
 basics of, 565–566
 Map Containers, Using (example), 571–578
 vs. multimap containers, 578
 objects, accessing, 568–569
 objects, storing, 566–568
 other map operations, 569–571
map<K, T> container, 565
mapping modes
 MM_LOENGLISH , 693, 753
 scalable, 797–799
 setting, 799–801
masked elements, 771–772

max() function
function overloading and, 251–255
function templates and, 255–258, 260
trailing return types and, 260

Max() function, class templates and, 383, 385–386

MDI applications
command message processing and, 670
creating, 659–661

measurements, UI, 873–874

member access operator, 283

member functions
calling, 300
in CDC class, 697
coding for, 402
defined, 294
overloading, inheritance and, 447
positioning function definitions, 300–301
public, CPrintInfo object, 842

member selection operator (.), 283

members. *See also* private class members
access level of inherited, 461–462
access to inherited members, 451–452
accessibility and, 292
adding to store color and element mode, 678–679
data members of classes, accessing, 296
default class members, 381–382
defined, 294
as friends, 466–468
member function definitions, 300–301
member functions of classes, 298–300
protected class members, declaring, 458–460
static function members of classes, 329
static members of classes, 326–329
of structs, accessing, 283–287
of structs, accessing through pointers, 290–291
template member functions, 385–386

memory. *See also* dynamic memory allocation
in Arrays of Pointers (example), 162
memory allocation errors, 249–251
memory leaks, 222
sharing between variables, 346–349

memory headers, 501–502

MemoryTest project. *See* Windows 8 apps, programming (example)

menu bars (windows), 608

menus. *See also* context menus
adding, 670–671
items, adding to element menu, 673
items, adding to menu bars, 672–673
items, modifying, 673
menu command message handlers, 681
menu message handlers, adding, 674–678
menu message handlers, implementing, 678–682
menu message update handlers, adding, 682–684
menu resources, creating and editing, 671–674
Text menu item, adding, 811–812

merge() function (lists), 543–544

message handlers
defined, 665
definitions, 667–668
menu command message handlers, 681
menu message handlers, adding, 674–678
menu message handlers, implementing, 678–682
menu message update handlers, adding, 682–684
message update handlers, adding, 682–684

mouse message handlers. *See* mouse message handlers
searching for, 667
update handlers, exercising, 684

message IDs, 620

message loops, 620

message maps (MFC), 664–666

message pumps, 620

message update handlers, adding, 682–684

messages. *See also* Windows messages
mouse messages, 709–710
radio button messages, 785–786

methods
defined, 294
in WinRT programming, 856

MFC (Microsoft Foundation Classes), 639–662
applications, creating, 20–23, 644–645
basic classes, 643–644
basics of, 7, 610, 631
building and executing, 22–23
document interfaces, 640
documents basics, 640
handling of exceptions in, 248–249
linking documents and views, 641–643
MDI applications, creating, 659–661
Minimal MFC Application (example), 632–636
notation, 631–632
program structure, 632
SDI applications, creating, 645–649. *See also* MFC Application Wizard output
views, 640–641
vs. Windows API, 2, 606
Windows data types and, 610

MFC Application Wizard
creating MDI applications with, 659–661
creating MFC applications with, 20–23, 644

MFC Application Wizard output
application class, 652–653
document class, 654–655
executable modules, creating, 657
frame window class, 653–654
program, running, 657–658
program, workings of, 658–659
TextEditor project folder, 649–650
view class, 656–657
viewing classes, 651–652
viewing project files, 651

MFC Class Wizard, 806

MFC drawing, 695–706
CDC class for, 697
circles, 699–701
in color. *See* MFC drawing in color
graphics, displaying, 697–699
OnDraw() function, 695–696
sketch drawing, 737–740

MFC drawing in color
basics of, 701–703
brushes and, 704–706

pens, using, 703–704
MM_ prefix, 693
MM_ANISOTROPIC mapping mode, 797–799, 801, 847
MM_ISOTROPIC mapping mode, 797–799
MM_LOENGLISH mapping mode, 695, 753
MM_TEXT logical coordinates, 802
MM_TEXT mapping mode, 694–695
modal dialogs, 780, 796
modifiers, const modifier, 58
modifying
curve constructor, 788–789
menu items, 673
source code (example), 13–14
strings, 424–428
variables, 61–62

modular structure, functions and, 193–194

modules, creating executable (MFC), 657

mouse, using for drawing
basics of, 712–714
CCircle class, 725–728
CCurve class, 728–730
CElement base class, 719–720
CLine class, 720–723
CRectangle class, 723–725
element classes, defining, 715–718
redrawing client area, 714–715
WM_MOUSEMOVE message handler. *See also* WM_MOUSEMOVE message handler
mouse message handlers. *See also* WM_MOUSEMOVE message handler
basics of, 710–712
basics of completing, 730–731
drawing mode, setting, 731–733
elements, creating, 735–736
mouse, capturing, 739
OnMouseMove() handler, 733–735
WM_LBUTTONDOWN messages, 736–737

mouse programming for drawing, 708–737
basics of, 709–710
mouse for drawing. *See* mouse, using
for drawing; WM_MOUSEMOVE message handler

mouse message handlers. *See* mouse message handlers
 mouse messages, 709–710
Move() function, 768–769, 812, 816–817
move semantics
 defined, 381
 vectors and, 521
MoveRect() function, 287
MoveTo() function, displaying graphics and, 697–698, 699
moving
 CText objects, 816–818
 elements, 764–767
MSDN library, 614
multidimensional arrays
 basics of, 150–154
 defined, 150
 dynamic memory allocation of, 179–180
 passing to functions, 208–210
Storing Multiple Strings (example), 152–154
 using pointers, 172–174
multimap containers
 basics of, 578–579
 vs. map containers, 578
multipage printing basics, 843–844
Multiple Document Interface (MDI)
 applications, creating, 659–661
 defined, 640
multiple top-level document architecture, 640
multiset<T>, 565
multitasking, cooperative, 622–623

N

named objects, as rvalues, 376–379
namespace keyword, 91
namespaces
 basics of, 90–93
 C++ standard library and, 93
 C++/CX, 857–858
 functions from C runtime library and, 342
 using declaration and, 33–34

WinRT, 856
naming
 class constructors, 302
 destructors, 338
 functions, 194, 350
 handler functions, 675
 lambda expressions, 599–600
 namespaces and, 33
 pointers, 236
 program files, 417–418
 projects, 11
 variables, 39–40
nCmdShow argument, 614
negative powers, support of, 229–230
nested classes, 487–491
nested if statements, 100–102
nested if-else statements, 104–106
nested loops, 130–133
new operator
Catching Exceptions Thrown by (example), 249–251
 dynamic memory allocation and, 174–176, 179
New Project dialog box, 11
nFlags, 711–712
noarg constructors, 304
non-queued messages, 620
normalized rectangles, 723
notation
 MFC, 631–632
 in Windows programming, 611–612
null characters, 147
nullptr pointers, 157
null-terminated strings
 vs. character strings, 418
 comparing, 186–187
 copying, 185
 finding lengths, 183
 joining, 183–185
 searching, 187–189
number() function, 268–271, 274–275
numbers, analyzing, 268–272
numeric header, algorithms and, 505, 588

numeric values, comparing, 97–115
conditional operators, 109–110
extended if statements, 102–104
if statements, 99–100
logical operators, 106–109
nested if statements, 100–102
nested if-else statements, 104–106
operators for, 97–99
switch statements, 111–114

O

.obj extension, 6
object code, compiler and, 6
object copying, 370–381
 avoiding unnecessary operations, 371–374
 Creeping Inefficiencies (example), 379–381
 problem of, 370
 rvalue reference parameters, applying, 374–376
 rvalues, named objects as, 376–379
object files, 6
object slicing, 496
object-oriented programming (OOP)
 basics of, 292, 445–447
 defined, 294
 inheritance and. *See* inheritance
 object-oriented techniques, importance of, 1
objects
 analyzing, 402–404
 of classes, declaring, 295–296
 combining, 400–402
 comparisons of, 399–400
 creating from class templates, 386–389
 defined, 294
 destructors and, 338
 map container objects, accessing, 568–569
 object members, accessing (`ref` class), 861
 packaging, 397
 pointers to, 474–476

storing, map containers and, 566–568
string objects, creating, 418–420
valid objects (`CBox` class), 397–399
WinRT, 856–857
`OnAppAbout()` message handler, 666
`OnColorBlack()` handler function, 681
`OnDraw()` function
 basics of, 695–696
 client area, redrawing and, 714–715
 displaying graphics and, 697
 drawing highlighted elements and, 763
 drawing lines and, 698
 drawing sketches and, 737
 using pens and, 703–704
one-dimensional arrays, defined, 150
`OnElementDelete()` handler, 764
`OnEndPrinting()` function, 845, 847
`OnInitDialog()` function, 784–785, 795
`OnInitialUpdate()` function, 753, 802
`OnLButtonUp()` function, 752–753
`OnMouseMove()` handler
 client coordinates and, 751–752
 coding, 733–735
 elements under cursors and, 759, 762, 766
 setting, 733–735
`OnOK()` function, of `CDialog` base class, 782–783
`OnPenWidth()` handler, 786
`OnPrepareDC()` function, 799–800
`OnPreparePrinting()` function, 840, 842, 844, 845, 846
`OnPrint()` function, 840, 848, 852
`OnRButtonDown()` handler, 770
`OnUpdate()` function, 746–747, 752
`OnUpdateColorBlack()` handler, 683, 684
OOP. *See* object-oriented programming (OOP)
.opensdf extension, 12
operands, type conversion and, 67
operating systems, Windows programs and, 608–609
`operator()` function, 505, 544

operator keyword, 350
 operator overloading, 349–370
 addition operators, 363–368
 assignment operators, 358–363
 basics of, 349–350
 function call operators, 369–370
 implementing, 350–353
 increment and decrement operators, 368–369
 non-overloading operators, 349
 support for comparison operators, 354–358
 operator%() function, 404
 operator*() function, 401–402
 operator+() function, 372, 374
 operator+=() function, 420, 422
 operator<() function, 350–351, 353, 354, 355, 357
 operator=() functions, 360, 361, 374, 375–376
 operator==() function, 353, 355, 360
 operators
 arithmetic, 65–66
 arithmetic operations and, 62
 for comparing numeric values, 97–99
 for comparing strings, 428
 conditional, 109–110
 incrementing variables and, 63
 logical, 106–109
 operator precedence in arithmetic calculations, 65–66
 overloaded operators (*CString* class), 807–808
 relational operators, defined, 97
 options
 setting (Visual C++), 19–20
 types (MFC applications), 645–647
 Options dialog box, 19
 OR operator (||), 107–108
 ostream_iterator<T> template, 584
 output. *See also* input/output operations
 CBox class, 415–416
 to command lines, 50–51
 formatting, 51–53

Using the Conditional Operator with Output (example), 110
 output statements, 35–36
 output stream iterators, 584–586
 Output window, 8
 overloading operators, 399
 override modifier, 473, 475

P

page numbers, printing and, 842
 pages (XML), 863
 pair<K, T> class template, 566
 panes
 Solution Explorer, new Windows 8 apps and, 855, 871–872
 status bar panes, creating, 804–805
 paper size, printing and, 843
 parameters
 in body of functions, 197
 class templates with multiple, 386–389
 default parameter values, 307–309
 defined, 194
 function parameters, initializing, 242–243
 parameter types of functions, 236
 parent and child elements (XAML), 869
 parent windows, 607, 618
 parentheses ()
 around dereferenced pointers, 290–291
 expressions between, 273–274
 extract() function and, 275–276
 overriding operator precedence and, 66
 sizeof operator and, 164
 std::min and std::max and, 724
 partial keyword, 860
 pass-by-reference method, 210–212
 pass-by-value mechanism, 202–204
 pens
 color of, 731–733
 creating, 701–703
 dialog controls and, 783–784
 displaying dialogs and, 779–780
 drawing in color with, 703–704

pens (*continued*)
 GetPenWidth() function, 786–787
 OnPenWidth() handler, 786
 pen objects, defined, 701
 pen widths, 777–778, 781, 786–789
perfect forwarding, 392–396
Person class
 defining, 393
 map containers and, 571
 vectors and, 521–523, 526–529
Person objects, storing in vectors, 524, 525
pfun pointer, 236, 237
Platform namespace, 857–858
Platform::Collections namespace, 857, 858
PointerEntered and PointerExited events, 881–882
pointers
 accessing members of structs through, 290–291
 arithmetic operations with, 168–169
 Array Names as Pointers (example), 169–171
 arrays and, 167
 basics of, 154, 235
 char*, 159
 to class objects, 329–330, 474–476
 comparisons of values, 168
 constant, 165–167
 counting characters in strings and, 171–172
 dangling, 176
 declaring, 154–155
 dynamic memory allocation and. *See also* dynamic memory allocation
 to function as parameters, 240–241
 handling strings and, 171–172
 initializing, 156–157, 175
 Lucky Stars with Pointers (example), 159–161
 multidimensional arrays and, 172–174
 vs. references, 212
 sizeof operator, 163–165
 smart, 176
 storing in vectors, 527–529
 structs and, 289–291
 using, 156–159
pointers to functions
 as arguments, 204–206, 239–240
 arrays of, 241–242
 basics of, 235–236
 declaring, 236–237
 Passing Function Pointers (example), 240–241
 Pointers to Functions (example), 237–239
 using like functions they point to, 239
pOldSelected and m_pSelected, cursors
 and, 763, 764
polymorphic function wrappers, 600
polymorphism, 472–473, 476
pop() function, containers and, 551, 554, 559
Pop() function, nested classes and, 489, 491
popup menus. *See* context menus
Popup property (element menus), 673
postfix form of increment operators
 basics of, 63
 increment/decrement operators and, 368–369
power() function, 230
precompiled headers feature (C++), 657
predicates
 defining (example), 544–548
 function objects and, 505
pre-emptive multitasking, 622
prefix form of increment operators
 basics of, 63
 increment/decrement operators and, 368–369
prefixes, variable names and, 611–612
preprocessor directives, #include directive and, 33
printing
 cleanup after, 847
 device context, preparing, 847–848
 document size and, 844
 documents, basics of, 839, 848–852
 multipage, introduced, 843–844

preparation for, 845–847
print data, storing, 844–845
print preview, 839, 852–853
printouts, 852–853
process of, 839–843
printing/print preview options (MFC), 648
priority queue containers
 basics of, 553–554
 example of using, 554–559
private class members
 access control and, 451
 of base classes, 452–454, 457–458
 basics of, 311–312
 default copy constructors, 317–318
 derived classes and, 450, 461
 friend functions, 314–317
 nested classes, 487–488
 Private Data Members (example), 312–314
 vs. public class members, 292
private keyword, 311, 458
product documentation, 10
program code, organizing, 416–418
program statements, 34–36, 115
program windows (Windows)
 creating, 617–619
 initializing, 619
 specifying, 615–617
programming
 with strings (example), 149–150
 with Visual C++. *See* C++ programming
 basics
 Windows 8 apps. *See* Windows
 8 apps
programs
 event-driven, 4
 structure of (C++). *See* C++ program
 structure
project context menu (MFC), 644
project folders, 10
projects and solutions
 Creating a Project for a Win32 Console
 Application (example), 11–13
 Creating an Empty Console Project
 (example), 16–19
defined, 10
defining projects, 10
errors, 18–19
executing, 16
versions, debugging and releasing, 15
Prompt property, 673
properties
 defined (Windows 8), 858
 defined (XAML), 863
 menu properties, defined, 672, 673
 toolbar button properties, editing, 686–687
 UI elements in XAML, 870
Properties pane, 865–866
property keyword, 858
Property Pages dialog, 16
protected keyword, 458
Protected Members, Using (example), 458–460
prototypes of functions, 198–199
public class members
 accessing, 295
 vs. private class members, 292
public keyword, 292, 295
public member functions, CPrintInfo
 object, 842
pure virtual functions, 477–478
Push() function, 489
push() function, containers and, 550, 554,
 559
push_back() function, vector containers
 and, 508

Q

queue containers, 550–553
queued messages, 620

R

radio buttons
 pen width options and, 778
 radio button messages, 785–786
random access iterators, 500
random_shuffle() function, 893

randomValues() function template, lambda expressions and, 598

range-based for loops, 129
iterating characters in strings with, 424
references, using in, 181–182

Raster OPeration (ROP)
drawing mode and, 731
trails and, 814

raw pointers, 504

ReadMe.txt file, 12

recording document changes, 829–831

RECT objects, 289

RECT structure, 289

rectangles
CRectangle constructor, 788
drawing, 707–708, 725, 739
enclosing, creating, 722–725
enclosing, for lines, 723
normalized, 723

Recursion in Lambda Expressions (example), 600–602

recursive functions
analyzing arithmetic expressions and, 267
basics of, 228–231

redrawing windows, 616

ref class
class types variables (C++/CX), 861
defined, 857
object members, accessing, 861

ref class keyword, 858

ref struct types, 857

reference cycles, 502

reference documentation for WinRT
namespaces, 856

reference types, function overload selection and, 254

references
as arguments to functions, 210–212
basics of, 180
to class objects, 329, 332–334
defined, 212

lvalue, declaring and initializing, 180–181
vs. pointers, 212

return types, 223–226

rvalue, 182
using in range-based for loops, 181–182
using with virtual functions, 476–477

referencing members of structs (example), 284–287

regions, clip rectangles and, 852

RegisterClassEx() API function, 617, 618

registering windows classes, 617

registry key (MFC), 658

reinterpret_cast<>(), 66–69

relational operators, 97

ReleaseCapture() function, 739

releasing
programs, 15
Release versions, 31

remainders, calculating, 61

remove() function (lists), 542

remove_if() function (lists), 544

removing toolbar buttons, 8

replace() algorithm, 588–589

replace() function
replacing parts of strings with, 427–428
using with pointers, 589

reserve() function, vector containers and, 509, 515

resize() function
numbers of elements in lists and, 537
vector containers and, 512

resizing windows, 607, 636

Resource Editor
creating MFC applications and, 644
pane, 672, 779, 781–782, 793

resource files
basics of, 608
menus and, 671

resource string tables, creating status bar panes and, 804–805

Resource View tab
MFC, 651
Windows programming, 13

- resources
- console programs and, 13
 - creating and modifying, 644
 - defined, 671
 - dialog resources, creating, 776–779
 - edit box resources, creating, 809–810
 - menu resources, creating and editing, 671–674
 - for XAML templates, 883
- rethrowing exceptions, 248
- return statements, functions and, 197–198
- return types of functions, 196
- return values of functions, 196
- returning references from functions, 223–226
- reverse iterators, 511
- ribbons (windows), 608
- RichTextBlock element, 875–876, 898, 899–900
- rollLength const variable, 58
- RotateTransform element, 904
- rubber-banding, 706
- Run() function (MFC), 659
- rvalue references
- basics of, 180, 182
 - function overload selection and, 254
 - lvalue references and, 216
 - passing values to functions and, 212
 - reference parameters, 214–216, 371, 374–376
- rvalues
- basics of, 76–77
 - named objects as, 376–379
- S**
- scaling
- document size, setting, 799
 - mapping modes, setting, 799–801
 - scalable mapping modes, 797–799
 - scale menu items, adding, 791
 - scrolling with, 801–803
 - UI elements, 901–903
- SCARY iterators, 501
- schema numbers, 827
- scope
- basics of, 77–78
 - declared within functions, 197
- scope resolution operator (::), 33, 82, 197
- screen coordinates, 797
- scrolling
- with scaling, 801–803
 - scrollbars, 802–803
- scrolling views
- client coordinates, 751–753
 - coordinate systems, 750–751
 - getting started, 748–749
- .sdf extension, 12
- SDI (Single Document Interface), 640. *See also* MFC Application Wizard output
- SDI applications
- command message processing and, 670
 - creating, 645–649. *See also* MFC Application Wizard output
- searching
- algorithms and, 589
 - for library files, 33
 - for message handlers, 667
 - namespaces, 84
 - null-terminated strings, 187–189
 - strings, 432–436, 440
- SelectObject() function
- using brushes and, 705
 - using pens and, 703
- semicolons (;)
- assignment statements and, 55
 - declarations and, 41, 153
 - else keywords and, 104
 - function prototypes and, 199
 - if statements and, 99
 - for loops and, 119
 - macros and, 827
- sequence containers. *See also* vector containers
- array containers, 530–533
 - basics of, 506–508
 - double-ended queue containers, 533–536

sequence containers (*continued*)
 forward_list container templates, 548–550
 list containers. *See* list containers
 priority queue containers basics, 553–554
 Priority Queue Containers, Using (example), 554–559
 queue containers, 550–553
 stack containers, 559–561

serialization
 basics of, 720, 821–822, 827–828
 basics of applying, 829
 document changes, recording, 829–831
 in document class definition, 822–823
 in document class implementation, 823–826
 documents, serializing, 831–833
 element classes, serializing, 833–837
 exercising, 837–839
 functionality of CObject-based classes, 826–827
 implementing for classes, 829

Serialize() Function, 824

set<T> container, 565

SetCheck() function, 683–684

SetModifiedFlag() function, 829–830

SetRegistryKey() function (MFC), 658

sets (containers), 506

SetScrollSizes() function, 748–749, 753

setValues() function template, lambda expressions and, 597–598

SetViewportOrg() member, 695

shape events, handling, 896–898

Shape_Tapped() handler (MemoryTest project), 881, 882

shared_ptr objects, 503–504

shared_ptr<T> type, 501–502

shift operators (bitwise), 74–76

short keyword, 43

shortcut menus. *See* context menus

shortcuts
 for creating game cards, 882

 menus and, 670, 672, 674, 755
 for viewing .h files, 668

Show_How_Tapped() handler (MemoryTest project), 899, 900

showit() function, 242–243

ShowVolume() function, 483

signatures, overloaded functions and, 252

signed keyword, 45

Simulator Debugger, 882–883

Single Document Interface (SDI). *See* SDI (Single Document Interface)

size
 document size, setting, 799
 of documents and printing, 842, 843, 844
 of Grid element, 901
 paper size, printing and, 843
 width and length when printing, 845–847, 849–850
 of windows, 607, 618, 636

size() function, containers and, 550, 554, 559, 571

size_t type, 163, 183

sizeof operator
 operator overloading and, 350
 pointers and, 163–165
 in Your First Use of Classes (example), 298

Sketcher program
 adding menus, 670–671
 classes, 666–667
 controls and. *See* controls
 creating, 659–661
 dialogs and. *See* dialogs
 drawing and. *See* drawing in windows
 printing and. *See* printing
 serialization and. *See* serialization
 views and. *See* views, improving
sketches, drawing, 737–740

slashes (/)
 comments and, 31
 start and end tags and, 864

.sln extension, solutions and, 10

-
- smart pointers
 - basics of, 176, 501–504
 - casting, 504
 - memory leaks and, 223
 - raw pointers, 504
 - `shared_ptr` object, 503–504
 - `unique_ptr` object, 502–503
 - using, 504
 - `SolidColorBrush` objects, 861
 - Solution Explorer
 - pane, new Windows 8 apps and, 855, 871–872
 - tab (MFC), 651
 - tab (Windows programming), 12
 - window, 8
 - solutions, building (example), 14
 - `sort()` algorithm, 505
 - `sort()` function, comparing strings and, 430, 431
 - `sort<T>()` function template
 - arrays and, 525
 - vectors and, 525–526
 - sorting
 - list elements, 539
 - Sorting Words from Text (example), 436–441
 - source code, modifying (example), 13–14
 - spaces, eliminating from strings, 264
 - spin button controls
 - basics of, 777, 791
 - `CSScaleDialog` class and, 793–796
 - scale menu items, adding and, 791
 - spin buttons, creating, 792–793
 - spin buttons, displaying, 796–797
 - toolbar buttons, adding, 791
 - `splice()` function (lists), 543
 - square brackets []
 - deleting arrays and, 176, 179
 - function pointer array elements and, 241
 - as subscript operator, 424
 - squares, creating, 879–880
 - stack containers, 559–561
 - stacks, 78
 - Standard C++ Library, 7
- Standard Template Library
 - algorithms, 504–505, 588–591
 - associative containers. *See* associative containers
 - basics of, 495–496
 - components, listed, 496
 - containers. *See* containers; sequence containers
 - function adapters, 506
 - function objects in, 505–506, 586–588
 - iterators. *See* iterators
 - lambda expressions. *See* lambda expressions
 - smart pointers, 501–504
 - static assertions, 591–592
 - storing tuples in arrays (example), 563–565
 - `tuple<>` class templates basic, 561–562
 - type traits, 591–592
 - Start button (MemoryTest project), 899
 - start tags (XAML), 863
 - startup transitions (applications), 903
 - stateless lambdas, 593, 599
 - statements
 - assignment statements
 - basics, 35
 - output statements, 35–36
 - program statements, 34–36
 - repeating blocks of. *See* loops
 - statement blocks, 37
 - static assertions, STL and, 591–592
 - static members of classes
 - static data members, 326, 329
 - static function members, 329
 - static resolution, 470
 - static storage duration, 81, 84
 - static variables
 - basics of, 84, 226
 - in functions, 226–228
 - `static_cast` keyword, 68
 - `static_cast` operator, 202
 - `static_cast<>()`, 68
 - `static_pointer_cast`, 504

status bars, adding to frames
 basics of, 803–804
 status bar frames, creating, 804–806
 status bars, updating, 806–807
`std`, namespaces and, 90
`stdafx.h` files
 compilation of files and, 16
 header files, in console programs, 38, 39
 modifying source code and, 13–14
`std::begin()` and `std::end()` functions, 501
`__stdcall`, 613
`std::cout`, 14, 90
`std::endl`, 18
`std::forward()` function, 393
`std::move()` function, 381
`std::move()` library function, 216
`std::shared_ptr<CElement>` smart pointer, 718
`std::string`, 448
storage duration
 automatic, 78
 static, 81, 84
storing
 class objects in vectors, 520–526
 integer values, 45
 Multiple Strings, Storing (example), 152–154
 objects, map containers and, 566–568
 Person objects in vectors, 524, 525
 pointers in vectors, 527–529
 print data, 844–845
 `std::string` for, 448
 tuples in arrays (example), 563–565
storyboard animations transitions, 904–906
`strcat()` functions, 183–185
`strcmp()` function, 186–187
`strcpy()` function, 185–186
`strcpy_s()` function , 185–186, 449
stream iterators, 579
streams, 35
string class
 basics of, 183

Perfect Forwarding example and, 393–396
`string` objects, 394
strings. *See also* library functions for strings; null-terminated strings
 character arrays and, 147–150
 constructors and, 341
 eliminating blanks from, 264
 eliminating spaces from, 264
 length of, 261
 pointer notation and, 171–172
 `std::string` for storing, 448
 Storing Multiple Strings (example), 152–154
strings, library classes for, 418–441
 accessing and modifying, 424–428
 comparing, 428–432
 concatenating, 420–423
 searching, 432–436
 Sorting Words from Text (example), 436–441
string objects, creating, 418–420
strings of characters, 44
`strlen()` function
 destructors and, 341, 342
 string length and, 183
Stroustrup, Bjarne, 147, 293
`strspn()` function, 187–188
struct keyword, 282, 292
structs
 basics of, 282
 vs. classes, 295
 classes and, 292
 defining, 282–283
 initializing, 283
 IntelliSense and, 287–288
 members, accessing, 283
 RECT structure, 289
 referencing members (example), 284–287
 using pointers with, 289–291
structure, of Windows programs. *See also*
 `WinMain()` function
 vs. typical console programs, 4

structure of C++ programs. *See* C++ program structure
structures. *See also* structs
 vs. classes, 292
 defined, 282
 unions in, 349
style members of struct, 615–617
subscript operator ([]), 423
substr() function, extracting characters
 from text and, 440
substrings, extracting, 275–277
subtraction operator (CBox class), 400
sumarray() function, 241
.suo extension, solutions and, 10
swap() function
 strings and, 431
 vectors and, 519–520
swap() member function, interchanging
 strings and, 427
switch statements
 for comparing numeric values,
 111–114
 decoding Windows messages and,
 626–627
synonyms, defining for data types, 49–50
system menus (windows), 607–608

T

tab sequence (controls), 792–793
tag names, 347
tags (XAML), 863
template keyword, 255, 384
templates. *See also* class templates
 document templates (MFC),
 641–643
 function object templates, 587, 588
 for function objects, 392
 function templates, 198, 255–258
 inserter templates, iterators and, 579
 instances of, 382
 instantiation and, 385
 lambda expressions and, 595

for operator functions, 355
type testing templates, 592
term() function, 263, 266, 267–268
terminology, classes, 294
terms
 defined, 263
 value of, 267
ternary operators, for comparing numeric
 values, 109–110
text
 Text, Sorting Words from (example),
 436–441
 text elements, creating, 813–815
 text elements, defining, 812
 Text menu item, adding, 811–812
TextEditor project folder (MFC),
 649–650
this pointer, 318–321
throw keyword, 244, 245, 249
throw statements, 245–246
throwing exceptions, 244–246
time, constant and linear, 517
titles
 creating (MemoryTest project), 874–876
 title bar icons (windows), 607
 title bars (windows), 607
_tmain() function, 14, 18
toolbar (windows), 608
toolbar buttons
 adding, 8, 684–687, 791
 defined, 685
 removing, 8
 tooltips, adding, 688
toolbars
 dockable (IDE), 9–10
 options (IDE), 8–9
 options (MFC applications), 648
Toolbox pane, 865–866, 867, 869
tooltips
 adding, 688
 basics of, 9
top() function, containers and, 559
TrackPopupMenu() function, 756–757

trailing return types, 198, 259, 260
trails
 moving geometric elements and, 816
 moving text elements and, 816–817
transform() algorithm, 590
transform() function, 592
transitions, 903–906
tree controls, 777
triangles, design of game cards and, 880
trivial properties, 858
TRUE value, numeric type variables and, 46
truth tables, 71
try blocks
 exceptions and, 245–246
 memory allocation and, 250
 nested, 247–248
try keyword, 244, 249
tuple<> class templates
 basics of, 561–562
 tuples, storing in arrays (example),
 563–565
type arguments, using containers and, 496,
 557–558, 559
type conversion, 59, 66–69
type modifiers, 58
type of variables, 35
type parameters, function templates and, 255
type testing templates, 592
type traits, STL and, 591–592
typedef keyword, synonyms for data types
 and, 49–50
typedef statements, tuples and, 562,
 564–565
typeid operator, 70
typename keyword, 256
type-safe enumerations, 87–88

U

unary minuses, 56
unary predicates, 506
underscore (_), variable names and, 39
Unicode libraries, 16
union keyword, 347

unions
 anonymous, 348–349
 in classes and structures, 349
 defined, 347
 defining, 347–348
unique() function (lists),
 542–543
unique_ptr objects, 502–503
unique_ptr<T> type, 501
unsigned keyword, 46
update region, 691
UPDATE_COMMAND_UI, 682
UpdateAllViews() function, 746–747,
 767–768, 770
UpdateWindow() function, 619
user interfaces (UIs)
 defining (MemoryTest project), 872–874
 for drawing sketches, 739
 event handling for UI elements (XAML),
 870–871
 GUI, 3
 vs. operation (Windows 8 apps), 855
 options (MFC applications), 647
 UI elements in XAML, 865–868
 Windows programs, 606–608
using declarations, namespaces and, 33–34,
 90–91
using directives, defined, 90
Using Manipulators (example), 52–53

V

va_arg macro, 218
validation
 dialog data validation, 795
 of pointer values, 657
value types (WinRT), 857
variables
 automatic, 78–80
 in body of functions, 197
 data types and, 42
 declaring, 41
 defined, 35, 39, 70
 defining, 39–40

- dynamic memory allocation and, 174
 globals, 30, 80–84
 increment operators and, 63
 initial values for, 41–42
 integer, 42–44
 modifying in arithmetic operations, 61–62
 naming, 39–40
 of `ref` class types (C++/CX), 861
 scope and, 77–78
 sharing memory between, 346–349
 specific, capturing (lambda expressions), 594–595
 static variables basics, 84
 static variables in functions, 226–228
 storage duration and, 77–78
 variable declarations, 35, 41, 80
 variable definition, 41
- vector containers**
 accessing elements in, 516–517
 capacity vs. size of, 511–516
 creating, 508–511
 vs. double-ended queue containers, 534
 inserting and deleting elements in, 517–520
 sorting elements of, 526–527
 storing class objects in, 520–526
 storing pointers in, 527–529
`vector<T>` template, 506–508
- vector<CPoint>** container, 728
- VerticalAlignment** property
 (`MemoryTest` project), 877, 880
- view class**
 menus, associating with, 756–757
`MFC`, 656–657
- views**
 basics of, 640–641
 linking to documents, 641–643
- views, improving**
 context menus and. *See* context menus
 elements, moving and deleting, 754
 elements in, creating, 789–790
 masked elements, 771–772
`MM_LOENGLISH` mapping mode, 753
- mouse cursor and. *See* elements under cursors, identifying
 scrolling views. *See* scrolling views
 updating, 746–748, 767
- virtual destructors**, 483–486
- virtual Draw()** function, 719
- virtual functions**
 abstract classes and, 478–481
 adding to classes, 300
 basics of, 468–470
 correct operation of, 473
 defined, 471–473
 function overriding, preventing, 473–474
 indirect base classes and, 481–483
 pointers to class objects, 474–476
 pure, 477–478
 references, using with, 476–477
Using an Inherited Function (example), 470–471
 virtual destructors, 483–486
- virtual keyword**, 471, 472, 485
- visibility** property, 871, 888–889, 896
- Volume()** function
`CBox` class definition and, 299–300, 313
`CCan` class and, 480
`CCandyBox` class, 451–454
`CCContainer` class, 477–478
 function overriding and, 474–475
 inherited functions and, 470–471
 member function `const` and, 322–323
 operator overloading and, 354–355
 protected class members and, 458–460
 virtual functions and, 471–473, 477–478

W

- `wchar_t` variables, 44
`wcslen()` function, 183
`weak_ptr<T>` type, 502

- Web sites for further information
 - Bjarne Stroustrup, 147
 - constant values for style, 615
 - constants specifying windows displays, 614
 - MSDN library, 614, 615
 - reference documentation, 856
- while loops
 - arrays, using and, 143
 - basics of, 126–128
 - comparing strings and, 430–431
- whitespace, 37
- wide character types, 44
- width
 - of documents when printing, 845–847, 849–850
 - of lines, 702
 - `m_PenWidth`, 783–785
 - `OnPenWidth()` handler, 786
 - pen widths, 777–778, 781, 786–789
- Win32
 - basics of, 2, 606. *See also* Windows programming
 - Project for Win32 Console Application, Creating (example), 11–13
 - Win32 Application Wizard, 11, 13
- window class, Windows programming and, 633–634
- WindowProc() function
 - basics of, 609, 612, 626
 - complete, 629–630
 - messages and, 620, 625–626
 - vs. `WinMain()` function, 612
- Windows 8 apps
 - basics of, 854
 - C++/CX. *See* C++/CX
 - developing, 855
 - environment for use of, 854
 - operation of vs. UI of, 855
 - vs. Windows desktop apps, 854
 - WinRT, 854, 856–857
- Windows 8 apps, programming (example)
 - application files, 871–872
- application startup transitions, 903
- card back events, handling, 894–896
- Card class, defining, 884–885
- card pack, initializing, 888
- cards, shuffling, 893
- child elements of `cardGrid`, 888–890
- game, initializing, 890–892
- game cards. *See* game cards
- game control button events, handling, 899–901
- game controls, adding, 876–878
- game operations, implementing, 883–887
- MainPage object, initializing, 887–888
- MemoryTest project introduced, 871
- shape events, handling, 896–898
- storyboard animations, 904–906
- title, creating, 874–876
- UI, defining, 872–874
- UI cards, highlighting, 893–894
- UI elements, scaling, 901–903
- wins, recognizing, 898–899
- XAML and. *See* XAML (Windows 8 apps and)

Windows API

- basics of, 606, 609–610
- vs. MFC, 2, 606

Windows messages

- application, closing, 629
- basics of, 609, 625–626, 665
- decoding, 626–629
- message categories (MFC), 668–669
- message maps (MFC), 666–667
- message pumps or loops, 620
- message type, 675
- in programs (MFC), 667–668
- WindowProc() function. *See* WindowProc() function

Windows programming, 605–636. *See also* Win32

- applications, creating and executing, 20–23
- data types, 610–611
- event-driven programs, 609

- messages. *See* Windows messages
MFC. *See* MFC (Microsoft Foundation Classes)
vs. MFC, 2, 606
notation in, 611–612
operating system and, 608–609
Simple Windows API Program (example),
 630–631
structure of, 612–613. *See also*
 WinMain() function
user interface elements, 606–608
vs. WindowProc() function, 609, 612,
 626–630
Windows API, 606, 609–610
windows defined, 608
- Windows programs
 basics of, 4–5, 608–609
 vs. console programs, 4
- Windows::Foundation::Collections
 namespace, 857, 858
- Windows::UI::Xaml::Controls
 namespace, 869
- WinMain() function
 basics of, 612–614
 completed, 624–625
 vs. main() function, 613
 program windows, creating, 617–619
 program windows, initializing, 619
 program windows, specifying,
 615–617
 vs. WindowProc() function, 612
 windows messages, 620–623
- WinRT (Windows Runtime)
 basics of, 854, 856–857
 class types, defining, 858–860
 namespaces, 856
 objects, 856–857
- wizards
 Add Member Variable Wizard, 407,
 793–794, 810, 811
 Application Wizard, 26–28, 822, 824,
 839, 845
 Class Wizard, 779–780, 812
 Event Handler Wizard, 675–678
- MFC Application Wizard, 20–23,
 659–661. *See also* MFC Application Wizard output
MFC Class Wizard, 806–807
Win32 Application Wizard, 11
- WM_ prefix, for message IDs,
 621, 668
- WM_LBUTTONDOWN message handler
 basics of, 709, 710–711
 coordinates and, 750
 implementing, 711
 modifying, 737
 revised version, 751
- WM_LBUTTONDOWN messages
 basics of, 709, 710
 capturing mouse images and, 739
 drawing and, 712, 728
 dropping elements and, 770
- WM_LBUTTONUP message handler
 basics of, 710
 capturing mouse images and, 739–740
 implementing, 737
- WM_LBUTTONUP messages
 basics of, 709, 710, 711
 dealing with, 736–737
- WM_MOUSEMOVE message handler
 basics of, 621, 710, 731–732
 completing, 714, 730–731
 CreateElement() function, 735–736
 drawing mode, setting, 731–733
 moving elements and, 766–767
 outlining code for, 714
- WM_MOUSEMOVE messages
 basics of, 709, 710, 711
 capturing mouse messages and, 739
 drawing curves and, 728
- WM_PAINT messages, 627
- WM_QUIT messages, 629
- wmain() function, 18, 39
- WNDCLASSEX struct type, 615
- WndProc() function. *See* WindowProc() function
- Words, Sorting from Text (example),
 436–441

wrappers, for function objects, 599–600
WRL (WinRT C++ Template Library), 854
wstring class
 basics of, 183
 character strings and, 418

layout elements, 869–870
parent and child elements, 869
UI elements in, 865–868
XAML basics, 863
XML (eXtensible Markup Language), 863

X

XAML (Windows 8 apps and)
 attached properties, 868
 control elements, 869
 elements, 863–865
 event handling, 870–871

Z

zeros
 bitwise AND operator and, 72
 decimal integer values and, 46

Try Safari Books Online FREE for 15 days + 15% off for up to 12 Months*

Read this book for free online—along with thousands of others—with this 15-day trial offer.



With Safari Books Online, you can experience searchable, unlimited access to thousands of technology, digital media and professional development books and videos from dozens of leading publishers. With one low monthly or yearly subscription price, you get:

- Access to hundreds of expert-led instructional videos on today's hottest topics.
- Sample code to help accelerate a wide variety of software projects
- Robust organizing features including favorites, highlights, tags, notes, mash-ups and more
- Mobile access using any device with a browser
- Rough Cuts pre-published manuscripts

START YOUR FREE TRIAL TODAY!

Visit www.safaribooksonline.com/wrox60 to get started.

*Available to new subscribers only. Discount applies to the Safari Library and is valid for first 12 consecutive monthly billing cycles. Safari Library is not available in all countries.



An Imprint of  WILEY
Now you know.



Programmer to Programmer™

Connect with Wrox.

g
d code
le

g
d code
le

Browse the vast selection of Wrox titles, e-books, and blogs and find exactly what you need

User Group Program

Become a member and take advantage of all the benefits

Wrox on twitter

Follow @wrox on Twitter and be in the know on the latest news in the world of Wrox

Wrox on facebook

Join the Wrox Facebook page at facebook.com/wroxpress and get updates on new books and publications as well as upcoming programmer conferences and user group events

Contact Us.

We love feedback! Have a book idea? Need community support?
Let us know by e-mailing wrox-partnerwithus@wrox.com

Related Wrox Books

Beginning ASP.NET 4.5

ISBN: 978-1-118-31180-6

Featuring a user-friendly, step-by-step format, the book guides you through customizing the IDE, building a Planet Wrox website example, working with files and web forms, designing web pages, displaying and updating data, creating tables, and much more. With this resource in hand, you will be completely at ease learning ASP.NET 4.5.

Beginning Visual C# 2012

ISBN 978-1-118-31441-8

Using this book, you will first cover the fundamentals such as variables, flow control, and object-oriented programming and gradually build your skills for web and Windows programming, Windows forms, and data access. Step-by-step directions walk you through processes and invite you to “Try it Out,” at every stage. By the end, you’ll be able to write useful programming code following the steps you’ve learned in this thorough, practical book. If you’ve always wanted to master Visual C# programming, this book is the perfect one-stop resource.

Professional C++, 2nd Edition

ISBN: 978-0-470-93244-5

With this no-nonsense book, you will learn to conquer the latest version of the C++ language: C++11. The authors share real-world examples, decipher little-known features of C++, and reveal the significant changes to C++ that accompany the latest release. Ultimately, you’ll discover programming methodologies, reusable design patterns, and good programming style that will increase the quality of your code and improve your programming efficiency.

Professional C# 2012 and .NET 4.5

ISBN 978-1-118-31442-5

After a quick refresher on C# basics, the author dream team moves on to provide you with details of language and framework features including LINQ, LINQ to SQL, LINQ to XML, WCF, WPF, Workflow, and Generics. Coverage also spans ASP.NET programming with C#, working in Visual Studio 2012 with C#, and more.

Professional Visual Basic 2012 and .NET 4.5

ISBN: 978-1-118-31445-6

Written by an author team of veteran programmers and developers, this book gets you quickly up to speed on what you can expect from Visual Studio 2012. Packed with helpful examples, this comprehensive guide examines the features of Visual Studio 2012, and walks you through every facet of the Integrated Development Environment (IDE), from common tasks and functions to its powerful tools.

Professional Visual Studio 2012

ISBN: 978-1-118-33770-7

This book is what you need to get up and running quickly on Visual Studio 2012. Written by a Microsoft Visual C# MVP, it guides you through the integrated development environment (IDE), showing you how to maximize each of the tools and features.

Visual Basic 2012 Programmer’s Reference

ISBN: 978-1-118-31407-4

Visual Basic 2012 is packed with powerful features and this book will help you master them all. You’ll gain a solid understanding of essential Visual Basic topics and begin applying the information to perform a host of important development tasks. The tutorials inside are filled with code examples and the best methods for using them to write your own programs.